

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: May 17, 2011  
Date of Addendum: April 28, 2011

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
165	77-0064-149	PCC Pavement Widening / HMA Resurfacing	Polk	STP-A-006-4(149)--86-77	17may165.a01

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to the ESTIMATING PROPOSAL -- FOR FEDERAL AID CONTRACT and the BIDDING DOCUMENT.

Change the Contracting Authority from IOWA DEPARTMENT OF  
TRANSPORTATION to CITY OF WINDSOR HEIGHTS

Attached is a SCHEDULE OF PRICES for the following item:

Line No. 0835 2555-0000010 DELIVER AND STOCKPILE SALVAGED  
MATERIALS

Bid this item as instructed and submit the bid for this item with the Bid Proposal.

Make the following change to the Proposal Special Provisions Text and the Proposal Special Provisions List.:

Add the following Special Provisions:

SP-090129    May 17, 2011

SPECIAL PROVISIONS FOR TRAFFIC SIGNALIZATION

\*\*\* INTENDED FOR: POLK COUNTY    STP-A-006-4(149)--86-77 \*\*\*

SP-090131    May 17, 2011

SPECIAL PROVISIONS FOR CLOSED CIRCUIT TELEVISION (CCTV)  
CAMERA SYSTEM

\*\*\* INTENDED FOR: POLK COUNTY    STP-A-006-4(149)--86-77 \*\*\*

Make the following change to the plan:

SHEET C.03:

Add reference note for bid item DELIVER AND STOCKPILE SALVAGED MATERIALS

Bid item is for salvaging, stockpiling and delivering existing traffic signal equipment from the Intersection of Hickman Rd. and 63rd St. to the City of Des Moines Signal Shop as noted in General Note #28 on sheet N.01.

\*\*\*\*\*

Proposal ID No.: 77-0064-149  
 Primary Work Type: PCC PAVEMENT WIDENING / HMA RESURFACING  
 Primary County: POLK  
 Bid Order No.: 165  
 Letting Date: May 17, 2011 10:00 A.M.

ITEMS LISTED ON THIS PAGE ARE ADDED BY ADDENDUM 17may165.a01

UNIT BIDS MUST BE TYPED OR SHOWN IN INK OR THE BID WILL BE REJECTED.

Line No	Item Number	Item Description	Quantity and Unit	Unit Price	Bid Amount
				Dollars   Cts	Dollars   Cts
Section 0001 (CONTINUED)					
ROADWAY ITEMS				STP-A-006-4(149)--86-77	
0835	2555-0000010	DELIVER AND STOCKPILE SALVAGED MATERIALS	1.000 LS	.	.
SECTION 0001 TOTAL					
Total Bid					



**SPECIAL PROVISIONS  
FOR  
TRAFFIC SIGNALIZATION**

**Polk County**

**STP-A-006-4(149)--86-77**

**Effective Date  
May 17, 2011**

**THE STANDARD SPECIFICATIONS, SERIES 2009, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.**

**TABLE OF CONTENTS**

**I GENERAL REQUIREMENTS**

- 1.1 RELATED SPECIFICATIONS AND STANDARDS
- 1.2 LOCAL REQUIREMENTS
- 1.3 COORDINATION WITH UTILITIES
- 1.4 CONTRACTOR SUBMISSIONS
- 1.5 SUBSTITUTIONS
- 1.6 SCHEDULING AND CONFLICTS
- 1.7 TESTING OF SIGNAL EQUIPMENT
- 1.8 GUARANTEE
- 1.9 MEASUREMENT FOR PAYMENT

**II INSTALLATION REQUIREMENTS**

- 2.1 FOUNDATIONS
- 2.2 HANDHOLES
- 2.3 CONDUIT
- 2.4 ELECTRICAL
- 2.5 FIBER OPTIC CABLE
- 2.6 BONDING AND GROUNDING
- 2.7 TRAFFIC SIGNAL DISPLAYS
- 2.8 CONTROLLER
- 2.9 PAINTING
- 2.10 LOOP DETECTORS
- 2.11 SIGNS
- 2.12 LOCATE BOX

**III**



**MATERIAL REQUIREMENTS**

- 3.1 TRAFFIC SIGNAL LAMPS
- 3.2 TRAFFIC SIGNAL CABLE
- 3.3 SIGNS
- 3.4 FIBER OPTIC CABLE AND ACCESSORIES
- 3.5 HANDHOLES
- 3.6 CONDUIT
- 3.7 LOOP DETECTOR SEALANT

**IV EQUIPMENT REQUIREMENTS**

- 4.1 TRAFFIC SIGNAL CONTROLLER SYSTEM, TYPE 170
- 4.2 TRAFFIC SIGNAL COMMUNICATIONS
- 4.3 VEHICULAR TRAFFIC SIGNAL HEADS
- 4.4 PEDESTRIAN TRAFFIC SIGNAL HEADS
- 4.5 ALUMINUM TRAFFIC SIGNAL PEDESTAL
- 4.6 GALVANIZED STEEL TRAFFIC SIGNAL SUPPORT
- 4.7 PEDESTRIAN PUSH BUTTON DETECTORS

**V POLE FINISH**

- 5.1 GENERAL
- 5.2 SURFACE PREPARATION
- 5.3 ZINC COATING
- 5.4 EXTERIOR COATING
- 5.5 QUALITY CONTROL
- 5.6 PACKAGING
- 5.7 FIELD REPAIR PROCEDURE
- 5.8 METHOD OF MEASUREMENT

**VI ADDITIONAL BIDDING ATTACHMENTS**

- 6.1 SCHEDULE OF UNIT PRICES

## **PART I GENERAL REQUIREMENTS**

This part consists of the general provisions necessary when furnishing a traffic signal installation complete, in place and operational as described in the project plans and these special provisions.

### **1.1 RELATED SPECIFICATIONS AND STANDARDS**

Unless otherwise specified in the project plans and special provisions the traffic signal installed under this specification shall comply with:

- A. Specifications of the Underwriters Laboratories Inc.
- B. National Electrical Code.
- C. Manual on Uniform Traffic Control Devices for Streets and Highways, as adopted by the Department per 761 of the Iowa Administrative Code (IAC), Chapter 130.

### **1.2 LOCAL REQUIREMENTS**

The Contractor shall notify and receive approval from the Engineer prior to any operational shutdown of any existing traffic signal installation. Adherence to the City Electrical Code will be required for service to the Controller.

All work on the project shall be supervised on-site or performed by an International Municipal Signal Association (IMSA), Level II Certified Traffic Signal Technician. This work includes the installation of conduit, handholes, pole footings, wiring, traffic signal poles, traffic signal heads, video/observation cameras and traffic signal controller/cabinets.

### **1.3 COORDINATION WITH UTILITIES**

- A. Location: The Contractor shall be responsible for determining the exact location and elevation of all public utilities in proximity to any construction work and shall conduct all activities to ensure that public utilities are not disturbed or damaged.
- B. Liability: The Contractor shall be fully Liable for any and all expenses incurred as a result of failing to obtain required clearances, location of utilities, and any damage to the public utilities caused by construction.

### **1.4 CONTRACTOR SUBMISSIONS**

- A. Material and Equipment List: A list of equipment and materials required for the project will be furnished each bidder with the proposal. Within sixty calendar days after awarding of the contract for the project, the Contractor shall complete the list by writing in the name of the equipment manufacturer and catalog number of each item listed on the project. The list shall be submitted in five copies to the Engineer for written approval before any equipment or materials are ordered.
- B. Schedule of Unit Prices: Forward to the Engineer three copies of a list of unit costs for each item listed on the Schedule of Unit Prices attached to the Specifications by the preconstruction meeting. The sum of the costs for each item shall equal the total Contract Lump Sum price for the traffic signal installation(s). Bi-weekly estimates of the work performed on the project will be made by the Contracting Authority and the unit costs will be used to prepare progress payments to the Contractor.
- C. IMSA Certification: The Contractor shall submit the name and contact information of the IMSA Level II Certified Traffic Signal Technician(s) working on the project and a copy of their IMSA certificate.

- D. Shop Drawings, Catalog Cuts, Certifications: Six copies of shop drawings shall be furnished for steel mast arm poles to be furnished on the Project. Six copies of catalog cuts and manufacturer's specifications shall be furnished for all standard "off-the-shelf" items. Manufacturers shall certify electrical equipment, signal equipment, and materials to ensure compliance with these project documents. Upon request, the Contractor shall provide material certifications to the Engineer.

Review of shop drawings by the Engineer is for the purpose of checking for general conformance with the project design concept and contract documents. On each submittal, the Contractor shall specify in writing any deviations from the requirements of the plans or contract documents.

#### **1.5 SUBSTITUTIONS**

- A. Use only materials conforming to these specifications unless permitted otherwise by Engineer.
- B. Obtain approval of Engineer for substitutions prior to use.

#### **1.6 SCHEDULING AND CONFLICTS**

- A. Schedule work to minimize disruption of public streets and facilities. Develop traffic control in accordance with the Manual on Uniform Traffic Control Devices for Streets and Highways, as adopted by the Department per 761 of the Iowa Administrative Code (IAC), Chapter 130. Submit a schedule of planned work activities.
- B. Immediately notify the Engineer of any conflicts discovered or any changes needed to accommodate unknown or changed conditions as soon as found.

#### **1.7 TESTING OF TRAFFIC SIGNAL INSTALLATION**

- A. Notify the Engineer the date the signal or signal system will be ready for testing once the project is open to traffic.
- B. A representative from the manufacturer and/or supplier of signal controller shall be at the project site when the signal controllers are ready to be turned on to provide technical assistance including, as a minimum, programming of all necessary input data. Required signal timing data shall be provided by the Engineer.
- C. Upon authorization of the Engineer, place the signal or signal system in operation for a consecutive 30-day test period. The signal(s) shall not be placed into operation without prior notification and authorization of the Engineer. Any failure or malfunction of the equipment furnished by the Contractor due to workmanship and/or material defects, exclusive of minor malfunctions (such as lamp burnouts) occurring during the test period, shall be corrected at the Contractor's expense and the signal or system tested for an additional 30 consecutive calendar day period. This procedure shall be repeated until the signal equipment has operated satisfactorily for 30 consecutive calendar days.
- D. Respond, within 24 hours, to perform maintenance or repair of any failure or malfunction reported, after signal turn on and prior to final acceptance of the completed traffic signal system.

#### **1.8 GUARANTEE**

- A. All equipment and materials shall be provided with a standard industry warranty. If defects develop under normal operating conditions within the warranty period, after acceptance of the completed installation by the Engineer, the defects shall be corrected by, and at the expense of the Contractor.

- B. Provide guarantee in writing on Company or Corporation letterhead stationery to the Contracting Authority prior to final acceptance. Transfer required equipment warranties prior to the date of final acceptance to the Contracting Authority.

**1.9 MEASUREMENT FOR PAYMENT**

All measurements for payment will be made by the Engineer.

- A. The Traffic Signal Installation(s) will be paid for at the contract lump sum price. This price shall be full compensation for furnishing all equipment, materials, and labor necessary or incidental to the construction of the complete signal installation.
- B. Monthly estimates of the work performed will be made based on the schedule of unit prices and will be used to prepare progress payments to the Contractor. The schedule of unit prices will also be used to establish the total cost for any extra work orders related to traffic signal installation work items unless otherwise negotiated.

**PART II  
INSTALLATION REQUIREMENTS**

This part consists of the installation details necessary during the construction of a traffic signal complete, in place, and operational as described in the project plans and these special provisions.

An anti-seize compound shall be used in the installation of all mechanical connections and fasteners, including all nuts and bolts.

**2.1 FOUNDATIONS**

The concrete bases shall conform to the dimensions shown on the plans. The bottom of all foundations shall rest securely on firm undisturbed ground. Forms shall be used for the upper portion of all foundations. Whenever the excavation for a foundation is irregular in shape, forms shall be used to provide the proper dimensions of the foundations below grade. The material for the forms shall be of sufficient thickness to prevent warping or other deflections from the specified pattern. The forms shall be set level and means shall be provided for holding them rigidly in place while the concrete is being deposited. Anchor bolts for the signal poles or the controller cabinet shall be set in place by means of a template constructed to space the anchor bolts in accordance with the manufacturer's requirements. The center of the template and the center of the concrete base shall coincide unless the Engineer shall direct otherwise. Concrete shall be consolidated by vibration during placement.

Footings shall be Class C structural concrete. Reinforcing Steel – deformed bars shall meet ASTM A 615, Grade 40. Fabricate and bend reinforcing steel cold, per approved submittals or plans.

Finish the top of the base level and round top edges with a 1/2 inch radius edger. In sidewalk areas, adjacent to sidewalks, or in other paved areas, the top 10 inches of the base shall be formed square and flush with the surrounding paved area. Provide preformed expansion material between the base and the other paved area. When installed in an earth shoulder away from the pavement edge, the top of the concrete base shall be approximately 2 inches above the surface of the ground. The exposed surface of the base shall have a rubbed surface finish.

After the foundation or base has been poured, absolutely no modification of any sort may be made. If the anchor bolts, conduit, or any part of the foundation or base is installed in an incorrect manner as determined by the Engineer, the entire foundation or base shall be removed and a new foundation or base installed at the Contractor's expense.

Cover the anchor bolts in such a manner as to protect them against damage and to protect the public from possible injury prior to setting poles.

Where the foundation cannot be constructed as shown on the plans because of an obstruction, the Contractor shall relocate the foundation or use other effective methods of supporting the pole as may be designated by the Engineer.

The Contractor shall be responsible for the proper elevation, offset, and level of each foundation.

Conduit, drains, and ground rods shall be installed as shown on the plans. Conduit inlets shall be installed as shown on the plans. As a minimum, one additional conduit inlet shall be installed per signal pole base and two per traffic signal controller base as shown on the plans. Inlets not used shall be capped below grade. A ground rod shall be placed at each controller or combination sign/street light pole foundation. The ground rod shall be a minimum of 5/8 inch diameter, by 10 feet long, copper plated steel.

The foundations must be given seven days to cure before poles are erected.

The Contractor shall provide designs for all concrete bases where mast arms are longer than 70 feet or when it is called for on the plans. The cost for the design shall be considered as part of the cost of the mast arm pole. This design would then be used as a substitute for footing design as shown on the signal detail sheet of the plans. The use of the ground rod and the number of conduits as indicated on the signal detail sheet of the plans shall remain the same.

Any cost associated with installing wire/conduit into an existing signal or cabinet base/foundation/pad is considered incidental to the other pay items. When installing a conduit bend in an existing base the conduit size shall be equivalent to the conduit in the ground. The steel in the base shall not be cut or damaged and the concrete shall be broken away in the shape of a "U" with an approximate depth of at least 12 inches below the depth of the surrounding ground surface. Enough concrete shall be removed so the conduit will be inside the anchor bolts of the foundation. The conduit shall be placed in the "U" with concrete added in the "U" and finished to match the base.

The Contractor shall also provide and install conductors in the Pole shaft and in the Luminaire Arm. Unless otherwise indicated on the plans, luminaires will be supplied and installed by others. The Contractor shall also connect the conductors in the pole shaft to the 2/C street lighting cable as shown on the plans. Fused connectors shall be used in pole bases and when connecting multiple conductors.

#### Existing Pole Foundations:

All existing traffic signal pole foundations that become unused for the new traffic signal shall be removed. Foundations three feet or less in depth shall be removed completely. Foundations greater than three feet in depth shall be removed to one foot below grade. All holes shall be filled and surface restored to match the surrounding area. This work is considered incidental to the other pay items.

## **2.2 HANDHOLES**

When precast concrete sections are used for handholes, the conduit entrances shall be neatly grouted between the conduit and the precast concrete. The handhole ring shall fit snugly inside the precast concrete section. The handhole ring on all 18 inch handholes shall be firmly attached using an adhesive caulk or other means approved by the Engineer.

Additional handholes may be installed at the Contractor's expense, to facilitate the work.

Provide four cable hooks in all handholes. Anchor in the wall of the handhole utilizing appropriate anchoring devices.

Handholes shall be installed in a neat and workmanlike manner. When the use of forms is required they shall be set level and of sufficient thickness to prevent warping or other deflections from the specified pattern. A means shall be provided for holding conduit runs rigidly in place while the concrete is placed. All conduits shall enter the handhole at a depth of 12 inches from the top of the handhole. The ends of all conduit leading into the handhole shall fit approximately 2 inches beyond the inside wall. Cast iron rings

and covers for handholes shall be set flush with the sidewalk or pavement, or 1 inch above the surface of the ground.

**EXISTING HAND HOLES:**

All existing traffic signal hand holes that become unused for the new traffic signal shall be removed and discarded by the contractor. The sidewalk area shall be properly restored to match the surrounding area. This work is considered incidental to the other pay items.

**2.3 CONDUIT**

All conduit ends shall have bell ends. Bell ends shall be installed prior to pulling any wiring and shall be capped until wired is pulled. A sealing compound (duct seal) shall be used at all conduit openings at; signal footings, controller footings, handholes, and tubs.

Conduit buried in open trenches shall be placed a minimum of 36 inches deep and a minimum of 2 feet from the back of curb unless otherwise directed by the Engineer. Open trench methods of placing conduit will be permitted except where the conduit is to be placed under existing pavement. Conduit in pavement areas shall be placed to a minimum depth of 2 feet below the finished pavement surface or as directed by the Engineer.

When underground conduits parallel an existing facility, maintain at least 1 foot of separation.

When it is necessary to cut and thread steel conduit, no exposed threads will be permitted. Tighten all coupling until the ends of conduits are brought together. Conduit and fittings shall be free from burrs and rough places and conduit runs shall be cleaned, swabbed and reamed before cables are installed. Use nipples to eliminate cutting and threading of short lengths of conduit. Paint damaged galvanized finish on conduit with zinc rich paint. Approved conduit bushings shall be installed on the exposed ends of rigid steel conduit.

Change in direction of conduit shall be accomplished by bending such that the conduit will not be injured or its internal diameter changed. Bends shall be of uniform curvature and the inside radius of curvature of any bend shall not be less than six times the internal diameter of the conduit. Extend conduit 2 to 4 inches above finished surface in all bases.

Deposit backfill material in layers not to exceed 6 inches in depth and compact thoroughly before the next layer is placed. Backfill material shall be free of cinders, broken concrete, or other hard or abrasive materials. Remove surplus material from the public right-of-way.

Place pushed conduit by jacking, pushing, boring or any other means necessary to place the conduit without cutting, removing, or disturbing existing pavement. The size of a bored hole shall not exceed the outside diameter of the conduit which is to be placed. Tunneling under the pavement or water jetting will not be permitted. Pits for boring shall not be closer than two feet to the back of curb.

When it is impractical to push the conduit under pavement due to unanticipated obstructions, the Contractor may, with the Engineer's permission, cut the existing pavement.

All conduit, whether PVC or Steel shall include one polypropylene Pull Rope with a minimum 600 pounds proper tensile strength. All conduit will be proofed upon completion to verify continuity and integrity of the duct.

**2.4 ELECTRICAL**

All conductor cable combinations shall be installed as specified on the Plans. No substitutions will be permitted. The required number of conductors to each signal head shall be one conductor for each optical unit or set of optical units operating identically through the same cycle and one conductor for common return. Each overhead red, yellow, green signal head shall be wired with a separate cable from a splice in the pole base according to the conductor combination specified on the Plans. Within the

cabinet, all signal cables shall be labeled as to their origin. If color or number coding is used, a key sheet shall be left in the print drawer and two copies shall be delivered to the Engineer.

Where practical, color codes shall be followed so that the red insulated conductor connects to the red indication terminal, yellow to yellow, and green to green. Identify circuits at the controller with durable labels attached to the cables.

Signal cable runs shall be continuous from connections made in the signal pole bases to the terminals in the controller cabinet. Splicing will not be allowed in underground handholes unless specifically called for in the project documents. Power lead-in cable runs shall be continuous from the secondary service point to the meter socket and from the meter socket to the controller cabinet. Tracer wire shall be spliced in the handholes and controller to form a continuous network.

Pull cables through conduit by means of a cable grip designed to provide a firm hold upon the exterior covering of the cable(s), with a minimum of dragging on the ground or pavement. This shall be accomplished by means of reels mounted on jacks, frame mounted pulleys, or other suitable devices. Only NEC or UL approved lubricants may be used to facilitate the pulling of cable.

All splices in the handhole compartment of a signal pole shall be made using silicone filled, screw-on wire connectors. Wires shall be twisted before the connector is added. Cable connections in signal heads and controller cabinets shall be made at the terminal blocks provided for that purpose, without using crimp-on connectors.

Slack for each cable shall be provided by a 4 foot length in each handhole and a 2 foot length in each signal and controller base (measured from the handhole compartment to the end of the cable). In those handholes where detector splices are made, a 4 foot length of cable slack shall be provided in both the detector wire and the detector lead-in cable.

All conduits shall include a 1c#10 tracer wire. A continuous orange tracer wire (1c #10) shall be included from each pole base to the controller cabinet. A separate orange tracer wire (1c #10) shall be included with all fiber optic communication cable. A yellow tracer wire shall be used in conduits with only streetlight circuits. Tracer wire for the signal system shall terminate in the controller cabinet and shall be labeled with the direction. Tracer wire for the communication/fiber system shall terminate in the locate box. The Contractor shall install, splice, and test the tracer wire for continuity. Every tracer wire run shall be grounded at one end.

### **Existing Wiring**

Unless otherwise indicated on the plans, all existing wiring that become unused in this project shall be removed and discarded of by the Contractor. This work is considered incidental to other measured items.

### **2.5 FIBER OPTIC CABLE**

The cable end shall be secured inside the controller cabinet so that no load is applied to the exposed fiber strands. The minimum bend radius for static storage shall not be less than ten times the diameter of the cable measuring the cable on the outside, or as recommended by the manufacturer.

The minimum bend radius during installation shall not be less fifteen times the diameter of the cable measuring the cable on the outside, or as recommended by the manufacturer. The Contractor shall not use tie wrap devices on fiber optic cable.

- A. Cable Slack: Slack shall be left in each handhole, at the top of any conduit riser, in each junction box, in each controller cabinet, and at each equipment rack or other point of termination. This slack cable requirement may be deleted where existing hand holes or through points lack sufficient area to maintain the minimum bend requirements. Where slack has been deleted, extra slack equal to the amount that would have been distributed in the through points shall be equally divided between the two controller cabinets and shall be in addition to the slack mandated at the

cabinets. Slack in each handhole type shall be provided as designated on the plans. Slack cable shall be coiled and the coils bound at three points around the coil perimeter and supported in their static storage position.

- B. Cable Installation in Conduits: A suitable cable feeder guide shall be used between the cable reel and the face of the conduit. The cable feeder shall be designed to protect the cable and guide the cable directly into the conduit off the reel. During the installation, the cable jacket shall be carefully inspected for jacket defects. If defects are found, the Engineer shall be notified prior to any additional cable being installed. The Contractor shall take care in the pulling of the cable to insure that the cable does not become kinked, crushed, twisted, snapped, etc. A pulling eye shall be attached to the cable and be used to pull the cable through the conduit. A pulling swivel shall be used to preclude twisting of the cable. The cable shall be lubricated prior to entering the conduit with a lubricant recommended by the manufacturer. Dynamometers or break away pulling swing shall be used to insure that the pulling tension does not exceed the specified force of 600 pounds or the cable manufacturer's recommendations, whichever is less. The mechanical stress on the cable shall not allow the cable to twist, stretch, become crushed, or forced around sharp turns which exceed the bend radius or scar or damage the jacket. The pulling of the cable shall be hand assisted at each pull point.

Cable shall not be pulled through any intermediate junction box, manhole, pull box, pole base or any other opening in the conduit unless specifically required by the Engineer in specific facilities. The necessary length of cable to be installed shall be pulled from one junction box, manhole, pull box, pole base, or cabinet to the immediate next downstream manhole, box, pole base, or cabinet. The remaining length of cable to be installed in the next conduit shall be carefully stored in a manner that is not hazardous to pedestrian or vehicular traffic yet ensures that no damage to the cable shall occur. The cable shall be stored in a manner that shall allow that length of cable to be safely pulled into the next conduit. The Engineer shall approve the storing methods to be used.

At each hand hole or through point and at the cabinet, the cable shall be visibly and durably marked or tagged as "FIBER OPTIC CABLE, CITY OF DES MOINES". Additionally, each cable shall be visibly and durably marked or tagged with the cable number as shown on the plans.

- C. Communications Cable Testing: A minimum of two fibers, selected at random, from each tube in the fiber optic cable shall be tested, both on-the-reel prior to installation and after installation using a high-resolution optical time domain reflectometer (OTDR). All single mode measurements shall be conducted at the  $1310 \pm 30$  nm wavelength. All multi-mode measurements shall be conducted at  $850 \pm 30$  nm wavelength. The Contractor shall record the identification, location, length, and attenuation measurements of each tested fiber and shall furnish all test reports to the Engineer. All cable readings/measurements shall be compared to the maximum allowable deviations in the cable specification and the levels of acceptance recommended by the manufacturer in their printed documentation. Any cable having measurements outside the allowable range shall be replaced and shall not be acceptable for installation on this project.
1. On-Reel Testing: Prior to the installation, the Contractor shall perform on-site, on-reel testing. This testing shall be for both attenuation and continuity. The tests shall be conducted at 850 nm for multi-mode fibers and at 1310 nm single mode fibers. The testing shall be performed using an OTDR by means of a pigtail splice. All test results shall be within  $\pm 3\%$  of factory-supplied attenuation measurements. Testing shall be done in one direction only. Hard copy or electronic copies (with applicable software) of the OTDR traces for the testing shall be furnished to the Engineer prior to installation of the cables. Except for the access to and the test preparation of any one end of the newly furnished cable to be tested, the Contractor shall preserve the cable in its originally-shipped condition. If any fiber of the cable fails the on-reel attenuation test, the cable shall be rejected and shall not be used on this project. The rejected cable shall be replaced at the Contractor's expense.

2. Cable Segment Testing: As each cable segment is terminated, the Contractor shall perform an end-to-end attenuation (power loss) test of each terminated fiber of each FO cable. This testing shall be performed using hand-held optical test sets and shall be tabulated and be included in the documentation package to be provided to the Engineer at the conclusion of the project. Overall loss for each link shall not exceed the cumulative specified maximum losses of the components. For example, at 850 nm, a one mile link with two splices and a connector on each end shall not exceed 7.0 dB:

1.0 mile x 5.6 dB/mile:	5.6 dB
0.2 dB per splice x 2:	0.4 dB
0.5 dB per connector x 2:	<u>1.0 dB</u>
Maximum allowable loss:	7.0 dB

The cable segment shall be rejected for use on this project if any terminated fiber of the cable segment fails the attenuation test. Rejected cables shall be repaired or replaced by the Contractor at the Contractor's expense. The Contractor shall retest all fibers of any repaired or replaced cable segment. The Contractor shall submit complete documentation of the cable segment attenuation tests. Such documentation shall be submitted in either hardcopy (written) form or in Engineer-approved electronic format on diskette.

3. Final System Testing: After the complete fiber optic system is installed and terminated, an OTDR reading shall be performed on all cables to insure that each section is in compliance with the issued specification. All fibers shall be tested. A hard copy of OTDR signature traces for all fibers for all sections shall be provided to the Engineer. Fibers which have been terminated shall be indicated in the report. In addition to the OTDR test report, the Contractor shall provide the test results of an Attenuation Test for the installed fibers using the insertion loss test procedure and the Transmitter/Receiver Power Level Test and the Continuity Test.

**2.6 BONDING AND GROUNDING**

Metal conduit, service equipment, anchor bolts, metal poles, pedestals, controller cabinets, interconnect cable shields, and all other electrical equipment shall be made mechanically and electrically secure to form a continuous system, and shall be effectively grounded. The grounding conductor shall be a No. 6 AWG copper, non-insulated wire.

Grounding shall be accomplished by bonding the grounding circuits to copper clad metal, driven electrodes. All electrodes shall be as a minimum, 5/8 inch in diameter by 10 feet long. The electrodes shall be driven vertically until the top of the rod is a minimum of 4 inches below grade. Bonding to the ground rod shall be made by means of suitable screw type positive ground rod clamps. The controller cabinet ground shall measure 10 ohms or less.

Grounding of the conduit and neutral at the service point shall be accomplished as required by the National Electric Safety Code, except bonding jumpers shall be No. 6 AWG or equal.

Install a ground wire in all conduit that carries 120 volt signal cables.

Grounding to existing water lines will not be permitted.

Bonding of standards and pedestals shall be by means of a bonding strap attached to an anchor bolt or to 1 inch, or longer, brass or bronze bolt installed in the lower portion of the shaft.

The service meter and socket shall be bonded to a ground electrode by use of a ground clamp and a No. 6 AWG copper wire.

Bonding of metallic conduit in concrete pull boxes and manholes shall be by means of galvanized grounding bushings and bonding jumpers. Where there is a change, at a pull box or manhole, from non-metallic conduit to metallic conduit, the grounding wire in the non-metallic conduit shall be bonded to the metallic conduit. Saddle clamps are not acceptable.

Existing ungrounded metal poles on which cabinets are mounted shall be grounded by means of a driven ground rod.

The interconnect cable shield shall be bonded to the controller ground buss at one controller termination point for each interconnect run.

## **2.7 TRAFFIC SIGNAL DISPLAYS**

All Overhead traffic signal heads shall have backplates and be centered over their respective lanes, unless otherwise noted on the plans. Brackets shall be used to mount all pole-mounted and mast arm-mounted overhead signals which have top and bottom brackets and are adjustable in both horizontal and vertical planes. All overhead displays located on each mast arm shall have each red indication set at approximately the same elevation, unless otherwise directed by the Engineer. All optically limited signal heads shall be properly masked to limit their field of view as directed by the Engineer.

During the course of construction and until the signals are placed in operation, signal faces shall be covered or turned away from approaching traffic. When ready for operation, they shall be securely fastened in position facing toward approaching traffic.

## **2.8 CONTROLLER**

The controller shall be installed at the location indicated on the Plans with the back of the cabinet toward the intersection such that the signal head can be viewed while facing the controller, unless otherwise directed by the Engineer.

The aluminum rack edge shall be labeled for each detector amplifier, load switch, and isolator.

## **2.9 PAINTING**

All signal poles, mast arms, and luminare arms shall be black. If the painted surface of any equipment is damaged in shipping or installation, such equipment shall be retouched or repainted in a manner satisfactory to the Engineer.

See Pole Finish section.

## **2.10 LOOP DETECTORS**

Obtain Engineer approval of loop locations prior to saw cutting.

Saw shall be equipped with a depth gauge and horizontal guide to assure proper depth and alignment of the slot. Provide a clean, straight, well-defined saw cut without damage to adjacent areas. Overlap saw cuts to provide full depth at corners.

Remove jagged edges or protrusions in the saw cuts before installing loop wire. The saw cuts must be cleaned to remove cutting dust, grit, oil, moisture, or other contaminants. Flush saw cuts clean with a stream of water under pressure, and dry the slots using oil-free compressed air.

Install detector loop wire in the bottom of the saw cut. If necessary, hold down by means of a material such as tape or doubled-over pieces of the plastic tubing.

Loop detector lead-in cable, shall be continuous from the terminal in the controller cabinet to a splice made with detector loop leads, in the first handhole provided adjacent to the detector loop. Apply Butyl Rubber Polymer Tape sealant between the wires and completely cover the silicone rubber. As an acceptable alternate, the Contractor may use a 3M Company Scotchcast Kit, or approved equal, for splicing in the handhole.

The field loop conductors and tubing shall be continuous from the terminating handhole or base with no splices permitted. At the time of placing the loop wire in the saw cuts, the ends of the tubing shall be sealed to prevent any entrance of moisture into the tubing. Loop wires and tubing that are not embedded in the pavement shall be twisted with at least five turns per foot.

Label each loop with durable tags corresponding to loop numbering as shown on the plans. Loops which are physically adjacent in an individual lane or adjacent lanes shall be wound with opposite rotation (i.e. #1 CW, #2 CCW, #3 CW, etc.). Rotation reversal can be accomplished by reversing leads at the handhole.

Solder electrical splice between the detector lead-in cable and the loop wire using resin core solder. Provide a watertight protective covering for the spliced wire, the shielding on the detector lead-ins and the end of the tubing containing the loop wires. The use of open flame to heat the wire connection will not be permitted. The Contractor shall use a soldering iron, gun, or torch equipped with a soldering tip. The splice shall be made by the following method:

1. Remove lead-in cable coverings and expose four inches of insulated wire.
2. Remove insulation from each conductor of detector lead-in cable and scrape both copper conductors with knife until bright.
3. Remove the plastic tubing from the loop wires for 1 1/2 inches.
4. Remove the insulation from the loop wires and scrape both copper conductors with knife until bright.
5. Wash the exposed copper conductors with turpentine spirits to clean the conductors.
6. Connect conductors by a soldered "Western Union" type splice, wrapped with waterproof tape and coated with a watertight protective covering.
7. Cover the exposed shielding, ground wire and end of any unused loop lead-in where the sheathing was cut, with liquid silicone rubber. Apply Butyl Rubber Polymer Tape sealant between the wires and completely cover the silicone rubber.

Meter the installed loops by test instruments capable of measuring electrical values of loop wires and lead-ins to measure induced AC voltage, inductance in microhenries, high-low "Q" indication, leakage resistance in megohms, and the resistance of the conductors in ohms. Provide the Engineer a report on company letterhead indicating the inductance and leakage to ground test values for each loop. An inductance and leakage to ground test shall also be conducted and reported for the total detector lead-in and loop system with the test being conducted at the controller cabinet. Before beginning the required test period, the Engineer may independently meter any or all loops. Should any loop be found unacceptable, the Contractor may be required to complete additional tests, as required, at his own expense. An acceptable loop installation shall be defined as follows:

1. Inductance: The inductance reading on the loop tester is approximately the calculated value.
2. Leakage to Ground: Deflection of the pointer to above 100 megohms.
3. Resistance: The resistance of the circuit is approximately the calculated value.

Any loop not meeting the requirements for an acceptable loop installation shall be repaired or replaced. The Contractor shall bear all costs of replacing loop installations deemed unsatisfactory by the Engineer.

All loop detectors in new pavement shall be preformed. No saw-cut loops will be accepted in new pavement.

## **2.11 STREET NAME SIGNS**

All signs shall be handled and installed carefully to prevent any damage to the sign faces. Any sign faces which are damaged prior to or as a result of improper installation will be rejected. Undamaged replacement signs shall then be promptly sent, at no extra cost to the Contracting Authority.

Sign mounting hardware shall include stainless steel bolts, washers, strapping, mounting brackets, etc.

Overhead mount:           18 inches by 48 inches - minimum of 2 places  
                                  18 inches by 60 inches - minimum of 3 places  
                                  18 inches by 72 inches - minimum of 3 places.

Pole mount:  12 inches by 36 inches - mount on bracket which is banded directly to pole. Greater than  
                  36 inches - add stiffener

## **2.12 LOCATE BOXES**

An outdoor-rated, single gang box to house communications/interconnect tracer wire shall be installed on the exterior of the controller cabinet. The location on the cabinet shall be determined by the project engineer. The locate box shall be constructed of die-cast aluminum with a die-cast zinc weatherproof cover and self-closing lid. The box shall be 2 3/4 inches by 4 1/2 inches by 2 5/8 inches D. A 12 inch long ground wire shall be attached to a lug within the box.

## **PART III MATERIAL REQUIREMENTS**

This part consists of material requirements necessary for the construction of a traffic signal installation complete, in place, and operational as described in the project plans and these special provisions.

### **3.1 TRAFFIC SIGNAL LAMPS**

The Contractor shall provide materials that meet or exceed industry standards for the type of operating conditions under which the bulbs will be used. Only newly manufactured bulbs will be considered as responsive to these specifications.

All vehicular and pedestrian signal lamps shall be light emitting diode (LED) and have the following specifications:

The number of LEDs per signal head shall be sufficient to achieve intensity to meet Institute of Transportation Engineers (ITE) photometric test criteria in "Vehicle Traffic Control Signal Heads".

All signals shall comply with ITE standards for LED signals, including color.

Operating voltage shall be between 92 VAC and 135 VAC, 60 HZ +/-3 HZ. Operating temperature shall be between -40°F and +170°F.

LEDs shall be in multiple series circuits connecting no more than 6% of the total LEDs in any single circuit, or the failure of any single circuit shall not result in more than a 6% reduction in total luminous intensity.

Enclosure shall be dust and water resistant.

Beam spread shall meet all aspects of the ITE specifications.

Lenses shall be replaceable, tinted polycarbonate (U stabilized) convex, minimum 0.125 inch thick, free of bubbles, flaws and imperfections. Non-polycarbonate lenses shall be accepted provided they meet the ITE color standards and 32 foot drop test. Chromaticity shall be measured in accordance with ITE standards at 44 points, meeting specifications after 30 minute warm up.

Candlepower distribution shall meet ITE specifications. Brightness shall be maintained in the event of voltage fluctuations or sags within 30% across the operating voltage and temperature range.

Lead wires shall be a minimum of 1.5 feet with NEMA #8 locking fork type terminals for connection to terminal block. Pedestrian signals shall have a screw in base and shall not use transformers. Gaskets shall be supplied and installed if applicable.

Each LED signal lens shall include all necessary components for LED technology. These include, but not limited to: LENS, LEDS, LED circuit board, #18 AWG wire leads with strain relief and insulation rated at 105 degrees C, conductors, electronic switching module, rigid housing, and neoprene one piece gasket.

The lens shall be field replaceable and shall be smooth on the outside. The lens shall require no special tools or sealant for field replacements.

Electrical components shall meet all applicable codes including ITE and cognizant, nationally recognized electrical testing laboratories.

Independent testing laboratory certification to demonstrate wattage and ITE conformance shall be supplied to the traffic engineer prior to ordering.

The LED traffic signal shall meet current ITE standards for intensity and spatial distribution after 30 minutes warm up of continuous operation.

The light output shall have a dominate wavelength of 620-635 nanometers (nm) for Red and 596-610 nm for Portland orange and at least 505 nm for green. Lens may be tinted or colored as long as the chromativity of the lens matches that of the LED's and that luminous intensity is not reduced.

Control circuiting shall prevent current flow through the LED's in the off state to avoid false indication in daylight and evening hours.

Light intensity shall not vary (nor flicker) by more than 30% over the allowable voltage and temperature operating range.

Operating current measured across each LED shall not exceed an average of 30 milliamps (mA).

All LEDs shall be "AlloGap" technology or equal, and rated for 100,000 hours or more (@ 77°F and 30 mA). (ALGaAs technology is not acceptable).

Transient voltage suppression of 1500 volts for 1 millisecond (ms) and fusing with a maximum rating of 2 Amps are required.

LEDs shall be arranged uniformly through the signal head and in an appropriate number of parallel strings to insure that no string accounts for more than 6% of the total.

Each LED signal shall be serialized by the manufacturer with date and lot numbering to facilitate warrant compliance.

Certification: The Engineer shall be furnished with a certification from the manufacturer of the signal head that the equipment furnished under this specification complies with all provisions of this specification. If there are any items, which do not comply with this specification, a list of those exceptions must be detailed on the certification.

#### Lamp Failures

1. The Contractor shall promptly replace any lamp which fails either during installation or within the 30 calendar day test period.

### 3.2 TRAFFIC SIGNAL CABLE

The number of conductors and size of all traffic signal cable shall be as specified on the plans. All wire shall be plainly marked on the outside of the sheath with the manufacturer's name and identification of the type of the cable. All wiring shall be copper. Aluminum wire will not be accepted.

- A. Cable for signalization shall be rated 600 volts minimum. Cable shall be plainly marked on the outside of the sheath with the manufacturer's name and identification of the type of the cable.
- B. Power Lead-In Cable shall be 600 volt, single conductor, stranded copper, Type USE, with UL approval.
- C. Signal Cable shall be multi-conductor copper wire, and meet the requirements of IMSA Specification 19-1.
- D. Loop Detector Wire (With Plastic Tubing) wire shall meet the requirements of IMSA Specifications 51-5.
- E. Detector lead-in cable shall be No. 14 AWG, meeting the requirements of IMSA Specification 50-2 or latest revision thereof.
- F. Tracer wire shall be a No. 10 AWG, single conductor, stranded copper, Type THHN, with UL approval and an orange colored jacket. Tracer wire used in lighting conduits shall have a yellow colored jacket.
- G. Ground wire shall be a No. 6 AWG bare copper wire and bonding jumpers shall be No. 6 AWG bare copper wire connected by approved clamps.

### 3.3 SIGNS

- A. Traffic Sign Blanks: Shall meet all requirements of the "City of Des Moines Standard Drawings and Specifications for Aluminum Sign Blanks."
- B. Traffic Sign Faces: Shall meet all requirements of the latest edition of the "Manual on Uniform Traffic Control Devices" (MUTCD).

The background sheeting used on all signs, with the exception of pedestrian pushbutton signs, shall be 3M DG3 material. Any other applied material, including legends, letters, numbers, or borders, again with the exception of pedestrian push-button signs, shall also be 3M DG3 material.

This material shall have a standard warranty to be free from any defects for a period of not less than seven (7) years from the date of manufacture. A copy of the standard warranty shall be provided as a part of the bid package.

- C. Street Name Signs:
  - 1. All overhead street name signs shall be on an 18 inch aluminum blank. Length shall be in 6 inch increments and will vary based on the legend.
  - 2. The aluminum blank shall be 0.08 inches thick.
  - 3. Signs shall be made of 3M DG3 material. The material shall have a standard warranty to be free from defects for a period of not less than seven years from the date of manufacture. A copy of the standard warranty shall be provided with the submittals.
  - 4. Lettering shall be white and the background shall be blue or green EC film as specified in the plans. All material shall be 3M standard highway colors.
  - 5. Lettering shall be Series B as outlined in the Standard Highway Signs Manual. Lettering size shall be as specified in the plans.

- 6. All signs shall have a 3/4 inch white border.
- 7. A shop drawing showing the sign legend, sign length, letter heights and spacing shall be submitted for approval prior to manufacturing the signs.

D. Completed Signs: Sign faces shall be firmly attached to the aluminum sign blanks, with no air bubbles, wrinkles, creases, tears or other surface blemishes. The faces shall be neatly trimmed to match the edge of the sign blank. The sign faces shall be properly positioned to provide a uniform border around all sides of the sign.

The signs shall be handled carefully and packaged to prevent any damage to the sign faces. Any sign faces which are damaged at the time of delivery will be rejected and returned to the manufacturer. Undamaged replacement signs shall then be promptly sent, at no extra cost to the City of Des Moines.

E. Sign Mounting Brackets: All signs shall be supplied with a sign bracket. The traffic sign bracket shall be an articulated serrated bracket assembly that includes top, middle, and bottom sign mounting brackets and provides a rigid-mount for the traffic sign. All necessary hardware for a complete installation on a mast arm shall be included. The mounting assembly shall be of a cable type. Approval of other bracket supports shall be based on specifications and/or test data about their physical properties and performance properties.

**3.4 FIBER OPTIC CABLE AND ACCESSORIES**

A. Fiber Optic Cable: Furnish and install the loose tube fiber optic cable(s) of the type, size, and number of fibers specified and all associated accessories.

The cable shall meet the latest applicable standard specifications by American National Standards Institute (ANSI), Electronics Industries Association (EIA), and Telecommunications Industries Association (TIA) for the type mode cable of the size specified and the specifications herein.

1.	Multimode Fiber - Grade Index	
	Core Diameter:	62.5 $\mu\text{m} \pm 1.0 \mu\text{m}$
	Cladding Diameter:	125.0 $\mu\text{m} \pm 1.0 \mu\text{m}$
	Core Concentricity:	$\pm 1\%$
	Max. Attenuation:	6.03 dB/mile
2.	Single-Mode Fiber	
	Typical Core Diameter:	8.3 $\mu\text{m} \pm 1.0 \mu\text{m}$
	Cladding Diameter:	125.0 $\mu\text{m} \pm 1.0 \mu\text{m}$
	Core Concentricity:	$\pm 1\%$
	Attenuation Uniformity:	No point discontinuity greater than 0.1 $\mu\text{m}$ at either 1300 nm or 1550 nm
	Max. Attenuation:	0.40 dB/mile

The coating shall be a dual layer UV cured acrylate applied by the fiber manufacturer. The coating shall be mechanically or chemically strippable without damage to the fiber.

The central member of the cable shall be a glass reinforced plastic rod designed to prevent the buckling of the cable. The cable core interstices shall be filled with water blocking tape to prevent water infiltration.

Dielectric fillers may be included in the cable core where needed to lend symmetry to the cable cross-section.

Buffer tubes shall be of dual layer construction with the inner layer made of polycarbonate and the outer layer made of polyester. Each buffer tube shall be filled with a non-hygroscopic, non-nutritive to fungus, electrically non-conducting homogeneous gel or a waterblocked with a water-swellaable yarn or tape. If gel is used it shall be free from dirt and foreign matter and shall be readily removable with conventional nontoxic solvents. Buffer tubes shall be stranded around the central member using reverse oscillation, or "SZ", stranding process.

The buffer tubes shall meet TIA/EIA-598A, "Color coding of fiber optic cables". The single mode cable shall include a total of 3 loose tubes with 12 fibers in each for a total of 36 fibers. The multi mode cable shall include one loose tube with 12 fibers. The tube and fiber colors shall follow the industry color code (BL, OR, GR, BR, SL, WH, RD, BK, YL, VI, RS, AQ).

The cable tensile strength shall be provided by a high tensile strength aramid yarn and/or fiber glass.

All dielectric cables, without armoring, shall be sheathed with medium density polyethylene. The minimum nominal jacket thickness shall be 0.055 inch. Jacketing material shall be applied directly over the tensile strength members and flooding compound. The jacket or sheath shall be marked with the manufacturer's name and the words "Optical Cable", the year of manufacture, and sequential feet marks. The markings shall be repeated every foot. The actual length of the cable shall be within the range plus one percent of the length marked. The marking shall be in a contrasting color to the cable jacket. Additionally, the jacket marking shall have a durable weather proof label which shows the actual attenuation of each fiber expressed in dB/mile.

The cable shall be fabricated to withstand a maximize pulling tension of 600 pounds during installation (Short term) and 135 pounds upon installation (Long term).

The shipping, storing, installing and operating temperature range of the cable shall be -40°F to +158°F.

The manufacturer shall test at the 100% level all fiber optic cable for the following tests:

- a. Each fiber proof tested at a minimum load of 350 MPa.
- b. Each fiber tested for attenuation and the reading shall be part of cable labeling.

The cable shall meet the appropriate standard Fiber Optic Test Procedure for the following measurements:

- a. Fluid Penetration
- b. Compound Drip
- c. Compressive Loading Resistance
- d. Cyclic Flexing
- e. Cyclic Impact
- f. Tensile Loading and Bending

The cable ends shall be available for testing. The cable ends must be sealed to prevent moisture impregnation.

- B. Fiber Optic Jumpers/Patch Cords: All fibers in the multi-mode fiber optic cable shall be terminated in the distribution unit within the traffic controller cabinet.

Length of patch cord will vary according to distribution unit to traffic signal controller, fiber optic modem, or video modem location within controller cabinet and shall provide for a minimum of 2 feet total slack.

Controller cabinet patch cords shall consist of factory-assembled patch cords, each of which shall contain two multi-mode fibers. Each such fiber shall have an STPC (ST compatible, Physical Contact) connector with ceramic ferrule on each end (i.e., a total of four STPC connectors per

cord). Each patch cord shall have a dielectric strength member and a durable outer jacket designed to withstand handling.

Simplex or duplex pigtail jumpers shall be used, in cases of existing 48-Fiber hybrid cable, to branch traffic signal controller/CCTV circuits from splice enclosure in handholes to distribution units/modems in controller cabinets.

Field pigtail jumpers shall consist of factory-assembled patch cords, each of which shall contain two multi-mode fibers. Each such fiber shall have an STPC (ST compatible, Physical Contact) connector with ceramic ferrule on one end (i.e., a total of two STPC connectors per cord) and no connector on the other end (for fusion or mechanical splice). Each patch cord shall have a dielectric strength member and a durable outer jacket designed to withstand handling.

- C. Distribution Unit/Fiber Closet: All fibers, unless stated otherwise in the plans, shall be terminated in the distribution unit. The unit shall be a rack mount, drawer type enclosure that is dust and moisture repellent.

The size of the unit shall be adequate for the number of fibers, proper winding area, and splices. A minimum of 24 ST (multi-mode) or 24 LC (single mode) type connectors shall be provided for each traffic signal controller cabinet.

The enclosure shall be mounted on a EIA 19 inch rack in an area that does not interfere with the normal maintenance of the cabinet electronics and shall have a maximum dimensions of 3.5 inches H x 18.5 inches W x 11.25 inches D. The distribution unit shall be of a slide out drawer type for easy front access with removable rear tray cover to provide easy rear access. The enclosure shall provide for side cable entries and be capable to accommodate up to 48 ST multimode or LC single mode adapters.

The field jumpers/cable shall be secured to the enclosure in a manner that does not degrade the fiber optic cable but insure a firm and secure mount. Sufficient lengths of every loose tube shall be coiled within the enclosure to provide spare distance and reach the fiber interface panel.

All multimode fibers shall be terminated with ST connectors. All single mode fibers shall be terminated with LC connectors

- D. Connectors: Only ST or LC type connectors of ceramic ferrule and Physical Contact end finish shall be used to terminate fibers to equipment. ST, LC or mechanical connectors shall not be used to splice cables.

Maximum attenuation per connector shall be 0.75 dB.

- E. Splices: Fusion splices shall be used to splice all continuous fiber runs in splice enclosures.

The fiber cable shall be installed in continuous runs as designated on the plans. Splices shall be allowed only in the splice enclosures and controller cabinets as located on the plans. Maximum attenuation per splice shall be 0.3 dB.

- F. Breakout Kits: Breakout kits shall be provided for separation and protection of individual fibers with buffer tubing and jacketing materials suitable for termination of the fiber and fiber optic connector as specified.

- G. Splice Enclosure: Ends of continuous fiber cable runs and/or traffic signal controller branch circuit points will be spliced in an outside plant splice enclosure located in handholes as shown on plans.

Enclosure will provide enough trays to splice all fibers, both single mode and multi mode.

Enclosure shall provide gel-compressed connections to provide environmental protection of cable and splices from water and dirt.

### **3.5 Handholes**

- A. Furnish precast concrete handhole, or poured in place concrete handhole, each with cast iron ring and cover. The body of a handhole shall meet the requirements for Class 1500D concrete pipe as applicable.
- B. Cast iron ring and cover may be rated light duty for non-traffic areas (145 pounds minimum); but shall be rated heavy duty for traffic areas (320 pounds minimum) where shown on the plans. Deviations in weights shall not exceed plus or minus five percent. The cover shall have the words TRAFFIC SIGNAL cast on the top of the cover.
- C. Cable hooks shall be galvanized steel with a minimum diameter of 3/8 inch and a minimum length of 5 inches.

### **3.5 CONDUIT**

- A. Rigid steel conduit shall be galvanized steel and meet the requirements of ANSI Standard Specification C80.1, latest revision. Fittings used with rigid steel conduit shall be galvanized steel only.
- B. Polyvinyl chloride conduit (PVC) shall meet the requirements of NEMA TC-2, Type 2, and applicable UL Standards.
- C. Sealing compound shall be readily workable soft plastic at temperatures as low as 30°F, and shall not melt or run at temperatures as high as 300°F.

### **3.6 LOOP DETECTOR SEALANT**

- A. Sealant shall be rapid cure, high viscosity, liquid epoxy, or approved equal, formulated for use in sealing inductive wire loops and leads embedded in asphaltic concrete and Portland cement concrete. The sealant shall be usable on grades of 15% or less without excessive flow of material.
- B. Sealant shall be two component system which consists of a resin constituent identified as pourable, and a hardener identified as quick-setting. Approval of other sealants shall be based on specifications and/or test data regarding physical properties, performance properties and chemical resistance.
- C. Cured sealant shall be unaffected by oils, gasoline, grease, acids, and most alkalis. The mixing of components and the filling of the cut shall be in accordance with the directions of the manufacturer.

## PART IV EQUIPMENT REQUIREMENTS

This part consists of the equipment requirements necessary for the construction of a traffic signal installation complete, in place, and operative as described in the project plans and this specification.

### 4.1 TYPE 170, TRAFFIC SIGNAL CONTROLLER SYSTEM

A. Related Specifications: Unless otherwise stated herein, all equipment furnished under this specification shall be new, meeting the requirements of "California/New York Type 170, Traffic Signal Controller System-Hardware Specification," U.S. Department of Transportation, Publication FHWA-IP-78-16, December 1978, with the following exceptions:

1. Any reference to the State of California shall mean the Jurisdiction.
2. Chapter 1, Section II "General" paragraph 3, the second sentence shall be deleted.
3. Chapter 1, Section VIII "Electrical, Environmental and Testing Requirements" shall be modified as follows:
  - a. Any reference to the Contractor shall mean equipment manufacturer or supplier.
  - b. Paragraph 5.2 shall be changed to read "Two manuals containing the flow chart, listing, and instructions of the test program shall be furnished to the Jurisdiction when the controller unit is delivered."
  - c. Paragraph 6.1 the words "State Approval" shall be deleted.
  - d. Paragraph 6.2 shall be deleted.
  - e. Paragraph 6.3.6 shall be deleted.
4. When specified, the Model 332A Cabinet furnished for the project shall meet the requirements of Chapter 11 "Specifications for Cabinet Model 332A," and the Model 336 Cabinet shall meet the requirements of "Specifications for Cabinet Model 336" dated February 1982, except that the color specified in Section 1, paragraph 3 shall be changed to silver. Molex Flash Blocks shall be provided for all eight vehicle phases to program either red or yellow flashing indications. A detector input panel shall be provided on the rear left side of the cabinet. Cabinet locks as specified in Section I, paragraph 4 shall be changed to Corbin Type 2 locks. An aluminum cabinet shall be furnished.
 

The aluminum surface shall have an anodic coating applied. The anodic coating and anodic coating process shall meet the requirements of Section 2.4.1 and 2.4.2 of the "Traffic Signal Control Equipment Specifications," California Business, Transportation and Housing Agency, Department of Transportation, January 1989. Alternative aluminum surface treatments, which produce an equivalent uniformly textured surface, may be substituted as approved by the Jurisdictional Engineer.
5. All loop detector amplifier units furnished for this project shall be Model 222, Two-Channel Loop Detector Sensor Units meeting the requirements of Chapter 4 with the following exceptions:
  - a. Digital design capable of normal operation when operated with a grounded loop.
  - b. Shall comply with all performance requirements when connected to an inductance of from 50 to 1500 microhenries.
  - c. Each detector channel shall respond to an absolute inductance change ( $\Delta L$ ) rather than as a percentage of the total inductance ( $\Delta L/L$ ).
6. In Chapter 11, Section III "Cabinet Accessories" paragraph 4, a new subsection will be added "Each vehicular and each pedestrian phase shall be provided with a separate switch pack."

7. A model 412C prom module shall be provided, configured to the following table:

Memory Socket	Address Range	Device Type	Chip No.*
U1	8000-FFFF	32K EPROM	INT 27256A
U2	3000-4FFF	8K ZPRAM	DAL 1225
U3	7010-7FFF	8K ZPRAM	DAL 1225
U4	1000-2FFF	8K RAM	HD 6264

\*or approved equal

8. A Model 242 Two-Channel Isolator shall be provided to introduce stop timing to the controller from the conflict monitor and the manual flash switch.
9. The Model 210 Monitor Unit shall meet the requirements of Chapter 3 with the following additional requirements:
- a. The Monitor Unit shall be capable of RED FAILURE detection in accordance with NEMA specifications. Following a long power outage, (greater than two seconds) the Monitor Unit shall be capable of disabling the RED FAILURE detection, until the signal heads are energized (approximately four seconds).
  - b. The Monitor Unit shall have the required circuitry to allow the early detection of a conflict caused by a green or yellow signal "hang up" and shall preclude the presentation of the conflicting signal display at the intersection.
  - c. Any additional harnesses or hardware required shall be furnished with the Monitor Unit.
  - d. The conflict monitor unit shall be capable of ignoring the watchdog and placing intersection in flash if line voltage is less than 98 (+/-2) VAC RMS.
10. A "PDA-2" Power Distribution Assembly shall be provided in lieu of the PDA-1 and the 24 volt D.C. Supply.
11. A standard print shelf drawer shall be provided and installed above the input file.
12. Four ACIA ports shall be provided.
13. One Model 400 internal modem shall be supplied for each controller to provide for communications between controllers. If a master controller is specified, a Hayes compatible Dial-up modem, designated for plug-in compatibility with Type 170 series Traffic Controllers, shall be supplied for communications between the master and a central office computer over standard lease or dial-up telephone lines.
14. All components supplied shall be on CalTrans Qualified Product Listing and operate successfully with MultiSonics OSAM and BITrans 233 software (McCain).
15. Each cabinet shall include 2 fluorescent lighting fixtures mounted inside the front and back portion of the cabinet. These fixtures shall include a cool white lamp with protective cover and shall operate by a normal power UL listed ballast. Two door actuated switches shall be installed to turn on the cabinet light when the door is open, front door front light back door back light. Each switch should work each individual light.
16. Each cabinet shall be provided with devices to protect the control equipment form surges and over voltages. This shall include incoming power lines, the Input File, the Output File, and communication lines.

All inductive loop detector inputs shall be protected with a 30V MOV with (30 Joule Rating)

P/n ERZ-C20 KE 470 or equal. The output of all load switch outputs shall be protected with a 150V MOV (80 Joule Rating). P/n ERZ-C20 DK 241U or equal. The MOVs shall be connected from the AC positive field terminal to the chassis ground.

For the 332A cabinet, appropriate input surge protection shall be mounted on the Lower Input Termination Panel (LIP). The power distribution assembly (PDA#2) of each controller cabinet shall include a surge protection unit on the AC Service Input. The protector shall be installed between the applied line voltage and earth ground. The surge protector shall be capable of reducing the effect of lightning transient voltages applied to the AC line. The protection device shall be a two stage series parallel device. It shall include the following features and functions:

- a. Maximum AC line voltage: 140 VAC.
- b. Twenty pulses of peak current, each of which will rise in 8 microseconds and fall in 20 microseconds to 1/2 the peak: 20,000 Amperes.
- c. The protector shall be provided with the following terminals:
  - 1) Main line (AC line first stage terminal).
  - 2) Main Neutral (AC Neutral input terminal).
  - 3) Equipment Line Out (AC Line second stage output terminal, 10 Amps.).
  - 4) Equipment Neutral Out (Neutral terminal to protected equipment).
  - 5) GND (Earth connection).
  - 6) The Main AC line in and the Equipment Line out terminals shall be separated by a 200 Microhenry (minimum) inductor rated to handle 10 Amp AC Service. The first stage clamp shall be between Main Line and Ground terminals.
  - 7) The second stage clamp shall be between Equipment Line out and Equipment Neutral.
  - 8) The protector for the first and second stage clamp must have a MOV or similar solid state device rate at 20 KA and be of a completely solid stage design (i.e., no gas discharge between tubes allowed).
  - 9) The Main Neutral and Equipment Neutral Out shall be connected together internally and shall have an MOV similar solid state device or gas discharge tubes rated at 20 KA between Main Neutral and Ground terminals.
  - 10) Peak clamp voltage: 350 Volts at 20 KA (Voltage measured between Equipment Line Out and Equipment Neutral Out terminals. Current applied between Main Line and Ground Terminals with Ground and Main Neutral terminals externally tied together.). Voltage shall never exceed 350 volts.
  - 11) The Protector shall be epoxy encapsulated in a flame retardant material.
  - 12) Continuous service current, 10 Amps at 120 VAC RMS.
  - 13) The Equipment Line Out shall provide power to the Type 170 and to the 24 V power supply.
  - 14) Provide communications line protector with a mounting connector for incoming and outgoing communication line.

B. Manufacturers: The controller units, cabinets, and auxiliary control equipment furnished under this specification shall be from a manufacturer whose Type 170 Controller System has been approved and purchased by either the State of California or the State of New York. The Engineer may allow exceptions to this requirement provided that the equipment to be furnished has been successfully operated on the street by a public agency for more than one year and has been certified by an independent testing laboratory as meeting the requirements of Chapter 1, Section VIII, U.S. Department of Transportation, Publication FHWA-IP-78-16.

C. Software: The software for this project will be provided by the Engineer. The Contractor shall supply two blank 27256 PROM chips per controller.

- D. Operational Modifications: When specified on the Plans, the following operational modifications shall be made by the equipment manufacturer through either software changes to the "Local Intersection Program," through hardware changes, or as determined by the manufacturer. Any changes to the software or hardware not already detailed on the Plans shall receive approval of the Engineer prior to implementation.
1. For those locations providing for protected/permissive display of the left turn indication, the operation shall be such that the protected left turn arrow is displayed only when there are a sufficient number of left turning vehicles queued to actuate the left turn phase calling detector. In the absence of left turn phase detector actuations, left turn demand is to be accommodated by displaying only the circular green permitting a permissive left turn to be made.
- E. Auxiliary Control Equipment:
1. Cabinets shall be furnished with all necessary auxiliary control equipment to properly operate eight signal phases and four pedestrian phases, which includes conflict monitor unit, isolation modules, detector sensing units as specified on contract documents, and load switch packs.
  2. A heavy-duty clear plastic envelope, minimum dimensions of 9 inch x 12 inch, shall be attached inside the cabinet for storing timing and maintenance records, electrical prints, etc.
- F. Certification: In addition to the testing certification required in Chapter 1, Section VIII "Electrical, Environmental and Testing Requirements," paragraph 6, the Engineer shall be furnished with a certification from the equipment manufacturer or supplier stating that the equipment furnished under this specification complies with all provisions of this specification. With prior approval of the Jurisdictional Engineer, minor exceptions to this specification may be allowed, provided these exceptions are detailed on the certification.
- G. Warranty: All Type 170 Controllers and auxiliary equipment furnished under this specification shall be provided with a standard industry warranty. Any parts found to be defective shall, upon concurrence of the defect by the manufacturer, be replaced free of charge.
- H. Manufacturer or Supplier: A representative from the manufacturer and/or supplier of the Type 170 Controllers shall be at the project site when the controllers are ready to be turned on, to provide technical assistance including, as a minimum, programming of all necessary input data. All required signal timing data shall be provided by the Engineer.

A minimum of one week prior to the scheduled "turn-on", the Contractor or supplier shall deliver the controller(s), (not including the cabinets), to the Traffic Signal Shop located at 2000 SE Scott. Since staff are not always present at this shop, it is the responsibility of the deliverer to call Mark Dakovich at (515) 208-1489 to schedule delivery.

The City of Des Moines will install and verify the specified software and timings. Should any controllers be found faulty at the shop, the person/company who delivered the equipment will be contacted. The Signal Shop is not responsible for trouble shooting this equipment nor is any part of this process intended to replace "burn-in" responsibilities of the manufacturer.

The Contractor/Supplier is responsible for picking up the controller(s) from the Signal Shop and is solely responsible for bringing the controller(s) to full operation at the intersection(s). No assistance will be provided by the Signal crew once the software is working correctly and the signal timings have been verified in the Signal Shop. Having a knowledgeable representative at the project site(s) when the controller(s) is ready to be turned on is paramount to the safety and efficiency of this operation.

The conflict monitor unit shall be capable of ignoring the watchdog and placing intersection in flash if line voltage is less than 98 (+/-2) VAC RMS.

## 4.2 FIBER OPTIC DATA LINK OR ETHERNET CARD

### A. Fiber Optic Data Link

When specified in the plans, a fiber optic data link shall be provided. It shall be of the type that will install in Type 170 controller chassis and provide a dual mode, double duplex, multi-drop communications link designed to interconnect traffic control equipment. Data links shall include the following functional requirements:

1. Master or Local operation mode set by board mounted switch.
2. Two sets of front mounted fiber optic receptacles with ST type connectors.
3. Accommodate 850nm, Multimode fiber optic cable.
4. Complies with 170 and NEMA Environmental specifications.
5. Includes a rechargeable NiCad battery backup to maintain communications in case of power disruption. Battery assembly shall be secured to board and charge circuit shall be built in.
6. Expansion port, which will allow for up to two additional fiber optic ports for directional branching of communication circuits.
7. Status LED's which provide visual signal indicators associated with communications between the modems and can be easily viewable by a maintenance technician. Signals displayed shall include:
  - a. Transmit Data 1 (TD-1)
  - b. Receive Data 1 (RD-1)
  - c. Transmit Data 2 (TD-2)
  - d. Receive Data 2 (RD-2)
  - e. Power (PWR)
  - f. Built-In Test Fail (Fault)

### B. Ethernet Card

When specified in the plans, an internal 170 Ethernet Card shall be provided to allow for Ethernet connection via the City's network. It shall be of the type that will install in a Type 170 controller chassis, connecting via RJ45 cable to an Ethernet switch located elsewhere within the controller cabinet. It shall include the following functional requirements:

1. Network interface to provide the following:
  - a. 10Base-T/100Base-TX Ethernet Connection
  - b. RJ45 connector
  - c. Protocols: TCP/IP, UDP/IP, ARP, SNMP, TFTP, Telnet, DHCP, BOOTP, HTTP, and AutoIP
2. Serial interface to provide the following:
  - a. 300 to 230, 400 bps data rate
  - b. 7 or 8 data bit characters
  - c. Parity – odd, even, none
  - d. Stop bits: 1 or 2
  - e. Control Signals: RTS/DCD, CTS

- f. Flow Control: XON/XOFF, RTS/CTS
- 3. Temperature hardened (-40°C to 75°C)
- 4. Password protection with 256 bit AES encryption for secure communications
- 5. Power requirements to be +12 volts and 12 volts  $\pm 5\%$  @A 75mA
- 6. Embedded webserver
- 7. E-mail alert capability
- 8. Full TCP/IP protocol stack
- 9. Provide two serial ports that communicate via a single communications channel. The host Interface connects through the card edge to the local controller. The Auxiliary Port utilizes a DB9 connector and can be used to bring copper or wireless communications into the main data stream. The Auxiliary Port is to be switch selectable, so that it can operate as either a DCE or DTE interface. IN DCE mode, it will operate in parallel with the Host interface, and can be used to configure the Etherport via a PC terminal program. In DTE mode, it will provide an external interface for the host which can be connected to another DCE device such as a FSK modem. Full "handshaking" is to be provided to facilitate interoperability across different transmission systems.
- 10. Management shall be SNMP, Telnet, serial, internal Web server, and Microsoft Windows®-based utility configuration.
- 11. Indicators shall be provided to show 10Base-T connection, 100Base-T connection, and link & activity-full/half duplex.

C. Ethernet Switch

When specified in the plans, a Gigabit Ethernet hardened field switch shall be provided. The switch shall be construction for modular port configuration housed in a high strength metal enclosure designed for DIN-Rail mounting and convection cooling. Nominal dimensions 1.75 inches H x 8.75 inches W x 10.0 inches D and weigh less than 4.75 lbs. The standard configuration will be with (4) 10/100 copper ports and (2) Gigabit singlemode fiber ports with one spare GBIC slot for future growth. Power input shall be AC. Manufactured in United States and Warranted for 3 years from day of contract acceptance for all parts and labor.

Additionally the Ethernet Switch shall provide:

- a. Two modular slots for user selection of 100Mb and 10MB fiber ports, Gigabit fiber ports, 10/100 copper ports, and PoE. Up to a maximum of 16 ports.
- b. Relay contacts for external "Alarm" monitoring of internal power, and of selected software operations. Form C, one NC indicating internal power, one NC software controllable.
- c. SNMP, rich commands including access control
- d. SNMPv3 for encrypted authentication & access security
- e. RMON with statistics, history, alarms and events

- f. GUI with Hubview/Bitview support
- g. CLI with multi-level password security
- h. VLANs, Port-based, Tag-based, with GVRP
- i. Spanning Tree Protocol, 802.1w
- j. LACP Link Aggregation Control Protocol, 802.3ad
- k. Rapid Spanning Tree Protocol, 802.1d
- l. Link-Loss-Learn (LLL) for fast switch buffer flush
- m. Ring Redundancy software available for sub-second recovery of ring faults
- n. QoS, multi-level 802.1p, ToS and DiffServ
- o. IGMP Snooping and multicast pruning
- p. Telnet, both client and server support
- q. Secure Web Management with SSL Secure Sockets Layer and TLS Transport Layer Security protocol support
- r. Port Security, controlled access by MAC address, support of 200 MAC addresses for port security
- s. Port mirroring for selective traffic analysis
- t. Event Log for the 1000 most recent events
- u. Port Settings Control, copper and fiber ports
- v. SMTP provides email alerts of traps and event
- w. SNTP with world-wide time zones
- x. Radius server and TACACS+ Terminal Access Controller Access Control System
- y. IP support for SNMP both TCP/IP and UDP/IP
- z. Passive or active FTP and TFTP for load/save convenience
- aa. CLI Script method supported for ease of upgrading multiple switches
- bb. BootP/DHCP for auto configuration
- cc. Back pressure and flow control option per
- dd. Temperature rating of  $-40^{\circ}\text{C}$  to  $75^{\circ}\text{C}$  and NEMA TS2 certified, or  $-50^{\circ}\text{C}$  to  $95^{\circ}\text{C}$  by the IEC 60068 Type Test method
- ee. Store and Forward with IEEE 802.3x full-duplex flow control. All ports non-blocking. System aggregate forward and filter rate 6.0 Mpps.

- ff. Address table: 4K nodes, with address aging time of 155 seconds typical
- gg. Latency:  $6\mu\text{s}$  + packet time max (TX – TX, TX – FX, FX – FX, TX-G, G-G)
- hh. MTFB of greater than 10 years calculated via Telcordia Bellcore method and/or MilStd Handbook 217

#### 4.3 VEHICULAR TRAFFIC SIGNAL HEADS

The purpose of the specification is to describe minimum acceptable design and operating requirements for vehicular traffic signal heads with either 8 inch or 12 inch diameter lens openings, including all fittings and brackets as specified on the Plans.

- A. Main body Assembly: Each section shall be complete with a one-piece, hinged door with water tight gaskets and two stainless steel locking devices. The hinged pins shall be designed so that the doors may be easily removed and reinstalled without use of special tools.

The optical system shall be so designed as to prevent any objectionable reflection of sun rays even at times of the day when the sun may shine directly into the lens. When the door of the optical unit is closed, all joints in the assembly between the interior and exterior of the reflector shall be closed against suitable gaskets in order that the units may be double dust-tight. Between the door and the lens, there shall be a neoprene gasket securely fastened around the outer surface of the lens, said gasket to be engaged by the rim of the reflector holder when the door is closed to render the union between the reflector holder and the door assembly dust-tight.

Each polycarbonate lens shall have a tunnel visor not less than 8 inches in length and designed to shield each lens. Polycarbonate tunnel visors shall have a minimum thickness of 0.1 inch.

The reflector holder shall be designed to separately support the reflector and socket in proper relation to the lens. The reflector holder shall either be hinged to the left-hand side of the signal body when viewed from the front with the right-hand side held in place by a spring catch or other quickly releasable means, or the reflector shall be mounted in a manner that does not require it to be removed from its normal position during bulb replacement. Both the hinge device and the spring catch or equivalent shall be of a flexible nature which will permit the reflector holder to be pushed inwardly for at least 1/16 inch to align itself correctly with the lens when the door of the optical unit is closed and pressed against the rim of the reflector holder. By such means, the joint between the reflector holder and the lens shall be rendered dust-tight. It shall not be necessary to remove any screws or nuts in order to swing the reflector holder out of the body section to obtain access to the light socket. The reflector shall be Alazak treated aluminum or an approved equal. Glass is not acceptable. The reflector assembly shall be interchangeable and shall be designed so that it can be easily removed without the use of tools.

The lamp receptacle shall be fixed focus type, positioning the lamp filament at the correct focal point in respect to the reflector. The assembly shall be designed so that the lamp socket can be rotated through 360 degrees and eight positions of adjustment for proper positioning of the lamp filament after relamping the signal. The lamp socket shall be equipped with color coded wire, either red, yellow, or green, depending upon the lens color of the section. The socket wires shall be a minimum of 26 inches long, composed of wire with insulation designed to withstand 221°F. The wiring leads shall be terminated with spade lugs for ease of connection to terminal block. The socket shall be equipped with a gasket to insure a dust-tight fit between socket and reflector.

- B. Specialized Options: All screws, latching bolts, and hinge pins shall be stainless steel to prohibit rust and corrosion.

One section of the three-section signal shall be equipped with a six position terminal block for termination of field wiring. Each five-indication signal shall be equipped with an eight (8) position terminal block.

All vehicular signal head housing shall be of the black polycarbonate type. The inside of visor shall be flat black. The black color shall be permanently molded into the components. The doors of the polycarbonate sign shall also be black.

Construct backplates of two piece durable black plastic capable of withstanding a 100 M.P.H wind.

C. Traffic Signal Mounting Brackets:

All overhead mounted signal heads shall have backplates. The traffic signal mounting bracket be an articulated serrated bracket assembly that includes top and bottom signal mounting brackets and provides a rigid-mount for the traffic signal head. It shall include internal wiring capability, and three axes of traffic signal adjustment, as well as vertical height adjustment. All necessary hardware for complete installation on a mast arm shall be included. The mounting assembly shall be of a cable type.

When a tenon-mount is indicated, the assembly shall be capable of mounting over a standard 2-inch Schedule 40 galvanized pipe tenon that extends 4 inches from the mast arm. A locking bolt shall be incorporated to secure the bracket to the tenon.

When a midpoint clamp bracket is specified, the assembly shall include mounting equipment including a stainless steel cable and hardware that allows the bracket to be securely tightened by means of a threaded nut around an existing mast arm.

#### 4.4 PEDESTRIAN SIGNAL HEADS

The purpose of this specification is to describe minimum acceptable design and operating requirements for one-section, pedestrian traffic signal heads with "Hand" and "Walking Person" symbol messages to include all fittings and brackets, as specified on the plans. Pedestrian signal heads shall meet the requirements outlined in them most recent ITE specifications for LED pedestrian traffic signal control heads.

- A. General Construction: The general construction shall include a single piece cast aluminum or polycarbonate housing, a single piece double parabolic reflector, a 3-line two color message lens, a single piece cast aluminum or polycarbonate swing down door frame, a blankout sun visor, LED modules, and other hardware.

All LEDs shall be rated for 100,000 hours or more (@ 77°F and 30 mA).

The individual symbols shall each be a minimum of 12 inches in height and 7 inches in width. Message configuration color and size shall be ITE Equipment Standard "Pedestrian Traffic Signal Control Signal Indications" most recent version. Internal illumination shall be provided by an LED module without transformer.

Optically, the pedestrian signal shall be capable of displaying, brightly and uniformly, the alternate messages "Hand" symbol in portland orange and "Walking Person" symbol in white. When subjected to strong ambient light conditions, the messages shall "blankout" when the signal is not energized. The signal shall be furnished with the LED module and hardware. The signal shall be designed so that all components are readily accessible from the front by merely opening the signal door.

- B. Main Body Assembly: The housing shall be one piece corrosion resistant aluminum alloy die casting or polycarbonate complete with intergrally cast top, bottom, sides, and back. Four integrally cast hinge lug pairs, two at the top and two at the bottom of each case. The case, when properly mated to other pedestrian signal components and mounting hardware shall provide a dustproof and weatherproof enclosure and shall provide for easy access to and replacement of all components.

The door frame shall be one piece corrosion resistant aluminum alloy die casting or polycarbonate, complete with two hinge lugs cast at the bottom and two latch slots cast at the top of each door. The door shall be attached to the case by means of two ASTM A193, Type 304 stainless steel spring pins. Two stainless steel hinged bolts with captive stainless steel spring pins. Latching or unlatching the door shall require no tools.

Each signal shall be provided a sun visor designed to eliminate sun phantom.

The optical system shall be designed so as to minimize the return of outside rays entering the unit from above horizontal (sun phantom). The optical system shall consist of; a three-line two color message lens, a double parabolic reflector, LED modules, and a sun visor. The inside face of each message section shall be silkscreened with a transparent coating of an appropriate color in the word message areas to produce a portland orange "Hand" symbol and an white "Walking Person" symbol when illuminated by LED traffic signal lamp operating at rated voltage. The entire background shall be a fired ceramic mask, black in color.

- C. Specialized Options: All screws, latching bolts, and hinge pins shall be stainless steel to prohibit rust and corrosion.

Prior to final assembly, the case, door frame, Clamshell mounting, and visor (aluminum portion only) shall be thoroughly cleaned and then etched with an iron phosphate solution. An appropriate chemical sealer shall then be applied with a top grade T.G.I.C. polyester powder then being electrostatically applied and oven baked. The housing shall be black with the visor being black.

- D. Miscellaneous Requirements: The pedestrian heads shall be constructed of the highest quality materials. High-grade workmanship shall be used throughout. Each head shall have a smooth surface both inside and outside and shall contain no sharp fins or sharp projections of any kind.

All components of the vehicular traffic signal heads furnished under this specification shall comply with the latest Institute of Transportation Engineers Standards on Adjustable Face Vehicle Traffic Control Signal Heads.

- E. Certification: The Engineer shall be furnished with a certification from the manufacturer of the pedestrian head that the equipment furnished under this specification complies with all provisions of this specification. If there are any items which do not comply with this specification, a list of those exceptions must be detailed on the certification.

- F. Countdown Pedestrian Indicator: The countdown pedestrian indicator unit shall fit in a traditional 16 inch X 16 inch pedestrian signal head housing. The unit shall display a digital numerical count in addition to the graphic display to show how much time remains to clear the intersection. The unit shall be able to monitor the timing sequence from the traffic signal controller and adjust the countdown to match the "WALK" and flashing "DON'T WALK" time intervals without the need for any additional adjustments to the settings of the unit. The unit shall automatically learn any new sequences and adjust its countdown accordingly.

The unit shall be set at the factory to operate in the "clearance countdown" option that counts down during the flashing "DON'T WALK" time interval only. The countdown shall start with the digital display in the blinking mode at the same time the graphic hand is displayed in blinking mode. The digital display shall finish counting down at the same instance that the hand is displayed in non-blinking mode. The digital countdown shall remain off through the walk interval until the controller once again displays the graphic hand in blinking mode.

To accommodate the emergency and manual preemption, the unit shall compare each countdown interval to the one prior to it. When the intervals are not equal, the unit shall blank out the countdown digits and the traffic signal controller shall then mandate what indicator is displayed.

#### 4.5 ALUMINUM TRAFFIC SIGNAL PEDESTALS

The purpose of this specification is to describe minimum acceptable design, material, and fabrication requirements for aluminum traffic signal pedestals and/or aluminum shafts.

- A. Construction: The pedestal base shall be cast-aluminum, square shape to maximize working area, with a handhole. The size of the handhole shall be at least 4 inches by 6 inches and equipped with a cover which can be securely fastened to the shaft with the use of simple tools. Bases shall have a minimum weight of 20 pounds and shall have a 4 bolt pattern uniformly spaced on a 13 3/4 inches diameter bolt circle. Poles with shaft lengths greater than 10 feet shall be supplied with a base collar. The exterior of the base shall be smooth and have a neat appearance. The top of the base shall be threaded to receive a standard aluminum shaft as described in Section C below.
- B. Anchor Bolts: Four, 3/4 inch by 15 inch hot rolled steel anchor bolts shall be supplied, complete with all hardware required for installation. The anchor bolts shall have a right angle bend at the bottom end and be hot dip galvanized at the threaded end.
- C. Pedestal Shafts: The length of the shaft shall be as specified in the plans or bid documents. The shaft shall be fabricated from aluminum alloy 6063-T6, ASTM B209 or approved equal, Schedule 40 (wall thickness not less than 0.23 inches, and shall have a satin brush or spun finish. The shaft shall have an outer diameter of 4 1/2 inches.

The top of the shaft shall be designed to receive a pole-top mounting bracket for a traffic signal head or a pedestal-mounted traffic signal controller, while the bottom of the shaft shall be threaded to screw into a standard cast-aluminum pedestal base as described in Section A above.

The fabricator shall certify that the pedestals are capable of withstanding winds up to 80 MPH with a 1.3 gust factor without failure.

#### 4.6 GALVANIZED STEEL TRAFFIC SIGNAL SUPPORTS

The purpose of this specification is to describe minimum acceptable design, material, and fabrication requirements for galvanized steel traffic signal supports.

- A. Construction: The mast arms shall be of the length specified and shall be designed to support traffic signals and/or signs as shown on the plan. All mast-arms shall have a 4 percent rise when in-place and fully loaded.

All mast arms exceeding 40 feet in length shall be provided with a dampening plate. Dampening plate shall be installed per manufacturer's instruction.

Poles shall be manufactured in accordance with the requirements of the latest Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals as approved by the American Association of State Highway and Transportation Officials.

The mast arms and support poles shall be tapered, round, steel poles of the transformer base type. Mast arms shall be continuous to 50 feet in length. Vertical pole configuration shall provide for two-piece combination pole with internal tapped plate connection to allow for addition or removal of luminaire pole extension. The poles shall be fabricated from low carbon (maximum carbon 0.30%) steel of U.S. Standard gauge.

After manufacture, they shall have a minimum yield strength of 55,000 PSI. The base and flange plates shall be of structural steel conforming to AASHTO M 183 (ASTM A 36) and cast steel conforming to ASTM A 27, Grade 65-35 or better. It shall not be permissible to fabricate poles and mast arms by welding two sections together.

Welding and fabrication shall conform to the Structural Welding Code AWS D1-180, as modified

by AASHTO 1981 Standard Specifications for Welding of Structural Steel Highway Bridges. Longitudinal butt welds, shall have a minimum 60 percent penetration for plates 3/8 inch and less in thickness, and minimum of 80 percent penetration for plates over 3/8 inch in thickness.

Personnel performing nondestructive testing shall be qualified in accordance with the American Society for Nondestructive Testing Recommended Practice No. SNT-TC-1A and applicable Supplements B (Magnetic Particle) and C (Ultrasonic). Evidence shall be presented for approval of the Engineer, concerning their qualifications. A report shall be required showing that welds have been inspected and either found satisfactory or found unsatisfactory but repaired and reinspected and found satisfactory. The cost of all nondestructive testing shall be paid by the Contractor and shall be considered incidental to the traffic signal installation.

The mast arms and pole assemblies shall be galvanized inside and out in accordance with ASTM A 123, latest revision.

The pole shall be equipped with a minimum 8 inch x 12 inch handhole and cover located in the transformer base of the pole. Securing of the cover to the base shall be done with the use of simple tools. Hardware shall be corrosion resistant.

Where a combination street lighting/signal pole is specified on the plans, the luminaire arm is to be mounted in the same vertical plane as the signal arm unless otherwise indicated on the plans. The luminaire arm type shall be a single member tapered type arm. The pole shall be equipped with a minimum 4 inch x 6 inch handhole and cover located opposite the signal mast arm.

The mast arms and poles shall be equipped with all necessary hardware, shims and anchor bolts to provide for a complete installation without additional parts. The anchor bolts shall meet the requirements of ASTM A 36 or better and be hot dip galvanized for a minimum of 12 inches on the threaded end.

The anchor bolts shall be threaded a minimum of 6 inches at one end and have a 4 inch long, 90 degree bend at the other end.

The fabricator shall certify that the mast arms and pole assemblies are capable of withstanding winds up to 80 MPH with a 1.3 gust factor without failure; that only certified welding operators in accordance with AWS D1.1-80 or latest revisions were used; and that only electrodes as modified by AASHTO 1981 Standard Specifications for Welding of Structural Steel for Highway Bridges were used.

Erect poles so as to be vertical under normal load, with mast arms oriented at 90 degrees to the curb line. Securely bolt bases to the cast-in-place concrete foundations.

After leveling the poles, expansive type grout shall be troweled between the pole base and the foundation for gaps of 1 inch or greater. Exposed edges of grout shall be neatly finished. Place a weep hole in the grout.

Ground each pole by installing a No. 6 AWG bare copper ground wire between the pole and the ground rod at the foundation.

If the painted or galvanized surface of any equipment is damaged in shipping or installation, such equipment shall be retouched or repaired in a manner satisfactory to the Engineer.

#### **4.7 PEDESTRIAN PUSH-BUTTON DETECTORS**

The purpose of this specification is to describe minimum acceptable design and operating requirements for side-of-pole mount, pedestrian push-button detectors, including all fittings and brackets as specified on the plans.

- A. Construction: Pedestrian push-button detectors shall be of the direct push type without levers, handles, or toggle switches. Each detector shall consist of a solid state electronic switch with no moving plunger or moving electrical contacts. The case shall have one outlet for a 1/2 inch pipe. The operating button shall be made of stainless steel and shall be of sturdy design. This button shall not protrude out from the case. The entire assembly shall be weather tight, secure against electrical shock and of such construction as to withstand continuous hard usage. The contact shall be normally open and no current flowing except at the moment of actuation. The push-buttons supplied shall be ADA accessible push button assembly with momentary LED indicator. The push-button casing shall be black in color, oval with a raised directional arrow.
- B. Certification: The Engineer shall be furnished with a certification from the manufacturer of the detectors that the equipment furnished under this specification complies with all provision of this specification. If there are any items which do not comply with this specification, a list of those exceptions must be detailed on the certification.
- C. Audible Pedestrian Pushbutton: Pushbutton assembly shall be black in color, have an integrated R10-3b pushbutton sign and ADA compliant pushbutton with raised directional arrow. The pushbutton shall provide an LED light which lights when the button is pushed. Pushbutton shall provide the options of sounds during the clearance interval, direction of travel messages, and special messages determined by the user.

## PART V POLE FINISH

### 5.1 GENERAL

This section specifies requirements for coating systems for certain items on the project; including light poles, light pole mast arms, and luminaires.

### 5.2 SURFACE PREPARATION

Prior to being incorporated into an assembled product, steel plates 3/4 inch or more in thickness shall be blast cleaned to removed rolled-in mill scale, impurities and non-metallic foreign materials. After assembly, all weld flux shall be mechanically removed. The iron or steel product shall be degreased by immersion in an agitated 4.5%-6% concentrated caustic solution elevated to a temperature ranging from 150 to 190°F. It shall then be pickled by immersion in a heated sulfuric acid solution of 6%-13% concentration, with a controlled temperature between 150 - 190°F. It shall next be rinsed clean from any residual effects of the caustic or acid solutions by immersion in a circulating fresh water bath. Final preparation shall be accomplished by immersion in a concentrated zinc ammonium chloride flux solution heated to 130°F. The solution's acidity content shall be maintained between 4.5-5.0 pH. The assembly shall be air dried to remove any moisture remaining in the flux coat and/or trapped within the product.

### 5.3 ZINC COATING

The product shall be hot-dip galvanized to the requirements of either ASTM A 123 (fabricated products) or ASTM A 153 (hardware items) by immersion in a molten bath of prime western grade zinc maintained between 810-850°F. The entire product shall be totally immersed with no part of it protruding out of the zinc (no double dipping). This is to limit a risk of trapped contaminates containing chlorides and reduce the risk of bare spots (bare spots can occur when flux on the steel surface is burned away by heat of the first dip). Maximum aluminum content of the bath shall be 0.01%. Flux ash shall be skimmed from the bath surface prior to immersion and extraction of the product to assure a debris free zinc coating.

### 5.4 EXTERIOR COATING

All galvanized exterior surfaces shall be coated with a Urethane or Triglycidyl Isocyanurate (TGIC) Polyester Powder to a minimum film thickness of 0.002 inch. Prior to application, the surfaces to be powder coated shall be mechanically etched by brush blasting (Ref. SSPC-SP7) and the zinc coated substrate preheated to 450°F for a minimum of one hour in a gas fired convection oven by heating the zinc coated substrate to a minimum of 350°F and a maximum of 400°F. The thermosetting powder resin shall provide both intercoat as well as substrate fusion adhesion that meets 5A or 5B classifications of

ASTM D 3359.

**5.5 QUALITY CONTROL**

The galvanizing and powder coating facilities shall be owned and operated by the pole manufacturer to ensure a quality coating system.

**5.6 PACKAGING**

Prior to shipment, small poles shall be wrapped in 0.188 inch thick Ultraviolet-inhibiting plastic backed foam. Larger poles shall be cradled in a 1.0 inch rubberized foam base.

**5.7 FIELD REPAIR PROCEDURES**

Where factory applied coatings have become damaged or abraded due to handling, transport, installation, welding or other circumstances, they shall be repaired by the field painting crew or miscellaneous metal contractor.

All damaged areas shall be thoroughly wire brushed. All dirt, oil, grease, or other contaminants shall be removed in accordance with SSPC-SP1 and SP5. Touch-up paint supplied the galvanizer or steel fabricator, identical in color and composition to that used in the plant, shall be applied to all prepared surfaces to a dry film thickness of at least 4.0 mils.

**5.8 METHOD OF MEASUREMENT AND BASIS OF PAYMENT**

Combination Coating – Galvanized-Powder Top Coat shall be considered incidental to the price bid per each pole and shall be considered incidental to the lump sum bid for the traffic signal system.

**6.1 SCHEDULE OF UNIT PRICES**  
**Hickman Road Widening. 63rd St. to Westover Blvd.**  
**Activity ID: 14-2011-045**  
**Iowa DOT Project No: STP-A-006-41(149)--86-77**

ITEM	UNIT	TOTAL QUANTITY	UNIT COST	EXTENSION
8 Phase Controller, Cabinet, and Accessories	EACH	2		
Controller Cabinet Riser	EACH	2		
Pedestrian Pushbutton with Sign	EACH	14		
2 ch. Inductive Loop Detector - Card Rack	EACH	27		
12" R, Y, G, Y arrow, G arrow w/backplate, mast arm mount	EACH	1		
12" R, Y, G, Y arrow, G arrow, SOP	EACH	2		
12" R arrow, Y arrow, Y arrow, G arrow w/backplate mast arm mount	EACH	3		
12" R arrow, Y arrow, G arrow w/backplate mast arm mount	EACH	2		
12" R, Y, G w/backplate, mast arm mount	EACH	13		
12" R, Y, G side of pole mount	EACH	6		
16" Hand/Walking Person with Countdown Timer	EACH	14		
Type I	EACH	15		
Type II	EACH	1		
Type III	LIN FT	7		
Signal - 16c #14	LIN FT	1107		
Signal - 7c #14	LIN FT	300		
Signal - 5c #14	LIN FT	1259		
Signal - 2c #14	LIN FT	2062		
Detector - 1c #14 Loop	LIN FT	5372		
Detector - 2c #14	LIN FT	9240		
Power - 1c #6	LIN FT	459		
Ground - 1c #6	LIN FT	1364		
Tracer - 1c #10 - Orange	LIN FT	5066		
Tracer - 1c #10 - Yellow	LIN FT	757		
Luminaire - 1c #10	LIN FT	714		

**6.1 SCHEDULE OF UNIT PRICES**  
**Hickman Road Widening. 63rd St. to Westover Blvd.**  
**Activity ID: 14-2011-045**  
**Iowa DOT Project No: STP-A-006-41(149)--86-77**

Luminaire - 1c #8	LIN FT	1514		
Pull Rope	LIN FT	5408		
Video Cable	LIN FT	112		
Fiber - 12 Single Mode	LIN FT	1561		
Detector Sawcut	LIN FT	198		
1" PVC, trenched	LIN FT	2212		
3" PVC, pushed	LIN FT	5411		
Controller Cabinet Footing	EACH	2		
3' dia. X 8' depth	EACH	2		
3' dia. X 10' depth	EACH	4		
3' dia. X 12' depth	EACH	3		
Signal Mast Arm - 42'	EACH	1		
Signal Mast Arm - 44'	EACH	1		
Combination Signal/Lighting Mast Arm - 35'	EACH	2		
Combination Signal/Lighting Mast Arm - 45'	EACH	2		
Combination Signal/Lighting Mast Arm - 52'	EACH	2		
Combination Signal/Lighting Mast Arm - 54'	EACH	1		
L-1 Connector	EACH	18		
Y-1 Connector	EACH	10		
Traffic Sign - 30" x 36", R3-5L	EACH	9		
Traffic Sign - 30" x 36", R3-5R	EACH	1		
Traffic Sign - 30" x 36", R10-10	EACH	1		
Street Name Sign - 18" x varies	EACH	8		
Locate Box	EACH	2		
Traffic Camera and accessories	LS	1		
Fiber Closet with fiber terminations	EACH	2		

**6.1 SCHEDULE OF UNIT PRICES**  
**Hickman Road Widening. 63rd St. to Westover Blvd.**  
**Activity ID: 14-2011-045**  
**Iowa DOT Project No: STP-A-006-41(149)--86-77**

Fusion Splices	EACH	36		
TOTAL SIGNALIZATION COST				



**SPECIAL PROVISIONS  
FOR  
CLOSED CIRCUIT TELEVISION (CCTV) CAMERA SYSTEM**

**Polk County  
STP-A-006-4(149)--86-77**

**Effective Date  
May 17, 2011**

**THE STANDARD SPECIFICATIONS, SERIES 2009, ARE AMENDED BY THE FOLLOWING MODIFICATIONS AND ADDITIONS. THESE ARE SPECIAL PROVISIONS AND THEY SHALL PREVAIL OVER THOSE PUBLISHED IN THE STANDARD SPECIFICATIONS.**

The Contractor shall ensure that all elements of the Closed Circuit Television (CCTV) Camera System are operational and function as intended, both in the field and in the Traffic Operations Center (TOC). The CCTV Camera System Specification may include field equipment as well as TOC equipment, hardware, software, and integration components.

The City of Des Moines (City) will provide IP addresses to the Contractor to be used for the CCTV cameras and traffic signal controllers. The City will also provide direction for connecting the new fiber optic system to the City's existing system.

**PART 1 - DESCRIPTION**

The CCTV Camera System shall comply with rules and regulations of the City of Des Moines, Department, and Federal Communications Commission (FCC). Proposed locations for CCTV camera equipment installation are shown on the Plans.

The new CCTV camera at each location will be located on an existing or new traffic signal pole, light pole, or traffic signal truss structure as shown on the plans. CCTV data and video transmission between the TOC and the CCTV camera system locations will be via a fiber optic cable, Ethernet communications system. The video and data shall be transmitted from the CCTV camera to a hardened one-channel MPEG video/data encoder to the Ethernet switch located in the traffic signal controller cabinet, to the Gigabit Ethernet switch at the communication hub for transmission to the City of Des Moines TOC.

The CCTV camera system shall be compatible and fully functional with the City's existing camera management system, which is Cameleon (Version 4) by the "360 Surveillance" Company. The Contractor shall update the existing CCTV camera management system to include the new camera locations that are being installed as part of this project.

The CCTV cameras and encoders shall be provided by the same vendor and shall be developed specifically for traffic management applications. They shall be compatible and fully functional with the City's existing camera system.

The Contractor will be responsible for incidental accessories necessary to make the CCTV camera system complete, fully functional, and ready for operation, even if not particularly specified. Such incidentals shall be furnished, delivered, and installed by the Contractor without additional expense to the City. Minor details not usually shown or specified, but necessary for the proper installation and operation of the CCTV camera system, shall be included in the work and in the Contractor's price bid. It is understood and agreed by the Contractor that the system description provided in this specification is complete and includes all equipment necessary for the proper functioning of the CCTV camera system, even though every item may not be specifically mentioned.

**1.1 General Requirements**

1. Contractor shall furnish all components of the CCTV camera system, including the dome CCTV cameras, hardened one-channel video and data MPEG encoders, integrated CCTV video/data cable, mounting hardware, and rack-mounted, hardened encoders for the field to ensure a fully-operational system.
2. Contactor shall furnish and install all necessary miscellaneous equipment and cabling to make the CCTV camera systems operational, including power to the CCTV camera systems, and connection to the communications equipment.
3. All equipment and materials used shall be standard components, regularly manufactured, and regularly utilized in the manufacturer's system.
4. Contractor shall integrate all CCTV system components with the existing City's Gigabit Ethernet network.
5. All systems and components shall be thoroughly tested and proven in actual use.
6. Unless otherwise shown on the plans, field equipment installed shall be operational in all weather conditions and able to withstand a wind load of 100 mph without permanent damage to mechanical and electrical equipment.
7. Equipment used shall be identical at each field location and be completely interchangeable.
8. Installed equipment shall be operational within NEMA TS2 standards – see below.

Test	NEMA TS2
Temperature	-34°C to 74°C
Humidity	18% to 90% RH, non condensing
Voltage	120 VAC–135 VAC @ 57 Hz – 63 Hz
Vibration	0.5 g @ (5-30) Hz
Shock	10 g's for 11 ms

**1.2 Power Requirements**

The CCTV equipment shall meet all of its specified requirements when the input power is 115 VAC plus or minus 10%, 60 plus or minus 3 Hz. The maximum power required shall not exceed 100 watts.

The equipment operations shall not be affected by the transient voltages, surges and sags normally experienced on commercial power lines. It is the Contractor's responsibility to check the local power service to determine if any special design is needed for the equipment. The extra

cost, if required, shall be included in the bid of this item.

### **1.3 Wiring Requirements**

All wiring shall meet the requirements of the national electric code. All wires shall be cut to proper length before assembly. No wire shall be doubled-back to take up slack. Wires shall be neatly laced into cable with nylon lacing or plastic straps. Cables shall be secured with tie-wraps. Service loops shall be provided at all connections.

### **1.4 Design Requirements**

The CCTV equipment shall be modular in design to allow major portions to be readily replaced. Modules and assemblies shall be clearly identified with name, model number, serial number and any other pertinent information required to facilitate equipment maintenance.

### **1.5 Fail Safe Provision**

The equipment shall be designed such that the failures of the equipment shall not cause the failure of any other unit of equipment.

## **PART 2 - MATERIALS**

The CCTV camera system shall consist of all of the following items in addition to any other items required for a fully-operational CCTV camera system:

- Pressurized dome CCTV camera assembly (including camera lenses, dome enclosure, Pan and Tilt Drive Units, and other necessary components) with vendor provided mounting hardware for installation on existing or new traffic signal pole, lighting pole, or traffic signal truss structure
- Dedicated power supply of adequate capacity for the CCTV camera system and all supporting control, communication, and network equipment
- Integrated CCTV camera cable that supports video, data and power to the CCTV dome camera
- Integrated one-channel video and data MPEG encoder at each CCTV camera location installed as part of this project
- Hardened Fast Ethernet switches at each CCTV camera location (refer to Ethernet Switch specification)
- New traffic signal or lighting poles as shown on the plans
- Fiber optic cable, conduit, and pull boxes to support the CCTV camera system
- Power surge and lightning suppression equipment, as required

### **2.1 Camera Assembly**

The CCTV camera shall have the following minimum features:

- The camera shall be analog DSP, Color CCD and capable of producing no less than 470 horizontal lines of resolution and communicate using non-proprietary control protocol.
- The camera shall have an active low-light sensor system and include automatic switching technology that makes use of color images during daylight and monochrome after dark or low light conditions.
- The camera shall have Pan, Tilt, Zoom (PTZ) capabilities with a 23X minimum optical zoom, 8X digital zoom, with manual as well as auto focus capability.
- The camera shall be able to operate with a continuous 360 degree horizontal rotation (no stops) and support at least 16 programmable zones.
- The camera shall be able to operate with a 180 degree vertical rotation and be capable of inverting the output camera image when passing through 90 degree down.
- The camera shall support a variable pan speed of 0.1 degree to at least 250 degrees per second and a variable tilt speed of 0.1 degree to at least 80 degrees per second.
- The camera shall be able to operate a light rating of 3.0 lux at 60 frames per second color and at 0.3 lux at 60 frames per second black and white.

- The camera shall operate at NEMA TS2 voltage levels of 89 VAC to 135 VAC and environmental temperatures of -34° C to 74°C at up to 100% relative humidity.
- The camera shall have a minimum of 6 programmable privacy zones at which the video is blanked.
- The camera shall support a minimum 8 tours and up to 32 preset positions.
- The camera shall be in a pressurized, tamper-proof, dry nitrogen sealed enclosure.
- The camera shall have a built-in character generator for site ID name and/or number, and alarm codes.
- The camera shall weigh no more than 30 pounds and shall have dimensions no greater than 18 inches tall and 15 inches long.
- The camera system shall meet the requirements of the National Transportation Communications for ITS Protocol (NTCIP) 1201 and 1205, as appropriate. The Contractor shall submit a certification letter from the CCTV camera vendor stating that the CCTV camera system has been tested and passed NTCIP certification. At the request of the City of Des Moines, the Contractor shall be prepared to submit a CCTV camera and peripheral equipment so that it can be subjected to NTCIP testing by the City or another third party selected by the City.
- The camera enclosure shall have a heater, operational in temperature ranges of -40°C to 75°C, to support efficient camera operation in cold weather, prevent formation and build-up of ice and condensation, and assure proper operation of the lens' iris mechanism. The heater shall not interfere with operation of the image sensor electronics or video signal.

All equivalencies must be approved by the Engineer prior to procurement.

## **2.2 Camera Mounting Hardware**

Camera shall use pole-mounting hardware provided by the CCTV camera vendor, capable of mounting to a vertical traffic signal or lighting pole, or a traffic signal truss structure. The camera mount shall be affixed to the pole to extend the camera towards the center of the signalized intersection and/or roadway corridor to provide optimal viewing capability. The CCTV camera and mounting hardware shall withstand a wind load of 100 mph when affixed to traffic signal pole, lighting pole, or traffic signal structure without permanent damage to mechanical and electrical equipment.

## **2.3 One-Channel Video and Data MPEG Encoder**

The one-channel video and data MPEG encoder shall provide compressed MPEG-1, MPEG-2 or MPEG-4 video streams onto the City's Gigabit Ethernet IP network. MPEG-4 is the preferred standard and will be used unless otherwise specified by Engineer. The video streams shall have video latency of under 500 ms (video delay) and a frame rate of 30 fps. Compression data rates shall be user selectable from 384 Kbits/second to 15 Mbits/second.

Encoders installed at the CCTV camera locations shall be hardened and shall be a shelf or wall mounted when installed in Type 170 controller cabinets used by the City. Contractor shall recommend mounting procedures to Engineer for approval, including the Contractor furnishing and installing a 19-inch rack mounted shelf in Type 170 cabinets where communication equipment is installed.

The encoder shall provide at least one video input for an NTSC CCTV camera. Camera control shall be RS422/RS485 to interface with the encoder. In addition, the encoder shall include a second COM port that can be utilized for RS232 or RS422 pass through of commands for other field equipment.

The encoder shall be equipped with a minimum of one independent LAN Ethernet port that can be configured with unique IP addresses. The compressed video streams shall be output through the LAN port.

Access to the encoder, including the MPEG video streams, camera control and setup, shall be through the on board web server. The host computer shall connect to the encoder's web server using Microsoft Internet Explorer (IE5 or above) or proprietary browser to access all functions of the encoder. The web server shall at a minimum include the camera protocols for the CCTV cameras installed as part of this contract, and shall control pan, tilt, zoom, presets, and on-screen display. The encoder shall have optional support for ISDN, wireless 802.11 and T1 protocols. In addition, the encoder shall be stereo analog audio ready. The encoder shall provide audio communications at rates up to 96 Kbits/s.

The encoder shall have the following features as a MINIMUM:

- NTSC or PAL video standards
- Composite and S-Video inputs
- One video input CODECs with vendor options for two or four inputs
- MPEG-4 CODECs shall be provided with vendor options for MPEG-1, MPEG-2 Video Compressed video data rate adjustable from 384 Kb/s and 15 Mb/s
- Resolution settings include:
  - 4 SIF
  - NTSC @ 320X240, 640X480 and 720X480
  - PAL @ 352X288 and 720X586
- NTSC frame rate is 30 fps and PAL frame rate is 25 fps
- Analog audio at rates from 8 to 96 Kb/s
  - Output formats are MPEG-1 & 2 (L1, L2), MP3 and AC3
- System management/setup and integrated camera control is through TCP/IP
- TCP/IP network protocols include Multicast (IGMP), Unicast and Broadcast
- Control I/O using COM port, RS232 protocol
- Input power from 85 to 250 VAC (auto-ranging power supply)
- Power supply rated at 250 watt maximum power consumption (60 – 80 watts typical)
- Operating temperature range from -20° to +70°C (hardened encoders only)
- Wall or standard 19 inch rack shelf mounted
- System control via standard web browsers including IE 5.0 or better
- Camera protocols for the vendor CCTV cameras installed as part of this contract.
- Minimum camera controls include pan/tilt/zoom, presets (set/move to), OSD on/off

#### **2.4 Gigabit Ethernet Hardened Field Switch**

If required in the plans, an Ethernet hardened field switch will be provided. The switch shall be constructed for modular port configuration housed in a high strength metal enclosure designed for DIN-Rail mounting and convection cooling. Nominal dimensions 1.75 inches H x 8.75 inches W x 10.0 inches D and weigh less than 4.75 pounds.

The standard configuration will be with (4) 10/100 copper ports and (2) Gigabit single mode fiber ports with one spare GBIC slot for future growth. Power input shall be AC. Manufactured in United States and Warranted for 3 years from day of contract acceptance for all parts and labor.

Additionally the Hardened Switch shall provide

- Two modular slots for user selection of 100Mb and 10MB fiber ports, Gigabit fiber ports, 10/100 copper ports, and PoE. Up to a maximum of 16 ports.
- Relay contacts for external "Alarm" monitoring of internal power, and of selected software operations. Form C, one NC indicating internal power, one NC software controllable.
- SNMP, rich commands including access control
- SNMPv3 for encrypted authentication & access security
- RMON with statistics, history, alarms and events
- GUI with Hubview/Bitview support

- CLI with multi-level password security
- VLANs, Port-based, Tag-based, with GVRP
- Spanning Tree Protocol, 802.1w
- LACP Link Aggregation Control Protocol, 802.3ad
- Rapid Spanning Tree Protocol, 802.1d
- Link-Loss-Learn (LLL) for fast switch buffer flush
- Ring Redundancy software available for sub-second recovery of ring faults
- QoS, multi-level 802.1p, ToS and DiffServ
- IGMP Snooping and multicast pruning
- Telnet, both client and server support
- Secure Web Management with SSL Secure Sockets Layer and TLS Transport Layer Security protocol support
- Port Security, controlled access by MAC address, support of 200 MAC addresses for port security
- Port mirroring for selective traffic analysis
- Event Log for the 1000 most recent events
- Port Settings Control, copper and fiber ports
- SMTP provides email alerts of traps and event
- SNTP with world-wide time zones
- Radius server and TACACS+ Terminal Access Controller Access Control System
- IP support for SNMP both TCP/IP and UDP/IP
- Passive or active FTP and TFTP for load/save convenience
- CLI Script method supported for ease of upgrading multiple switches
- BootP/DHCP for auto configuration
- Back pressure and flow control option per
- Temperature rating of  $-40^{\circ}\text{C}$  to  $75^{\circ}\text{C}$  and NEMA TS2 certified, or  $-50^{\circ}\text{C}$  to  $95^{\circ}\text{C}$  by the IEC 60068 Type Test method
- Store and Forward with IEEE 802.3x full-duplex flow control. All ports non-blocking. System aggregate forward and filter rate 6.0 Mpps.
- Address table: 4K nodes, with address aging time of 155 seconds typical
- Latency:  $6\mu\text{s}$  + packet time max (TX – TX, TX – FX, FX – FX, TX-G, G-G)
- MTFB of greater than 10 years calculated via Telcordia Bellcore method and/or MilStd Handbook 217

## 2.5 Connectors and Harnesses

All external connections shall be made by means of connectors. The connectors shall be keyed to preclude improper hookups. All wires to and from the connectors shall be color-coded and/or appropriately marked. In order to assure compatibility and performance compliance, the cables from the dome CCTV camera shall be assembled by the camera manufacturer.

Connecting harnesses of appropriate length and terminated with matching connectors shall be provided for interconnection with the communications system equipment.

All pins and mating connectors shall be gold-plated to provide good electrical connection and resist corrosion. Connectors utilizing solder-type connections shall have each soldered connection covered by a piece of heat shrink tubing securely shrunk to insure that it protects the connection.

## 2.6 Camera Interface

1. Each camera unit shall have a user selectable PTZ address. The unit shall respond to the central command only if it is addressed.
2. Camera shall be able to interface the encoder through proper cable connections

on the CODEC

3. Minimum camera controls shall be PTZ Auto, or Manual Focus, Iris, and Power.
4. Control signals shall be EIA/TIA 422/485. A minimum 9600-baud data rate shall be used.
5. Camera control protocol shall be non-proprietary.

## **2.7 CCTV Camera Pole**

The Contractor shall furnish and install CCTV camera poles and foundations at locations requiring new poles, if shown on the plans. The CCTV pole and foundation shall be per City standards. Installation of CCTV poles shall include necessary conduit, pull boxes, and integrated CCTV camera cable to support the CCTV installation, as shown on the Plans.

## **2.8 Lightning Suppression**

The Contractor shall provide lightning and surge suppression devices to protect the CCTC camera system deployed in this project. At a minimum, lightning suppression devices shall be installed to protect the following system components:

- The CCTV camera pole
- The enclosure (traffic signal controller cabinet) housing CCTV equipment
- Video cable between the camera and encoder
- Camera enclosure power cable between the power supply and camera enclosure
- PTZ cable between the cabinet and the camera enclosure

Alternatively, and at the direction of the Engineer, the installed CCTV system and its components shall be tied to the existing lightning/surge suppression system currently in place at each CCTV camera location. Lightning/surge suppression equipment shall meet City of Des Moines standards.

## **PART 3 - CONSTRUCTION AND INTEGRATION**

### **3.1 CCTV Camera Site Installation**

The CCTV camera system shall be installed as shown on the Plans or as specified in these Special Provisions, unless otherwise directed by the Engineer. The mounting standards and specifications shall be provided by the camera manufacturer. The Contractor shall verify the mounting requirements and hole patterns of the camera enclosure and the suitability of the approach depicted in the manufacturer's standards. The Contractor may request approval for alternate mounting details by submitting a shop drawing. The Contractor shall incur complete responsibility for the integrity of all mounting structures.

CCTV camera assemblies shall be mounted at the highest feasible point on the existing pole structure to provide optimal viewing capability.

During mounting of camera enclosures or any other work operation, the Contractor is responsible for avoiding and protecting from damage any existing poles, structures or wiring. All damage to existing poles, structures or wiring shall be repaired by the Contractor at his/her sole expense. The Engineer will have final authority in determining the extent of repairs that shall be required.

The video and camera control data for the CCTV cameras installed, as part of this project, shall terminate at the existing Video server at the City TOC.

### **3.2 CCTV Service (Power)**

The Contractor shall furnish and install a wall-mounted power strip/surge suppressor that plugs into the 120 VAC GFI outlet in each traffic signal controller cabinet associated with a new CCTV installation. The power strip/surge suppressor shall be sized to accommodate the CCTV camera and other communications equipment installed in the traffic signal controller cabinet, including the Ethernet Switch, encoder and other equipment to be installed at the CCTV camera installation as shown on the Plans.

The Contractor shall coordinate all activities related to service for power with both the City, and any other utility as directed by the Engineer. The power strip/surge suppressor shall satisfy City or Department standards.

### **3.3 Des Moines TOC Integration**

The Contractor shall be responsible for the integration of the elements installed as part of this contract with the existing systems at the City's TOC, to make the CCTV system installed as part of this Contract fully operational and functional as shown on the Plans, as specified in these Special Provisions, and as directed by the Engineer. The contract elements include the following:

1. Fiber optic cable
2. Ethernet network system
3. CCTV camera system and software

The work to be performed under this Contract shall consist of, but not be limited to, the project elements listed below, in support of the TOC Integration effort, as shown on the plans, as specified in these specifications, and as directed by Engineer.

1. Integration of the new CCTV cameras and existing CCTV cameras into one IP video management system.
2. Integration of Ethernet System into the existing City TOC operations to support the CCTV camera system.
3. Furnish accurate project documentation, as specified in these specifications.

### **3.4 Warranty**

All components of the CCTV camera system, except cameras, shall have a minimum 1-year manufacturer's warranty for parts and labor. The cameras shall have a minimum of a 2-year manufacturer's warranty for parts and labor from date of contract acceptance. This warranty does not replace any manufacturer's warranty if greater than what is required herein. Repair or replacement of defective parts for a period of two (2) years from the date of shipment is required.

## **PART 4 - METHOD OF MEASUREMENT AND BASIS OF PAYMENT**

Plan quantities are for estimating purposes only, and these quantities will not be paid for separately. Payment will be made on a lump sum basis.

No direct payment will be made for any incidental materials or work required to complete the CCTV camera system unless specifically provided for in the contract documents. All work or materials for which no basis of payment is specifically provided will be considered incidental to the bid item for "Traffic Signalization".