

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: July 19, 2011
Date of Addendum: July 18, 2011

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
081	17-1372-617	Alternate Pavement Types - Mainline Paving	Cerro Gordo	STP-U-1372(617)--70-17	19jul081.a02

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Attached is a tabulation to define pavement removal.

PAVEMENT REMOVAL				
		VK-20		
		07-18-11		
STATION TO STATION	SIDE	WIDTH (FT)	AREA (SY)	REMARKS
10TH AVENUE N				
90+38	--	26	3,611	ASPHALT PAVEMENT
90+38	RT	VARIES	73.0	CONCRETE PAVEMENT
90+38	LT	2.5	168.1	PCC CURB & GUTTER
90+38	RT	2.5	178.1	PCC CURB & GUTTER
96+43	LT	2.5	4.5	PCC CURB & GUTTER
96+58	LT	6.5	46.0	INTERSECTION 10TH AVE N & N 5TH ST - CONCRETE PAVEMENT
96+79	RT	2.5	6.6	PCC CURB & GUTTER
96+94	RT	VARIES	22.0	CONCRETE PAVEMENT
96+94	RT	2.5	4.5	PCC CURB & GUTTER
96+94	RT	13.4	96.1	INTERSECTION 10TH AVE N & N 5TH ST - CONCRETE PAVEMENT
97+06	LT	2.5	161.7	PCC CURB & GUTTER
97+08	RT	19.5	9.0	PCC CURB & GUTTER
97+41	RT	2.5	6.6	CONCRETE PAVEMENT
97+56	RT	2.5	147.8	PCC CURB & GUTTER
10TH AVENUE N TOTAL			4,535	

PAVEMENT REMOVAL NOTES:
 1. WIDTH OR LENGTH VARIES AT INTERSECTIONS.