

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 21-C021-116-A

Proposed Contract Period: Late Start Date of 04/02/12 with 120 WORK DAYS

Project(s):

Project No: HDP-C021(116)--6B-21

County: CLAY

Type of Work: BRIDGE NEW - PPCB

Route: M44 Length: 4.00 miles

Location: OVER THE OCHEYEDAN RIVER

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A 243'-0 X 44'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	51,961 CY
2403-0100010	STRUCT CONC (BRIDGE)	613 CY
2404-7775000	REINFORC STEEL	27,244 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	111,465 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 002                      Proposal ID: 33-C033-098

Proposed Contract Period: Late Start Date of 08/13/12 with 40 WORK DAYS

Project(s):

Project No: BROS-C033(98)--8J-33

County: FAYETTE

Type of Work: RCB CULVERT REPLACEMENT - TRIPLE BOX

Route: 80TH STREET                      Length: 0.00 miles

Location: OVER OTTER CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TRIPLE 12' X 8' X 49' REINFORCED BOX CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	293 CY
2404-7775000	REINFORC STEEL	46,983 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 33-C033-111

Proposed Contract Period: Late Start Date of 08/13/12 with 40 WORK DAYS

Project(s):

Project No: BROS-C033(111)--8J-33

County: FAYETTE

Type of Work: RCB CULVERT REPLACEMENT - TRIPLE BOX

Route: CRYSTAL ROAD Length: 0.00 miles

Location: 0.3 MILE EAST OF INTERSECTION WITH DEERFIELD ROAD,  
OVER DIBBLE CREEK

Item No.	Item Description	Quantity/Unit
-----		
	SECTION NO. 0001	
	ITEMS FOR A TRIPLE 12'-0 X 10'-0 X 56'-0 REINFORCED CONCRETE BOX CULVERT	
2403-0100020	STRUCT CONC (RCB CULV)	376 CY
2404-7775000	REINFORC STEEL	54,602 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 65-5341-084-A

Proposed Contract Period: Approx Start Date of 10/31/11 with 75 WORK DAYS

Proposal Note:

\*\*\*SITE AVAILABILITY\*\*\*

A GRADING CONTRACT FOR PROJECT NHSX-534-1(83)--3H-65 WAS LET 09/21/10 AND AWARDED TO C.J. MOYNA & SONS, ELKADER, IOWA. THE CONTRACT HAD A LATE START DATE OF 04/04/11 AND 120 WORKING DAYS FOR THE ENTIRE PROJECT (SITE 00). THERE IS A LATE START DATE OF 07/11/11 AND 40 WORKING DAYS FOR THE EB I-29 BRIDGE BERMS (SITE 01). IN ADDITION, THERE ARE SETTLEMENT PLATES IN THE BERMS AND A 60 CALENDAR DAY SETTLEMENT PERIOD AFTER COMPLETION OF THE BERM. WORK ON THE APPROACH PAVING MAY NOT BEGIN UNTIL COMPLETION OF THE BERM AND SETTLEMENT PERIOD. THE SETTLEMENT PERIOD MAY BE INCREASED OR DECREASED BASED ON SETTLEMENT PLATE DATA.

AN ASPHALT RESURFACING PROJECT IMX-29-1(81)33-02-65 WAS LET 03/15/11 AND AWARDED TO WESTERN ENGINEERING, HARLAN, IOWA. THE CONTRACTOR BEGAN WORK THE WEEK OF MAY 9, 2011 WITH 140 CALENDAR DAYS TO COME OUT OF HEAD-TO-HEAD TRAFFIC CONTROL ON INTERSTATE 29. THERE IS AN APPROXIMATE START DATE OF SEPTEMBER 19, 2011 AND 15 WORKING DAYS TO COMPLETE WORK AFTER SWITCHING TO NORMAL TRAFFIC (SITE 03).

Project(s):

Project No: NHSX-534-1(84)--3H-65

County: MILLS

Type of Work: BRIDGE NEW - PPCB

Route: IOWA 534

Length: 0.00 miles

Location: US 34 EASTBOUND OVER I-29

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 1111; A 344'-0 X VARIES, PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	49 CY
2403-0100010	STRUCT CONC (BRIDGE)	331 CY
2404-7775000	REINFORC STEEL	19,232 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	263,659 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	300 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 78-0801-351

Proposed Contract Period: Late Start Date of 04/16/12 with 120 WORK DAYS

Project(s):

Project No: IMX-080-1(351)40--02-78  
County: POTTAWATTAMIE  
Type of Work: BRIDGE REPLACEMENT - STEEL GIRDER  
Route: I-80 Length: 0.00 miles  
Location: WB OVER WEST NISHNABOTNA RIVER  
0.8 MI. WEST OF US 59

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0411; A 319'-0 X 40'-0 CONTINUOUS WELDED GIRDER BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	795 CY
2404-7775000	REINFORC STEEL	61,859 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	155,947 LB
SECTION NO. 0002		
	ROADWAY ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,596 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	296 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 081                      Proposal ID: 90-5825-635

Proposed Contract Period: Late Start Date of 06/04/12 with 15 WORK DAYS

Project(s):

Project No: STP-E-5825(635)--8V-90  
 County: WAPELLO  
 Type of Work: ALTERNATE PAVED SIDEWALK/TRAIL TYPES  
 Route: WILLIAMS ST. TRAIL    Length: 1.30 miles  
 Location: HWY 34 BRIDGE TO WILLIAMS STREET

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAILL ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,050 CY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	255 SY
SECTION NO. 0002		
ALTERNATE 'AA' OPTION 1: PCC TRAIL		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	6,200 SY
SECTION NO. 0003		
ALTERNATE 'AA' OPTION 2: HMA TRAIL		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2511-0301500	RECREATIONAL TRAIL, HMA, 5"	6,200 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 101                      Proposal ID: 21-7170-620

Proposed Contract Period: Late Start Date of 09/10/12 with 25 WORK DAYS

Project(s):

Project No: SRTS-U-7170(620)--8U-21

County: CLAY

Type of Work: PCC SIDEWALK/TRAIL

Route: 7TH STREET SW                      Length: 0.56 miles

Location: IN THE CITY OF SPENCER

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 102                      Proposal ID: 33-5657-611

Proposed Contract Period: Late Start Date of 06/04/12 with 40 WORK DAYS

Project(s):

Project No: STP-U-5657(611)--70-33

County: FAYETTE

Type of Work: PCC PAVEMENT - NEW

Route: 10TH STREET                      Length: 0.25 miles

Location: IN THE CITY OF OELWEIN FROM EAST  
OF 2ND AVE TO WEST OF OUTER RD

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,438 CY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	3,589 SY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	161 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	27 SY



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 65-5341-081-A

Proposed Contract Period: Approx Start Date of 04/02/12 with 100 WORK DAYS  
Site 01: TO COMPLETE EAST AND WEST BERMS FOR THE WB BRIDGE OVER I-29  
Approx Start Date of 08/13/12 with 20 WORK DAYS

Proposal Note:

SITE AVAILABILITY:

A GRADING CONTRACT FOR PROJECT NHSX-534-1(80)--3H-65 WAS LET 10/19/10 AND AWARDED TO JB HOLLAND CONSTRUCTION, DECORAH, IOWA. THE CONTRACT HAD A LATE START DATE OF 04/04/11 AND 120 WORKING DAYS FOR THE ENTIRE PROJECT (SITE 00). THERE IS A LATE START DATE OF 08/01/11 AND 40 WORKING DAYS FOR THE MISSOURI RIVER BRIDGE EAST BERM (SITE 01). IN ADDITION, THERE ARE SETTLEMENT PLATES IN THE EAST BRIDGE BERM AND A 116 CALENDAR DAY SETTLEMENT PERIOD AFTER COMPLETION OF THE BERM. WORK ON THE APPROACH PAVING MAY NOT BEGIN UNTIL COMPLETION OF THE BERM AND SETTLEMENT PERIOD. THE SETTLEMENT PERIOD MAY BE INCREASED OR DECREASED BASED ON SETTLEMENT PLATE DATA.

A GRADING CONTRACT FOR PROJECT NHSX-534-1(83)--3H-65 WAS LET 09/21/10 AND AWARDED TO C.J. MOYNA & SONS, ELKADER, IOWA. THE CONTRACT HAD A LATE START DATE OF 04/04/11 AND 120 WORKING DAYS FOR THE ENTIRE PROJECT (SITE 00). THERE IS A LATE START DATE OF 07/11/11 AND 40 WORKING DAYS FOR THE EB I-29 BRIDGE BERMS (SITE 01). IN ADDITION, THERE ARE SETTLEMENT PLATES IN THE BERMS AND A 60 CALENDAR DAY SETTLEMENT PERIOD AFTER COMPLETION OF THE BERM. WORK ON THE APPROACH PAVING MAY NOT BEGIN UNTIL COMPLETION OF THE BERM AND SETTLEMENT PERIOD. THE SETTLEMENT PERIOD MAY BE INCREASED OR DECREASED BASED ON SETTLEMENT PLATE DATA

Project(s):

Project No: NHSX-534-1(81)--3H-65  
County: MILLS  
Type of Work: PCC PAVEMENT - GRADE AND NEW  
Route: IOWA 534 Length: 4.60 miles  
Location: RELOC. US 34 FROM MISSOURI RIVER E. TO JUST E. OF BN/SF R.R.  
(EBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	151,807 CY
2108-5025000	OVERHAUL	1,934,432 ST-Y
2122-5190010	PAVED SHLD, PCC, 10"	819 SY
2301-1003080	STD/S-F PCC PAV'T, QM-C CL 3, 8"	14,393 SY
2301-1003100	STD/S-F PCC PAV'T, QM-C CL 3, 10"	115,182 SY
SECTION NO. 0002		
ALTERNATE 'AA' OPTION 1: PCC PAVED SHOULDER		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN  
2122-5190007 PAVED SHLD, PCC, 7" 9,153 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 151                      Proposal ID: 02-1484-500

Proposed Contract Period: Late Start Date of 10/24/11 with 5 WORK DAYS

Project(s):

Project No: MB-148-4(500)30--77-02

County: ADAMS

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 148                      Length: 0.11 miles

Location: FROM US 34 TO CO. RD. H-20(2 LOC.)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	85 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 152                      Proposal ID: 15-1484-500

Proposed Contract Period: Late Start Date of 10/24/11 with 5 WORK DAYS

Project(s):

Project No: MB-148-4(500)49--77-15

County: CASS

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 148                      Length: 0.05 miles

Location: OVER W. NODAWAY RIVER 0.8 MILE S. OF IA. 92

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	42 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 153                      Proposal ID: 57-1513-148

Proposed Contract Period: Late Start Date of 10/24/11 with 15 WORK DAYS

Project(s):

Project No: HSIPX-151-3(148)--3L-57

County: LINN

Type of Work: HMA PAVED SHOULDER - NEW

Route: U.S. 151                      Length: 0.00 miles

Location: CO. RD. X-20 IN SPRINGVILLE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 154                      Proposal ID: 61-C061-085

Proposed Contract Period: Late Start Date of 08/06/12 with 60 WORK DAYS

Project(s):

Project No: STP-S-C061(85)--5E-61

County: MADISON

Type of Work: HMA RESURFACING

Route: P-53

Length: 6.00 miles

Location: E1/4 COR 4-76-29 TO E1/4 COR 4-77-29

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	901 TON
2303-0032750	HMA (1M ESAL) INTERMEDIATE, 3/4"	16,273 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	7,282 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 155                      Proposal ID: 69-0344-502

Proposed Contract Period: Late Start Date of 10/24/11 with 5 WORK DAYS

Project(s):

Project No: MB-034-4(502)32--77-69

County: MONTGOMERY

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 34                              Length: 0.11 miles

Location: 3.4 MILES W. OF IA. 48 & 0.6 MILE W. OF CO. RD. M-63

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	63 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 156 Proposal ID: 73-0594-500

Proposed Contract Period: Late Start Date of 10/24/11 with 5 WORK DAYS

Project(s):

Project No: MB-059-4(500)14--77-73

County: PAGE

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 59 Length: 0.11 miles

Location: AT 2 LOCATIONS BETWEEN IA. 48 & CO. RD. J-18

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	85 TON



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 201                      Proposal ID: 00-0002-737

Proposed Contract Period: Late Start Date of 10/24/11 with 15 WORK DAYS

Project(s):

Project No: MP-000-2(737)0--76-00

County: STATEWIDE

Type of Work: PCC PATCHING

Route: MULTIPLE ROUTES                      Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 2

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	907 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	50 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 03-0262-704

Proposed Contract Period: Late Start Date of 06/25/12 with 60 WORK DAYS

Project(s):

Project No: MP-026-2(704)0--76-03  
County: ALLAMAKEE  
Type of Work: HMA JOINT & CRACK SEALING  
Route: IOWA 26 Length: 11.23 miles  
Location: FROM IN THE CITY OF LANSING TO THE MINNESOTA STATE LINE.

Project No: MP-218-2(703)199--76-09  
County: BREMER  
Type of Work: HMA JOINT & CRACK SEALING  
Route: U.S. 218 Length: 14.51 miles  
Location: FROM THE S. LIMITS OF THE WAVERLY BYPASS TO PLAINFIELD.  
INCLUDES INTERCHANGE RAMPS AT MP 198, 203 AND 205

Project No: MP-024-2(705)1--76-19  
County: CHICKASAW  
Type of Work: HMA JOINT & CRACK SEALING  
Route: IOWA 24 Length: 8.10 miles  
Location: FROM ECL OF NEW HAMPTON TO W. JCT. CO. RD. V-56 IN LAWLER.

Project No: MP-076-2(705)3--76-22  
County: CLAYTON  
Type of Work: HMA JOINT & CRACK SEALING  
Route: IOWA 76 Length: 2.03 miles  
Location: FROM MCGREGOR TO MARQUETTE.

Project No: MP-057-2(704)32--76-38  
County: GRUNDY  
Type of Work: HMA JOINT & CRACK SEALING  
Route: IOWA 57 Length: 7.88 miles  
Location: FROM BUTLER COUNTY LINE TO NEAR UNION ROAD IN THE  
CITY OF CEDAR FALLS.

Project No: MP-009-2(708)231--76-45  
County: HOWARD  
Type of Work: HMA JOINT & CRACK SEALING  
Route: IOWA 9 Length: 8.32 miles  
Location: FROM U.S. 63 TO CRESCO

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 203                      Proposal ID: 29-0345-703

Proposed Contract Period: Late Start Date of 10/24/11 with 20 WORK DAYS

Project(s):

Project No: MP-034-5(703)258--76-29

County: DES MOINES

Type of Work: PCC PATCHING

Route: U.S. 34                                      Length: 5.05 miles

Location: IN THE CITY OF BURLINGTON FROM MT. PLEASANT ST.  
INTERCHANGE E. TO MISSISSIPPI RIVER BRIDGE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	2,087 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	176 EACH



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 29-C029-064

Proposed Contract Period: Late Start Date of 10/24/11 with 20 WORK DAYS

Project(s):

Project No: ER-C029(63)--58-29  
 County: DES MOINES  
 Type of Work: SLIDE REPAIR  
 Route: SKUNK RIVER ROAD Length: 0.00 miles  
 Location: SKUNK RIVER ROAD @ 200TH AVENUE DDIR IA  
 -10-01-29-SKUNKRIVERRD-1

Project No: ER-C029(64)--58-29  
 County: DES MOINES  
 Type of Work: SLIDE REPAIR  
 Route: X70 Length: 0.00 miles  
 Location: SLIDE SOUTH OF 80TH AVENUE  
 DDIR NO. IA-10-01-29-X99-1

Project No: ER-C029(65)--58-29  
 County: DES MOINES  
 Type of Work: SLIDE REPAIR  
 Route: X70 Length: 0.00 miles  
 Location: SLIDE ON HWY 99 SOUTH OF 188TH STREET  
 DDIR NO. IA-10-01-29-X99-3

Project No: ER-C029(66)--58-29  
 County: DES MOINES  
 Type of Work: SLIDE REPAIR  
 Route: X70 Length: 0.00 miles  
 Location: SLIDE ON X99 SOUTH OF 195TH STREET  
 DDIR NO. IA-10-01-29-X99-4

Project No: ER-C029(67)--58-29  
 County: DES MOINES  
 Type of Work: SLIDE REPAIR  
 Route: X70 Length: 0.00 miles  
 Location: SLIDE ON DMC HWY 99 NORTH OF 70TH AVENUE  
 DDIR NO. IA-10-01-29-X99-6

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
2102-2710070	ROADWAY ITEMS - ER-C029(63)--58-29 EXCAVATION, CL 10, RDWY+BORROW	40 CY
SECTION NO. 0002		
2102-2710070	ROADWAY ITEMS - ER-C029(64)--58-29 EXCAVATION, CL 10, RDWY+BORROW	205 CY
SECTION NO. 0003		
2102-2710070	ROADWAY ITEMS - ER-C029(65)--58-29 EXCAVATION, CL 10, RDWY+BORROW	500 CY
SECTION NO. 0004		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

ROADWAY ITEMS - ER-C029(66)--58-29	
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	203 CY
SECTION NO. 0005	
ROADWAY ITEMS - ER-C029(67)--58-29	
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	81 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 302                      Proposal ID: 54-1491-066

Proposed Contract Period: Late Start Date of 10/24/11 with 20 WORK DAYS

Project(s):

Project No: ER-092-8(28)--28-54  
County: KEOKUK  
Type of Work: SLIDE REPAIR  
Route: IOWA 92                      Length: 0.00 miles  
Location: 4.6 MILES E. OF SIGOURNEY

Project No: ER-092-8(29)--28-54  
County: KEOKUK  
Type of Work: SLIDE REPAIR  
Route: IOWA 92                      Length: 0.00 miles  
Location: APPROX. 2 MILES W. OF SIGOURNEY

Project No: ER-149-1(66)--28-54  
County: KEOKUK  
Type of Work: SLIDE REPAIR  
Route: IOWA 149                      Length: 0.00 miles  
Location: 4.5 MILES S. OF SIGOURNEY

---

Item No.	Item Description	Quantity/Unit
SECTION NO. 0002		
2102-2710070	ROADWAY ITEMS - ER-092-8(29)--28-54 EXCAVATION, CL 10, RDWY+BORROW	340 CY

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 303                      Proposal ID: 56-0611-179

Proposed Contract Period: Late Start Date of 10/24/11 with 10 WORK DAYS

Project(s):

Project No: ER-061-1(179)--28-56

County: LEE

Type of Work: SLIDE REPAIR

Route: U.S. 61                      Length: 0.00 miles

Location: APPROX. 1 MILE N. OF US 136

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,846 CY



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 304                      Proposal ID: 62-0633-085

Proposed Contract Period: Late Start Date of 10/24/11 with 5 WORK DAYS

Project(s):

Project No: ER-063-3(85)--28-62

County: MAHASKA

Type of Work: SLIDE REPAIR

Route: U.S. 63                              Length: 0.00 miles

Location: SB EXIT RAMP TO EDDYVILLE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 305                      Proposal ID: 91-0925-053

Proposed Contract Period: Late Start Date of 10/24/11 with 20 WORK DAYS

Project(s):

Project No: STPN-092-5(53)--2J-91

County: WARREN

Type of Work: DITCH IMPROVEMENT

Route: IOWA 92                      Length: 0.00 miles

Location: JUST W. OF WCL OF MARTENSDALE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 401                      Proposal ID: 82-0741-217

Proposed Contract Period: Approx Start Date of 11/28/11 with 50 WORK DAYS

Project(s):

Project No: IMN-074-1(217)6--0E-82

County: SCOTT

Type of Work: SALVAGE AND REMOVAL

Route: I-74                                      Length: 0.00 miles

Location: 1123-1129 GRANT ST. IN BETTENDORF  
PARCEL NO. 310

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 451 Proposal ID: 37-3800-601-A

Proposed Contract Period: Late Start Date of 04/02/12 with 130 WORK DAYS

Proposal Note:

\*\*\* CONTRACT AWARD LIMIT \*\*\*  
PER SECTION 09009.04 OF THE DEVELOPMENTAL SPECIFICATIONS FOR  
ADDED OPTIONS BIDDING, THE CONTRACT AWARD LIMIT FOR THIS  
PROPOSAL IS \$1,405,000.00

Project(s):

Project No: STP-E-3800(601)--8V-37  
County: GREENE  
Type of Work: MISCELLANEOUS  
Route: EAST LINCOLN WAY Length: 0.25 miles  
Location: COURTHOUSE SQUARE TO BUSINESS SIDE  
SCENIC OR HISTORIC HWY

---

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS - BASE BID		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	2,530 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	16 EACH

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 452                      Proposal ID: 56-5195-601-A

Proposed Contract Period: Late Start Date of 10/24/11 with 20 WORK DAYS

Project(s):

Project No: EDP-5195(601)--7Y-56

County: LEE

Type of Work: MISCELLANEOUS

Route: J74

Length: 0.00 miles

Location: IN THE CITY OF MONTROSE;  
MONTROSE ENTRANCE SIGNS

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: September 20, 2011 10:00 A.M.

Proposed Bid Order: 501                      Proposal ID: 56-2181-075

Proposed Contract Period: Late Start Date of 04/16/12 with 60 WORK DAYS

Project(s):

Project No: NHSN-218-1(75)--2R-56

County: LEE

Type of Work: LANDSCAPING

Route: U.S. 218                      Length: 0.00 miles

Location: IA. 27 INTERCHANGE N. TO IA. 2 INTERCHANGE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

