

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: October 18, 2011
Date of Addendum: October 4, 2011

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
014	85-7430-611	Bridge New - Steel Girder	Story	STP-E-7430(611)--8V-85	18oct014.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the plan: SHEET C.02

Add the following Tab. CGA-1 TABULATION OF PERMANENT SIGNS:

TABULATION OF PERMANENT SIGNS					CGA-1
					10-3-11
LOCATION	LT/RT	DESCRIPTION	SIZE	NOTES	
STA 22+ 30	13' RT	W1-1L	18x18		
STA 23+ 69	13' RT	W1-1R	18x18		
STA 24+ 18	13' LT	W1-1R	18x18		
STA 25+ 27	13' LT	W1-1L	18x18		

Make the following change to the plan: SHEET C.01:

Add the following note to the ESTIMATE REFERENCE NOTES for the item 2101-0850001, CLEARING & GRUBBING:

Contractor is required to deliver cleared trees to City Tree Disposal Site cut in 8 to 10 foot lengths. Grubbing of stumps and root balls shall be performed at the construction site. Transporting of stumps and root balls to City Tree Disposal Site is not allowed. The stumps and root balls shall be disposed of offsite by the Contractor.