

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: December 20, 2011
Date of Addendum: December 16, 2011

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
016	77-C077-173	RETAINING WALL - CAST-IN-PLACE	Polk	STP-S-C077(173)--5E-77	20dec016.a04

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the plans:

The following consists of a list of changes on each sheet due to Addendum 20dec016.a03.

Sheets U19, U20, U22, U23, U25 & U26:

1. The soldier pile listed as MC10x33.6 shall be fabricated using either MC10x33.6 channels or with a channel that meets the following section properties:
 - a) The section depth shall be between 10 inches and 12 inches.
 - b) The Section Modulus about the X-axis (SX-X) shall meet or exceed 27.8 in³.

2. The soldier pile listed as MC12x45 shall be fabricated using either MC12x45 channels or with a channel that meets the following section properties:
 - a) The section depth shall be 12 inches.
 - c) The Section Modulus about the X-axis (SX-X) shall meet or exceed 42.0 in³.

All other construction shall be in accordance with the plans and specifications unless noted otherwise.