

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 03-0511-013

Proposed Contract Period: Late Start Date of 04/02/12 with 120 WORK DAYS

Project(s):

Project No: BRFN-051-1(12)--39-03
 County: ALLAMAKEE
 Type of Work: BRIDGE DECK OVERLAY
 Route: IOWA 51 Length: 0.00 miles
 Location: OVER N. FORK YELLOW RIVER 7.4 MILES N. OF POSTVILLE

Project No: BRFN-051-1(13)--39-03
 County: ALLAMAKEE
 Type of Work: BRIDGE DECK OVERLAY
 Route: IOWA 51 Length: 0.00 miles
 Location: OVER BRANCH OF YELLOW RIVER 5.1 MILES N. OF POSTVILLE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0212; OVERLAY AND REPAIRS TO A 280'-0 X 30'-0 CONTINUOUS WELDED GRIDER BRIDGE - BRFN-051-1(12)--39-03		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	17 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,950 LB
2413-0698074	DECK REPAIR, CL A	134 SY
SECTION NO. 0002		
DESIGN NO. 0212; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN - (12)		
2413-0698066	DECK OVERLAY (CL O PCC)	925 SY
SECTION NO. 0003		
DESIGN NO. 0212; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN - (12)		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	925 SY
SECTION NO. 0004		
ROADWAY ITEMS BRFN-051-1(12)--39-03		
2102-2625000	EMBANKMENT-IN-PLACE	100 CY
SECTION NO. 0005		
DESIGN NO. 0312; OVERLAY AND REPAIRS TO A 270'-0 X 30'-0 CONTINUOUS WELDED GIRDER BRIDGE - BRFN-051-1(13)--39-03		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	17 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,950 LB
2413-0698074	DECK REPAIR, CL A	176 SY
SECTION NO. 0006		
DESIGN NO. 0312; ALTERNATE 'BB' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN - (13)		
2413-0698066	DECK OVERLAY (CL O PCC)	893 SY
SECTION NO. 0007		
DESIGN NO. 0312; ALTERNATE 'BB' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN - (13)		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	893 SY
SECTION NO. 0008		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

ROADWAY ITEMS

BRFN-051-1(13)--39-03

2102-2625000 EMBANKMENT-IN-PLACE

100 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 04-0051-043

Proposed Contract Period: Late Start Date of 06/11/12 with 100 WORK DAYS

Project(s):

Project No: BRFN-005-1(43)--39-04
 County: APPANOOSE
 Type of Work: BRIDGE REPAIR
 Route: IOWA 5 Length: 0.00 miles
 Location: OVER DME R.R. 1 MILE S. OF COL RD. J-18

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 112; A 335'0 X 44' CONTINUOUS WELDED PLATE GIRDER BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	24 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,335 LB
2413-0698074	DECK REPAIR, CL A	367 SY
SECTION NO. 0002		
DESIGN NO. 112; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2413-0698066	DECK OVERLAY (CL O PCC)	1,628 SY
SECTION NO. 0003		
DESIGN NO. 112; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	1,628 SY
SECTION NO. 0004		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	160 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 07-0272-500

Proposed Contract Period: Late Start Date of 04/02/12 with 120 WORK DAYS

Project(s):

Project No: MB-027-2(500)185--77-07

County: BLACK HAWK

Type of Work: DECK JOINT REPAIR

Route: IOWA 27 Length: 0.00 miles

Location: IN THE CITY OF CEDAR FALLS ON RAMPS OVER CEDAR RIVER/
R.R./DRY RUN CREEK 0.8 MILES S. OF US 218

Project No: MB-218-2(501)188--77-07

County: BLACK HAWK

Type of Work: DECK JOINT REPAIR

Route: U.S. 218 Length: 0.00 miles

Location: IN THE CITY OF CEDAR FALLS OVER LINCOLN ST. &
CEDAR RIVER OVERFLOW 0.3 MILE N. OF IA. 57

Project No: MB-218-2(502)185--77-07

County: BLACK HAWK

Type of Work: DECK JOINT REPAIR

Route: U.S. 218 Length: 0.00 miles

Location: IN THE CITY OF WATERLOO OVER QUARRY LAKE 2.5 MILES S.
OF IA. 57

Project No: MB-218-2(503)181--77-07

County: BLACK HAWK

Type of Work: DECK JOINT REPAIR

Route: U.S. 218 Length: 0.00 miles

Location: IN THE CITY OF WATERLOO OVER 4TH, 5TH, 6TH & W. PARK AVE.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 07-0572-024

Proposed Contract Period: Late Start Date of 04/02/12 with 120 WORK DAYS

Project(s):

Project No: BRFN-057-2(24)--39-07
 County: BLACK HAWK
 Type of Work: BRIDGE DECK OVERLAY
 Route: IOWA 57 Length: 0.00 miles
 Location: IN THE CITY OF WATERLOO OVER THE CEDAR RIVER OVERFLOW
 (EBL)

Project No: BRFN-057-2(25)--39-07
 County: BLACK HAWK
 Type of Work: BRIDGE DECK OVERLAY
 Route: IOWA 57 Length: 0.00 miles
 Location: IN THE CITY OF WATERLOO OVER THE CEDAR RIVER OVERFLOW
 (WBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0712; OVERLAY AND REPAIRS TO A 530'-0 X 56' CONCRETE SLAB BRIDGE - EBL BRFN-057-2(24)--39-07	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	14 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	68 LB
2413-0698074	DECK REPAIR, CL A	624 SY
SECTION NO. 0002		
	DESIGN NO. 0712; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN - (24)	
2413-0698066	DECK OVERLAY (CL O PCC)	3,263 SY
SECTION NO. 0003		
	DESIGN NO. 0712; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN - (24)	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	3,263 SY
SECTION NO. 0004		
	ROADWAY ITEMS BRFN-057-2(24)--39-07	
2102-2625000	EMBANKMENT-IN-PLACE	288 CY
SECTION NO. 0005		
	DESIGN NO. 0812; OVERLAY AND REPAIRS TO A 530'-0 X 56' CCS BRIDGE - WBL BRFN-057-2(25)--39-07	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	14 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	68 LB
2413-0698074	DECK REPAIR, CL A	576 SY
SECTION NO. 0006		
	DESIGN NO. 0812; ALTERNATE 'BB' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN - (25)	
2413-0698066	DECK OVERLAY (CL O PCC)	3,263 SY
SECTION NO. 0007		
	DESIGN NO. 0812; ALTERNATE 'BB' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN - (25)	

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0007

DESIGN NO. 0812; ALTERNATE 'BB' OPTION 2: CLASS HPC-O PCC

BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN - (25)

2413-0698067 DECK OVERLAY (CL HPC-O PCC) 3,263 SY

SECTION NO. 0008

ROADWAY ITEMS

BRFN-057-2(25)--39-07

2102-2625000 EMBANKMENT-IN-PLACE 44 CY

2413-0698074 DECK REPAIR, CL A 182 SY

SECTION NO. 0009

ALTERNATE 'CC' OPTION 1: CLASS O PCC

BID THIS SECTION IF ALTERNATE 'CC' OPTION 1 IS CHOSEN - (25)

2413-0698066 DECK OVERLAY (CL O PCC) 974 SY

SECTION NO. 0010

ALTERNATE 'CC' OPTION 2: CLASS HPC-O PCC

BID THIS SECTION IF ALTERNATE 'CC' OPTION 2 IS CHOSEN - (25)

2413-0698067 DECK OVERLAY (CL HPC-O PCC) 974 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 14-C014-133

Proposed Contract Period: Late Start Date of 07/09/12 with 75 WORK DAYS

Project(s):

Project No: BROS-C014(133)--5F-14

County: CARROLL

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 295TH ST Length: 0.00 miles

Location: SECTION 12 NEWTON

Item No.	Item Description	Quantity/Unit

	SECTION NO. 0001	
	ITEMS FOR A 150' X 30' CONTINUOUS CONCRETE SLAB BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	421 CY
2404-7775000	REINFORC STEEL	92,382 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 14-C014-134

Proposed Contract Period: Late Start Date of 07/30/12 with 55 WORK DAYS

Project(s):

Project No: BROS-C014(134)--8J-14

County: CARROLL

Type of Work: BRIDGE REPLACEMENT - CCS

Route: PHOENIX AVE Length: 0.00 miles

Location: OVER WILLEY BRANCH

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 80' X 30 CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	174 CY
2404-7775000	REINFORC STEEL	45,519 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 15-0713-051

Proposed Contract Period: Late Start Date of 04/02/12 with 120 WORK DAYS

Project(s):

Project No: BRFN-071-3(45)--39-15
 County: CASS
 Type of Work: BRIDGE DECK OVERLAY
 Route: U.S. 71 Length: 0.00 miles
 Location: OVER SEVEN MILE CREEK 1.1 MILE N. OF LYMAN

Project No: BRFN-071-3(49)--39-15
 County: CASS
 Type of Work: BRIDGE DECK OVERLAY
 Route: U.S. 71 Length: 0.00 miles
 Location: OVER LONE TREE CREEK 0.1 MILE S. OF CO. RD. G-35

Project No: BRFN-071-3(50)--39-15
 County: CASS
 Type of Work: BRIDGE DECK OVERLAY
 Route: U.S. 71 Length: 0.00 miles
 Location: OVER TURKEY CREEK 0.1 MILE N. OF CO. RD. G-35

Project No: ER-071-3(51)--28-15
 County: CASS
 Type of Work: REVETMENT
 Route: U.S. 71 Length: 0.00 miles
 Location: OVER SEVEN MILE CREEK 0.6 MILE S. OF N. JCT. IA. 92

Project No: ER-071-3(52)--28-15
 County: CASS
 Type of Work: REVETMENT
 Route: U.S. 71 Length: 0.00 miles
 Location: OVER TURKEY CREEK 0.1 MILE N. OF CO. RD. G-35

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0112; OVERLAY AND REPAIRS TO A 201'-4 X 44' PPCB		
BRIDGE - BRFN-071-3(45)--39-15		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	32 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	13,735 LB
SECTION NO. 0002		
DESIGN NO. 0112; ALTERNATE 'AA' OPTION 1: CLASS O PCC		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN - (45)		
2413-0698066	DECK OVERLAY (CL O PCC)	1,552 SY
SECTION NO. 0003		
DESIGN NO. 0112; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN - (45)		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	1,552 SY
SECTION NO. 0004		
ROADWAY ITEMS		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

BRFN-071-3(45)--39-15
2102-2625000 EMBANKMENT-IN-PLACE 307 CY
SECTION NO. 0006
DESIGN NO. 0312; ALTERNATE 'BB' OPTION 1: CLASS O PCC
BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN - (49)
2413-0698066 DECK OVERLAY (CL O PCC) 1,557 SY
SECTION NO. 0007
DESIGN NO. 0312; ALTERNATE 'BB' OPTION 2: CLASS HPC-O PCC
BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN - (49)
2413-0698067 DECK OVERLAY (CL HPC-O PCC) 1,557 SY
SECTION NO. 0008
ROADWAY ITEMS
BRFN-071-3(49)--39-15
2102-2625000 EMBANKMENT-IN-PLACE 307 CY
SECTION NO. 0010
DESIGN NO. 0212; ALTERNATE 'CC' OPTION 1: CLASS O PCC
BID THIS SECTION IF ALTERNATE 'CC' OPTION 1 IS CHOSEN - (50)
2413-0698066 DECK OVERLAY (CL O PCC) 1,615 SY
SECTION NO. 0011
DESIGN NO. 0212; ALTERNATE 'CC' OPTION 2: CLASS HPC-O PCC
BID THIS SECTION IF ALTERNATE 'CC' OPTION 2 IS CHOSEN - (50)
2413-0698067 DECK OVERLAY (CL HPC-O PCC) 1,615 SY
SECTION NO. 0012
ROADWAY ITEMS
BRFN-071-3(50)--39-15
2102-2625000 EMBANKMENT-IN-PLACE 307 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 16-C016-082

Proposed Contract Period: Late Start Date of 07/30/12 with 55 WORK DAYS

Project(s):

Project No: BRS-C016(82)--60-16

County: CEDAR

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: F28 Length: 0.00 miles

Location: OVER GOWER CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 12'-0 X 8'-0 X 80'-0 REINFORCED CONCRETE BOX CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,459 CY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	1,186 SY
2403-0100020	STRUCT CONC (RCB CULV)	308 CY
2404-7775000	REINFORC STEEL	45,303 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 31-0522-083

Proposed Contract Period: Late Start Date of 04/02/12 with 240 WORK DAYS

Project(s):

Project No: NHSX-052-2(83)--3H-31
 County: DUBUQUE
 Type of Work: PCC PAVEMENT - GRADE & REPLACE
 Route: U.S. 52 Length: 1.37 miles
 Location: IN THE CITY OF DUBUQUE FROM US 61/151 N. TO
 GRANDVIEW AVE.(CATFISH CREEK)

Project No: BRF-052-2(90)--38-31
 County: DUBUQUE
 Type of Work: BRIDGE REPLACEMENT - PPCB
 Route: U.S. 52 Length: 0.00 miles
 Location: IN THE CITY OF DUBUQUE OVER
 CATFISH CREEK/CC R.R.

Project No: NHSN-052-2(91)--2R-31
 County: DUBUQUE
 Type of Work: LIGHTING
 Route: U.S. 52 Length: 0.00 miles
 Location: IN THE CITY OF DUBUQUE AT US 61/151/
 GRANDVIEW AVE. INTERSECTION

Project No: NHSN-052-2(112)--2R-31
 County: DUBUQUE
 Type of Work: TRAFFIC SIGNS
 Route: U.S. 52 Length: 1.23 miles
 Location: IN THE CITY OF DUBUQUE JUST S. OF GRANDVIEW AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		NHSX-052-2(83)--3H-31
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	88,679 CY
2122-5190010	PAVED SHLD, PCC, 10"	18,945 SY
2301-1003100	STD/S-F PCC PAV'T, QM-C CL 3, 10"	48,329 SY
SECTION NO. 0002		
	DESIGN NO. 211; FOR A 623'-8 X VARIOUS HEIGHT SOLDIER PILE	
	RETAINING WALL	NHSX-052-2(83)--3H-31
2403-0100000	STRUCT CONC (MISCELLANEOUS)	498 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	32,086 LB
SECTION NO. 0003		
	DESIGN NO. 311; FOR A 658'-10 X VARIOUS HEIGHT REINFORCED	
	CONCRETE RETAINING WALL	NHSX-052-2(83)--3H-31
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1,220 CY
2404-7775000	REINFORC STEEL	48,666 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	81,320 LB
SECTION NO. 0006		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

DESIGN NO. 111; DUAL 518'-0 X 40' PRETENSIONED

PRESTRESSED CONCRETE BEAM BRIDGE BRF-052-2(90)--38-31

2403-0100010	STRUCT CONC (BRIDGE)	3,607 CY
2404-7775000	REINFORC STEEL	191,057 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	524,637 LB

SECTION NO. 0008

ROADWAY ITEMS - SIGNING

NHSN-052-2(112)--2R-31

2403-0100000	STRUCT CONC (MISCELLANEOUS)	11 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,120 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 34-C034-084

Proposed Contract Period: Late Start Date of 08/13/12 with 45 WORK DAYS

Project(s):

Project No: BROS-C034(84)--5F-34

County: FLOYD

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: T18 Length: 0.00 miles

Location: OVER A LOCAL STREAM APPROXIMATELY THREE MILES SOUTH OF
ROCKFORD

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ITEMS FOR A TWIN 12'-0 X 8'-0 X 64'-0 REINFORCED CONCRETE BOX CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	275 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	220 SY
2403-0100020	STRUCT CONC (RCB CULV)	255 CY
2404-7775000	REINFORC STEEL	37,817 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 35-C035-066

Proposed Contract Period: Late Start Date of 05/14/12 with 65 WORK DAYS

Project(s):

Project No: NRT-C035(66)--9G-35

County: FRANKLIN

Type of Work: BRIDGE AND APPROACHES - PPCB

Route: RECREATION TRAIL Length: 0.00 miles

Location: S. LINE UP RR SPUR W. OLIVE AVE TO 250FT
E. SQUAW CREEK BRIDGE, IN CITY HAMPTON

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ITEMS FOR A 110'-0 X 12'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,438 CY
2403-0100010	STRUCT CONC (BRIDGE)	91 CY
2404-7775000	REINFORC STEEL	12,858 LB
SECTION NO. 0002		
TRAIL ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	80 CY
2511-0301600	RECREATIONAL TRAIL, HMA, 6"	476 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 37-C037-063

Proposed Contract Period: Late Start Date of 04/02/12 with 80 WORK DAYS

Project(s):

Project No: BHS-C037(63)--63-37

County: GREENE

Type of Work: RECONSTRUCTION - BRIDGE DECK REPLACEMENT

Route: E-53 Length: 0.00 miles

Location: OVER BUTTRICKS CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR REPAIRS TO A 175'-0 X 30'-0 CONTINUOUS I-BEAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	166 CY
2404-7775000	REINFORC STEEL	770 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	59,306 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	94 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	417 CY
2122-5190007	PAVED SHLD, PCC, 7"	1,408 SY
2122-5190010	PAVED SHLD, PCC, 10"	33 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	200 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	10 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 43-0301-119

Proposed Contract Period: Late Start Date of 04/30/12 with 105 WORK DAYS

Proposal Note:

WORK RESTRICTION

STAGE CONSTRUCTION SHALL NOT BEGIN PRIOR TO APRIL 2, 2012.

Project(s):

Project No: NHSX-030-1(119)--3H-43

County: HARRISON

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: U.S. 30 Length: 0.00 miles

Location: OVER SMALL NATURAL STREAM 3.6 MILES E. OF
CO. RD. F-32

Item No.	Item Description	Quantity/Unit
	SECTION NO. 0001	
	DESIGN NO. 109; A 122' - 2 X 53' - 0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	396 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	79,318 LB
	SECTION NO. 0002	
	ROADWAY ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,092 CY
	SECTION NO. 0003	
	ALTERNATE 'AA' OPTION 1: PCC SHOULDERS BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	
2122-5190007	PAVED SHLD, PCC, 7"	1,034 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 43-0301-122

Proposed Contract Period: Late Start Date of 07/16/12 with 65 WORK DAYS

Project(s):

Project No: BRFN-030-1(122)--39-43
 County: HARRISON
 Type of Work: BRIDGE DECK OVERLAY
 Route: U.S. 30 Length: 0.00 miles
 Location: OVER YOUNG'S DITCH 3.8 MILES E. OF
 NEBRASKA STATE LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
2413-0698074	DESIGN NO. 212; 194'-0 X 28' CONTINUOUS CONCRETE SLAB BRIDGE DECK REPAIR, CL A	62 SY
SECTION NO. 0002		
2413-0698066	DESIGN NO. 212; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN DECK OVERLAY (CL O PCC)	608 SY
SECTION NO. 0003		
2413-0698067	DESIGN NO. 212; ALTERNATE 'AA' OPTION 1: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN DECK OVERLAY (CL HPC-O PCC)	608 SY
SECTION NO. 0004		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	664 CY
2303-0053500	HMA (10M ESAL) SURF, 1/2", NO FRIC	44 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 015 Proposal ID: 43-1271-021

Proposed Contract Period: Late Start Date of 06/04/12 with 90 WORK DAYS

Project(s):

Project No: BRFN-127-1(15)--39-43
 County: HARRISON
 Type of Work: BRIDGE DECK OVERLAY
 Route: IOWA 127 Length: 0.00 miles
 Location: OVER ALLEN CREEK 8.5 MILES W. OF
 US 30

Project No: ER-127-1(21)--28-43
 County: HARRISON
 Type of Work: REVETMENT
 Route: IOWA 127 Length: 0.00 miles
 Location: OVER ALLEN CREEK 8.5 MILES W. OF US 30

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 209; 180'-6 X 32' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	BRFN-127-1(15)--39-43
2403-0100000	STRUCT CONC (MISCELLANEOUS)	10 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	4,382 LB
2413-0698074	DECK REPAIR, CL A	32 SY
SECTION NO. 0002		
	DESIGN NO. 209; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	(15)
2413-0698066	DECK OVERLAY (CL O PCC)	652 SY
SECTION NO. 0003		
	DESIGN NO. 209; ALTERNATE 'AA' OPTION 2: CLASS HPC-0 PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	(15)
2413-0698067	DECK OVERLAY (CL HPC-0 PCC)	652 SY
SECTION NO. 0004		
	ROADWAY ITEMS	BRFN-127-1(15)--39-43
2102-2625000	EMBANKMENT-IN-PLACE	980 CY
2303-0133500	HMA (1M ESAL) SURF, 1/2", NO FRIC	466 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 016 Proposal ID: 58-0929-136

Proposed Contract Period: Late Start Date of 06/25/12 with 90 WORK DAYS

Project(s):

Project No: BRFN-092-9(136)--39-58

County: LOUISA

Type of Work: BRIDGE REPAIR

Route: IOWA 92 Length: 0.00 miles

Location: OVER IOWA RIVER 1 MILE E. OF IA. 70

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 112; REPAIRS TO A 1447'-0 X 32'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	68 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	5,101 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 017 Proposal ID: 61-C061-087

Proposed Contract Period: Late Start Date of 07/30/12 with 65 WORK DAYS

Project(s):

Project No: BROS-C061(87)--8J-61

County: MADISON

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 270TH Length: 0.10 miles

Location: 1/2 MI. E. OF P53

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 80' - 0 X 24 - 6 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,740 CY
2403-0100010	STRUCT CONC (BRIDGE)	157 CY
2404-7775000	REINFORC STEEL	39,321 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 018 Proposal ID: 62-C062-075

Proposed Contract Period: Late Start Date of 07/23/12 with 70 WORK DAYS

Project(s):

Project No: BROS-C062(75)--8J-62

County: MAHASKA

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 325TH ST Length: 0.20 miles

Location: 1/4 MILE WEST OF DEAN AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 120' - 0 X 30' - 0 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	767 CY
2403-0100010	STRUCT CONC (BRIDGE)	319 CY
2404-7775000	REINFORC STEEL	71,050 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 019 Proposal ID: 77-1417-038

Proposed Contract Period: Late Start Date of 06/04/12 with 10 WORK DAYS

Proposal Note:

*** WORK RESTRICTION ***

STAGE 1 SHOULDER STRENGTHENING SHALL BE DONE FROM 8:00 P.M.
TO 3:00 P.M. MONDAY THROUGH FRIDAY WITH NO LANE CLOSURES
ALLOWED FROM 3:00 P.M. TO 8:00 P.M.

*** WORKING DAYS ***

THE WORKING DAYS ARE INTENDED FOR COMPLETION OF CONTRACT
ITEMS THAT DO NOT REQUIRE LANE CLOSURES.

*** INCENTIVE/DISINCENTIVE ***

SECTION 1111 OF THE STANDARD SPECIFICATIONS FOR
INCENTIVE/DISINCENTIVE (I/D) FOR EARLY COMPLETION SHALL
APPLY TO THIS PROJECT WITH THE FOLLOWING CONDITIONS:
CLOSURE DAYS: 90
MAXIMUM INCENTIVE: \$36,000.00
INCENTIVE RATE PER DAY: \$1,200.00
DISINCENTIVE RATE PER DAY: \$1,200.00
THE CRITICAL CLOSURE ACTIVITY INCLUDES COMPLETION OF ALL
CONTRACT ITEMS THAT REQUIRE A LANE CLOSURE. THE
INCENTIVE/DISINCENTIVE AMOUNT WILL BE PAID/COLLECTED BY THE
CONTRACTING AUTHORITY UPON COMPLETION OF THE CRITICAL
CLOSURE ACTIVITY.

Project(s):

Project No: BRFN-141-7(38)--39-77
County: POLK
Type of Work: BRIDGE DECK OVERLAY
Route: IOWA 141 Length: 0.00 miles
Location: E.B. IA 141 OVER BEAVER CREEK
2.6 MILES W. OF IA 44

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0212; 339'-4 X 40' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2403-010000	STRUCT CONC (MISCELLANEOUS)	9 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,006 LB
2413-0698074	DECK REPAIR, CL A	30 SY
SECTION NO. 0002		
DESIGN NO. 0212; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2413-0698066	DECK OVERLAY (CL O PCC)	1,500 SY
SECTION NO. 0003		
DESIGN NO. 0212; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0003	DESIGN NO. 0212; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC	
	BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	1,500 SY
SECTION NO. 0004	ROADWAY ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	600 CY
SECTION NO. 0005	CONTRACT ITEMS	
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	30 CDAY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 020 Proposal ID: 81-C081-061

Proposed Contract Period: Late Start Date of 08/13/12 with 50 WORK DAYS

Project(s):

Project No: BRS-C081(61)--60-81

County: SAC

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: SIERRA AVE. Length: 0.00 miles

Location: AT A STREAM, 0.4 MILES NORTH OF 190TH STREET.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A SINGLE 12' X 12' RCB CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,120 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	195 SY
2403-0100020	STRUCT CONC (RCB CULV)	249 CY
2404-7775000	REINFORC STEEL	34,662 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	2,086 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 021 Proposal ID: 81-C081-062

Proposed Contract Period: Late Start Date of 07/16/12 with 50 WORK DAYS

Project(s):

Project No: BROS-C081(62)--5F-81

County: SAC

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: CORY AVE. Length: 0.02 miles

Location: AT SILVER CREEK, 0.9 MILES SOUTH OF 220TH STREET.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 8' X 10' RCB CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,220 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	195 SY
2403-0100020	STRUCT CONC (RCB CULV)	240 CY
2404-7775000	REINFORC STEEL	29,833 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	2,086 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 022 Proposal ID: 82-C082-050

Proposed Contract Period: Late Start Date of 07/16/12 with 65 WORK DAYS

Project(s):

Project No: BRS-C082(50)--60-82

County: SCOTT

Type of Work: BRIDGE REPLACEMENT - CCS

Route: Y68 Length: 0.00 miles

Location: OVER MCDONALD'S CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR 100' X 30' CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	227 CY
2404-7775000	REINFORC STEEL	3,116 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	56,159 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	25 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 023 Proposal ID: 96-C096-106

Proposed Contract Period: Late Start Date of 07/09/12 with 70 WORK DAYS

Project(s):

Project No: BROS-C096(106)--8J-96

County: WINNESHIEK

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 180TH AVE. Length: 0.00 miles

Location: AT NUTTING CREEK, 950 FT. NORTH OF THE INTERSECTION
WITH 107TH STREET IN SECTION 26-96-08.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 12' X 12' RCB CULVERT		
2102-2625000	EMBANKMENT-IN-PLACE	2,876 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	934 CY
2403-0100020	STRUCT CONC (RCB CULV)	315 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	40,478 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 07-8155-711

Proposed Contract Period: Late Start Date of 04/02/12 with 120 WORK DAYS

Project(s):

Project No: STP-U-8155(711)--70-07

County: BLACK HAWK

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: MULTIPLE ROUTES Length: 2.04 miles

Location: IN THE CITY OF WATERLOO FROM US 20 TO
IA 21 ON ANSBOROUGH AVE AND SHAULIS RD

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	81,693 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	33,198 SY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	8,552 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 37-3800-601-B

Proposed Contract Period: Late Start Date of 04/02/12 with 150 WORK DAYS

Proposal Note:

*** CONTRACT AWARD LIMIT ***

PER SECTION 09009.04 OF THE DEVELOPMENTAL SPECIFICATIONS FOR
ADDED OPTIONS BIDDING, THE CONTRACT AWARD LIMIT FOR THIS
PROPOSAL IS \$1,405,000.00

Project(s):

Project No: STP-E-3800(601)--8V-37

County: GREENE

Type of Work: PCC SIDEWALK/TRAIL

Route: EAST LINCOLN WAY Length: 0.25 miles

Location: IN THE CITY OF JEFFERSON
COURTHOUSE SQUARE TO BUSINESS SIDE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS - BASE BID		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	2,530 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	16 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 57-C057-115

Proposed Contract Period: Late Start Date of 08/06/12 with 25 WORK DAYS

Project(s):

Project No: STP-S-C057(115)--5E-57

County: LINN

Type of Work: PCC OVERLAY - UNBONDED

Route: TROY MILLS RD (W45) Length: 3.10 miles

Location: WAPSI BRIDGE TO JUST N OF PARIS RD

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	209 TON
2310-5151040	PCC OVERLAY, FURN ONLY	7,924 CY
2310-5151251	PCC OVERLAY PLACE ONLY (UNBONDED)	43,948 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 62-C062-077

Proposed Contract Period: Late Start Date of 07/30/12 with 65 WORK DAYS

Project(s):

Project No: FM-C062(77)--55-62

County: MAHASKA

Type of Work: PCC PAVEMENT - NEW

Route: V13 Length: 2.40 miles

Location: 255TH ST. TO 275TH ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	12,289 CY
2301-1034080	STD/S-F PCC PAV'T, CL C CL 3I, 8"	31,479 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 74-C074-095

Proposed Contract Period: Late Start Date of 04/02/12 with 110 WORK DAYS

Project(s):

Project No: STP-S-C074(95)--5E-74

County: PALO ALTO

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: B63 Length: 6.46 miles

Location: 460 AVE (HWY 4) TO 525AVE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	211,689 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	90,829 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 106 Proposal ID: 77-0187-625

Proposed Contract Period: Late Start Date of 04/02/12 with 130 WORK DAYS

Project(s):

Project No: STP-U-0187(625)--70-77

County: POLK

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: NE 36TH STREET Length: 0.80 miles

Location: IN THE CITY OF ANKENY

FROM RAINTREE DR TO E OF NE OTTER CR DR

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	31,873 CY
2122-5190009	PAVED SHLD, PCC, 9"	537 SY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	29,234 SY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	1,654 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	98 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 77-2352-634

Proposed Contract Period: Late Start Date of 05/07/12 with 30 WORK DAYS

Project(s):

Project No: IMN-235-2(634)6--0E-77

County: POLK

Type of Work: PCC SIDEWALK/TRAIL

Route: I-235 Length: 0.00 miles

Location: IN THE CITY OF DES MOINES NEAR 42ND ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,867 CY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	489 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 108 Proposal ID: 94-C094-092

Proposed Contract Period: Late Start Date of 07/16/12 with 60 WORK DAYS

Project(s):

Project No: STP-E-C094(92)--8V-94

County: WEBSTER

Type of Work: PCC SIDEWALK/TRAIL

Route: S. C. NATURE TRAIL Length: 0.00 miles

Location: FROM HARLAN ROGERS SPORTS COMPLEX TO KENNEDY PARK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	6,840 CY
2303-0031750	HMA (1M ESAL) BASE, 3/4"	61 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	61 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	41 TON
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	15,610 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	200 SY
2511-0302800	RECREATIONAL TRAIL, PCC, 8"	3 SY
2511-0302800	RECREATIONAL TRAIL, PCC, 8"	260 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 109 Proposal ID: 97-0296-223

Proposed Contract Period: Specified Start Date of 03/19/12 with 25 WORK DAYS

Proposal Note:

*** WORKING DAYS, INCENTIVE/DISINCENTIVE AND NO EXCUSE ROAD
OPENING BONUS NOTES ***
REFER TO PROPOSAL SPECIAL PROVISIONS TEXT NOTE NUMBER
656.0180 AT THE BACK OF THE PROPOSAL FOR FURTHER
INFORMATION.

Project(s):

Project No: IM-NHS-029-6(195)142--03-97
County: WOODBURY
Type of Work: RCB CULVERT NEW - TWIN BOX
Route: I-29 Length: 0.00 miles
Location: OVER AIRPORT OUTFALL IN SIOUX CITY
(SBL)

Project No: IM-NHS-029-6(223)143--03-97
County: WOODBURY
Type of Work: PCC PAVEMENT - GRADE AND NEW
Route: I-29 Length: 2.58 miles
Location: IN THE CITY OF SIOUX CITY FROM HARBOR DR. OUTFALL N. TO S.
OF US 20/I-129 SYSTEMS INTERCHANGE(SBL)/SINGING HILLS BLVD.

Project No: IM-NHS-029-6(224)143--03-97
County: WOODBURY
Type of Work: BRIDGE REPLACEMENT - PPCB
Route: I-29 Length: 4.65 miles
Location: IN THE CITY OF SIOUX CITY OVER SINGING HILLS BLVD.
(SBL)

Project No: ITS-029-6(230)145--25-97
County: WOODBURY
Type of Work: DYNAMIC MESSAGE SIGNS
Route: I-29 Length: 4.65 miles
Location: IN THE CITY OF SIOUX CITY 1 MILE N. OF
US 20/I-129 SYSTEMS INTERCHANGE

Project No: IM-029-6(235)142--13-97
County: WOODBURY
Type of Work: TRAFFIC SIGNS
Route: I-29 Length: 4.65 miles
Location: IN THE CITY OF SIOUX CITY FROM HARBOR DR. OUTFALL N. TO S.
OF US 20/I-129 SYSTEMS INTERCHANGE(SBL) SINGING HILLS BLVD.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO.313; TWIN 8 X 6 X 92 CIP RCB,ALT 'AA' OPT 1	(195)
	BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0001

DESIGN NO.313; TWIN 8 X 6 X 92 CIP RCB,ALT 'AA' OPT 1 (195)

BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN

2403-0100020	STRUCT CONC (RCB CULV)	173 CY
2404-7775000	REINFORC STEEL	22,425 LB

SECTION NO. 0003

ROADWAY ITEMS - IM-NHS-029-6(223)143--03-97

2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	111,013 CY
2301-1004110	STD/S-F PCC PAV'T, QM-C CL 3I, 11"	107,709 SY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	4,441 SY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	205 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	25,518 LB

SECTION NO. 0006

DESIGN NO. 0609; A 256'-0 X 73'-4 PPCB BRIDGE

IM-NHS-029-6(224)143--03-97

2403-0100010	STRUCT CONC (BRIDGE)	855 CY
2404-7775000	REINFORC STEEL	54,237 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	266,316 LB

SECTION NO. 0007

DYNAMIC MESSAGE SIGN - ITS-029-6(230)145--25-97

2102-2625000	EMBANKMENT-IN-PLACE	10 CY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	217 CY
2404-7775000	REINFORC STEEL	7,694 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	7,538 LB

SECTION NO. 0009

NO EXCUSE ROAD OPENING BONUS FOR CONTRACT

2528-5160000	NO EXCUSE ROAD OPENING BONUS, _____	Lump Sum	LUMP
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	1	CDAY
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	1	CDAY
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	1	CDAY
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	1	CDAY
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	1	CDAY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 03-C003-048

Proposed Contract Period: Late Start Date of 07/16/12 with 40 WORK DAYS

Project(s):

Project No: FM-C003(48)--55-03

County: ALLAMAKEE

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: X-32 Length: 3.50 miles

Location: IA 76 TO WATERVILLE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0021750	HMA (300K ESAL) BASE, 3/4"	5,569 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	5,569 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 05-0443-031

Proposed Contract Period: Late Start Date of 06/18/12 with 80 WORK DAYS

Project(s):

Project No: STP-044-3(31)--2C-05

County: AUDUBON

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: IOWA 44 Length: 9.73 miles

Location: FROM KIMBALLTON E. TO US 71

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	200 CY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	15,144 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	14,962 TON
2303-0133500	HMA (1M ESAL) SURF, 1/2", NO FRIC	659 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	20 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	32 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 09-8190-627

Proposed Contract Period: Late Start Date of 09/04/12 with 25 WORK DAYS

Project(s):

Project No: STP-E-8190(627)--8V-09

County: BREMER

Type of Work: HMA SIDEWALK/TRAIL

Route: 8TH ST SE Length: 0.79 miles

Location: IN THE CITY OF WAVERLY, FROM BROOKWOOD PARK TO THE SOCCER
COMPLEX AND WEST TO EXISTING TRAIL NEAR SE ELEMENTARY SCHOOL

Item No.	Item Description	Quantity/Unit

	SECTION NO. 0001	
	TRAIL ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	800 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 14-C014-143

Proposed Contract Period: Late Start Date of 07/09/12 with 65 WORK DAYS

Project(s):

Project No: FM-C014(135)--55-14
County: CARROLL
Type of Work: HMA RESURFACING
Route: N20 Length: 1.39 miles
Location: HWY 30 TO MAPLE RIVER

Project No: FM-C014(136)--55-14
County: CARROLL
Type of Work: HMA RESURFACING
Route: E37 Length: 1.88 miles
Location: MAHOGANY AVE TO OLYMPIC AVE

Project No: FM-C014(137)--55-14
County: CARROLL
Type of Work: HMA RESURFACING
Route: E37 Length: 1.38 miles
Location: US71 TO MESQUITE AVE

Project No: FM-C014(138)--55-14
County: CARROLL
Type of Work: HMA RESURFACING
Route: N38 Length: 1.29 miles
Location: THE CARROLL AIRPORT TO HY 30

Project No: FM-C014(139)--55-14
County: CARROLL
Type of Work: HMA RESURFACING
Route: E57 Length: 1.60 miles
Location: GRANITE AVE TO WCL TEMPLETON

Project No: FM-C014(140)--55-14
County: CARROLL
Type of Work: HMA RESURFACING
Route: N18 Length: 0.93 miles
Location: IA 141 TO E57

Project No: FM-C014(141)--55-14
County: CARROLL
Type of Work: HMA RESURFACING
Route: N47 Length: 2.94 miles
Location: SW CORNER 15-85-33 TO NW CORNER 3-85-33

Project No: FM-C014(142)--55-14
County: CARROLL
Type of Work: HMA RESURFACING
Route: E-26 Length: 2.91 miles
Location: JCT E26 AND N38 IN LIDDERDALE TO JCT OF
E26 AND N44

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Project No: FM-C014(143)--55-14
 County: CARROLL
 Type of Work: HMA RESURFACING
 Route: E-63 Length: 1.94 miles
 Location: COON RAPIDS TO GREENE COUNTY LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		FM-C014(135)--55-14
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	808 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,212 TON
SECTION NO. 0002		
ROADWAY ITEMS		
		FM-C014(136)--55-14
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	1,307 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,960 TON
SECTION NO. 0003		
ROADWAY ITEMS		
		FM-C014(137)--55-14
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	897 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,345 TON
SECTION NO. 0004		
ROADWAY ITEMS		
		FM-C014(138)--55-14
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	867 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,301 TON
SECTION NO. 0005		
ROADWAY ITEMS		
		FM-C014(139)--55-14
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	396 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	594 TON
SECTION NO. 0006		
ROADWAY ITEMS		
		FM-C014(140)--55-14
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	791 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,186 TON
SECTION NO. 0007		
ROADWAY ITEMS		
		FM-C014(141)--55-14
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	2,089 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	3,217 TON
SECTION NO. 0008		
ROADWAY ITEMS		
		FM-C014(142)--55-14
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	3,128 TON
SECTION NO. 0009		
ROADWAY ITEMS		
		FM-C014(143)--55-14
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	1,483 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	2,225 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 155 Proposal ID: 17-1221-013

Proposed Contract Period: Late Start Date of 04/16/12 with 115 WORK DAYS

Project(s):

Project No: STP-122-1(13)--2C-17

County: CERRO GORDO

Type of Work: HMA RESURFACING

Route: IOWA 122 Length: 2.37 miles

Location: IN THE CITY OF MASON CITY FROM ILLINOIS AVE. E. TO
ECL

Project No: MP-122-2(707)7--76-17

County: CERRO GORDO

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 122 Length: 0.00 miles

Location: IN THE CITY OF MASON AT VARIOUS LOCATIONS.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		STP-122-1(13)--2C-17
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	6,185 CY
2301-1033095	STD/S-F PCC PAV'T, CL C CL 3, 9.5"	1,100 SY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	1,802 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	6,796 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	7,275 TON
SECTION NO. 0006		
ROADWAY ITEMS		
		MP-122-2(707)7--76-17
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	135 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	135 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 156 Proposal ID: 26-C026-072

Proposed Contract Period: Late Start Date of 07/30/12 with 60 WORK DAYS

Project(s):

Project No: FM-C026(72)--55-26

County: DAVIS

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: J40 Length: 3.41 miles

Location: FROM TIMBER AVE TO WHEAT AVE

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
HMA RESURFACING AND WIDENING ITEMS		
2303-0021750	HMA (300K ESAL) BASE, 3/4"	8,102 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	8,102 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 157 Proposal ID: 28-C028-078

Proposed Contract Period: Late Start Date of 09/04/12 with 20 WORK DAYS

Project(s):

Project No: FM-C028(78)--55-28

County: DELAWARE

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: X21 Length: 3.50 miles

Location: FROM D42 NORTH TO D5X

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	75 TON
2303-0021500	HMA (300K ESAL) BASE, 1/2"	4,500 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	4,500 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 158 Proposal ID: 40-C040-080

Proposed Contract Period: Late Start Date of 05/29/12 with 95 WORK DAYS

Project(s):

Project No: STP-S-C040(80)--5E-40

County: HAMILTON

Type of Work: HMA PAVEMENT - GRADE AND REPLACE

Route: 190TH Length: 3.40 miles

Location: HWY 69 TO I-35

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0031750	HMA (1M ESAL) BASE, 3/4"	7,330 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	7,370 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 159 Proposal ID: 43-0295-213

Proposed Contract Period: Late Start Date of 09/10/12 with 30 WORK DAYS

Proposal Note:

Project(s):

Project No: IMN-029-5(213)72--0E-43

County: HARRISON

Type of Work: HMA RESURFACING

Route: I-29 Length: 0.00 miles

Location: FROM POTTAWATTAMIE CO. LINE N. TO SOUTH DAKOTA
STATE LINE

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ROADWAY ITEMS		
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	340 TON
2303-0062500	HMA (30M ESAL) INTERMEDIATE, 1/2"	1,253 TON
2303-0063502	HMA (30M ESAL) SURF, 1/2", FRIC L-2	1,253 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	892 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	90 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 160 Proposal ID: 47-0596-038

Proposed Contract Period: Late Start Date of 07/09/12 with 70 WORK DAYS

Project(s):

Project No: STP-059-6(37)--2C-47
 County: IDA
 Type of Work: HMA RESURFACING WITH MILLING
 Route: U.S. 59 Length: 1.50 miles
 Location: US 59 FROM W. JCT. US 20 N. TO NCL OF
 HOLSTEIN

Project No: STP-059-6(38)--2C-47
 County: IDA
 Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
 Route: U.S. 59 Length: 4.50 miles
 Location: US 59 FROM NCL OF HOLSTEIN N. TO CHEROKEE CO. LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		STP-059-6(37)--2C-47
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	14 CY
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	5,645 TON
SECTION NO. 0003		
ROADWAY ITEMS		
		STP-059-6(38)--2C-47
2102-2625000	EMBANKMENT-IN-PLACE	720 CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	10,220 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	5,251 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	5,224 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	16 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 161 Proposal ID: 77-8500-022

Proposed Contract Period: Late Start Date of 07/23/12 with 55 WORK DAYS

Project(s):

Project No: NG-850-0(22)--7D-77

County: POLK

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: VARIOUS Length: 0.00 miles

Location: CAMP DODGE IN JOHNSTON ON 3RD ST. 10TH ST., 11TH ST.,
12TH ST. & BURMA RD.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,179 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	1,292 SY
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	1,908 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 162 Proposal ID: 79-0631-706

Proposed Contract Period: Late Start Date of 08/27/12 with 35 WORK DAYS

Project(s):

Project No: MP-063-1(706)102--76-79

County: POWESHIEK

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 63 Length: 17.20 miles

Location: FROM THE WEST JCT. OF US 6, NORTH TO OLD US 30 IN TOLEDO,
VARIOUS LOCATIONS.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	1,412 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	1,406 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,087 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	41 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 163 Proposal ID: 82-0225-030

Proposed Contract Period: Late Start Date of 07/16/12 with 60 WORK DAYS

Project(s):

Project No: STPN-022-5(30)--2J-82

County: SCOTT

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: IOWA 22 Length: 4.04 miles

Location: IN THE CITY OF DAVENPORT FROM 0.75 MILE W. OF
WCL E. NE TO US 61

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	1,929 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	57 CY
2122-5190010	PAVED SHLD, PCC, 10"	532 SY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	49 TON
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	2,107 TON
2303-0053503	HMA (10M ESAL) SURF, 1/2", FRIC L-3	1,706 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	837 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	79 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 164 Proposal ID: 85-0695-095

Proposed Contract Period: Late Start Date of 05/29/12 with 90 WORK DAYS
Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.
No Start Date Specified with 40 WORK DAYS

Proposal Note:

*** SITE NUMBER 01 ***

IN ORDER TO MINIMIZE THE IMPACT TO THE CITY OF GILBERT THE CONTRACTOR SHALL COMPLETE THE SECTION FROM THE BOP, (STATION 158+00, JUST NORTH OF 190TH) TO THE GILBERT CORNER (STATION 266+50, COUNTY ROAD E23) IN A REDUCED TIME FRAME.

Project(s):

Project No: STP-069-5(95)--2C-85

County: STORY

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 69 Length: 6.08 miles

Location: FROM 0.04 MILE S. OF 190TH ST. N. TO
0.05 MILE S. OF CO. RD. E-18

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	450 CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	30,935 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	9,650 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	10,065 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 15-0801-343

Proposed Contract Period: Late Start Date of 09/10/12 with 40 WORK DAYS

Proposal Note:

Project(s):

Project No: IMN-080-1(343)50--0E-15

County: CASS

Type of Work: PCC PATCHING

Route: I-80

Length: 46.67 miles

Location: FROM POTTAWATTAMIE CO. LINE EAST TO POLK CO. LINE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	3,038 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	297 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 16-0306-705

Proposed Contract Period: Late Start Date of 04/23/12 with 110 WORK DAYS

Proposal Note:

Project(s):

Project No: MP-030-6(705)269--76-16
County: CEDAR
Type of Work: SLURRY SEAL
Route: U.S. 30 Length: 16.75 miles
Location: FROM LINN COUNTY LINE TO ECL OF CLARENCE.

Project No: MP-136-6(712)19--76-23
County: CLINTON
Type of Work: SLURRY SEAL
Route: IOWA 136 Length: 11.02 miles
Location: FROM JUST W. OF CHARLOTTE, WESTERLY TO U.S. 61.

Project No: MP-136-6(713)1--76-23
County: CLINTON
Type of Work: SLURRY SEAL
Route: IOWA 136 Length: 2.07 miles
Location: IN THE CITY OF CLINTON FROM W. JCT. OF U.S. 67 TO WCL

Project No: MP-013-6(715)8--76-57
County: LINN
Type of Work: SLURRY SEAL
Route: IOWA 13 Length: 3.57 miles
Location: FROM U.S. 151 NORTHERLY TO NORTH OF COUNTY HOME ROAD
(E-34)

Item No. Item Description Quantity/Unit

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 203 Proposal ID: 18-7020-014

Proposed Contract Period: Late Start Date of 09/10/12 with 25 WORK DAYS

Project(s):

Project No: DHS-702-0(14)--7H-18

County: CHEROKEE

Type of Work: PCC PATCHING

Route: CEDAR LOOP Length: 0.00 miles

Location: CHEROKEE MENTAL HEALTH INSTITUTE AT VARIOUS LOCATIONS

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,455 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	16 EACH
SECTION NO. 0002		
TUNNEL REPAIRS		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	21 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	5,149 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 204 Proposal ID: 27-0351-121

Proposed Contract Period: Late Start Date of 09/10/12 with 25 WORK DAYS

Project(s):

Project No: IMN-035-1(121)0--0E-27

County: DECATUR

Type of Work: PCC PATCHING

Route: I-35 Length: 72.69 miles

Location: FROM MISSOURI STATE LINE N. TO W. I-35/80/235
INTERCHANGE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,663 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	181 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 206 Proposal ID: 63-0143-046

Proposed Contract Period: Late Start Date of 08/06/12 with 50 WORK DAYS

Proposal Note:

Project(s):

Project No: HSIPX-014-3(46)--3L-63
County: MARION
Type of Work: MILLED RUMBLE STRIPS
Route: IOWA 14 Length: 0.00 miles
Location: FROM NCL OF KNOXVILLE N. TO JUST S. OF I-80 IN NEWTON

Project No: HSIPX-030-6(199)--3L-86
County: TAMA
Type of Work: MILLED RUMBLE STRIPS
Route: U.S. 30 Length: 0.00 miles
Location: FROM TAMA BY-PASS E. TO JUST W. OF U.S. 218

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 207 Proposal ID: 67-0293-713

Proposed Contract Period: Late Start Date of 04/02/12 with 70 WORK DAYS

Project(s):

Project No: MP-183-3(703)44--76-43
County: HARRISON
Type of Work: HMA CRACK FILLING
Route: IOWA 183 Length: 7.27 miles
Location: FROM F-20 IN PISGAH NORTHEAST TO THE SCL OF MOORHEAD

Project No: MPIN-029-3(713)113--0N-67
County: MONONA
Type of Work: HMA CRACK FILLING
Route: I-29 Length: 13.70 miles
Location: FROM JUST NORTH OF THE IA 175 INTERCHANGE TO THE
WOODBURY COUNTY LINE. (SBL)

Project No: MP-037-3(708)0--76-67
County: MONONA
Type of Work: HMA CRACK FILLING
Route: IOWA 37 Length: 10.00 miles
Location: FROM ECL OF TURIN TO JCT. OF IOWA 183 IN SOLDIER.

Project No: MP-141-3(703)26--76-67
County: MONONA
Type of Work: HMA CRACK FILLING
Route: IOWA 141 Length: 10.00 miles
Location: FROM ECL OF MAPLETON TO ECL OF UTE.

Project No: MP-175-3(709)9--76-67
County: MONONA
Type of Work: HMA CRACK FILLING
Route: IOWA 175 Length: 19.50 miles
Location: FROM ECL OF ONAWA TO JCT. IOWA 141 IN MAPLETON.

Project No: MP-012-3(706)8--76-97
County: WOODBURY
Type of Work: HMA CRACK FILLING
Route: IOWA 12 Length: 2.00 miles
Location: RIVERSIDE BLDV. FROM WAR EAGLE TO MILITARY RD. IN SIOUX CITY

Project No: MP-141-3(705)16--76-97
County: WOODBURY
Type of Work: HMA CRACK FILLING
Route: IOWA 141 Length: 7.90 miles
Location: FROM ECL OF SMITHLAND TO NCL OF MAPLETON.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 208 Proposal ID: 73-C073-114

Proposed Contract Period: Late Start Date of 09/04/12 with 5 WORK DAYS

Project(s):

Project No: FM-C073(114)--55-73

County: PAGE

Type of Work: SEAL COAT

Route: MULTIPLE ROUTES Length: 10.05 miles

Location: VARIOUS LOCATIONS IN PAGE COUNTY.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 209 Proposal ID: 82-0741-167

Proposed Contract Period: Late Start Date of 08/27/12 with 35 WORK DAYS

Proposal Note:

Project(s):

Project No: IMN-074-1(167)0--0E-82

County: SCOTT

Type of Work: PCC PATCHING

Route: I-74 Length: 5.36 miles

Location: FROM I-80 SOUTH TO MISSISSIPPI RIVER

Project No: IMN-080-8(251)278--0E-82

County: SCOTT

Type of Work: PCC PATCHING

Route: I-80 Length: 28.63 miles

Location: FROM CEDAR COUNTY LINE EAST TO MISSISSIPPI RIVER

Item No.	Item Description	Quantity/Unit

	SECTION NO. 0001	
	ROADWAY ITEMS	
	IMN-74-1(167)0--0E-82	
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,702 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	101 EACH
	SECTION NO. 0002	
	ROADWAY ITEMS	
	IMN-80-8(251)278--0E-82	
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,361 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	91 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 210 Proposal ID: 85-0301-708

Proposed Contract Period: Late Start Date of 09/24/12 with 15 WORK DAYS

Project(s):

Project No: MP-030-1(708)156--76-85

County: STORY

Type of Work: HMA PATCHING

Route: U.S. 30 Length: 3.50 miles

Location: FROMW. 18TH ST. (AIRPORT RD.) TO NEAR CO. RD. S-27
IN THE CITY OF NEVADA.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	280 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	33 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 211 Proposal ID: 94-1696-085

Proposed Contract Period: Late Start Date of 10/01/12 with 15 WORK DAYS

Proposal Note:

Project(s):

Project No: HSIPX-169-6(85)--3L-94

County: WEBSTER

Type of Work: MILLED RUMBLE STRIPS

Route: U.S. 169 Length: 0.00 miles

Location: FROM N. OF IOWA 7 NEAR FORT DODGE N. TO C-29

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 49-0521-100

Proposed Contract Period: Late Start Date of 10/01/12 with 15 WORK DAYS

Project(s):

Project No: STPN-052-1(100)--2J-49

County: JACKSON

Type of Work: STORM SEWER/INTAKES

Route: U.S. 52 Length: 0.00 miles

Location: IN ST. DONATUS

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	12 CY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	57 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	8 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 73-C073-115

Proposed Contract Period: Late Start Date of 05/14/12 with 15 WORK DAYS

Project(s):

Project No: FM-C073(115)--55-73

County: PAGE

Type of Work: GRANULAR SURFACING OF ROADWAY

Route: MULTIPLE ROUTES Length: 60.00 miles

Location: VARIOUS LOCATIONS IN PAGE COUNTY.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 77-8500-024

Proposed Contract Period: Late Start Date of 07/02/12 with 75 WORK DAYS

Project(s):

Project No: NG-850-0(24)--7D-77

County: POLK

Type of Work: GRADING

Route: DES MOINES AVE Length: 0.00 miles

Location: CAMP DODGE IN JOHNSTON ON DES MOINES AVE. FROM 13TH ST. TO
NW 90TH ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	79,265 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 304 Proposal ID: 91-0355-501

Proposed Contract Period: Late Start Date of 06/18/12 with 30 WORK DAYS

Proposal Note:

*** DEFINITION OF MAINTENANCE BRIDGE NUMBERS ***

THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS
AS SHOWN FOR THE FOLLOWING EXAMPLE:

. BRIDGE NO. 5210.90380:
. (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
. {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
. 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
. (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
. 5210.9{o}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
. (ALPHA VALUES;
. O = OVER, R = RIGHT, L = LEFT,
. A = RAMP, S = SINGLE)
. 5210.9o{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE
FOLLOWING BRIDGES:

. 9158.50035

Project(s):

Project No: MBIN-035-5(501)59--0M-91

County: WARREN

Type of Work: SLOPE PROTECTION

Route: I-35

Length: 0.00 miles

Location: UNDER G-6R 1.7 MILES N. OF IOWA 92

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 305 Proposal ID: 91-0355-707

Proposed Contract Period: Late Start Date of 10/01/12 with 25 WORK DAYS

Proposal Note:

Project(s):

Project No: MPIN-035-5(707)51--0N-91

County: WARREN

Type of Work: SLIDE REPAIR

Route: I-35

Length: 0.00 miles

Location: 1 MILE S. OF G-50 INTERCHANGE

Item No.	Item Description	Quantity/Unit

	SECTION NO. 0001	
	SLIDE REPAIR ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	6,068 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 306 Proposal ID: 97-0297-051

Proposed Contract Period: Late Start Date of 05/28/12 with 80 WORK DAYS

Project(s):

Project No: IM-NHS-029-7(51)149--13-97

County: WOODBURY

Type of Work: SANITARY SEWER

Route: I-29 Length: 0.00 miles

Location: IN THE CITY OF SIOUX CITY FROM PERRY CREEK
LIFT STATION TO TRI-VIEW AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
SANITARY SEWER ITEMS - DIVISION 1		
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	4,759 SY
2511-0302400	RECREATIONAL TRAIL, PCC, 4"	33 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 351 Proposal ID: 00-000S-471

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE DIVISION 1 SIGNS

Completion Date of 07/30/12

Site 02: TO COMPLETE DIVISION 2 SIGNS

Late Start Date of 03/30/12 with 15 WORK DAYS

Project(s):

Project No: NHSN-000-S(471)--2R-00

County: STATEWIDE

Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS STATEWIDE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 25-8177-612

Proposed Contract Period: Late Start Date of 08/06/12 with 50 WORK DAYS

Project(s):

Project No: STP-A-8177(612)--86-25

County: DALLAS

Type of Work: FIBER OPTIC INSTALLATION

Route: MULTIPLE ROUTES Length: 6.70 miles

Location: IN THE CITY OF WAUKEE
CITY FIBER OPTIC NETWORK

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 601 Proposal ID: 08-2101-500

Proposed Contract Period: Late Start Date of 06/18/12 with 45 WORK DAYS

Proposal Note:

*** DEFINITION OF MAINTENANCE BRIDGE NUMBERS ***

THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS
AS SHOWN FOR THE FOLLOWING EXAMPLE:

. BRIDGE NO. 5210.9O380:
. (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
. {52}10.9O380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
. 52{10.9}O380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
. (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
. 5210.9{O}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
. (ALPHA VALUES;
. O = OVER, R = RIGHT, L = LEFT,
. A = RAMP, S = SINGLE)
. 5210.9O{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE
FOLLOWING BRIDGES:

. 0804.9S210

Project(s):

Project No: MB-210-1(500)5--77-08

County: BOONE

Type of Work: BRIDGE PAINTING

Route: IOWA 210

Length: 0.00 miles

Location: OVER DES MOINES RIVER W. OF MADRID

Item No. Item Description Quantity/Unit

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 602 Proposal ID: 43-0294-506

Proposed Contract Period: Late Start Date of 06/18/12 with 45 WORK DAYS

Proposal Note:

*** DEFINITION OF MAINTENANCE BRIDGE NUMBERS ***

THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE:

. BRIDGE NO. 5210.90380:
. (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
. {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
. 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
. (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
. 5210.9{o}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
. (ALPHA VALUES;
. O = OVER, R = RIGHT, L = LEFT,
. A = RAMP, S = SINGLE)
. 5210.90{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES:

. 4396.9S029

Project(s):

Project No: MBIN-029-4(506)96--0M-43
County: HARRISON
Type of Work: BRIDGE PAINTING
Route: I-29 Length: 0.00 miles
Location: OVER LITTLE SIOUX RIVER 0.4 MILE N. OF F-20

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: February 21, 2012 10:00 A.M.

Proposed Bid Order: 603 Proposal ID: 57-3806-539-A

Proposed Contract Period: Late Start Date of 05/07/12 with 60 WORK DAYS

Proposal Note:

*** CLARIFICATION OF LOCATION DESCRIPTION ***

THERE ARE 4 BRIDGES TO BE PAINTED ON THIS CONTRACT. THE LOCATION OF BRIDGE NOS. 5719.7R380 & 5719.7A380 IS I-380 OVER 1ST ST., 2ND AVE. SW, 3RD AVE. SW & 3RD ST. NW IN CEDAR RAPIDS.

BRIDGE NO. 5734.30380 IS AT BOAR ROAD &
BRIDGE NO. 5739.40380 IS AT URBANA ROAD NEAR CEDAR POINT.

*** DEFINITION OF MAINTENANCE BRIDGE NUMBERS ***

THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE:

. BRIDGE NO. 5210.90380:
. (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
. {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
. 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
. (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
. 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
. (ALPHA VALUES;
. O = OVER, R = RIGHT, L = LEFT,
. A = RAMP, S = SINGLE)
. 5210.90{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES:

. 5719.7R380 5719.7A380 5734.30380 5739.40380

Project(s):

Project No: MBIN-380-6(539)31--0M-57

County: LINN

Type of Work: BRIDGE PAINTING

Route: I-380 Length: 0.00 miles

Location: OVER 1ST ST., 2ND AVE. SW, 3RD AVE. SW & 3RD ST. NW IN CEDAR RAPIDS, AT BOAR ROAD & URBANA ROAD NEAR CEDAR POINT.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

