

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: March 20, 2012
Date of Addendum: March 1, 2012

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
001	02-1590-602	Bridge and Approaches - PPCB	Adams	BROS-1590(602)--8J-02	20mar001.a02

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Line No. 0150 2404-7775005 REINFORCING STEEL, EPOXY COATED from 75,941 LB to 78,966 LB.

If the quantity is not changed on the proposal form, the bid amount will be extended using the unit price times the correct quantity as shown here.

Make the following change to the plan:

Sheet Number 2:

TOTAL ESTIMATED QUANTITIES; Change Reinforcing Steel, Epoxy Coated (Super) from 67,842 LB. to 70,867 LB.

TOTAL ESTIMATED QUANTITIES; Change Reinforcing Steel, Epoxy Coated (Total) from 75,941 LB. to 78,966 LB.

Sheet Number 17:

REINFORCING BAR LIST - SUPERSTRUCTURE; Add 5j1 bar| Slab, Transverse, Top at Rail|----|464| 6'-3| 3,025 LB.

BAR	LOCATION	SHAPE	NO.	LENGTH	WEIGHT
5j1	SLAB, TRANSV., TOP AT RAIL	-----	464	6'-3	3,025

REINFORCING BAR LIST - SUPERSTRUCTURE; Change EPOXY COATED TOTAL from 67,842 LB. to 70,867 LB.

ESTIMATED QUANTITIES - SUPERSTRUCTURE; Change REINFORCING STEEL, EPOXY COATED TOTAL from 67,842 LB. to 70,867 LB.