

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 28-C028-076

Proposed Contract Period: Late Start Date of 06/25/12 with 75 WORK DAYS
Project(s):

Project No: BROS-C028(76)--8J-28

County: DELAWARE

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 218TH STREET Length: 0.25 miles

Location: EAST OF EARLVILLE OVER PLUM CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 150-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	987 CY
2403-0100010	STRUCT CONC (BRIDGE)	479 CY
2404-7775000	REINFORC STEEL	6,114 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	96,575 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 31-C031-050-A

Proposed Contract Period: Late Start Date of 05/21/12 with 105 WORK DAYS

Project(s):

Project No: EDP-C031(50)--7Y-31

County: DUBUQUE

Type of Work: BRIDGE NEW - OTHER

Route: RUPP HOLLOW ROAD Length: 0.10 miles

Location: PEDESTRIAN BRIDGE OVER US 52

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	2,055 CY
SECTION NO. 0002		
ITEMS FOR A 136.7 X 12'-0 STEEL TRUSS PEDESTRIAN BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,309 CY
2403-0100010	STRUCT CONC (BRIDGE)	52 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	11,698 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 34-2189-125-A

Proposed Contract Period: Late Start Date of 08/06/12 with 35 WORK DAYS

Project(s):

Project No: BRFN-218-9(125)--39-34
 County: FLOYD
 Type of Work: BRIDGE DECK OVERLAY
 Route: U.S. 218 Length: 0.00 miles
 Location: OVER D.D. 0.4 MILE S. OF MITCHELL
 CO. LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0112; 26'-0 X 44 CONTINUOUS CONCRETE SLAB BRIDGE	
2413-0698074	DECK REPAIR, CL A	17 SY
SECTION NO. 0002		
	DESIGN NO. 0112; ALTERNATE 'AA' OPTION 1: CLASS O PCC	
	BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	
2413-0698066	DECK OVERLAY (CL O PCC)	136 SY
SECTION NO. 0003		
	DESIGN NO. 0112; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC	
	BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	136 SY
SECTION NO. 0004		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	100 CY
2303-0143503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	490 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 36-C036-060

Proposed Contract Period: Late Start Date of 06/25/12 with 75 WORK DAYS

Project(s):

Project No: BRS-C036(60)--60-36

County: FREMONT

Type of Work: BRIDGE AND APPROACHES - PPCB

Route: WASHINGTON STREET Length: 0.00 miles

Location: PLUM CREEK BRIDGE REPLACEMENT

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 110'-0 X 30'-6 PRETENSSED PRESTRESSED CONCRETE BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,236 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	726 SY
2403-0100010	STRUCT CONC (BRIDGE)	193 CY
2404-7775000	REINFORC STEEL	246 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	46,753 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 41-0698-022

Proposed Contract Period: Late Start Date of 07/23/12 with 60 WORK DAYS

Project(s):

Project No: STPN-069-8(22)--2J-41

County: HANCOCK

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: U.S. 69 Length: 0.00 miles

Location: AT 2 LOCATIONS S. OF KLEMME

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0109; ALT. 'AA' OPTION 1: C.I.P. 8'-0 X 6'-0 RCB		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2403-0100020	STRUCT CONC (RCB CULV)	114 CY
2404-7775000	REINFORC STEEL	16,121 LB
SECTION NO. 0003		
DESIGN NO. 0209; ALT. 'BB' OPTION 1: C.I.P. TWIN 8' X 6' RCB		
BID THIS SCETION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN		
2403-0100020	STRUCT CONC (RCB CULV)	193 CY
2404-7775000	REINFORC STEEL	23,906 LB
SECTION NO. 0005		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,913 CY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	306 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 53-C053-056

Proposed Contract Period: Late Start Date of 06/18/12 with 80 WORK DAYS

Project(s):

Project No: BROS-C053(56)--8J-53

County: JONES

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 98TH STREET Length: 0.10 miles

Location: OVER LITTLE BEAR CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 90'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	13,155 CY
2403-0100010	STRUCT CONC (BRIDGE)	217 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	54,632 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 53-1514-116

Proposed Contract Period: Late Start Date of 07/09/12 with 60 WORK DAYS

Project(s):

Project No: BRFN-151-4(116)--39-53
 County: JONES
 Type of Work: BRIDGE DECK OVERLAY
 Route: U.S. 151 Length: 0.00 miles
 Location: US 151 OVER WAPSI RIVER 1.4 MILES S. OF
 IA. 64

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0109; 427' X 30' CONTINUOUS WELDED GIRDER BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	24 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	3,266 LB
2413-0698074	DECK REPAIR, CL A	288 SY
SECTION NO. 0002		
DESIGN NO. 0109; ALTERNATE 'AA' OPTION 1: CLASS O PCC		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2413-0698066	DECK OVERLAY (CL O PCC)	1,410 SY
SECTION NO. 0003		
DESIGN NO. 0109; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	1,410 SY
SECTION NO. 0004		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	400 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 57-3806-281

Proposed Contract Period: Late Start Date of 09/10/12 with 25 WORK DAYS

Project(s):

Project No: IMN-380-6(281)21--0E-57

County: LINN

Type of Work: PPCB REPAIR

Route: I-380 Length: 0.00 miles

Location: IN THE CITY OF CEDAR RAPIDS AT 8TH ST. OVER I-380

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0512; 264'-6 X 30'-0 PPCB BEAM REPLACEMENT	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	67 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	11,351 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 71-C071-068

Proposed Contract Period: Late Start Date of 06/04/12 with 85 WORK DAYS

Project(s):

Project No: BROS-C071(68)--8J-71

County: OBRIEN

Type of Work: BRIDGE REPLACEMENT - CCS

Route: NEST AVENUE Length: 0.00 miles

Location: NW CORNER S 0.8 MI

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 150' -0 X 30'-6 3 SPAN CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	7,889 CY
2108-5025000	OVERHAUL	20,560 ST-Y
2403-0100010	STRUCT CONC (BRIDGE)	430 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	95,745 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 00A Proposal ID: 78-0293-080-M

Proposed Contract Period: By individual sites.

- Site 01: SEE PROPOSAL NOTE FOR SITE 01
Late Start Date of 06/04/12 with 240 WORK DAYS
- Site 02: SEE PROPOSAL NOTE FOR SITE 02
Late Start Date of 06/04/12 with 100 WORK DAYS
- Site 03: SEE PROPOSAL NOTE FOR SITE 03
Late Start Date of 08/06/12 with 40 WORK DAYS
- Site 04: SEE PROPOSAL NOTE FOR SITE 04
Completion Date of 10/03/14

Proposal Note:

SITE 01

FOR COMPLETION OF PROJECTS:
IM-NHS-029-3(086) 52--03-78
IM-NHS-029-3(087) 52--03-78
IM-NHS-029-3(094) 52--03-78
IM-NHS-029-3(095) 52--03-78

SITE 02

TO COMPLETE WORK IN STAGE 1 AS SHOWN IN THE STAGING NOTES ON SHEET C.10 OF IM-NHS-29-3(86) 52--03-78.

SITE 03

TO COMPLETE WORK IN STAGE 1B.1 AND 1B.2 AS SHOWN IN THE STAGING NOTES ON SHEET J.1 OF IM-NHS-029-3(87) 52--03-78

SITE 04

TO COMPLETE IM-NHS-029-3(080) 52--03-78
AND IM-NHS-029-3(081) 52--03-78

OPTIONALLY COMBINED AND INDIVIDUAL PROPOSALS LISTING

THE WORK ON THE FOLLOWING PROJECTS ARE OFFERED IN THIS LETTING ON AN OPTIONALLY COMBINED PROPOSAL AND ON INDIVIDUAL PROPOSALS AS SHOWN BELOW:

B.O.	PROPOSAL ID	COUNTY	PROJECT NO.
011	78-0293-080	POTTAWATTAMIE	IM-NHS-029-3(080) 52--03-78
.			IM-NHS-029-3(081) 52--03-78
113	78-0293-086	POTTAWATTAMIE	IM-NHS-029-3(086) 52--03-78
.			IM-NHS-029-3(087) 52--03-78
.			IM-NHS-029-3(094) 52--03-78
.			IM-NHS-029-3(095) 52--03-78
.	AND		
00A	78-0293-080-M	POTTAWATTAMIE	IM-NHS-029-3(080) 52--03-78

IM-NHS-029-3 (081) 52--03-78

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Project(s) :

Project No: IM-NHS-029-3(80)52--03-78
 County: POTTAWATTAMIE
 Type of Work: BRIDGE NEW - STEEL GIRDER
 Route: I-29 Length: 0.00 miles
 Location: IN THE CITY OF COUNCIL BLUFFS ON NE CONNECTOR SB I-29
 TO I-29/80 OVER I-80 & RAMPS

Project No: IM-NHS-029-3(81)52--03-78
 County: POTTAWATTAMIE
 Type of Work: BRIDGE NEW - STEEL GIRDER
 Route: I-29 Length: 0.00 miles
 Location: IN THE CITY OF COUNCIL BLUFFS ON EB I-80 TO NB
 I-29- RAMP "H" OVER I29/80/RAMPS

Project No: IM-NHS-029-3(86)52--03-78
 County: POTTAWATTAMIE
 Type of Work: PCC PAVEMENT - GRADE AND NEW
 Route: I-29 Length: 1.20 miles
 Location: IN THE CITY OF COUNCIL BLUFFS FROM JUST S. OF NEBRASKA
 AVE. TO JUST W. OF 24TH ST.(I-29 SB)

Project No: IM-NHS-029-3(87)52--03-78
 County: POTTAWATTAMIE
 Type of Work: PCC PAVEMENT - GRADE AND NEW
 Route: I-29 Length: 0.00 miles
 Location: IN THE CITY OF COUNCIL BLUFFS FROM I-80 EB TO
 I-29 NB RAMP "H"

Project No: IM-NHS-029-3(94)52--03-78
 County: POTTAWATTAMIE
 Type of Work: TRAFFIC SIGNS
 Route: I-29 Length: 0.00 miles
 Location: IN THE CITY OF COUNCIL BLUFFS FROM W. OF W. MIXMASTER
 TO E. OF INDIAN CREEK & ON I-29 TO N. OF UP R.R.

Project No: IM-NHS-029-3(95)52--03-78
 County: POTTAWATTAMIE
 Type of Work: LIGHTING
 Route: I-29 Length: 0.00 miles
 Location: IN THE CITY OF COUNCIL BLUFFS FROM E. OF MO. RIVER TO E.
 OF INDIAN CR. & I-29 SB FR 24TH ST TO E. OF INDIAN CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0612; A 2166'-0 X VARIES CONTINUOUS WELDED CURVED GIRDER BRIDGE - IM-NHS-029-3(80)52--03-78		
2102-2625000	EMBANKMENT-IN-PLACE	810 CY
2403-0100010	STRUCT CONC (BRIDGE)	873 CY
2404-7775000	REINFORC STEEL	384,810 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	1,603,705 LB
SECTION NO. 0003		

DESIGN NO. 0512; A 1980'-0 X 32'-0 CONTINUOUS WELDED GIRDER

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

BRIDGE - IM-NHS-029-3(81)52--03-78		
2403-0100010	STRUCT CONC (BRIDGE)	1,746 CY
2404-7775000	REINFORC STEEL	510,081 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	1,000,400 LB
SECTION NO. 0005		
ROADWAY ITEMS - IM-NHS-029-3(86)52--03-78		
2102-2625000	EMBANKMENT-IN-PLACE	67,643 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	887,705 CY
2122-5190012	PAVED SHLD, PCC, 12"	22,584 SY
2301-1004120	STD/S-F PCC PAV'T, QM-C CL 3I, 12"	48,232 SY
SECTION NO. 0010		
ROADWAY ITEMS - IM-NHS-029-3(87)52--03-78		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	14,465 CY
2301-1004120	STD/S-F PCC PAV'T, QM-C CL 3I, 12"	8,418 SY
SECTION NO. 0012		
TRAFFIC SIGN ITEMS - IM-NHS-029-3(94)52--03-78		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	59 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	7,032 LB
SECTION NO. 0013		
LIGHTING ITEMS - IM-NHS-029-3(95)52--03-78		
2404-7775000	REINFORC STEEL	29,686 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 77-2351-506

Proposed Contract Period: Late Start Date of 10/01/12 with 10 WORK DAYS

Project(s):

Project No: MBIN-235-1(506)6--0M-77

County: POLK

Type of Work: BRIDGE REPAIR

Route: I-235 Length: 0.00 miles

Location: IN THE CITY OF DES MOINES AT 3 LOCATIONS ALONG
I-235

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 78-0293-080

Proposed Contract Period: Completion Date of 10/03/14

Proposal Note:

OPTIONALLY COMBINED AND INDIVIDUAL PROPOSALS LISTING
=====

THE WORK ON THE FOLLOWING PROJECTS ARE OFFERED IN THIS
LETTING ON AN OPTIONALLY COMBINED PROPOSAL AND ON INDIVIDUAL
PROPOSALS AS SHOWN BELOW:

B.O.	PROPOSAL ID	COUNTY	PROJECT NO.
====	=====	=====	=====
011	78-0293-080	POTTAWATTAMIE	IM-NHS-029-3 (080) 52--03-78
.			IM-NHS-029-3 (081) 52--03-78
113	78-0293-086	POTTAWATTAMIE	IM-NHS-029-3 (086) 52--03-78
.			IM-NHS-029-3 (087) 52--03-78
.			IM-NHS-029-3 (094) 52--03-78
.			IM-NHS-029-3 (095) 52--03-78
.	AND		
00A	78-0293-080-M	POTTAWATTAMIE	IM-NHS-029-3 (080) 52--03-78
.			IM-NHS-029-3 (081) 52--03-78
.			IM-NHS-029-3 (086) 52--03-78
.			IM-NHS-029-3 (087) 52--03-78
.			IM-NHS-029-3 (094) 52--03-78
.			IM-NHS-029-3 (095) 52--03-78

SEE NOTE 700.11 IN THE PROPOSAL SPECIAL PROVISIONS TEXT.

Project(s):

Project No: IM-NHS-029-3 (80) 52--03-78
 County: POTTAWATTAMIE
 Type of Work: BRIDGE NEW - STEEL GIRDER
 Route: I-29 Length: 0.00 miles
 Location: IN THE CITY OF COUNCIL BLUFFS ON NE CONNECTOR SB I-29
 TO I-29/80 OVER I-80 & RAMPS

Project No: IM-NHS-029-3 (81) 52--03-78
 County: POTTAWATTAMIE
 Type of Work: BRIDGE NEW - STEEL GIRDER
 Route: I-29 Length: 0.00 miles
 Location: IN THE CITY OF COUNCIL BLUFFS ON EB I-80 TO NB
 I-29- RAMP "H" OVER I29/80/RAMPS

Item No.	Item Description	Quantity/Unit

	SECTION NO. 0001	
	DESIGN NO. 0612; A 2166'-0 X VARIES CONTINUOUS WELDED	

CURVED GIRDER BRIDGE - IM-NHS-029-3(80)52--03-78

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0001

DESIGN NO. 0612; A 2166'-0 X VARIES CONTINUOUS WELDED
CURVED GIRDER BRIDGE - IM-NHS-029-3(80)52--03-78

2102-2625000	EMBANKMENT-IN-PLACE	810 CY
2403-0100010	STRUCT CONC (BRIDGE)	873 CY
2404-7775000	REINFORC STEEL	384,810 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	1,603,705 LB

SECTION NO. 0004

DESIGN NO. 0512; A 1980'-0 X 32'-0 CONTINUOUS WELDED GIRDER
BRIDGE - IM-NHS-029-3(81)52--03-78

2403-0100010	STRUCT CONC (BRIDGE)	1,746 CY
2404-7775000	REINFORC STEEL	510,081 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	1,000,400 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 82-0671-130

Proposed Contract Period: Late Start Date of 10/01/12 with 15 WORK DAYS

Project(s):

Project No: MB-067-1(130)--77-82

County: SCOTT

Type of Work: PIER REPAIR

Route: U.S. 67 Length: 0.00 miles

Location: ROCK ISLAND ARSENAL TRAFFIC OVER US 67 IN DAVENPORT

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0212; PIER REPAIR TO A 54'-6 X VAR. WIDTH I-BEAM BRIDGE WITH 2 - 6'-0 SIDEWALKS		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	17 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,685 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 90-0347-130

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE BRF-034-7(131)--38-90

Late Start Date of 05/21/12 with 110 WORK DAYS

Site 02: TO COMPLETE BRF-034-7(130)--38-90

Late Start Date of 04/15/13 with 120 WORK DAYS

Project(s):

Project No: BRF-034-7(130)--38-90

County: WAPELLO

Type of Work: RECONSTRUCTION -BRIDGE SUPER REPLACEMENT

Route: U.S. 34 Length: 0.00 miles

Location: IN THE CITY OF OTTUMWA OVER THE DES MOINES RIVER (EBL)

Project No: BRF-034-7(131)--38-90

County: WAPELLO

Type of Work: RECONSTRUCTION -BRIDGE SUPER REPLACEMENT

Route: U.S. 34 Length: 0.00 miles

Location: OVER DES MOINES RIVER IN OTTUMWA (WBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0112; 770'-0 X 77' CONTINUOUS WELDED GIRDER		
BRIDGE STAGE 2 BRF-034-7(130)--38-90		
2403-0100010	STRUCT CONC (BRIDGE)	385 CY
2404-7775000	REINFORC STEEL	40,163 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	343,060 LB
SECTION NO. 0002		
ROADWAY ITEMS		
BRF-034-7(130)--38-90		
2102-2625000	EMBANKMENT-IN-PLACE	16 CY
2301-1033120	STD/S-F PCC PAV'T, CL C CL 3, 12"	210 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	28 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH
SECTION NO. 0003		
DESIGN NO. 0111; 770'-0 X 77' CONTINUOUS WELDED GIRDER		
BRIDGE STAGE 1 BRF-034-7(131)--38-90		
2403-0100010	STRUCT CONC (BRIDGE)	1,419 CY
2404-7775000	REINFORC STEEL	167,856 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	244,290 LB
SECTION NO. 0004		
ROADWAY ITEMS - NON PARTICIPATING		
BRF-034-7(131)--38-90		
2102-2625000	EMBANKMENT-IN-PLACE	930 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	112 CY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	28 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH
SECTION NO. 0005		

ALTERNATE 'AA' OPTION 1: HMA SHOULDER

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (131)
2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 32 CY
SECTION NO. 0006
ALTERNATE 'AA' OPTION 2: PCC SHOULDER
BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN (131)
2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 29 CY
2122-5190007 PAVED SHLD, PCC, 7" 89 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 015 Proposal ID: 99-0352-500

Proposed Contract Period: Late Start Date of 05/21/12 with 100 WORK DAYS

Project(s):

Project No: MBIN-035-2(500)155--0M-99

County: WRIGHT

Type of Work: DECK JOINT REPAIR

Route: I-35 Length: 0.00 miles

Location: OVER IOWA RIVER AT FRANKLIN CO. LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0111; REPAIRS TO A DUAL 288'-0 X 40' PPCB BRIDGE	
	NBL	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	27 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	3,361 LB
SECTION NO. 0002		
	DESIGN NO. 0211; REPAIRS TO A DUAL 288'-0 X 40' PPCB BRIDGE	
	SBL	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	27 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	3,361 LB
SECTION NO. 0003		
	ROADWAY ITEMS	
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	333 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 07-1185-645

Proposed Contract Period: Late Start Date of 07/30/12 with 10 WORK DAYS

Project(s):

Project No: SRTS-U-1185(645)--8U-07

County: BLACK HAWK

Type of Work: PCC SIDEWALK/TRAIL

Route: ANGIE DRIVE Length: 0.22 miles

Location: IN THE CITY OF CEDAR FALLS
ON ANGIE DR FROM CRESCENT DR TO 3RD ST

Item No.	Item Description	Quantity/Unit
	SECTION NO. 0001	
	SIDEWALK ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	95 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 21-0718-055

Proposed Contract Period: Late Start Date of 05/21/12 with 110 WORK DAYS

Project(s):

Project No: NHSX-071-8(55)--3H-21

County: CLAY

Type of Work: PCC OVERLAY - UNBONDED

Route: U.S. 71 Length: 9.00 miles

Location: FROM N. JCT. US 18 N. TO SCL OF MILFORD (NBL/SBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	284 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	16,245 CY
2122-5190008	PAVED SHLD, PCC, 8"	88 SY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	213 SY
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	2,333 TON
2310-5151600	PCC OVERLAY, QM-C, FURN ONLY	66,292 CY
2310-5151620	PCC OVERLAY, QM-C, PLACE ONLY (UNBONDED)	362,471 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 22-0133-042

Proposed Contract Period: Late Start Date of 05/21/12 with 100 WORK DAYS

Proposal Note:

*** NO EXCUSE ROAD OPENING BONUS FOR CONTRACT ***
THE CONTRACTOR WILL BE PAID THE PREDETERMINED LUMP SUM AMOUNT SHOWN IN THE PROPOSAL SCHEDULE OF PRICES FOR THE BID ITEM 'NO EXCUSE ROAD OPENING BONUS' FOR COMPLETING CONSTRUCTION SO THAT IA 13 IS OPEN TO TRAFFIC ON OR BEFORE THE CALENDAR DATE SHOWN. COMPLIANCE REQUIRES THAT THE CONTRACTOR MUST HAVE ALL OF IA 13 OPEN TO TRAFFIC WITH NO FURTHER LANE CLOSURES. ANY OTHER DELAYS DUE TO WEATHER, CHANGE ORDERS, OVERRUNS OF QUANTITIES, UTILITY DELAYS, OR ANY OTHER DELAYS WILL NOT BE CONSIDERED AS JUSTIFICATION TO MODIFY THE CALENDAR DATE.

Project(s):

Project No: STPN-013-3(42)--2J-22
County: CLAYTON
Type of Work: PCC PAVEMENT - GRADE & REPLACE
Route: IOWA 13 Length: 0.47 miles
Location: IN THE CITY OF STRAWBERRY POINT

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
DIVISION 1 - STATE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,657 CY
2301-1033095	STD/S-F PCC PAV'T, CL C CL 3, 9.5"	8,786 SY
SECTION NO. 0003		
NO EXCUSE ROAD OPENING BONUS FOR THE CONTRACT		
2528-5160000	NO EXCUSE ROAD OPENING BONUS, _____	Lump Sum LUMP

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 25-C025-088

Proposed Contract Period: Late Start Date of 05/21/12 with 110 WORK DAYS

Project(s):

Project No: STP-S-C025(88)--5E-25
 County: DALLAS
 Type of Work: PCC PAVEMENT - REPLACE
 Route: P-58 Length: 3.50 miles
 Location: F-25 TO 150TH ST.

Project No: BRS-C025(89)--60-25
 County: DALLAS
 Type of Work: BRIDGE REPLACEMENT - PPCB
 Route: P-58 Length: 0.10 miles
 Location: OVER N. RACCOON RIVER

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
ROADWAY ITEMS		
		STP-5-C025(88)--5E-25
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,440 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	51,450 SY
SECTION NO. 0002		
ITEMS FOR A 409'-0 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
		BRS-C025(89)--60-25
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	320 CY
2403-0100010	STRUCT CONC (BRIDGE)	307 CY
2404-7775000	REINFORC STEEL	45,540 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	137,388 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 31-PA27-003

Proposed Contract Period: Late Start Date of 05/21/12 with 55 WORK DAYS

Project(s):

Project No: TCSP-PA27(003)--9S-31

County: DUBUQUE

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: LORAS BLVD Length: 0.35 miles

Location: IN THE CITY OF DUBUQUE

LORAS BLVD TO KIRKWOOD ST

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,300 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	1,719 SY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	380 SY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	342 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 106 Proposal ID: 51-2465-621

Proposed Contract Period: Late Start Date of 06/11/12 with 40 WORK DAYS

Proposal Note:

WORK RESTRICTION

WORK CANNOT BEGIN PRIOR TO JUNE 11, 2012 FOR
STP-U-2465(621)--70-51.

Project(s):

Project No: STP-U-2465(621)--70-51

County: JEFFERSON

Type of Work: PCC PAVEMENT - REPLACE

Route: SOUTH D STREET Length: 0.28 miles

Location: IN THE CITY OF FAIRFIELD
180 FT. S. OF MADISON TO BURLINGTON AVE.

Project No: STP-U-2465(622)--70-51

County: JEFFERSON

Type of Work: PCC PAVEMENT - REPLACE

Route: KIRKWOOD AVE. Length: 0.11 miles

Location: IN THE CITY OF FAIRFIELD
7TH ST TO 5TH ST

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
STP-U-2465(621)--70-51		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	618 CY
2301-1033070	STD/S-F PCC PAV'T, CL C CL 3, 7"	5,016 SY
SECTION NO. 0002		
ROADWAY ITEMS		
STP-U-2465(622)--70-51		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	160 CY
2301-1033070	STD/S-F PCC PAV'T, CL C CL 3, 7"	1,904 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 52-C052-091

Proposed Contract Period: Late Start Date of 06/04/12 with 55 WORK DAYS

Project(s):

Project No: FM-C052(91)--55-52

County: JOHNSON

Type of Work: PCC OVERLAY - UNBONDED

Route: F62 Length: 0.00 miles

Location: FROM UTAH AVE. TO WAPSIE AVE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	11,900 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	192 SY
2303-0133500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,266 SY
2310-5151040	PCC OVERLAY, FURN ONLY	4,000 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	19,794 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	120 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 108 Proposal ID: 52-0806-306

Proposed Contract Period: Late Start Date of 05/21/12 with 120 WORK DAYS

Project(s):

Project No: IM-080-6(276)244--13-52
 County: JOHNSON
 Type of Work: LIGHTING
 Route: I-80 Length: 0.00 miles
 Location: IN THE CITY OF IOWA CITY AT THE DUBUQUE ST.
 INTERCHANGE

Project No: IM-080-6(278)244--13-52
 County: JOHNSON
 Type of Work: TRAFFIC SIGNALS
 Route: I-80 Length: 0.00 miles
 Location: IN THE CITY OF IOWA CITY AT THE DUBUQUE ST.
 INTERCHANGE

Project No: IM-080-6(306)244--13-52
 County: JOHNSON
 Type of Work: PCC PAVEMENT - GRADE & REPLACE
 Route: I-80 Length: 0.00 miles
 Location: IN THE CITY OF IOWA CITY AT THE DUBUQUE ST.
 INTERCHANGE

Project No: IM-080-6(319)244--13-52
 County: JOHNSON
 Type of Work: TRAFFIC SIGNS
 Route: I-80 Length: 0.00 miles
 Location: IN THE CITY OF IOWA CITY AT THE DUBUQUE ST.
 INTERCHANGE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0003		
ROADWAY ITEMS		
IM-080-6(306)244--13-52		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	31,662 CY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	20,334 SY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	277 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	360 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	300 TON
SECTION NO. 0005		
ALTERNATE 'AA' OPTION 2: PCC PAVED SHOULDER - (306)		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2122-5190007	PAVED SHLD, PCC, 7"	5,729 SY
SECTION NO. 0006		
DESIGN NO. 0110; REPAIRS TO DUAL 236'-0 X 30'-0 CONTINUOUS		
I-BEAM BRIDGES - IM-080-6(306)244-13-52		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	13 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0006

DESIGN NO. 0110; REPAIRS TO DUAL 236'-0 X 30'-0 CONTINUOUS

I-BEAM BRIDGES - IM-080-6(306)244-13-52

2404-7775005 REINFORC STEEL, EPOXY COATED

2,159 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 109 Proposal ID: 52-3715-637

Proposed Contract Period: Late Start Date of 05/21/12 with 200 WORK DAYS
Site 01: SEE PROPOSAL NOTES
Late Start Date of 05/21/12 with 50 WORK DAYS
Site 02: SEE PROPOSAL NOTES
Late Start Date of 05/21/12 with 115 WORK DAYS

Proposal Note:

SITE 01

TO COMPLETE THE FOLLOWING CONSTRUCTION ACTIVITIES:
PHASE 2 - STAGE 2A AND 3A (SYCAMORE STREET INTERSECTION)
PHASE 2 - STAGE 2A AND 3A (SYCAMORE ST AND DEFOREST AVE)
PHASE 3 - STAGE 1 (KIRKWOOD COMMUNITY COLLEGE DRIVE/PARKING)

SITE 02

TO COMPLETE THE FOLLOWING CONSTRUCTION ACTIVITIES:
PHASE 2 - ALL PERMANENT CONSTRUCTION AND OPEN TO TRAFFIC

Project(s):

Project No: STP-U-3715(637)--70-52
County: JOHNSON
Type of Work: PCC PAVEMENT - GRADE & REPLACE
Route: LOWER MUSCATINE ROAD Length: 0.84 miles
Location: IN THE CITY OF IOWA CITY
KIRKWOOD AVENUE TO FIRST AVENUE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 110 Proposal ID: 58-C058-044

Proposed Contract Period: Late Start Date of 09/03/12 with 35 WORK DAYS

Project(s):

Project No: STP-S-C058(44)--5E-58

County: LOUISA

Type of Work: PCC OVERLAY - UNBONDED

Route: X-17 Length: 5.70 miles

Location: STATE HIGHWAY 92 TO X AVENUE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,450 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	4,977 SY
2310-5151040	PCC OVERLAY, FURN ONLY	14,543 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	69,398 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 111 Proposal ID: 77-1425-621

Proposed Contract Period: Late Start Date of 07/30/12 with 55 WORK DAYS

Project(s):

Project No: STP-A-1425(621)--86-77

County: POLK

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: NW 142ND STREET Length: 0.20 miles

Location: IN THE CITY OF CLIVE FROM NORTH OF HAWTHORN DR AND SOUTH OF
HICKMAN RD (U.S. 6)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,754 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	4,691 SY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	741 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 112 Proposal ID: 77-8260-624

Proposed Contract Period: Late Start Date of 05/21/12 with 125 WORK DAYS

Site 01: TO COMPLETE ALL STAGE 2B WORK SHOWN ON PLAN SHEET J.1.

No Start Date Specified with 30 WORK DAYS

Site 02: OUTSIDE SB HWY 28 LANE CLOSURE, SEE STAGE 3A ON SHEET J.1.

No Start Date Specified with 15 WORK DAYS

Site 03: TO COMPLETE CONSTRUCTION OF THE S. 1ST ST. CUL-DE-SAC.

Completion Date of 08/15/12

Site 04: TO COMPLETE ALL STAGE 3B WORK SHOWN ON PLAN SHEET J.1.

No Start Date Specified with 15 WORK DAYS

Project(s):

Project No: STP-U-8260(624)--70-77

County: POLK

Type of Work: PCC PAVEMENT - GRADE AND NEW

Route: SW CONNECTOR Length: 0.69 miles

Location: IN THE CITY OF WEST DES MOINES

FROM INT WITH BROWNS WOODS DR TO IA-28

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	77,526 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	1,200 CY
2301-1033060	STD/S-F PCC PAV'T, CL C CL 3, 6"	990 SY
2301-1033070	STD/S-F PCC PAV'T, CL C CL 3, 7"	1,346 SY
2301-1033095	STD/S-F PCC PAV'T, CL C CL 3, 9.5"	5,733 SY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	6,534 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	1,505 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 113 Proposal ID: 78-0293-086

Proposed Contract Period: Late Start Date of 06/04/12 with 240 WORK DAYS
Site 01: SEE PROPOSAL NOTE FOR SITE 01
Late Start Date of 06/04/12 with 100 WORK DAYS
Site 02: SEE PROPOSAL NOTE FOR SITE 02
Late Start Date of 08/06/12 with 40 WORK DAYS

Proposal Note:

SITE 01

TO COMPLETE WORK IN STAGE 1 AS SHOWN IN THE STAGING NOTES ON SHEET C.10 OF IM-NHS-29-3(86)52--03-78.

SITE 02

TO COMPLETE WORK IN STAGE 1B.1 AND 1B.2 AS SHOWN IN THE STAGING NOTES ON SHEET J.1 OF IM-NHS-029-3(87)52--03-78

OPTIONALLY COMBINED AND INDIVIDUAL PROPOSALS LISTING
=====

THE WORK ON THE FOLLOWING PROJECTS ARE OFFERED IN THIS LETTING ON AN OPTIONALLY COMBINED PROPOSAL AND ON INDIVIDUAL PROPOSALS AS SHOWN BELOW:

B.O.	PROPOSAL ID	COUNTY	PROJECT NO.
====	=====	=====	=====
011	78-0293-080	POTTAWATTAMIE	IM-NHS-029-3(080)52--03-78
.			IM-NHS-029-3(081)52--03-78
113	78-0293-086	POTTAWATTAMIE	IM-NHS-029-3(086)52--03-78
.			IM-NHS-029-3(087)52--03-78
.			IM-NHS-029-3(094)52--03-78
.			IM-NHS-029-3(095)52--03-78
.	AND		
00A	78-0293-080-M	POTTAWATTAMIE	IM-NHS-029-3(080)52--03-78
.			IM-NHS-029-3(081)52--03-78
.			IM-NHS-029-3(086)52--03-78
.			IM-NHS-029-3(087)52--03-78
.			IM-NHS-029-3(094)52--03-78
.			IM-NHS-029-3(095)52--03-78

SEE NOTE 700.11 IN THE PROPOSAL SPECIAL PROVISIONS TEXT.

Project(s):

Project No: IM-NHS-029-3(86)52--03-78
County: POTTAWATTAMIE
Type of Work: PCC PAVEMENT - GRADE AND NEW
Route: I-29 Length: 1.20 miles
Location: IN THE CITY OF COUNCIL BLUFFS FROM JUST S. OF NEBRASKA AVE. TO JUST W. OF 24TH ST.(I-29 SB)

Project No: IM-NHS-029-3(87)52--03-78

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

County: POTTAWATTAMIE
 Type of Work: PCC PAVEMENT - GRADE AND NEW
 Route: I-29 Length: 0.00 miles
 Location: IN THE CITY OF COUNCIL BLUFFS FROM I-80 EB TO
 I-29 NB RAMP "H"

Project No: IM-NHS-029-3(94)52--03-78
 County: POTTAWATTAMIE
 Type of Work: TRAFFIC SIGNS
 Route: I-29 Length: 0.00 miles
 Location: IN THE CITY OF COUNCIL BLUFFS FROM W. OF W. MIXMASTER
 TO E. OF INDIAN CREEK & ON I-29 TO N. OF UP R.R.

Project No: IM-NHS-029-3(95)52--03-78
 County: POTTAWATTAMIE
 Type of Work: LIGHTING
 Route: I-29 Length: 0.00 miles
 Location: IN THE CITY OF COUNCIL BLUFFS FROM E. OF MO. RIVER TO E.
 OF INDIAN CR. & I-29 SB FR 24TH ST TO E. OF INDIAN CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS - IM-NHS-029-3(86)52--03-78		
2102-2625000	EMBANKMENT-IN-PLACE	67,643 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	887,705 CY
2122-5190012	PAVED SHLD, PCC, 12"	22,584 SY
2301-1004120	STD/S-F PCC PAV'T, QM-C CL 3I, 12"	48,232 SY
SECTION NO. 0006		
ROADWAY ITEMS - IM-NHS-029-3(87)52--03-78		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	14,465 CY
2301-1004120	STD/S-F PCC PAV'T, QM-C CL 3I, 12"	8,418 SY
SECTION NO. 0008		
TRAFFIC SIGN ITEMS - IM-NHS-029-3(94)52--03-78		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	59 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	7,032 LB
SECTION NO. 0009		
LIGHTING ITEMS - IM-NHS-029-3(95)52--03-78		
2404-7775000	REINFORC STEEL	29,686 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 23-C023-091

Proposed Contract Period: Late Start Date of 08/27/12 with 25 WORK DAYS

Project(s):

Project No: STP-S-C023(91)--5E-23

County: CLINTON

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: Y60 Length: 4.45 miles

Location: SCL OF DELMAR S. TO U.S. 61

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0021500	HMA (300K ESAL) BASE, 1/2"	5,032 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	5,032 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 23-1855-615

Proposed Contract Period: Late Start Date of 05/21/12 with 110 WORK DAYS

Project(s):

Project No: STP-U-1855(615)--70-23

County: CLINTON

Type of Work: HMA RESURFACING WITH MILLING

Route: 11TH ST Length: 0.95 miles

Location: IN THE CITY OF DE WITT
6TH AVE TO SILVER CREEK BRIDGE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	81 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	760 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	3,095 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 31-1147-604

Proposed Contract Period: Late Start Date of 09/17/12 with 15 WORK DAYS

Project(s):

Project No: STP-U-1147(604)--70-31

County: DUBUQUE

Type of Work: HMA RESURFACING WITH MILLING

Route: 1ST AVENUE Length: 0.60 miles

Location: IN THE CITY OF CASCADE

MONROE ST NE TO FOX ST. SE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	851 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	888 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	72 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	1 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 41-C041-107

Proposed Contract Period: Late Start Date of 08/27/12 with 30 WORK DAYS

Project(s):

Project No: STP-S-C041(107)--5E-41

County: HANCOCK

Type of Work: HMA RESURFACING

Route: B20 Length: 7.00 miles

Location: JCT US 69 EAST TO CERRO GORDO CO. LINE

Project No: FM-C041(108)--55-41

County: HANCOCK

Type of Work: HMA RESURFACING

Route: R70 Length: 3.17 miles

Location: JCT B-20 N AND W TO NEAR CEN SEC 16-97-2
3

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
STP-S-C041(107)--5E-41		
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	16,202 TON
SECTION NO. 0002		
ROADWAY ITEMS		
FM-C041(108)--55-41		
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	6,034 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 155 Proposal ID: 45-C045-063

Proposed Contract Period: Late Start Date of 08/06/12 with 45 WORK DAYS

Project(s):

Project No: STP-S-C045(63)--5E-45

County: HOWARD

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: V-18 Length: 8.50 miles

Location: CITY OF ELMA TO HWY 9

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	17,719 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	224 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 156 Proposal ID: 60-C060-076

Proposed Contract Period: Late Start Date of 06/04/12 with 85 WORK DAYS

Project(s):

Project No: FM-C060 (76)--55-60
 County: LYON
 Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
 Route: K52 Length: 6.25 miles
 Location: A34 TO HWY9

Project No: FM-C060 (93)--55-60
 County: LYON
 Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
 Route: K60 Length: 5.00 miles
 Location: INT. OF A52 TO INT.OF A34

Project No: FM-C060 (94)--55-60
 County: LYON
 Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
 Route: K52 Length: 5.00 miles
 Location: INT. OF A52 TO INT. OF A34

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
FM-C060 (76)--55-60		
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	3,896 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	9,885 TON
SECTION NO. 0002		
ROADWAY ITEMS		
FM-C060 (93)--55-60		
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	4,079 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	6,548 TON
SECTION NO. 0003		
ROADWAY ITEMS		
FM-C060 (94)--55-60		
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	6,386 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	6,564 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 157 Proposal ID: 60-C060-089

Proposed Contract Period: Late Start Date of 09/10/12 with 20 WORK DAYS

Project(s):

Project No: STP-S-C060(89)--5E-60

County: LYON

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: K30 Length: 3.00 miles

Location: SIOUX CO LNE TO INT OF K30 & A42

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	3,609 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	3,697 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 158 Proposal ID: 83-C083-052

Proposed Contract Period: Late Start Date of 08/20/12 with 35 WORK DAYS

Project(s):

Project No: STP-S-C083(52)--5E-83

County: SHELBY

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: F-58 Length: 10.00 miles

Location: M-47 TO EAST 8.6 MILES

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	19,771 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 159 Proposal ID: 84-C084-139

Proposed Contract Period: Late Start Date of 06/25/12 with 70 WORK DAYS

Project(s):

Project No: STP-S-C084(139)--5E-84
 County: SIOUX
 Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
 Route: B-40 Length: 6.50 miles
 Location: B40 AT SIOUX CENTER, IA TO 6.5 MILE WEST

Project No: FM-C084(140)--55-84
 County: SIOUX
 Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
 Route: B-46 Length: 5.00 miles
 Location: N. OF HAWARDEN, IA

Project No: FM-C084(141)--55-84
 County: SIOUX
 Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
 Route: B-14 Length: 2.00 miles
 Location: NORTH OF HULL, IA TO

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		STP-S-C084(139)--5E-84
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	10,951 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	7,465 TON
SECTION NO. 0002		
ROADWAY ITEMS		
		FM-C084(140)--55-84
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	13,781 TON
SECTION NO. 0003		
ROADWAY ITEMS		
		FM-C084(141)--55-84
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	5,557 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 160 Proposal ID: 85-C085-114

Proposed Contract Period: Late Start Date of 09/17/12 with 25 WORK DAYS

Project(s):

Project No: FM-C085(114)--55-85

County: STORY

Type of Work: HMA RESURFACING

Route: E57 Length: 2.50 miles

Location: 595TH AVE EAST 2.48 MILES TO S14

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	3,260 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 161 Proposal ID: 85-0305-240

Proposed Contract Period: Late Start Date of 07/09/12 with 75 WORK DAYS

Project(s):

Project No: NHSX-030-5(240)--3H-85

County: STORY

Type of Work: HMA RESURFACING

Route: U.S. 30 Length: 8.20 miles

Location: FROM COLO E. TO STATE CENTER (EBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	470 CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	6,003 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	22,217 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	17,877 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,515 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	6 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 162 Proposal ID: 92-0929-104

Proposed Contract Period: Late Start Date of 06/25/12 with 75 WORK DAYS

Project(s):

Project No: STP-092-9(104)--2C-92

County: WASHINGTON

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 92 Length: 5.15 miles

Location: FROM N. JCT. IA. 1 E. TO ECL OF WASHINGTON

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0031500	HMA (1M ESAL) BASE, 1/2"	2,538 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	9,202 TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	2,267 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	4,701 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	830 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	23 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 163 Proposal ID: 96-C096-107

Proposed Contract Period: Late Start Date of 07/09/12 with 60 WORK DAYS

Project(s):

Project No: FM-C096(107)--55-96

County: WINNESHIEK

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: POLE LINE ROAD Length: 4.56 miles

Location: CO. RD. W14 TO ST. HWY 9 & 139

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	300 CY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	7,234 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	7,075 TON
2403-0100020	STRUCT CONC (RCB CULV)	137 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	21,556 LB
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	73 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 164 Proposal ID: 97-6890-607

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE ALL SEGMENT 1 WORK SHOWN ON PLAN SHEET J.1.

Specified Start Date of 06/04/12 with 40 WORK DAYS

Site 02: TO COMPLETE ALL SEGMENT 2 WORK SHOWN ON PLAN SHEET J.1.

Specified Start Date of 07/16/12 with 35 WORK DAYS

Project(s):

Project No: STP-U-6890(607)--70-97

County: WOODBURY

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: K45 Length: 0.65 miles

Location: IN THE CITY OF SERGEANT BLUFF
SOUTH LEWIS BLVD AT WARRIOR RD INTERSEC

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	2,080 CY
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,368 TON
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	30 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 04-0025-704

Proposed Contract Period: Late Start Date of 10/01/12 with 35 WORK DAYS

Project(s):

Project No: MP-002-5(704)172--76-04

County: APPANOOSE

Type of Work: HMA CRACK FILLING

Route: IOWA 2 Length: 24.87 miles

Location: FROM EAST OF IA 5 IN THE CITY OF CENTERVILLE TO THE EAST
JCT. OF US 63 AND IA 2, SOUTH OF BLOOMFIELD.

Project No: MP-202-5(702)8--76-04

County: APPANOOSE

Type of Work: HMA CRACK FILLING

Route: IOWA 202 Length: 2.55 miles

Location: FROM 8TH STREET IN THE CITY OF MOULTON TO IA 2.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 06-2186-705

Proposed Contract Period: Late Start Date of 07/30/12 with 40 WORK DAYS

Project(s):

Project No: MP-218-6(705)150--76-06

County: BENTON

Type of Work: SLURRY SEAL

Route: U.S. 218 Length: 16.17 miles

Location: FROM WCL OF VINTON TO LAPORTE CITY.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 203 Proposal ID: 13-0071-702

Proposed Contract Period: Late Start Date of 05/21/12 with 75 WORK DAYS

Project(s):

Project No: MP-007-1(702)58--76-13
County: CALHOUN
Type of Work: HMA JOINT & CRACK SEALING
Route: IOWA 7 Length: 15.22 miles
Location: FROM 3.9 MILES W. OF WEBSTER CO. LINE E. TO US 169

Project No: MP-014-1(711)129--76-38
County: GRUNDY
Type of Work: HMA JOINT & CRACK SEALING
Route: IOWA 14 Length: 7.46 miles
Location: FROM WCL OF GRUNDY CENTER E & N TO NEAR US 20.

Project No: MP-069-1(707)139--76-40
County: HAMILTON
Type of Work: HMA JOINT & CRACK SEALING
Route: U.S. 69 Length: 7.62 miles
Location: FROM JUST N. OF JEWELL TO NEAR US 20.

Project No: MP-175-1(709)188--76-42
County: HARDIN
Type of Work: HMA JOINT & CRACK SEALING
Route: IOWA 175 Length: 8.02 miles
Location: FROM ECL OF ELDORA TO JCT. T19.

Project No: MP-014-1(708)106--76-64
County: MARSHALL
Type of Work: HMA JOINT & CRACK SEALING
Route: IOWA 14 Length: 5.73 miles
Location: FROM 1.5 MILE S. OF IA 330, NORTH 5.7 MILES.

Project No: MP-021-1(705)30--76-79
County: POWESHIEK
Type of Work: HMA JOINT & CRACK SEALING
Route: IOWA 21 Length: 11.70 miles
Location: FROM IA. 85 N. TO US 6

Project No: MP-021-1(705)57--76-86
County: TAMA
Type of Work: HMA JOINT & CRACK SEALING
Route: IOWA 21 Length: 3.38 miles
Location: FROM NCL OF BELLE PLAINE TO US 30.

Project No: MP-030-1(703)206--76-86
County: TAMA
Type of Work: HMA JOINT & CRACK SEALING
Route: U.S. 30 Length: 12.01 miles
Location: FROM 2 MILES EAST OF TAMA TO NEAR THE BENTON CO. LINE.

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Project No: MP-063-1(707)140--76-86
County: TAMA
Type of Work: HMA JOINT & CRACK SEALING
Route: U.S. 63 Length: 10.19 miles
Location: FROM NCL OF TRAER TO SCL OF HUDSON.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 204 Proposal ID: 26-0631-073

Proposed Contract Period: Late Start Date of 08/20/12 with 35 WORK DAYS

Project(s):

Project No: HSIPX-063-1(73)--3L-26

County: DAVIS

Type of Work: MILLED RUMBLE STRIPS

Route: U.S. 63 Length: 15.43 miles

Location: FROM 0.25 MILE N. OF NCL OF BLOOMFIELD N. TO
0.25 MILE S. OF SCL OF OTTUMWA

Project No: HSIPX-005-3(64)--3L-63

County: MARION

Type of Work: MILLED RUMBLE STRIPS

Route: IOWA 5 Length: 0.00 miles

Location: FROM NCL OF LOVILIA N. TO IA. 92 NEAR KNOXVILLE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 205 Proposal ID: 48-0806-711

Proposed Contract Period: Late Start Date of 07/23/12 with 40 WORK DAYS

Project(s):

Project No: MPIN-080-6(711)210--0N-48

County: IOWA

Type of Work: HMA JOINT & CRACK SEALING

Route: I-80 Length: 5.47 miles

Location: FROM 3.5 MI. E. OF CO. RD. V-38 TO 3.5 MI. E. OF
CO. RD. V-52. (WBL)

Project No: MPIN-074-6(706)0--0N-82

County: SCOTT

Type of Work: HMA JOINT & CRACK SEALING

Route: I-74 Length: 5.36 miles

Location: FROM I-80 TO ILLINOIS STATE LINE.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 206 Proposal ID: 48-0806-712

Proposed Contract Period: Late Start Date of 08/13/12 with 10 WORK DAYS

Project(s):

Project No: MPIN-080-6(706)258--0N-16

County: CEDAR

Type of Work: HMA PAVED SHOULDER - FOG SEAL

Route: I-80 Length: 8.10 miles

Location: FROM 3 MI. E. OF WEST BRANCH TO THE CEDAR RIVER.

Project No: MPIN-080-6(712)226--0N-48

County: IOWA

Type of Work: HMA PAVED SHOULDER - FOG SEAL

Route: I-80 Length: 14.90 miles

Location: FROM 1 MI. E. OF US 151 TO E. OF IA 965.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 207 Proposal ID: 52-3806-707

Proposed Contract Period: Late Start Date of 07/23/12 with 20 WORK DAYS

Project(s):

Project No: MPIN-380-6(707)0--0N-52

County: JOHNSON

Type of Work: HMA PAVED SHOULDER - FOG SEAL

Route: I-380 Length: 17.27 miles

Location: FROM I-80 TO 1 MI. N. OF US 30.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 208 Proposal ID: 55-0152-702

Proposed Contract Period: Late Start Date of 08/27/12 with 15 WORK DAYS

Project(s):

Project No: MP-015-2(702)31--76-55

County: KOSSUTH

Type of Work: SLURRY SEAL

Route: IOWA 15 Length: 17.59 miles

Location: FROM E. JCT. US 18 N. TO CO. RD. P-12

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 209 Proposal ID: 58-0929-142

Proposed Contract Period: Late Start Date of 10/01/12 with 15 WORK DAYS

Project(s):

Project No: HSIPX-092-9(142)--3L-58

County: LOUISA

Type of Work: MILLED RUMBLE STRIPS

Route: IOWA 92 Length: 17.18 miles

Location: FROM APPROX. 0.5 MILE E. OF US 218 TO NEAR WCL OF
COLUMBUS JCT. AND FROM ECL OF COLUMBUS JCT. TO US 61

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 210 Proposal ID: 77-2351-704

Proposed Contract Period: Late Start Date of 06/04/12 with 70 WORK DAYS

Project(s):

Project No: MP-163-1(702)21--76-50
 County: JASPER
 Type of Work: HMA JOINT & CRACK SEALING
 Route: IOWA 163 Length: 6.68 miles
 Location: FROM NEAR F62 EAST TO 0.7 MI. N. OF OTLEY (WB LANES)

Project No: MP-224-1(703)0--76-50
 County: JASPER
 Type of Work: HMA JOINT & CRACK SEALING
 Route: IOWA 224 Length: 1.50 miles
 Location: FROM I-80 NORTH 1.5 MILES.

Project No: MP-163-1(705)3--76-77
 County: POLK
 Type of Work: HMA JOINT & CRACK SEALING
 Route: IOWA 163 Length: 10.39 miles
 Location: IN THE CITY OF PLEASANT HILL FROM WCL EAST TO SE 128TH ST.

Project No: MPIN-235-1(704)0--0N-77
 County: POLK
 Type of Work: HMA JOINT & CRACK SEALING
 Route: I-235 Length: 6.50 miles
 Location: FROM JCT. I-35/80 EAST 6.5 MILES.

Project No: MP-415-1(710)13--76-77
 County: POLK
 Type of Work: HMA JOINT & CRACK SEALING
 Route: IOWA 415 Length: 4.00 miles
 Location: FROM S. 3RD STREET IN POLK CITY, WEST TO IA 141.

Project No: MPIN-035-1(707)104--0N-85
 County: STORY
 Type of Work: HMA JOINT & CRACK SEALING
 Route: I-35 Length: 7.75 miles
 Location: FROM 1 MILE NORTH OF IA 210 TO NEAR US 30.
 (SB INSIDE SHOULDER ONLY.)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 212 Proposal ID: 81-0713-709

Proposed Contract Period: Late Start Date of 09/10/12 with 20 WORK DAYS

Project(s):

Project No: MP-030-3(709)84--76-14
 County: CARROLL
 Type of Work: PCC PATCHING
 Route: U.S. 30 Length: 0.10 miles
 Location: IN THE CITY OF CARROLL NEAR THE ECL. (EB LANES.)

Project No: MP-071-3(709)129--76-81
 County: SAC
 Type of Work: PCC PATCHING
 Route: U.S. 71 Length: 12.00 miles
 Location: NEAR ULMER AND FROM THE W. JCT. OF IA 175, TO NORTH OF THE
 N. JCT. OF US 20.

Project No: MP-175-3(701)59--76-81
 County: SAC
 Type of Work: PCC PATCHING
 Route: IOWA 175 Length: 9.26 miles
 Location: FROM THE IDA COUNTY LINE TO THE W. JCT. OF US 71.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
MP-030-3(709)84--76-14		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	190 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH
SECTION NO. 0002		
ROADWAY ITEMS		
MP-071-3(709)129--76-81		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,479 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	74 EACH
SECTION NO. 0003		
ROADWAY ITEMS		
MP-175-3(701)59--76-81		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	138 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	16 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 213 Proposal ID: 83-0593-704

Proposed Contract Period: Late Start Date of 09/04/12 with 65 WORK DAYS

Project(s):

Project No: MP-141-3(704)63--76-24

County: CRAWFORD

Type of Work: HMA CRACK FILLING

Route: IOWA 141 Length: 20.95 miles

Location: FROM THE S. JCT. OF US 59, EAST TO NEAR THE W. JCT. OF US 71

Project No: MP-059-3(704)77--76-83

County: SHELBY

Type of Work: HMA CRACK FILLING

Route: U.S. 59 Length: 27.49 miles

Location: FROM THE NCL OF HARLAN TO THE S. JCT. OF US 30 IN DENISON.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 214 Proposal ID: 97-0203-714

Proposed Contract Period: Late Start Date of 09/24/12 with 20 WORK DAYS

Project(s):

Project No: MP-020-3(714)13--76-97
 County: WOODBURY
 Type of Work: PCC PATCHING
 Route: U.S. 20 Length: 8.47 miles
 Location: FROM ECL OF LAWTON TO THE END OF THE 4-LANE SECTION.
 (EBL & WBL)

Project No: MP-031-3(707)21--76-97
 County: WOODBURY
 Type of Work: PCC PATCHING
 Route: IOWA 31 Length: 0.01 miles
 Location: AT THE JCT. OF IA 31 AND US 20.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
MP-020-3(714)13--76-97		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,268 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	88 EACH
SECTION NO. 0002		
ROADWAY ITEMS		
MP-031-3(707)21--76-97		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	266 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 18-0032-059

Proposed Contract Period: Late Start Date of 10/08/12 with 15 WORK DAYS

Project(s):

Project No: STPN-003-2(59)--2J-18

County: CHEROKEE

Type of Work: SLIDE REPAIR

Route: IOWA 3 Length: 0.15 miles

Location: NEAR ECL OF CHEROKEE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: NOTUSED; 12/04

Project(s):

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 27-0691-040

Proposed Contract Period: Late Start Date of 10/22/12 with 10 WORK DAYS

Project(s):

Project No: ER-069-1(40)--28-27

County: DECATUR

Type of Work: SLIDE REPAIR

Route: U.S. 69 Length: 0.00 miles

Location: 1.5 MILES S. OF DAVIS CITY

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	100 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 304 Proposal ID: 39-1415-024

Proposed Contract Period: Late Start Date of 10/08/12 with 15 WORK DAYS

Project(s):

Project No: STPN-141-5(24)--2J-39

County: GUTHRIE

Type of Work: SLIDE REPAIR

Route: IOWA 141 Length: 0.00 miles

Location: APPROX. 3.4 MILES E. OF COON RAPIDS

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	5,671 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 305 Proposal ID: 62-0633-081

Proposed Contract Period: Late Start Date of 10/15/12 with 15 WORK DAYS

Project(s):

Project No: ER-063-3(81)--28-62

County: MAHASKA

Type of Work: SLIDE REPAIR

Route: U.S. 63 Length: 0.00 miles

Location: 4 MILES S. OF OSKALOOSA

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	7,023 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 306 Proposal ID: 64-1464-028

Proposed Contract Period: Late Start Date of 07/23/12 with 55 WORK DAYS
Site 01: TO COMPLETE ALL WORK THAT REQUIRES IOWA 146 TO BE DETOURED.
No Start Date Specified with 25 WORK DAYS

Project(s):

Project No: STPN-146-4(28)--2J-64

County: MARSHALL

Type of Work: PIPE CULVERTS

Route: IOWA 146 Length: 0.00 miles

Location: IA. 146 FROM GILMAN TO LE GRAND(8 LOC)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,500 CY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	360 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH
SECTION NO. 0002		
DESIGN NO. 0111; 10' X 4' X 94" RCB, FUTURE 26' FILL		
2403-0100020	STRUCT CONC (RCB CULV)	156 CY
2404-7775000	REINFORC STEEL	24,102 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 307 Proposal ID: 68-C068-068-A

Proposed Contract Period: Late Start Date of 05/21/12 with 15 WORK DAYS

Project(s):

Project No: ER-C068(68)--58-68

County: MONROE

Type of Work: SLIDE REPAIR

Route: T61 Length: 0.08 miles

Location: 2.5 MI. NORTH OF HWY 34
DDIR NO. IA-10-02-68-T61-1

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	8,393 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 308 Proposal ID: 79-0634-034

Proposed Contract Period: Late Start Date of 07/09/12 with 65 WORK DAYS

Project(s):

Project No: STPN-063-4(34)--2J-79
 County: POWESHIEK
 Type of Work: PIPE CULVERTS
 Route: U.S. 63 Length: 0.00 miles
 Location: 9 LOCATIONS BETWEEN MAHASKA CO. LINE & US 6

Project No: STPN-063-4(36)--2J-79
 County: POWESHIEK
 Type of Work: SLIDE REPAIR
 Route: U.S. 63 Length: 0.00 miles
 Location: SLIDE AREA 1.3 MILES N. OF MAHASKA CO. LINE

Project No: STPN-063-5(47)--2J-86
 County: TAMA
 Type of Work: PIPE CULVERTS
 Route: U.S. 63 Length: 0.00 miles
 Location: 4.6 MILES N. OF POWESHIEK CO. LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
		STPN-63-4(34)--2J-79
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	14,500 CY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	96 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH
SECTION NO. 0002		
ROADWAY ITEMS		
		STPN-83-4(36)--2J-79
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	13,900 CY
SECTION NO. 0003		
ROADWAY ITEMS		
		STPN-63-5(47)--2J-86
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	100 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 31-0206-709

Proposed Contract Period: Late Start Date of 10/01/12 with 15 WORK DAYS

Project(s):

Project No: MP-020-6(709)293--76-31

County: DUBUQUE

Type of Work: DELINEATOR & MILEPOST SIGNS

Route: U.S. 20 Length: 22.25 miles

Location: FROM THE DELAWARE COUNTY LINE TO OLD HIGHWAY ROAD
IN DUBUQUE.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 353 Proposal ID: 52-3806-708

Proposed Contract Period: Late Start Date of 10/01/12 with 15 WORK DAYS

Project(s):

Project No: MPIN-380-6(708)0--0N-52

County: JOHNSON

Type of Work: DELINEATOR & MILEPOST SIGNS

Route: I-380 Length: 17.00 miles

Location: FROM I-80 TO 1 MI. N. OF US 30.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 354 Proposal ID: 97-0297-053

Proposed Contract Period: By individual sites.

Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.

Approx Start Date of 10/01/12 with 20 WORK DAYS

Site 02: SEE SITE NUMBER 02 DESCRIPTION BELOW.

Approx Start Date of 07/08/13 with 30 WORK DAYS

Proposal Note:

*** SITE NUMBER 01 ***

THIS SITE INCLUDES THE TWO TRUSSES TO BE CONSTRUCTED IN 2012 WITH STAGE 2C. THE TRUSSES ARE LOCATED AT STATION 2513+00 AND 3523+50. THESE TRUSSES ARE LOCATED ON THE RAMPS FOR WESLEY PARKWAY.

*** SITE NUMBER 02 ***

THIS SITE IS FOR ALL WORK NOT INCLUDED IN SITE NUMBER 01.

Project(s):

Project No: IM-NHS-029-7(53)149--03-97

County: WOODBURY

Type of Work: TRAFFIC SIGNS

Route: I-29 Length: 0.00 miles

Location: IN THE CITY OF SIOUX CITY AT THE WESLEY PKY.
INTERCHANGE

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
TRAFFIC SIGN ITEMS		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	105 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	12,828 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 401 Proposal ID: 31-0209-220

Proposed Contract Period: Late Start Date of 06/25/12 with 20 WORK DAYS

Project(s):

Project No: NHSN-020-9(220)--2R-31

County: DUBUQUE

Type of Work: SALVAGE AND REMOVAL

Route: U.S. 20 Length: 0.00 miles

Location: 15 S. MAIN ST. IN DUBUQUE-PARCEL NO. 106

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 402 Proposal ID: 42-0571-023

Proposed Contract Period: Late Start Date of 06/25/12 with 15 WORK DAYS

Project(s):

Project No: STPN-057-1(23)--2J-42

County: HARDIN

Type of Work: SALVAGE AND REMOVAL

Route: IOWA 57 Length: 0.00 miles

Location: IN THE CITY OF ACKLEY AT 922 SHERMAN AVE.
PARCEL NO. 7

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 403 Proposal ID: 78-0293-131

Proposed Contract Period: Late Start Date of 06/25/12 with 15 WORK DAYS

Project(s):

Project No: IMN-029-3(131)54--0E-78

County: POTTAWATTAMIE

Type of Work: SALVAGE AND REMOVAL

Route: I-29 Length: 0.00 miles

Location: IN THE CITY OF COUNCIL BLUFFS AT 3757 AVE. "D"
PARCEL NO. 439

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 404 Proposal ID: 82-0741-224

Proposed Contract Period: Approx Start Date of 06/25/12 with 30 WORK DAYS

Project(s):

Project No: IMN-074-1(224)5--0E-82

County: SCOTT

Type of Work: SALVAGE AND REMOVAL

Route: I-74 Length: 0.00 miles

Location: IN THE CITY OF BETTENDORF AT 333 14TH ST.
PARCEL NO. 341A

Project No: IMN-074-1(225)5--0E-82

County: SCOTT

Type of Work: SALVAGE AND REMOVAL

Route: I-74 Length: 0.00 miles

Location: IN THE CITY OF BETTENDORF AT 1522 GRANT ST.
PARCEL NO. 362

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 48-0066-707

Proposed Contract Period: Late Start Date of 09/17/12 with 15 WORK DAYS

Project(s):

Project No: MP-006-6(707)232--76-48

County: IOWA

Type of Work: CLEARING AND GRUBBING

Route: U.S. 6 Length: 14.56 miles

Location: FROM THE E. JCT. OF US 151 TO IA 965. (VARIOUS LOCATIONS)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 502 Proposal ID: 56-0611-166

Proposed Contract Period: Late Start Date of 05/21/12 with 70 WORK DAYS

Project(s):

Project No: NHSN-061-1(159)--2R-56

County: LEE

Type of Work: WETLAND MITIGATION

Route: U.S. 61 Length: 0.00 miles

Location: EAST US 61 INDIANA BAT HABITAT MITIGATION SITE

Project No: NHSN-061-1(166)--2R-56

County: LEE

Type of Work: WETLAND MITIGATION

Route: U.S. 61 Length: 0.00 miles

Location: W. US 61 INDIANA BAT MITIGATION SITE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 503 Proposal ID: 82-0806-707

Proposed Contract Period: Late Start Date of 09/17/12 with 5 WORK DAYS

Project(s):

Project No: MPIN-080-6(707)278--0N-82

County: SCOTT

Type of Work: CLEARING AND GRUBBING

Route: I-80 Length: 28.63 miles

Location: FROM THE CEDAR COUNTY LINE, EAST TO THE MISSISSIPPI RIVER.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 504 Proposal ID: 91-0054-072

Proposed Contract Period: Late Start Date of 10/15/12 with 15 WORK DAYS

Project(s):

Project No: STPN-005-4(72)--2J-91

County: WARREN

Type of Work: WETLAND MITIGATION

Route: IOWA 5 Length: 0.00 miles

Location: ARCHER REMEDIATION

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 601 Proposal ID: 03-0099-062

Proposed Contract Period: Late Start Date of 05/14/12 with 110 WORK DAYS

Project(s):

Project No: BRFN-009-9(62)--39-03

County: ALLAMAKEE

Type of Work: BRIDGE PAINTING

Route: IOWA 9 Length: 0.00 miles

Location: MISSISSIPPI RIVER (BLACK HAWK) BRIDGE IN
LANSING

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 602 Proposal ID: 97-1296-034

Proposed Contract Period: Late Start Date of 06/04/12 with 40 WORK DAYS

Project(s):

Project No: IMN-129-6(34)0--0E-97

County: WOODBURY

Type of Work: BRIDGE CLEANING

Route: I-129 Length: 0.00 miles

Location: MISSOURI RIVER BRIDGE IN SIOUX CITY

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: April 17, 2012 10:00 A.M.

Proposed Bid Order: 981 Proposal ID: 22-0132-705

Proposed Contract Period: Late Start Date of 10/08/12 with 15 WORK DAYS

Project(s):

Project No: MP-013-2(705)60--76-22

County: CLAYTON

Type of Work: PIPE CULVERTS

Route: IOWA 13 Length: 0.00 miles

Location: AT VARIOUS LOCATIONS BETWEEN STRAWBERRY POINT & ELKADER

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------
