

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: April 17, 2012
Date of Addendum: March 26, 2012

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
983	48-0066-707	Clearing and Grubbing	Iowa	MP-006-6(707)232--76-48	17apr983.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the plan:

SHEET C.1:

DELETE the following tab 232-3A 04-17-12

SHEET C.1

ADD the attached tab 232-3A MODIFIED

232-3A
MODIFIED

EROSION CONTROL (RURAL SEEDING)

Following the completion of work, place seed, fertilizer, and mulch on all disturbed areas as follows:

SEEDING:

3 lbs. of Fescue or Fawn per 1000 sq. ft.

FERTILIZER:

17 lbs. of 13-13-13 (or equivalent) commercial fertilizer per 1000 sq. ft.

MULCH:

70 lbs. of dry cereal straw per 1000 sq. ft. Consolidate all mulch into the soil using a mulch stabilizer.

Preparing the seedbed and furnishing and applying seed, fertilizer, and mulch is incidental to mobilization. No extra compensation will be allowed.