

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: April 17, 2012  
Date of Addendum: April 12, 2012

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
003	34-2189-125-A	Bridge Deck Overlay	Floyd	BRFN-218-9(125)--39-34	17apr003.a01

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to the Plan Sheet C.3:

Tab. 232-3A EROSION CONTROL (RURAL SEEDING):

Replace 232-3A Dated 04-17-12  
With attached 232-3A MODIFIED

## EROSION CONTROL (RURAL SEEDING)

Following the completion of work **in a disturbed area**, place seed, fertilizer, and mulch on the portion of the area lying 8 feet adjacent to shoulder as follows:

**SEEDING:**

3 lbs. of Fescue or Fawn per 1000 sq. ft.

**FERTILIZER:**

17 lbs. of 13-13-13 (or equivalent) commercial fertilizer per 1000 sq. ft.

**MULCH:**

70 lbs. of dry cereal straw per 1000 sq. ft. Consolidate all mulch into the soil using a mulch stabilizer.

Preparing the seedbed and furnishing and applying seed, fertilizer, and mulch is incidental to mobilization and will not be paid for separately.