

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: May 15, 2012  
Date of Addendum: April 24, 2012

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
308	78-0293-126	PIPE CULVERTS	POTTAWATTAMIE	IMN-029-3(126)48--0E-78	15MAY308.A01

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to the Proposal Special Provisions List and the Proposal Special Provisions Text:

Add the following Special Provisions:

720.121      ATTACHMENT OF "POINT 25 UTILITY DATA"

Attached "Utility Bid Attachment"



# Iowa Department of Transportation

## UTILITY BID ATTACHMENT

County:

**Pottawattamie**

Project Classification:

**Point 25**

Project No.:

**IMN-029-3(126)48--0E-78 (CONST)**

District Utility Coordinator:

**Eric Keiner**

**Iowa Department of Transportation**

**District Utility Coordinator**

Highway Route Number or Name:

**I 29**

**300 West Broadway, Suite 401**

**Council Bluffs, IA 51503**

Segment or Section:

**In the City of Council Bluffs at 3 Locations on Mosquito Creek Levee**

### Utilities:

This project comes under the provisions of IAC 761-Chapter 115.25 Iowa Code.

Some of the utility work described below is dependent on prior work being performed by the Contractor at a specific site. In such situations the Contractor shall provide the Engineer and the affected utility a good faith notice of when the utility is to start work at the site. The notice shall be given 14 calendar days in advance of when the Contractor expects to complete the prior work and the site will be available to the utility. The Contractor shall follow up with a confirmation notice to the Engineer and the utility not less than 3 working days before the site will be ready for the utility to begin its' work.

Additional detailed information regarding the location of relocated utility facilities is available on the permits issued to the utility companies. These permits can be viewed at the District office during normal working hours. Contact the **District Utility Coordinator at 712-323-6125.**

**Facilities- Affected:**

**Buckeye Partners, L.P. (Gas):** Buckeye pipeline (G5 on plans) passes through the southern edge of the construction limits for Levee 1064. Pipeline is to be located/protected during excavation. No relocation is planned to accommodate culvert replacement.

**CenturyLink (Local Fiber Optic):** CenturyLink - Local (T1 on plans) has a 9 way duct structure running east-west through levee that may be impacted by the construction of Levee 1042. Existing MH on levee bike trail (not shown on plans) is approximately 17 ft. south of existing/proposed culvert. MH and duct structure are to be protected during excavation. No relocation is planned to accommodate culvert replacement.

**Council Bluffs Water Works (Water):** 16" water main (W on plans) along E. South Omaha Bridge Rd attached to south side of bridge over Mosquito Creek. Water line passes along the north and west edges of construction limits for Levee 1042. No relocation planned.

**MidAmerican Energy Company (Electric Distribution):** MEC has a distribution pole located along the northern construction limits of Levee 1042 and a meter pole (CB traffic) to the NW near the end of the ring levee for Levee 1042. Relocation not planned prior to letting - to be discussed at pre-con mtg.

**Facilities- Not Affected:** The following utility owners may have facilities in the vicinity of the project area but are not impacted by this project.

A T & T (Local Fiber Optic)

Black Hills Energy (Gas)

CenturyLink (Long Distance Fiber Optic)

Council Bluffs, City of (Sanitary Sewer)

Iowa Communications Network (Local Fiber Optic)

Iowa Network Services (Local Fiber Optic)

MCI (Local Fiber Optic)

Magellan Midstream Partners (Gas)

NuStar Energy (formerly Valero LP) (Gas)

Oneok North Systems LLC (Gas)

Windstream (Local Fiber Optic)