

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: May 15, 2012
Date of Addendum: May 10, 2012

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
109	82-1827-662	PCC Pavement - Grade & Replace	Scott	STP-U-1827(662)--70-82	15may109.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the plan:

SHEET C.03:

Add the following note to the reference notes for the item 2599-9999009, 2 IN.
CONDUIT, FIBER OPTIC AND ELECTRICAL:

The 2" conduit is to be placed approximately 4.5 feet west of the west back of curb under the proposed sidewalk, and either behind or in front of any existing sidewalk that remains. Virtually all the sidewalk on the west side of Pine Street from Kimberly Road to 47th Street will be removed for water main replacement work. From 47th Street to 49th Street, the sidewalk is scheduled to remain in place.

SHEET N.01:

Delete the following note from the notes on Plans Sheet N.01:

Communication cable (IMSA 39) from controller to Main St. controller.