

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: June 19, 2012  
Date of Addendum: June 15, 2012

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
002	07-1185-644	Bridge New - Other	Black Hawk	EDP-1185(644)--7Y-07	19jun002.a03

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to the plan:

**SHEET C.3:**

Add the following note to the reference notes for the item 2599-9999003,  
LIMESTONE:

The limestone archway is 2' – 3" high over the RCB entrance and matches the thickness of the stone columns at 1' – 6". The archway may be supported by a steel plate underneath the archway and inserted into the limestone columns. The limestone columns on either side of the RCB may be attached to the MSE wall if the design of the MSE wall allows for the additional loading. The limestone on all treatments is to be at least 8" in depth. The limestone caps shall be monolithic at least 2" thick.