

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 12-C012-079

Proposed Contract Period: Late Start Date of 06/03/13 with 80 WORK DAYS

Project(s):

Project No: BRS-C012(79)--60-12

County: BUTLER

Type of Work: BRIDGE REPLACEMENT - CCS

Route: T16 Length: 0.00 miles

Location: APPROX. 3 MILES NORTH OF THE CITY OF DUMONT BETWEEN  
160TH STREET & 170TH STREET.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 130.0' X 30.0' CCS BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	294 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	72,648 LB





IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 33-C033-107

Proposed Contract Period: Late Start Date of 08/27/12 with 35 WORK DAYS

Project(s):

Project No: BROS-C033(107)--5F-33

County: FAYETTE

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 40TH STREET Length: 0.00 miles

Location: AT UNNAMED CREEK, 1/4 MILE EAST OF 'X' AVE., SEC. 20-91-10.

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A TWIN 12' X 8' X 76'-0 RCB CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	283 CY
2404-7775000	REINFORC STEEL	47,107 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 36-3331-026

Proposed Contract Period: Late Start Date of 10/15/12 with 10 WORK DAYS

Project(s):

Project No: BRFN-333-1(26)--39-36

County: FREMONT

Type of Work: PERMANENT SCOUR COUNTERMEASURES

Route: IOWA 333 Length: 0.00 miles

Location: OVER DD NO. 6, 0.3 MILE E. OF I-29

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 44-C044-070

Proposed Contract Period: Late Start Date of 08/20/12 with 55 WORK DAYS

Project(s):

Project No: BROS-C044(70)--8J-44

County: HENRY

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 310TH STREET Length: 0.00 miles

Location: OVER FISH CREEK, SECTION 22-70-06

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 100' X 24' CCS BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	647 CY
2403-0100010	STRUCT CONC (BRIDGE)	186 CY
2404-7775000	REINFORC STEEL	2,610 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	46,141 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 48-C048-063

Proposed Contract Period: Late Start Date of 08/20/12 with 45 WORK DAYS

Project(s):

Project No: BHS-C048(63)--63-48  
 County: IOWA  
 Type of Work: BRIDGE DECK OVERLAY  
 Route: F-67 Length: 0.10 miles  
 Location: APPROX. 4 MI. E. OF NORTH ENGLISH  
 OVER NORTH ENGLISH RIVER

Project No: BHS-C048(64)--63-48  
 County: IOWA  
 Type of Work: BRIDGE DECK OVERLAY  
 Route: F-67 Length: 0.10 miles  
 Location: APPROX. 1 MI. W. OF NORTH ENGLISH  
 OVER UNNAMED STREAM

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR REPAIRS TO A 225'-0 X 28'-0 CONT. I-BEAM BRIDGE		
BHS-C048(63)--63-48		
2403-0100010	STRUCT CONC (BRIDGE)	5 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	686 LB
2413-0698066	DECK OVERLAY (CL O PCC)	704 SY
2413-0698074	DECK REPAIR, CL A	205 SY
SECTION NO. 0002		
ITEMS FOR REPAIRS TO A 100'-0 X 28'-0 CCS BRIDGE		
BHS-C048(64)--63-48		
2303-0013380	HMA (100K ESAL) B-I-S, 3/8", NO FRIC	20 TON
2413-0698066	DECK OVERLAY (CL O PCC)	319 SY
2413-0698074	DECK REPAIR, CL A	47 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 54-0928-030

Proposed Contract Period: Late Start Date of 08/20/12 with 30 WORK DAYS

Project(s):

Project No: BRFN-092-8(30)--39-54

County: KEOKUK

Type of Work: BRIDGE DECK OVERLAY

Route: IOWA 92 Length: 0.00 miles

Location: OVER CEDAR CREEK 4.9 MILES W. OF JCT. V-45

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 62-C062-076

Proposed Contract Period: Late Start Date of 04/15/13 with 75 WORK DAYS

Project(s):

Project No: BROS-C062(76)--8J-62

County: MAHASKA

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 255TH STREET Length: 0.10 miles

Location: 1/4 MILE EAST OF OSBURN AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 12' X 12' X 60'-0 RCB CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	365 CY
2404-7775000	REINFORC STEEL	47,840 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 80-C080-055

Proposed Contract Period: Late Start Date of 04/15/13 with 85 WORK DAYS

Project(s):

Project No: BROS-C080(55)--5F-80

County: RINGGOLD

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 125TH AVE Length: 0.00 miles

Location: 2 MILES SOUTH OF IOWA 2

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 12'-0 X 12'-0 X 76'-0 RCB CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	430 CY
2404-7775000	REINFORC STEEL	57,729 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 82-0808-280

Proposed Contract Period: Late Start Date of 09/24/12 with 25 WORK DAYS

Project(s):

Project No: IMN-080-8(280)305--0E-82

County: SCOTT

Type of Work: BRIDGE REPAIR

Route: I-80 Length: 0.00 miles

Location: 35TH ST. SW OVER I-80, 9.3 MILES E. OF US 61

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0412; 232'-1 X 24' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	27 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	6,040 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 86-C086-082

Proposed Contract Period: Late Start Date of 05/06/13 with 45 WORK DAYS

Project(s):

Project No: BROS-C086(82)--8J-86

County: TAMA

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 370TH ST Length: 0.10 miles

Location: OVER RICHLAND CREEK, C AVENUE TO T47

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 12' X 10' X 54' REINFORCED CONCRETE BOX		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,670 CY
2403-0100020	STRUCT CONC (RCB CULV)	221 CY
2404-7775000	REINFORC STEEL	31,371 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 86-C086-083

Proposed Contract Period: Late Start Date of 09/04/12 with 45 WORK DAYS

Project(s):

Project No: BROS-C086(81)--5F-86  
 County: TAMA  
 Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX  
 Route: H AVE Length: 0.00 miles  
 Location: OVER BRANCH IOWA RIVER  
 360TH STREET TO 340TH STREET

Project No: BROS-C086(83)--5F-86  
 County: TAMA  
 Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX  
 Route: 340TH ST Length: 0.10 miles  
 Location: OVER BRANCH IOWA RIVER, H AVE. TO I AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 12' X 10' X 54' REINFORCED BOX CULVERT		
BROS-C086(81)--5F-86		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,020 CY
2403-0100020	STRUCT CONC (RCB CULV)	143 CY
2404-7775000	REINFORC STEEL	22,459 LB
SECTION NO. 0002		
ITEMS FOR A 12' X 10' X 54' REINFORCED BOX CULVERT		
BROS-C086(83)--5F-86		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	885 CY
2303-0021500	HMA (300K ESAL) BASE, 1/2"	210 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	62 TON
2403-0100020	STRUCT CONC (RCB CULV)	135 CY
2404-7775000	REINFORC STEEL	21,603 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 87-C087-043

Proposed Contract Period: Late Start Date of 04/15/13 with 115 WORK DAYS

Proposal Note:

\*\*\*WORK RESTRICTION FOR BRS-C087(43)--60-87\*\*\*  
NO WORK WILL BE ALLOWED BETWEEN NOVEMBER 15, 2012 TO APRIL 1, 2013. IF THE CONTRACTOR ELECTS TO CONSTRUCT THIS PROJECT BEFORE NOVEMBER 15, 2012 THEN THE PROJECT SHALL BE SUBSTANTIALLY COMPLETE WITH THE ROADWAY OPEN TO TRAFFIC BY NOVEMBER 15, 2012. AFTER NOVEMBER 15, 2012 LIQUIDATED DAMAGES WILL BE CHARGED UNTIL THE ROADWAY IS OPEN TO TRAFFIC.

Project(s):

Project No: BROS-C087(42)--5F-87  
County: TAYLOR  
Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX  
Route: 170TH ST Length: 0.10 miles  
Location: OVER MIDDLE 102 RIVER

Project No: BRS-C087(43)--60-87  
County: TAYLOR  
Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX  
Route: 130TH ST Length: 0.00 miles  
Location: ON 130TH ST. 1.9 MI. WEST OF HIGHWAY 148

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 10' X 12' X 56'-0 REINFORCED CONCRETE BOX CULVERT BROS-C087(42)--5F-87		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,265 CY
2403-0100020	STRUCT CONC (RCB CULV)	312 CY
2404-7775000	REINFORC STEEL	38,538 LB
SECTION NO. 0002		
ITEMS FOR A TWIN 10' X 12' X 50'-0 REINFORCED CONCRETE BOX CULVERT BRS-C087(43)--60-87		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	175 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	208 SY
2403-0100020	STRUCT CONC (RCB CULV)	307 CY
2404-7775000	REINFORC STEEL	38,509 LB



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 07-8155-718

Proposed Contract Period: Late Start Date of 08/27/12 with 30 WORK DAYS

Project(s):

Project No: SRTS-U-8155(718)--8U-07

County: BLACK HAWK

Type of Work: PCC SIDEWALK/TRAIL

Route: LONGFELLOW AVE Length: 0.00 miles

Location: IN THE CITY OF WATERLOO

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 07-8155-723

Proposed Contract Period: Late Start Date of 09/10/12 with 30 WORK DAYS

Project(s):

Project No: STP-E-8155(723)--8V-07

County: BLACK HAWK

Type of Work: PCC SIDEWALK/TRAIL

Route: WASHINGTON STREET Length: 0.25 miles

Location: IN THE CITY OF WATERLOO, BETWEEN PARK STREET AND 4TH STREET

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	162 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 29-0977-638

Proposed Contract Period: Late Start Date of 10/01/12 with 25 WORK DAYS

Project(s):

Project No: SRTS-U-0977(638)--8U-29

County: DES MOINES

Type of Work: PCC SIDEWALK/TRAIL

Route: 14TH STREET Length: 0.11 miles

Location: IN THE CITY OF BURLINGTON

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	119 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 31-2160-612

Proposed Contract Period: Late Start Date of 08/20/12 with 15 WORK DAYS

Project(s):

Project No: STP-E-2160(612)--8V-31

County: DUBUQUE

Type of Work: PCC SIDEWALK/TRAIL

Route: 3 RD AVE Length: 0.50 miles

Location: IN THE CITY OF DYERSVILLE  
3RD AVE (5TH ST TO 1ST ST) & 3RD ST SW

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
PCC SIDEWALK ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	878 CY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	2,383 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	52 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 52-0806-306-A

Proposed Contract Period: Late Start Date of 08/20/12 with 170 WORK DAYS  
 Site 01: TO COMPLETE STAGE 1A AS SHOWN ON SHEET J.1  
 Late Start Date of 08/20/12 with 50 WORK DAYS  
 Site 02: TO COMPLETE WORK THROUGH STAGE 3 AS SHOWN ON J.1  
 Approx Start Date of 04/01/13 with 100 WORK DAYS

Project(s):

Project No: IM-080-6(276)244--13-52  
 County: JOHNSON  
 Type of Work: LIGHTING  
 Route: I-80 Length: 0.00 miles  
 Location: IN THE CITY OF IOWA CITY AT THE DUBUQUE ST.  
 INTERCHANGE

Project No: IM-080-6(278)244--13-52  
 County: JOHNSON  
 Type of Work: TRAFFIC SIGNALS  
 Route: I-80 Length: 0.00 miles  
 Location: IN THE CITY OF IOWA CITY AT THE DUBUQUE ST.  
 INTERCHANGE

Project No: IM-080-6(306)244--13-52  
 County: JOHNSON  
 Type of Work: PCC PAVEMENT - GRADE & REPLACE  
 Route: I-80 Length: 0.00 miles  
 Location: IN THE CITY OF IOWA CITY AT THE DUBUQUE ST.  
 INTERCHANGE

Project No: IM-080-6(319)244--13-52  
 County: JOHNSON  
 Type of Work: TRAFFIC SIGNS  
 Route: I-80 Length: 0.00 miles  
 Location: IN THE CITY OF IOWA CITY AT THE DUBUQUE ST.  
 INTERCHANGE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0003		
ROADWAY ITEMS		
IM-080-6(306)244--13-52		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	31,662 CY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	20,690 SY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	277 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	360 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	300 TON
SECTION NO. 0005		
ALTERNATE 'AA' OPTION 2: PCC PAVED SHOULDER - (306)		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2122-5190007	PAVED SHLD, PCC, 7"	5,729 SY
SECTION NO. 0006		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

DESIGN NO. 0110; REPAIRS TO DUAL 236'-0 X 30'-0 CONTINUOUS  
I-BEAM BRIDGES - IM-080-6(306)244-13-52

2403-0100000	STRUCT CONC (MISCELLANEOUS)	13 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	2,159 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 106 Proposal ID: 56-3942-615

Proposed Contract Period: Late Start Date of 09/24/12 with 30 WORK DAYS

Project(s):

Project No: SRTS-U-3942(615)--8U-56

County: LEE

Type of Work: PCC SIDEWALK/TRAIL

Route: MIDDLE ROAD Length: 0.46 miles

Location: IN THE CITY OF KEOKUK

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 57-1187-756-A

Proposed Contract Period: Late Start Date of 09/24/12 with 15 WORK DAYS

Project(s):

Project No: SRTS-U-1187(756)--8U-57

County: LINN

Type of Work: PCC SIDEWALK/TRAIL

Route: E AVENUE Length: 0.47 miles

Location: IN THE CITY OF CEDAR RAPIDS

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
PCC SIDEWALK ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	240 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 108 Proposal ID: 77-0654-133

Proposed Contract Period: Late Start Date of 08/27/12 with 40 WORK DAYS

Project(s):

Project No: NHSX-065-4(133)--3H-77

County: POLK

Type of Work: MEDIAN CROSSOVER

Route: U.S. 65 Length: 0.00 miles

Location: OVER DES MOINES RIVER OVERFLOW SE OF DES MOINES  
(CROSSOVERS)

Project No: BRF-065-3(70)--38-91

County: WARREN

Type of Work: MEDIAN CROSSOVER

Route: U.S. 65 Length: 0.00 miles

Location: AT NORTH RIVER 1.1 MILES N. OF CO. RD. G-16

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
NHSX-065-4(133)--3H -77		
2102-2625000	EMBANKMENT-IN-PLACE	467 CY
SECTION NO. 0002		
ROADWAY ITEMS		
BRF-065-3(70)--38-91		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	10,249 CY



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 10-0207-038

Proposed Contract Period: Late Start Date of 08/20/12 with 180 WORK DAYS

Project(s):

Project No: NHSX-020-7(38)--3H-10

County: BUCHANAN

Type of Work: HMA RESURFACING

Route: U.S. 20 Length: 14.40 miles

Location: FROM IOWA AVENUE NEAR INDEPENDENCE EASTERLY TO IOWA 187

Project No: MP-150-6(703)40--76-10

County: BUCHANAN

Type of Work: HMA PATCHING

Route: IOWA 150 Length: 2.00 miles

Location: IN THE CITY OF INDEPENDENCE, FROM US 20 NORTHERLY TO  
NEAR THE NCL

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
NHSX-020-7(38)--3H-10		
2102-2625000	EMBANKMENT-IN-PLACE	5,250 CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	27,675 TON
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	86,837 TON
2303-0053503	HMA (10M ESAL) SURF, 1/2", FRIC L-3	48,254 TON
2303-7000510	HMA MIX INCORPORATED W/ ANTI-STRIP AGENT	135,091 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	785 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	80 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 57-3806-271-A

Proposed Contract Period: Late Start Date of 08/20/12 with 180 WORK DAYS

Project(s):

Project No: IMX-380-6(271)16--02-57

County: LINN

Type of Work: HMA RESURFACING

Route: I-380 Length: 8.89 miles

Location: FROM 33RD AVE. BRIDGE IN CEDAR RAPIDS N. TO 1.4 MILES N. OF  
CO. RD. E-34(SBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	634 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	1,438 CY
2122-5190006	PAVED SHLD, PCC, 6"	5,152 SY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	1,106 TON
2303-0031500	HMA (1M ESAL) BASE, 1/2"	20,139 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	3,510 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	7,422 TON
2303-0062500	HMA (30M ESAL) INTERMEDIATE, 1/2"	20,400 TON
2303-0063502	HMA (30M ESAL) SURF, 1/2", FRIC L-2	20,868 TON
2303-7000510	HMA MIX INCORPORATED W/ ANTI-STRIP AGENT	41,269 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	839 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	66 EACH
SECTION NO. 0009		
DESIGN NO. 1710; RETROFIT RAIL 638'-0 X 51'-6 CWPG BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	43 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	7,271 LB
SECTION NO. 0010		
DESIGN NO. 0112; RETROFIT RAIL END SECTION		
482'-0 X 52'-0 PPCB BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	232 LB
SECTION NO. 0011		
DESIGN NO. 0212; RETROFIT RAIL END SECTION		
267'-0 X 52'-0 CWPG BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	232 LB



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 75-0752-083

Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS

Project(s):

Project No: NHSX-075-2(83)--3H-75

County: PLYMOUTH

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: U.S. 75 Length: 15.70 miles

Location: FROM IA. 60 N. TO SCL OF SIOUX CENTER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	4,655 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	320 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	24,063 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	23,813 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	346 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	8 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 155 Proposal ID: 85-2103-031

Proposed Contract Period: Late Start Date of 05/06/13 with 105 WORK DAYS

Project(s):

Project No: STP-210-3(31)--2C-85  
 County: STORY  
 Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING  
 Route: IOWA 210 Length: 8.70 miles  
 Location: FROM 0.25 MILE E. OF I-35 E. TO WCL OF MAXWELL

Project No: TSF-210-3(33)--92-85  
 County: STORY  
 Type of Work: MILLED RUMBLE STRIPS  
 Route: IOWA 210 Length: 0.00 miles  
 Location: W. OF MAXWELL NEAR 650TH ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
STP-210-3(31)--2C-85		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,780 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	7,199 CY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	11,686 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	11,533 TON
SECTION NO. 0004		
ROADWAY ITEMS		
TSF-210-3(33)--92-85		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	393 CY



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 36-0021-098

Proposed Contract Period: Late Start Date of 10/29/12 with 5 WORK DAYS

Project(s):

Project No: ER-002-1(98)--28-36

County: FREMONT

Type of Work: PCC PATCHING

Route: IOWA 2 Length: 0.00 miles

Location: APPROX. 1.6 MILES W. OF I-29

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	160 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: NOTUSED; 12/07

Project(s):

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 50-1171-026

Proposed Contract Period: Late Start Date of 10/15/12 with 10 WORK DAYS

Project(s):

Project No: STPN-117-1(26)--2J-50

County: JASPER

Type of Work: SLIDE REPAIR

Route: IOWA 117 Length: 11.09 miles

Location: I-80 INTERCHANGE AT COLFAX

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	950 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 52-0806-315

Proposed Contract Period: Late Start Date of 09/10/12 with 35 WORK DAYS

Project(s):

Project No: IMN-080-6(315)230--0E-52  
County: JOHNSON

Type of Work: SLIDE REPAIR  
Route: I-80 Length: 0.00 miles  
Location: W. OF CO. RD. W-38(OXFORD) INTERCHANGE

Project No: NHSN-218-4(38)--2R-52  
County: JOHNSON

Type of Work: SLIDE REPAIR  
Route: U.S. 218 Length: 0.00 miles  
Location: 2.3 MILES N. OF IA. 22

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS - IMN-080-6(315)230--0E-52		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	20,589 CY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	16 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	1 EACH
SECTION NO. 0003		
ROADWAY ITEMS - NHSN-218-4(38)--2R-52		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,997 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 304 Proposal ID: 56-0271-001

Proposed Contract Period: Late Start Date of 09/10/12 with 40 WORK DAYS

Project(s):

Project No: NHSN-027-1(1)--2R-56

County: LEE

Type of Work: SLIDE REPAIR

Route: IOWA 27 Length: 0.00 miles

Location: OVER BN/SF R.R. IN ARGYLE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 305 Proposal ID: 77-0352-407

Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS

Project(s):

Project No: IM-035-2(407)67--13-77  
 County: POLK  
 Type of Work: GRADING  
 Route: I-35 Length: 0.00 miles  
 Location: IN THE CITY OF WEST DES MOINES AT GRAND AVE.  
 INTERCHANGE & 2 LOCATIONS N. OF GRAND AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	234,389 CY
SECTION NO. 0004		
DESIGN NO. 0513; A 12'-0 X 12'-0 RCB CULVERT EXTENSION		
2403-0100020	STRUCT CONC (RCB CULV)	1,512 CY
2404-7775000	REINFORC STEEL	270,602 LB
SECTION NO. 0005		
DESIGN NO. 0613; A 5'-0 X 5'-0 RCB CULVERT EXTENSION W/ 6'-0 X 6'-0 TAPERED DROP INLET		
2403-0100020	STRUCT CONC (RCB CULV)	67 CY
2404-7775000	REINFORC STEEL	10,403 LB
SECTION NO. 0006		
DESIGN NO. 0514; A 5'-0 X 5'-0 RCB CULVERT EXTENSION W/ 6'-0 X 6'-0 TAPERED DROP INLET		
2403-0100020	STRUCT CONC (RCB CULV)	66 CY
2404-7775000	REINFORC STEEL	8,877 LB



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 20-C020-092

Proposed Contract Period: Late Start Date of 09/10/12 with 25 WORK DAYS

Project(s):

Project No: FM-C020(92)--55-20

County: CLARKE

Type of Work: PAVEMENT MARKINGS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS IN CLARKE COUNTY.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 451 Proposal ID: 17-1372-618

Proposed Contract Period: Late Start Date of 09/04/12 with 40 WORK DAYS

Project(s):

Project No: STP-E-1372(618)--8V-17

County: CERRO GORDO

Type of Work: MISCELLANEOUS SURFACE TRAIL

Route: NORTH SHORE DR. Length: 0.11 miles

Location: IN THE CITY OF CLEAR LAKE  
FROM MIDPOINT NORTH

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
SIDEWALK ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	462 CY
2301-1033070	STD/S-F PCC PAV'T, CL C CL 3, 7"	227 SY
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	30 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 452 Proposal ID: 56-3942-614

Proposed Contract Period: Late Start Date of 04/15/13 with 120 WORK DAYS

Project(s):

Project No: ER-3942(614)--8R-56

County: LEE

Type of Work: MISCELLANEOUS

Route: RIVER ROAD Length: 0.50 miles

Location: IN THE CITY OF KEOKUK  
15TH ST. TO 1500 FT. N. OF 17TH ST

---

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	10,553 CY
2303-0021750	HMA (300K ESAL) BASE, 3/4"	1,697 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	848 TON

---



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 15-0802-227

Proposed Contract Period: Late Start Date of 08/27/12 with 50 WORK DAYS

Project(s):

Project No: IMN-080-2(227)55--0E-15

County: CASS

Type of Work: LANDSCAPING

Route: I-80 Length: 0.00 miles

Location: FROM IA. 173 E. TO CO. RD. N-16

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------







IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: July 17, 2012 10:00 A.M.

Proposed Bid Order: 981 Proposal ID: 21-0183-710

Proposed Contract Period: Late Start Date of 10/15/12 with 10 WORK DAYS

Project(s):

Project No: MP-018-3(710)78--76-21

County: CLAY

Type of Work: PIPE CULVERTS

Route: U.S. 18 Length: 0.10 miles

Location: JUST WEST OF THE IOWA STATE PATROL POST NORTH OF SPENCER.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------



