

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: July 17, 2012
Date of Addendum: July 10, 2012

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
451	17-1372-618	Miscellaneous Surface Trail	Cerro Gordo	STP-E-1372(618)--8V-17	17jul451.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Attached is a SCHEDULE OF PRICES for the following item:

Line No. 0481 2401-6745356 REMOVAL OF CONCRETE FOOTING OF LIGHT
POLES

Line No. 0482 2401-6745765 REMOVAL OF LIGHT POLES

Line No. 0483 2599-9999014 REMOVAL OF BRICK PAVERS

Bid these items as instructed and submit the bid for these items with the Bid Proposal.

Make the following change to the PROPOSAL DETAILS, Page 2:

CHANGE the LIQUIDATED DAMAGES as follows:

From \$1,000.00 to \$500.00

ADD the following PROPOSAL NOTE:

*** WORK RESTRICTION ***

THE CONTRACTOR WILL NOT BE ALLOWED TO BEGIN WORK UNTIL
SEPTEMBER 4, 2012.

Make the following change to the plan:

SHEET C.02:

Add the following note to the reference notes for the items 2401-6745356,
REMOVAL OF CONCRETE FOOTING OF LIGHT POLES AND 2401-
6745765, REMOVAL OF LIGHT POLES:

Contractor is to remove existing light poles and foundations along project corridor. Contractor shall disconnect power source to lights at panel. Contractor responsible for damage caused removing poles. Contractor shall completely remove existing light pole foundations, dispose of foundation, and backfill hole. There are two lights and foundations to be removed. Payment includes full compensation for all labor, material, and equipment for disconnecting lights, removing and salvaging fixture, removing and disposing of foundation, providing and compacting granular backfill material to 95% standard proctor.

Add the following note to the reference notes for the item 2599-9999014,
REMOVAL OF BRICK PAVERS:

Contractor to remove and salvage existing brick pavers. There are approximately 574 SF of existing pavers to be removed and stacked on a pallet and returned to the owner.

Replace the reference notes with the following notes for the item 2555-0000010,
DELIVER AND STOCKPILE SALVAGED MATERIALS:

This item is for delivery and stockpiling of light poles and brick pavers salvaged during removal operations on this project. Contractor to deliver and stockpile salvaged materials to 1419 2nd Avenue South, Clear Lake, IA care of Joe Weigel, Public Works Director. Ph: 641-357-6135

Replace Article 2511.03, B, 1, with the following:

Widths shown in contract documents are minimums, excluding curbs or flares.

The contract documents will contain sheets for construction of curb ramps, turning spaces, and transitions. Measure or stake as required to construct features. If either of the following is met, Engineer will provide staking for that quadrant and verify slopes during finishing:

- Running Slope. Tolerance between design slope and maximum allowable slope is less than 1.0%.
- Cross Slope and Turning Space Slopes. Tolerance of $\pm 0.5\%$ from design slope would exceed minimum or maximum allowable slope.

If adequate construction tolerances are allowed, Engineer will not provide staking for construction of sidewalk or recreation trail. If field adjustments outside the acceptable range indicated in the contract documents are necessary, notify the Engineer prior to construction.

At locations other than curb ramps, turning spaces, and transitions, ensure cross slope is between 0.5% and 2.0%. Ensure grade is within approximately 2% steeper than profile grade of adjacent roadway, or does not exceed 5.0%, whichever is steeper.

Install detectable warnings according to manufacturer's recommendations. Install detectable warnings for full width of curb ramp, excluding curbs and flares.

Note: The changes shown above are classified as Addendum level per Article 1105.04, CONFORMITY WITH AND COORDINATION OF THE CONTRACT DOCUMENTS. If there are any discrepancies between any contents of the contract documents, the changes shown above shall govern.

Proposal ID No.: 17-1372-618 Bid Order No.: 451
 Primary Work Type: MISCELLANEOUS SURFACE TRAIL Letting Date: JULY 17, 2012
 Primary County: CERRO GORDO 10:00 A.M.

ITEMS LISTED ON THIS PAGE ARE ADDED BY ADDENDUM 17jul451.a01

UNIT BIDS MUST BE TYPED OR SHOWN IN INK OR THE BID WILL BE REJECTED.

Line No	Item Number Item Description	Item Quantity and Unit	Unit Price		Bid Amount	
			Dollars	Cts	Dollars	Cts
Section 0001 (continued)						
ROADWAY ITEMS						
0481	2401-6745356 REMOVAL OF CONCRETE FOOTING OF LIGHT POLES	2.000 EACH	.		.	
0482	2401-6745765 REMOVAL OF LIGHT POLES	2.000 EACH	.		.	
0483	2599-9999014 ('SQUARE FEET' ITEM) REMOVAL OF BRICK PAVERS	574.000 SF	.		.	
Total Bid			.		.	