

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 05-C005-052

Proposed Contract Period: Late Start Date of 07/29/13 with 65 WORK DAYS

Project(s):

Project No: BROS-C005(52)--8J-05

County: AUDUBON

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 140TH ST Length: 0.10 miles

Location: OVER E. BRANCH OF WEST NISHNABOTNA RIVER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 120'-0 X 24'-0 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	176 CY
2403-0100010	STRUCT CONC (BRIDGE)	255 CY
2404-7775000	REINFORC STEEL	61,245 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 06-C006-085

Proposed Contract Period: Late Start Date of 04/01/13 with 125 WORK DAYS

Proposal Note:

\*\*\* WORK RESTRICTION \*\*\*

THERE ARE TWO LANDOWNERS BETWEEN THE STRUCTURES, IN ORDER TO  
MAINTAIN ACCESS, THE PROJECTS SHALL BE BUILT ONE AT A TIME.

Project(s):

Project No: BRS-C006(85)--60-06  
County: BENTON  
Type of Work: RCB CULVERT NEW - TRIPLE BOX  
Route: V37 Length: 0.00 miles  
Location: OVER BR WOLF CREEK

Project No: BRS-C006(87)--60-06  
County: BENTON  
Type of Work: RCB CULVERT NEW - TWIN BOX  
Route: V37 Length: 0.00 miles  
Location: OVER BR WOLF CREEK

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR TRIPLE 12' X 8' X 142'-0 REINFORCED CONCRETE BOX		
CULVERT BRS-C006(85)--60-06		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,170 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	453 SY
2403-0100020	STRUCT CONC (RCB CULV)	711 CY
2404-7775000	REINFORC STEEL	105,661 LB
SECTION NO. 0002		
ITEMS FOR A TWIN 12' X 10' X 74'-0 REINFORCED CONCRETE BOX		
CULVERT BRS-C006(87)--60-06		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	160 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	240 SY
2403-0100020	STRUCT CONC (RCB CULV)	348 CY
2404-7775000	REINFORC STEEL	52,673 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 09-C009-047

Proposed Contract Period: Late Start Date of 07/22/13 with 65 WORK DAYS

Project(s):

Project No: BROS-C009(47)--8J-09

County: BREMER

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 110TH STREET Length: 0.00 miles

Location: OVER LITTLE WAPSIPINICON RIVER APPROXIMATELY 3 MILES NORTH  
OF SUMNER NEAR CO. HWY V62

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 120'-0 X 24'-6 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	6,255 CY
2403-0100010	STRUCT CONC (BRIDGE)	246 CY
2404-7775000	REINFORC STEEL	60,267 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 004                      Proposal ID: 26-C026-071

Proposed Contract Period: Late Start Date of 08/05/13 with 60 WORK DAYS

Project(s):

Project No: BROS-C026(71)--8J-26

County: DAVIS

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: JADE AVE                      Length: 0.10 miles

Location: OVER SOUTH WYACONDAH RIVER APPROXIMATELY 4 MILES SOUTHWEST  
OF BLOOMFIELD

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A 80'-0 X 24'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,119 CY
2403-0100010	STRUCT CONC (BRIDGE)	132 CY
2404-7775000	REINFORC STEEL	32,506 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 30-C030-041

Proposed Contract Period: Late Start Date of 06/03/13 with 85 WORK DAYS

Proposal Note:

\*\*\* WINTER WORK \*\*\*

WINTER WORK WILL BE ALLOWED FOR THE SECTION 1 BRIDGE ITEMS SHOWN ON PLAN SHEET C.01 DURING THE WINTER OF 2012/2013. WORKING DAYS WILL NOT BE CHARGED FOR WORK COMPLETED DURING "WINTER WORK" NOVEMBER 15, 2012 THROUGH APRIL 1, 2013. NO ADDITIONAL PAYMENT WILL BE MADE FOR HEATING OR PROTECTING STRUCTURAL CONCRETE.

Project(s):

Project No: BROS-C030(41)--8J-30

County: DICKINSON

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 230TH ST Length: 0.00 miles

Location: OVER DRAINAGE DITCH

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR 120' X 30' CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	311 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	74,951 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	9,100 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 31-2100-659

Proposed Contract Period: Late Start Date of 05/20/13 with 105 WORK DAYS

Project(s):

Project No: BROS-2100(659)--8J-31

County: DUBUQUE

Type of Work: BRIDGE REPLACEMENT - CCS

Route: BRUNSKILL ROAD Length: 0.17 miles

Location: IN THE CITY OF DUBUQUE  
OVER CATFISH CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	9,399 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	1,877 SY
2303-0041500	HMA (3M ESAL) BASE, 1/2"	195 TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	115 TON
2403-0100010	STRUCT CONC (BRIDGE)	116 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	83,564 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 43-0295-222

Proposed Contract Period: Late Start Date of 05/13/13 with 90 WORK DAYS

Project(s):

Project No: IMN-029-5(222)96--0E-43  
 County: HARRISON  
 Type of Work: BRIDGE DECK OVERLAY  
 Route: I-29 Length: 0.00 miles  
 Location: CO. RD. F-20 OVER I-29

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0113; 215'-5 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	35 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	4,205 LB
2413-0698074	DECK REPAIR, CL A	98 SY
SECTION NO. 0002		
DESIGN NO. 0113; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2413-0698066	DECK OVERLAY (CL O PCC)	711 SY
SECTION NO. 0003		
DESIGN NO. 0113; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	711 SY
SECTION NO. 0004		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	240 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 52-0806-265

Proposed Contract Period: Late Start Date of 04/01/13 with 115 WORK DAYS

Project(s):

Project No: IMN-080-6(265)231--0E-52  
 County: JOHNSON  
 Type of Work: BRIDGE DECK OVERLAY  
 Route: I-80 Length: 0.00 miles  
 Location: EBL & WBL OVER BLACK HAWK AVE.  
 1.6 MILES E. OF IOWA CO. LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0312; REPAIRS TO A 130'-0 X 43'-0 PRESTRESSED CONCRETE BEAM BRIDGE	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	22 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	2,946 LB
2413-0698074	DECK REPAIR, CL A	123 SY
SECTION NO. 0002		
	DESIGN NO. 0312; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	
2413-0698066	DECK OVERLAY (CL O PCC)	617 SY
SECTION NO. 0003		
	DESIGN NO. 0312; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	617 SY
SECTION NO. 0004		
	DESIGN NO. 0412; REPAIRS TO A 130'-0 X 40'-0 PRESTRESSED CONCRETE BEAM BRIDGE	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	20 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	2,719 LB
2413-0698074	DECK REPAIR, CL A	114 SY
SECTION NO. 0005		
	DESIGN NO. 0412; ALTERNATE 'BB' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN	
2413-0698066	DECK OVERLAY (CL O PCC)	574 SY
SECTION NO. 0006		
	DESIGN NO. 0412; ALTERNATE 'BB' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	574 SY
SECTION NO. 0007		
	ROADWAY ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	220 CY



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 57-1513-132

Proposed Contract Period: Late Start Date of 06/03/13 with 75 WORK DAYS

Project(s):

Project No: BRFN-151-3(132)--39-57  
 County: LINN  
 Type of Work: BRIDGE DECK OVERLAY  
 Route: U.S. 151 Length: 0.00 miles  
 Location: IN THE CITY OF CEDAR RAPIDS OVER BIG CREEK  
 1.1 MILES N. OF US 30(NBL)

Project No: BRFN-151-3(133)--39-57  
 County: LINN  
 Type of Work: BRIDGE DECK OVERLAY  
 Route: U.S. 151 Length: 0.00 miles  
 Location: IN THE CITY OF CEDAR RAPIDS OVER UP R.R.  
 1.3 MILES N. OF US 30(NBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0113; 221'-8 X 30' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE BRFN-151-3(132)--39-57		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	408 LB
2413-0698074	DECK REPAIR, CL A	10 SY
SECTION NO. 0002		
DESIGN NO. 0113; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (132)		
2413-0698066	DECK OVERLAY (CL O PCC)	748 SY
SECTION NO. 0003		
DESIGN NO. 0113; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN (132)		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	748 SY
SECTION NO. 0004		
ROADWAY ITEMS BRFN-151-3(132)--39-57		
2102-2625000	EMBANKMENT-IN-PLACE	200 CY
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	37 TON
SECTION NO. 0005		
DESIGN NO. 0213; 155'-0 X 30' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE BRFN-151-3(133)--39-57		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	408 LB
2413-0698074	DECK REPAIR, CL A	45 SY
SECTION NO. 0006		
DESIGN NO. 0213; ALTERNATE 'BB' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN (133)		
2413-0698066	DECK OVERLAY (CL O PCC)	526 SY
SECTION NO. 0007		
DESIGN NO. 0213; ALTERNATE 'BB' OPTION 2: CLASS HPC-O PCC		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN (133)

2413-0698067 DECK OVERLAY (CL HPC-O PCC) 526 SY

SECTION NO. 0008

ROADWAY ITEMS

BRFN-151-3(133)--39-57

2102-2625000 EMBANKMENT-IN-PLACE 200 CY

2303-0052500 HMA (10M ESAL) INTERMEDIATE, 1/2" 37 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 67-0371-046

Proposed Contract Period: Specified Start Date of 06/03/13 with 95 WORK DAYS

Project(s):

Project No: BRFN-037-1(46)--39-67  
 County: MONONA  
 Type of Work: BRIDGE DECK OVERLAY  
 Route: IOWA 37 Length: 0.00 miles  
 Location: OVER WILLIOW RIVER  
 1.2 MI. W. OF S.R. E-54

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 113; REPAIRS TO A 180' X 28' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	45 CY
2404-7775000	REINFORC STEEL	3,293 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	2,912 LB
2413-0698074	DECK REPAIR, CL A	160 SY
SECTION NO. 0002		
	DESIGN NO. 113; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	
2413-0698066	DECK OVERLAY (CL O PCC)	556 SY
SECTION NO. 0003		
	DESIGN NO. 113; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	556 SY
SECTION NO. 0004		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	999 CY
2303-0143504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	653 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 68-C068-064

Proposed Contract Period: Late Start Date of 06/10/13 with 100 WORK DAYS

Project(s):

Project No: BROS-C068(64)--5F-68

County: MONROE

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 695TH AVE Length: 0.20 miles

Location: 695TH AVE W 0.3 MI

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR TWIN 12' X 12' X 118'-0 REINFORCED CONCRETE BOX		
CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	697 CY
2404-7775000	REINFORC STEEL	87,211 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,378 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	2,323 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 012                      Proposal ID: 90-C090-066

Proposed Contract Period: Late Start Date of 07/29/13 with 65 WORK DAYS

Project(s):

Project No: BROS-C090(66)--5F-90

County: WAPELLO

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: POINT ISABELLE RD      Length: 0.00 miles

Location: OVER VILLAGE CREEK APPROXIMATELY 1 MILE SOUTH OF OTTUMWA

Item No.	Item Description	Quantity/Unit
-----		
	SECTION NO. 0001	
	ITEMS FOR A 100'-0 X 24'-0 PRETENSIONED PRESTRESSED CONCRETE	
	BEAM BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	128 CY
2404-7775000	REINFORC STEEL	27,854 LB
	SECTION NO. 0002	
	ROADWAY ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,677 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 91-0653-059

Proposed Contract Period: Late Start Date of 04/01/13 with 100 WORK DAYS  
Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.  
No Start Date Specified with 75 WORK DAYS  
Site 02: SEE SITE NUMBER 02 DESCRIPTION BELOW.  
No Start Date Specified with 15 WORK DAYS

Proposal Note:

\*\*\* SITE NUMBER 01 \*\*\*

THIS SITE IS FOR WHEN TRAFFIC IS IN THE TWO-WAY, TWO-LANE  
CONFIGURATION SHOWN IN THE J SHEETS.

\*\*\* SITE NUMBER 02 \*\*\*

THIS SITE IS FOR WORK WHICH ONLY REQUIRES A SINGLE LANE  
CLOSURE. NO LANE CLOSURES WILL BE ALLOWED FROM 6:00 AM TO  
9:00 AM OR FROM 3:00 PM TO 6:00 PM, MONDAY THROUGH FRIDAY.

Project(s):

Project No: BRF-065-3(59)--38-91  
County: WARREN  
Type of Work: BRIDGE REPLACEMENT - PPCB  
Route: U.S. 65 Length: 0.00 miles  
Location: OVER NORTH RIVER 1.1 MILES N. OF CO. RD. G-16(SBL)

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
DESIGN NO. 0512; 346'-0 X 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	794 CY
2404-7775000	REINFORC STEEL	48,913 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	135,033 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	14,622 CY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	3,065 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	130 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 014                      Proposal ID: 96-C096-111

Proposed Contract Period: Late Start Date of 08/19/13 with 45 WORK DAYS

Project(s):

Project No: BRS-C096(111)--60-96

County: WINNESHIEK

Type of Work: RCB CULVERT NEW - TWIN BOX

Route: W42                                      Length: 0.00 miles

Location: 0.5 MILE SOUTH OF THE INTERSECTION WITH VALDRES ROAD

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A TWIN 12'-0 X 12'-0 X 74'-0 REINFORCED CONCRETE		
BOX CULVERT		
2102-2625000	EMBANKMENT-IN-PLACE	400 CY
2303-0131500	HMA (1M ESAL) BASE, 1/2"	611 SY
2303-0132500	HMA (1M ESAL) INTERMEDIATE, 1/2"	611 SY
2303-0133500	HMA (1M ESAL) SURF, 1/2", NO FRIC	611 SY
2403-0100020	STRUCT CONC (RCB CULV)	428 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	55,299 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 101                      Proposal ID: 52-C052-098

Proposed Contract Period: Late Start Date of 06/10/13 with 60 WORK DAYS

Project(s):

Project No: STP-S-C052(98)--5E-52

County: JOHNSON

Type of Work: PCC OVERLAY - BONDED

Route: F62                                      Length: 4.00 miles

Location: FROM WAPSI AVE. TO MUSCATINE COUNTY

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	6,920 CY
2310-5151040	PCC OVERLAY, FURN ONLY	9,025 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	45,101 SY



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 102                      Proposal ID: 77-0187-630

Proposed Contract Period: Late Start Date of 07/08/13 with 60 WORK DAYS

Site 01: A + B RAILROAD FLAGGERS

Cost Plus Time Site (A + B). Road User Cost per Day: \$ 700.00

Project(s):

Project No: STP-E-0187(630)--8V-77

County: POLK

Type of Work: PCC SIDEWALK/TRAIL

Route: GAY LEA WILSON TRAIL Length: 3.18 miles

Location: IN THE CITY OF ANKENY, FROM NE 62ND ST AND DELAWARE AVE  
TO SE FOUR MILE DR AND NE 54TH AVE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	9,015 CY
2511-0301800	RECREATIONAL TRAIL, HMA, 8"	5 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	17,033 SY
2511-0302800	RECREATIONAL TRAIL, PCC, 8"	1,402 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 96-C096-099

Proposed Contract Period: Late Start Date of 06/03/13 with 65 WORK DAYS

Project(s):

Project No: STP-S-C096(99)--5E-96

County: WINNESHIEK

Type of Work: PCC PAVEMENT - REPLACE

Route: V64 Length: 3.30 miles

Location: FROM THE JUNCTION WITH B16 JUST EAST OF PROTOVIN SOUTH 3.3  
MILES TO THE JUNCTION WITH 345TH AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	290 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	43,756 SY
2403-0100020	STRUCT CONC (RCB CULV)	99 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	15,929 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 151                      Proposal ID: 16-C016-083

Proposed Contract Period: Late Start Date of 07/08/13 with 50 WORK DAYS

Project(s):

Project No: STP-S-C016(83)--5E-16

County: CEDAR

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: Y24                                      Length: 3.50 miles

Location: FROM LOWDEN CITY LIMITS TO 122ND STREET

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	839 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	182 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	990 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	4,280 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	4,255 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 152                      Proposal ID: 25-0445-025

Proposed Contract Period: Late Start Date of 08/26/13 with 35 WORK DAYS

Project(s):

Project No: HSIPX-044-5(25)--3L-25

County: DALLAS

Type of Work: HMA PAVED SHOULDER - NEW

Route: IOWA 44                      Length: 7.56 miles

Location: FROM DALLAS CENTER E. TO GRIMES

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	4,148 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	3,084 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	617 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	61 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 153                      Proposal ID: 34-2189-119

Proposed Contract Period: Late Start Date of 05/13/13 with 100 WORK DAYS

Project(s):

Project No: STP-218-9(119)--2C-34

County: FLOYD

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: U.S. 218                      Length: 9.17 miles

Location: FROM CN R.R. CROSSING N. OF FLOYD N. TO 0.7 MILE S. OF  
E. JCT. IA. 9

---

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	674 CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	3,781 CY
2303-0041750	HMA (3M ESAL) BASE, 3/4"	9,156 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	16,096 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	16,551 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	26 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)	933 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	6 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 154                      Proposal ID: 76-C076-065

Proposed Contract Period: Late Start Date of 08/26/13 with 30 WORK DAYS

Project(s):

Project No: FM-C076(65)--55-76

County: POCAHONTAS

Type of Work: HMA RESURFACING

Route: C-66

Length: 7.00 miles

Location: IA4 TO N65

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0032750	HMA (1M ESAL) INTERMEDIATE, 3/4"	9,533 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	7,225 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 55-0092-706

Proposed Contract Period: Late Start Date of 08/26/13 with 20 WORK DAYS

Project(s):

Project No: MP-169-2(704)172--76-46

County: HUMBOLDT

Type of Work: HMA JOINT & CRACK SEALING

Route: U.S. 169 Length: 1.91 miles

Location: IN THE CITY OF HUMBOLDT, FROM WILLOW RIDGE DRIVE, NORTH  
TO THE JCT. OF IA 3.

Project No: MP-009-2(706)127--76-55

County: KOSSUTH

Type of Work: HMA JOINT & CRACK SEALING

Route: IOWA 9 Length: 10.01 miles

Location: E. JCT. OF US 169 TO COUNTY ROAD R-20 AND COUNTY ROAD R-50  
TO THE NORTH JCT. OF US 69.

Project No: MP-003-2(709)154--76-99

County: WRIGHT

Type of Work: HMA JOINT & CRACK SEALING

Route: IOWA 3 Length: 4.30 miles

Location: IN THE CITY OF CLARION FROM E. OF 2ND ST. NW TO  
E. OF SHERWOOD ST. SE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 202                      Proposal ID: 74-0183-092

Proposed Contract Period: Late Start Date of 08/05/13 with 35 WORK DAYS

Project(s):

Project No: NHSN-018-3(92)--2R-74

County: PALO ALTO

Type of Work: MICROSURFACING

Route: U.S. 18                              Length: 7.91 miles

Location: FROM E. OF HURON ST. IN EMMETSBURG E. TO ECL OF CYLINDER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	162 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	3 EACH



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 301                      Proposal ID: 15-0922-039

Proposed Contract Period: Late Start Date of 08/26/13 with 45 WORK DAYS

Project(s):

Project No: STPN-092-2(39)--2J-15

County: CASS

Type of Work: REVETMENT

Route: IOWA 92                      Length: 0.00 miles

Location: APPROX. 1.9 MILES W. OF U.S. 71

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 302                      Proposal ID: 44-2182-136-A

Proposed Contract Period: Late Start Date of 04/15/13 with 30 WORK DAYS

Project(s):

Project No: ER-218-2(136)--28-44

County: HENRY

Type of Work: SLIDE REPAIR

Route: U.S. 218                      Length: 0.00 miles

Location: APPROX. 2 MILES N. OF LEE CO. LINE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 303                      Proposal ID: 57-0136-500

Proposed Contract Period: Late Start Date of 05/06/13 with 50 WORK DAYS

Project(s):

Project No: MB-013-6(500)14--77-57

County: LINN

Type of Work: SLOPE PROTECTION

Route: IOWA 13                      Length: 0.00 miles

Location: OVER E. INDIAN CREEK 6 MILES N. OF US 151

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 351                      Proposal ID: 00-000S-573

Proposed Contract Period: Completion Date of 12/01/14

Project(s):

Project No: IMN-000-S(573)0--0E-00

County: STATEWIDE

Type of Work: GUARDRAIL

Route: MULTIPLE ROUTES              Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 6

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 401                      Proposal ID: 06-0306-201

Proposed Contract Period: Approx Start Date of 02/04/13 with 10 WORK DAYS

Project(s):

Project No: NHSN-030-6(201)--2R-06

County: BENTON

Type of Work: SALVAGE AND REMOVAL

Route: U.S. 30                              Length: 0.00 miles

Location: 1542 73RD ST., KEYSTONE IA. PARCEL NO. 29A

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 402                      Proposal ID: 97-0296-249

Proposed Contract Period: Approx Start Date of 02/04/13 with 30 WORK DAYS

Project(s):

Project No: IMN-029-6(249)147--0E-97

County: WOODBURY

Type of Work: SALVAGE AND REMOVAL

Route: I-29                                      Length: 0.00 miles

Location: IN THE CITY OF SIOUX CITY AT 313-313 S.FLOYD ST.(#233)/305  
S. VIRGINIA/1022 DACE(#225/1010 GORDON DR/205 S. CT.(#205C)

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 501                      Proposal ID: 77-2352-638

Proposed Contract Period: Late Start Date of 03/04/13 with 30 WORK DAYS

Project(s):

Project No: IMN-235-2(638)2--0E-77

County: POLK

Type of Work: LANDSCAPING

Route: I-235                                      Length: 0.00 miles

Location: FROM 35TH ST. IN WEST DES MOINES E. TO 2ND AVE.  
(VARIOUS LOCATIONS)

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 601                      Proposal ID: 00-0002-502

Proposed Contract Period: Late Start Date of 05/06/13 with 5 WORK DAYS

Project(s):

Project No: MB-000-2(502)0--77-00

County: STATEWIDE

Type of Work: BRIDGE CLEANING

Route: MULTIPLE ROUTES                      Length: 0.00 miles

Location: VARIOUS LOCATION IN DISTRICT 2

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 602                      Proposal ID: 00-0003-502

Proposed Contract Period: Late Start Date of 05/06/13 with 40 WORK DAYS

Project(s):

Project No: MB-000-3(502)0--77-00

County: STATEWIDE

Type of Work: BRIDGE CLEANING

Route: MULTIPLE ROUTES                      Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 3

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 603                      Proposal ID: 00-0004-502

Proposed Contract Period: Late Start Date of 05/06/13 with 5 WORK DAYS

Project(s):

Project No: MB-000-4(502)0--77-00

County: STATEWIDE

Type of Work: BRIDGE CLEANING

Route: MULTIPLE ROUTES                      Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 4

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 604                      Proposal ID: 00-0005-502

Proposed Contract Period: Late Start Date of 05/06/13 with 50 WORK DAYS

Project(s):

Project No: MB-000-5(502)0--77-00

County: STATEWIDE

Type of Work: BRIDGE CLEANING

Route: MULTIPLE ROUTES                      Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 5

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: November 20, 2012 10:00 A.M.

Proposed Bid Order: 605                      Proposal ID: 09-0036-057

Proposed Contract Period: Late Start Date of 04/01/13 with 45 WORK DAYS

Project(s):

Project No: BRFN-003-6(57)--39-09

County: BREMER

Type of Work: BRIDGE PAINTING

Route: IOWA 3

Length: 0.00 miles

Location: OVER CEDAR RIVER

0.3 MI. E. OF US 218

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
DESIGN NO. 0112; REPAIRS TO A 370'-0 X 48' CONTINUOUS STEEL		
GIRDER BRIDGE		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	684 SY
2413-0698074	DECK REPAIR, CL A	140 SY

