IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 001 Proposal ID: 10-1503-067 Proposed Contract Period: Late Start Date of 04/01/13 with 130 WORK DAYS Project(s): Project No: BRFN-150-3(67)--39-10 County: BUCHANAN Type of Work: BRIDGE REPLACEMENT - PPCB Route: IOWA 150 Length: 0.00 miles Location: OVER BEAR CREEK 0.9 MILES NORTH OF CO. RD. D-47 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 DESIGN NO. 0113; 193'-0 X 44' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 458 CY 2404-7775000 REINFORC STEEL 7,898 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 94,302 LB SECTION NO. 0003 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 19,705 CY 2301-1033095 STD/S-F PCC PAV'T, CL C CL 3, 9.5" 374 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 002 Proposal ID: 11-C011-072 Proposed Contract Period: Late Start Date of 07/22/13 with 60 WORK DAYS Project(s): Project No: BROS-C011(72)--8J-11 County: BUENA VISTA Type of Work: BRIDGE NEW - CCS Route: 240TH AVE Length: 0.00 miles Location: OVER DRAINAGE DITCH _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEMS FOR A 70'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE WITH OPEN RAIL 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 2,467 CY 153 CY 2404-7775000 REINFORC STEEL 39,653 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 003 Proposal ID: 11-C011-090 Proposed Contract Period: Late Start Date of 07/22/13 with 60 WORK DAYS Project(s): Project No: BROS-C011(90)--8J-11 County: BUENA VISTA Type of Work: BRIDGE REPLACEMENT - CCS Route: 650TH STREET Length: 0.00 miles Location: OVER DRAINAGE DITCH _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEMS FOR A 80'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE WITH OPEN RAIL 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 4,474 CY 2403-0100010 STRUCT CONC (BRIDGE) 183 CY 2404-7775000 REINFORC STEEL 46,977 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 004 Proposal ID: 15-C015-034 Proposed Contract Period: Late Start Date of 05/06/13 with 120 WORK DAYS Project(s): Project No: BROS-C015(34)--5F-15 County: CASS Type of Work: BRIDGE AND APPROACHES - PPCB Route: LANSING ROAD Length: 0.13 miles Location: ON LANSING RD OVER NISHNABOTNA RIVER APPROX. 2.5 MI. SW OF ATLANTIC _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 299'-0 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 558 CY 2404-7775000 REINFORC STEEL 37,685 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 91,590 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 7,987 CY 2301-1032080 STD/S-F PCC PAV'T, CL C CL 2, 8" 1,303 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 005 Proposal ID: 29-C029-070 Proposed Contract Period: Late Start Date of 07/08/13 with 85 WORK DAYS Project(s): Project No: BROS-C029(70)--5F-29 County: DES MOINES Type of Work: BRIDGE AND APPROACHES - CCS Route: 155TH STREET Length: 0.30 miles Location: 155 STREET OVER YELLOW SPRINK CREEK _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 150'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 415 CY 91,377 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 11,076 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 006 Proposal ID: 34-6567-601 Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS Project(s): Project No: BRS-6567(601)--60-34 County: FLOYD Type of Work: BRIDGE REPLACEMENT - PPCB Route: E. MAIN Length: 0.00 miles Location: IN THE CITY OF ROCKFORD ROCK RIVER IN THE CITY OF ROCKFORD _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 201'-6 X 32'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 960 CY 2403-0100000 STRUCT CONC (MISCELLANEOUS) 390 CY 2403-0100010 STRUCT CONC (BRIDGE) 589 CY 2404-7775000 REINFORC STEEL 27,726 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 111,479 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 009 Proposal ID: 43-C043-070 Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS

Project(s):
Project No: BROS-C043(70)--5F-43
County: HARRISON
Type of Work: BRIDGE REPLACEMENT - PPCB
 Route: KELLEY AVE Length: 0.23 miles
 Location: OVER SOLDIER RIVER

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
I	TEMS FOR A 201'-4 X 24' PRETENSIONED PREST	RESSED CONCRETE
В	EAM BRIDGE	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	100,136 CY
2403-0100010	STRUCT CONC (BRIDGE)	416 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	84,002 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M.

Proposed Bid Order: 00A Proposal ID: 77-0654-135-M

Proposed Contract Period: Specified Start Date of 04/01/13 with 140 WORK DAYS

Proposal Note:

OPTIONALLY COMBINED AND INDIVIDUAL PROPOSALS LISTING

THE WORK ON THE FOLLOWING PROJECTS ARE OFFERED IN THIS LETTING ON AN OPTIONALLY COMBINED PROPOSAL AND ON INDIVIDUAL PROPOSALS AS SHOWN BELOW:

в.О.	PROPOSAL ID	COUNTY	PROJECT NO.
====	================	================	===============================
???	77-0654-135	POLK	NHSX-065-4(135)3H-77
???	77-0654-127	POLK	NHSX-065-4(127)3H-77
. ANI	D		

77-0654-135-M	POLK	NHSX-065-4(135)3H-77
		NHSX-065-4(127)3H-77

SEE NOTE 700.11 IN THE PROPOSAL SPECIAL PROVISIONS TEXT.

Location: OVER DES MOINES RIVER MIDDLE OVERFLOW SE

OF DES MOINES (NBL)

```
Project(s):
```

???

•

Project No:	NHSX-065-4(127)3H-	77		
County:	POLK			
Type of Work:	BRIDGE NEW - PPCB			
Route:	U.S. 65	Length:	0.00 miles	
Location:	OVER DES MOINES RIVE	R SOUTH	OVERFLOW SE OF	
	DES MOINES(NBL)			
Project No:	NHSX-065-4(135)3H-	77		
County:	POLK			
Type of Work:	BRIDGE NEW - PPCB			
Route:	U.S. 65	Length:	0.00 miles	

_____ Item Description Item No. Quantity/Unit _____ SECTION NO. 0001 DESIGN NO. 0512; A 466'-0 X 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE NHSX-065-4(127)--3H-77 2403-0100010 STRUCT CONC (BRIDGE) 773 CY 2404-7775000 REINFORC STEEL 86,732 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 184,627 LB SECTION NO. 0002 ROADWAY ITEMS NHSX-065-4(127)--3H-77

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) SECTION NO. 0002 ROADWAY ITEMS NHSX-065-4(127)--3H-77 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 34,861 CY SECTION NO. 0005 DESIGN NO. 0912; A 700'-0 X 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE NHSX-065-4(135)--3H-77 2403-0100010 STRUCT CONC (BRIDGE) 1,180 CY 2404-7775000 REINFORC STEEL 163,911 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 272,948 LB SECTION NO. 0006 ROADWAY ITEMS NHSX-065-4(135)--3H-77 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033120 STD/S-F PCC PAV'T, CL C CL 3, 12" 43,005 CY 6,159 SY SECTION NO. 0010 ALTERNATE 'CC' OPTION 2: PCC SHOULDERS BID THIS SECTION IF ALTERNATE 'CC' OPTION 2 IS CHOSEN (135) 2122-5190007 PAVED SHLD, PCC, 7" 3,042 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 010 Proposal ID: 48-0806-310 Proposed Contract Period: Late Start Date of 06/10/13 with 95 WORK DAYS Project(s): Project No: IMN-080-6(310)217--0E-48 County: IOWA Type of Work: BRIDGE REPAIR Route: I-80 Length: 0.00 miles Location: AT CO. RD. V66 3.6 MILES W. OF IA. 149 _____ Item No. Quantity/Unit Item Description _____ SECTION NO. 0001 DESIGN NO. 0113; 223'-9 X 28' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2403-0100000 STRUCT CONC (MISCELLANEOUS) 38 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 3,743 LB 2413-0698067 DECK OVERLAY (CL HPC-O PCC) 709 SY 2413-0698074 DECK REPAIR, CL A 122 SY SECTION NO. 0002 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 240 CY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 011 Proposal ID: 52-0806-311 Proposed Contract Period: By individual sites. Site 01: TO COMPLETE STAGE 1 ON SHEET J.1 Specified Start Date of 06/03/13 with 15 WORK DAYS Site 02: TO COMPLETE STAGE 3 ON SHEET J.1 Specified Start Date of 07/29/13 with 5 WORK DAYS Project(s): Project No: IMN-080-6(311)242--0E-52 County: JOHNSON Type of Work: BRIDGE REPAIR Route: I-80 Length: 0.00 miles Location: ON LOCAL RD. OVER I-80, 2.9 MILES E. OF I-380 _____ _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 012 Proposal ID: 57-C057-081 Proposed Contract Period: Late Start Date of 06/17/13 with 90 WORK DAYS Project(s): Project No: BRS-C057(81)--60-57 County: LINN Type of Work: BRIDGE REPLACEMENT - CCS Route: E34 Length: 0.00 miles Location: OVER BERRYS RUN SEC 18, T84N, R6W _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 70'-0 X 70'-0 THREE SPAN CONTINUOUS CONCRETE SLAB BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,100 CY 2303-0043500 HMA (3M ESAL) SURF, $1/2"\,,$ NO FRIC 312 TON 2310-5151040 PCC OVERLAY, FURN ONLY 254 CY 2310-5151551 PCC OVERLAY PLACE ONLY (WHITE TOPPING) 1,019 SY 2403-0100010 STRUCT CONC (BRIDGE) 544 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 100,411 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 77-0654-127

Proposed Contract Period: Specified Start Date of 04/01/13 with 130 WORK DAYS

Proposal Note:

OPTIONALLY COMBINED AND INDIVIDUAL PROPOSALS LISTING

THE WORK ON THE FOLLOWING PROJECTS ARE OFFERED IN THIS LETTING ON AN OPTIONALLY COMBINED PROPOSAL AND ON INDIVIDUAL PROPOSALS AS SHOWN BELOW:

в.О.	PROPOSAL ID	COUNTY	PROJECT NO.
====	===============	=============	=======================================
???	77-0654-135	POLK	NHSX-065-4(135)3H-77
???	77-0654-127	POLK	NHSX-065-4(127)3H-77
. AN	D		
???	77-0654-135-M	POLK	NHSX-065-4(135)3H-77

POLK NHSX-065-4(135)--3H-77 NHSX-065-4(127)--3H-77

SEE NOTE 700.11 IN THE PROPOSAL SPECIAL PROVISIONS TEXT.

Project(s):

•

Project No:	NHSX-065-4(127)3H-77
County:	POLK
Type of Work:	BRIDGE NEW - PPCB
Route:	U.S. 65 Length: 0.00 miles
Location:	OVER DES MOINES RIVER SOUTH OVERFLOW SE OF
	DES MOINES(NBL)

Item No. Item Description Quantity/Unit SECTION NO. 0001 DESIGN NO. 0512; A 466'-0 X 40'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 773 CY

2404-7775000	REINFORC	STEEL			86,732	LB
2404-7775005	REINFORC	STEEL, EPC	YXC	COATED	184,627	LB
SECTION	NO. 0002					
R	OADWAY ITE	MS				
2102-2710070	EXCAVATIO	N, CL 10,	RDV	IY+BORROW	34,861	СҮ

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 77-0654-135

Proposed Contract Period: Specified Start Date of 04/01/13 with 140 WORK DAYS

Proposal Note:

2122-5190007 PAVED SHLD, PCC, 7"

OPTIONALLY COMBINED AND INDIVIDUAL PROPOSALS LISTING -----

THE WORK ON THE FOLLOWING PROJECTS ARE OFFERED IN THIS LETTING ON AN OPTIONALLY COMBINED PROPOSAL AND ON INDIVIDUAL PROPOSALS AS SHOWN BELOW:

в.О.	PROPOSAL ID	COUNTY	PROJECT NO.
====	==============	================	=======================================
???	77-0654-135	POLK	NHSX-065-4(135)3H-77
???	77-0654-127	POLK	NHSX-065-4(127)3H-77
. ANI	D		

???	77-0654-135-M	POLK	NHSX-065-4(135)3H-77
•			NHSX-065-4(127)3H-77

SEE NOTE 700.11 IN THE PROPOSAL SPECIAL PROVISIONS TEXT.

Project(s): Project No: NHSX-065-4(135)3H-77 County: POLK Type of Work: BRIDGE NEW - PPCB Route: U.S. 65 Length: 0.00 mil	
Location: OVER DES MOINES RIVER MIDDLE OVERFLOW OF DES MOINES (NBL)	SE
Item No. Item Description	Quantity/Unit
SECTION NO. 0001	
DESIGN NO. 0912; A 700'-0 X 40'-0 PRETENSI CONCRETE BEAM BRIDGE	ONED PRESTRESSED
2403-0100010 STRUCT CONC (BRIDGE)	1,180 CY
2404-7775000 REINFORC STEEL	163,911 LB
2404-7775005 REINFORC STEEL, EPOXY COATED	272,948 LB
SECTION NO. 0002	
ROADWAY ITEMS	
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	43,005 CY
2301-1033120 STD/S-F PCC PAV'T, CL C CL 3, 12"	6,159 SY
SECTION NO. 0006	
ALTERNATE 'BB' OPTION 2: PCC SHOULDERS	
BID THIS SECTION IF ALTERNATE 'BB' OPTION 2	2 IS CHOSEN

3,042 SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 015 Proposal ID: 77-2352-628 Proposed Contract Period: Late Start Date of 04/01/13 with 130 WORK DAYS Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW. Late Start Date of 04/01/13 with 60 WORK DAYS Proposal Note: *** SITE NUMBER 01 *** TO COMPLETE THE (628) PROJECT, THE WEST BRIDGE APPROACH WORK FOR THE (628) PROJECT AND ALL WORK ON 73RD STREET. *** SITE NUMBER 02 *** TO COMPLETE THE GRADING AND PAVING FROM STATION 1515+00 TO 1522+25. REFER TO THE J SHEETS FOR MORE INFORMATION. Project(s): Project No: IM-235-2(627)4--13-77 County: POLK Type of Work: HMA PAVEMENT - GRADE AND NEW Route: I-235 Length: 0.00 miles Location: IN THE CITY OF WINDSOR HEIGHTS FROM 73RD /8TH ST. E. TO 63RD ST.(WB AUXILIARY LANE) Project No: IM-235-2(628)4--13-77 County: POLK Type of Work: RECONSTRUCTION - BRIDGE WIDENING Length: 0.00 miles Route: I-235 Location: IN THE CITY OF WINDSOR HEIGHTS OVER 73RD ST./8TH ST. AND IAIS R.R. Project No: IM-235-2(629)4--13-77 County: POLK Type of Work: RECONSTRUCTION - BRIDGE WIDENING Route: I-235 Length: 0.00 miles Location: IN THE CITY OF WINDSOR HEIGHTS OVER WALNUT CREEK Project No: IM-235-2(630)4--13-77 County: POLK Type of Work: TRAFFIC SIGNS Route: I-235 Length: 0.00 miles Location: IN THE CITY OF WINDSOR HEIGHTS FROM 73RD /8TH ST. E. TO 63RD ST.(WB AUXILIARY LANE) Project No: IM-235-2(631)4--13-77 County: POLK Type of Work: LIGHTING Route: I-235 Length: 0.00 miles Location: IN THE CITY OF WINDSOR HEIGHTS FROM 73RD /8TH ST. E. TO 63RD ST.(WB AUXILIARY LANE) _____ Item No. Item Description Ouantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)		
SECTION NO. 0001		
ROADWAY ITEMS- IM-235-2(627)413-77		
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	25,071	CY
2301-1034120 STD/S-F PCC PAV'T, CL C CL 3I, 12"	12	SY
2303-0052500 HMA (10M ESAL) INTERMEDIATE, 1/2"	27	TON
2303-0053503 HMA (10M ESAL) SURF, 1/2", FRIC L-3	27	TON
2303-0061500 HMA (30M ESAL) BASE, 1/2"	763	TON
2303-0062500 HMA (30M ESAL) INTERMEDIATE, 1/2"	152	TON
2303-0063502 HMA (30M ESAL) SURF, 1/2", FRIC L-2	152	TON
SECTION NO. 0002		
DESIGN NO. 0312; A 332'-0 X 69'-6 CONTINUOUS WELDED	GIRDER	
BRIDGE - IM-235-2(628)413-77		
2403-0100010 STRUCT CONC (BRIDGE)	388	CY
2404-7775000 REINFORC STEEL	17,517	LB
2404-7775005 REINFORC STEEL, EPOXY COATED	105,835	LB
SECTION NO. 0004		
DESIGN NO. 0412; A 331'-0 X 69'-6 CONTINUOUS WELDED	GIRDER	
BRIDGE - IM-235-2(629)413-77		
2403-0100010 STRUCT CONC (BRIDGE)	181	
2404-7775000 REINFORC STEEL	17,200	LB
2404-7775005 REINFORC STEEL, EPOXY COATED	63,016	LB
SECTION NO. 0005		
TRAFFIC SIGN ITEMS - IM-235-2(630)413-77		
2403-0100000 STRUCT CONC (MISCELLANEOUS)	68	
2404-7775005 REINFORC STEEL, EPOXY COATED	8,152	LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 016 Proposal ID: 78-1924-500 Proposed Contract Period: Late Start Date of 09/09/13 with 35 WORK DAYS Project(s): Project No: MB-192-4(500)1--77-78 County: POTTAWATTAMIE Type of Work: BRIDGE REHABILITATION Route: IOWA 192 Length: 0.00 miles Location: IN THE CITY OF COUNCIL BLUFFS AT VIADUCT OVER R.R. & CITY STREETS 1.1 MILES N. OF I-80 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 DESIGN NO. 0413; 2644'-11 X 71'-0 PRETENSIONED PRESTRESSED AND WELDED PLATE GIRDER BRIDGE N.B. 2403-0100000 STRUCT CONC (MISCELLANEOUS) 6 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 983 LB SECTION NO. 0002 DESIGN NO. 0513; 2644'-11 X 71'-0 PRETENSIONED PRESTRESSED AND WELDED PLATE GIRDER BRIDGE S.B. 2403-0100000 STRUCT CONC (MISCELLANEOUS) 5 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 898 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 017 Proposal ID: 97-1411-028 Proposed Contract Period: Late Start Date of 07/15/13 with 70 WORK DAYS Project(s): Project No: BRFN-141-1(28)--39-97 County: WOODBURY Type of Work: BRIDGE DECK OVERLAY Route: IOWA 141 Length: 0.00 miles Location: OVER SMOKEY HOLLOW CREEK 0.2 MILES EAST OF IA 31 _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 DESIGN NO. 0213; 80'-0 X 50'-0 CONTINUOUS CONCRETE SLAB BRIDGE 2413-0698074 DECK REPAIR, CL A 100 SY SECTION NO. 0002 DESIGN NO. 0213; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN 2413-0698066 DECK OVERLAY (CL O PCC) 457 SY SECTION NO. 0003 DESIGN NO. 0213; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN 2413-0698067 DECK OVERLAY (CL HPC-O PCC) 457 SY SECTION NO. 0004 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 100 CY

IOWA DEPARTMENT OF TRANSPORTATION

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 101 Proposal ID: 21-C021-115 Proposed Contract Period: Late Start Date of 04/01/13 with 135 WORK DAYS Project(s): Project No: L-1898--73-21 County: CLAY Type of Work: PCC OVERLAY - UNBONDED Route: WEST 4TH STREET Length: 1.50 miles Location: IN THE CITY OF SPENCER FROM W OF 37TH AVE W TO E OF COUNTRY CL Project No: HDP-C021(115)--6B-21 County: CLAY Type of Work: PCC PAVEMENT - NEW Route: M-44 Length: 4.00 miles Location: FROM US18 SOUTH TO 360TH STREET. Project No: STP-S-C021(125)--5E-21 County: CLAY Type of Work: PCC OVERLAY - BONDED Route: WEST 18TH STREET Length: 4.01 miles Location: FROM HWY 18 SOUTH TO W 18TH ST. THEN EAS T TO W 4TH ST. _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS DIVISION 4 L-1898--73-21 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,100 CY 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 617 SY 2310-5151040 PCC OVERLAY, FURN ONLY 3,353 CY 2310-5151551 PCC OVERLAY PLACE ONLY (WHITE TOPPING) 20,122 SY SECTION NO. 0002 ROADWAY ITEMS HDP-C021(115)--6B-21 DIVISION 1 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 56,981 CY 2122-5190008 PAVED SHLD, PCC, 8" 1,155 SY 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 43,498 SY 2301-1083090 STD/S-F PCC PAV'T, CL M CL 3, 9" 250 SY 2310-5151040PCC OVERLAY, FURN ONLY2310-5151551PCC OVERLAY PLACE ONLY (WHITE TOPPING)2403-0100000STRUCT CONC (MISCELLANEOUS) 188 CY 1,133 SY 18 CY 2404-7775000 REINFORC STEEL 3,187 LB 2511-0302500 RECREATIONAL TRAIL, PCC, 5" 601 SY SECTION NO. 0003 ROADWAY ITEMS STP-S-C021(125)--5E-21 2301-1083090 STD/S-F PCC PAV'T, CL M CL 3, 9" 2310-5151040 PCC OVERLAY 1,119 SY 4,277 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

	003 OADWAY ITEMS IVISION 2 STP-S-C021(12	5)5E-21	
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	25,662	SY
SECTION 1	NO. 0004		
R	OADWAY ITEMS		
D	VIVISION 3 STP-S-C021(12	5)5E-21	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	11,754	СҮ
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	643	SY
2310-5151040	PCC OVERLAY, FURN ONLY	4,256	СҮ
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	25,538	SY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	60	SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 102 Proposal ID: 57-3432-606 Proposed Contract Period: Late Start Date of 04/15/13 with 130 WORK DAYS Proposal Note: ***SEC. 1111 INCENTIVE/DISINCENTIVE FOR EARLY COMPLETION*** THIS APPLIES TO SITES 01,02, 03 AND 04. THE CRITICAL CLOSURE ACTIVITY IS DEFINED AS COMPLETION OF ALL CONTRACT ITEMS DESCRIBED AS STAGES 1, 2A, 2B AND 3 ON SHEET J.1 OF THE PLANS. THE INCENTIVE/DISINCENTIVE DAILY RATE IS \$1,000.00. THERE IS MAXIMUM INCENTIVE PAYMENT OF \$5,000.00 PER SITE. Project(s): Project No: STP-U-3432(606)--70-57 County: LINN Type of Work: PCC PAVEMENT - GRADE & REPLACE Route: BOYSON & ROBINS Length: 0.10 miles Location: IN THE CITY OF HIAWATHA, BOYSON ROAD & ROBINS ROAD INTERSECTION _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,000 CY 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 3,705 SY 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 52 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 1 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 103 Proposal ID: 70-C070-042 Proposed Contract Period: Late Start Date of 08/19/13 with 50 WORK DAYS Project(s): Project No: FM-C070(42)--55-70 County: MUSCATINE Type of Work: PCC OVERLAY - UNBONDED Route: X43 Length: 6.80 miles Location: BEGINNING AT THE LOUISA COUNTY LINE, THENCE NORTH TO THE JCT OF G-28 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 1,755 SY 2310-5151040 PCC OVERLAY, FURN ONLY 21,349 CY 2310-5151551 PCC OVERLAY PLACE ONLY (WHITE TOPPING) 87,949 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 104 Proposal ID: 75-3485-602 Proposed Contract Period: Late Start Date of 07/08/13 with 45 WORK DAYS Project(s): Project No: STP-E-3485(602)--8V-75 County: PLYMOUTH Type of Work: PCC SIDEWALK/TRAIL Route: GROVER & 2ND AVE Length: 0.20 miles Location: IN THE CITY OF HINTON, GROVER ST. FROM 1ST TO 2ND AVE THEN 2ND AVE FROM GROVER TO MAIN ST _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 595 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1032060 STD/S-F PCC PAV'T, CL C CL 2, 6" 40 SY 2511-0302400 RECREATIONAL TRAIL, PCC, 4" 888 SY 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 45 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 105 Proposal ID: 75-4257-630 Proposed Contract Period: Late Start Date of 06/17/13 with 40 WORK DAYS Project(s): Project No: STP-U-4257(630)--70-75 County: PLYMOUTH Type of Work: PCC OVERLAY - UNBONDED Route: 4TH AVE Length: 0.00 miles Location: IN THE CITY OF LE MARS 2ND STREET SOUTH TO 10TH STREET SOUTH _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2301-1033070 STD/S-F PCC PAV'T, CL C CL 3, 7" 2,421 SY 2310-5151040 PCC OVERLAY, FURN ONLY 2310-5151251 PCC OVERLAY PLACE ONLY (UNBONDED) 1,935 CY 12,432 SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 106 Proposal ID: 77-0352-364 Proposed Contract Period: Late Start Date of 04/01/13 with 130 WORK DAYS Site 01: A + B RAILROAD FLAGGERS Cost Plus Time Site (A + B). Road User Cost per Day: \$ 700.00 Proposal Note: *** NO EXCUSE ROAD OPENING BONUS *** THE CONTRACTOR WILL BE PAID THE PREDETERMINED LUMP SUM AMOUNT SHOWN IN THE PROPOSAL SCHEDULE OF PRICES FOR THE BID ITEM 'NO EXCUSE ROAD OPENING BONUS' FOR COMPLETING ALL CONSTRUCTION SO THAT I-35 IS OPEN TO TRAFFIC ON OR BEFORE THE CALENDAR DATE SHOWN. COMPLIANCE REQUIRES THAT THE CONTRACTOR MUST HAVE ALL CONSTRUCTION ON THE CONTRACT COMPLETED AND HAVE I-35 OPEN TO TRAFFIC WITH NO FURTHER LANE OR RAMP CLOSURES. ANY OTHER DELAYS DUE TO WEATHER, CHANGE ORDERS, OVERRUNS OF QUANTITIES, UTILITY DELAYS, OR ANY OTHER DELAYS WILL NOT BE CONSIDERED AS JUSTIFICATION TO MODIFY THE CALENDAR DATE. Project(s): Project No: IM-035-2(329)67--13-77 County: POLK Type of Work: TRAFFIC SIGNS Route: I-35 Length: 3.56 miles Location: WARREN CO. LINE N. TO I-80/235(SBL) Project No: BRFIM-035-2(351)72--05-77 County: POLK Type of Work: BRIDGE REPLACEMENT - PPCB Route: I-35 Length: 0.00 miles Location: IN THE CITY OF WEST DES MOINES I-35 SB OVER EP TRUE PKY., UP R.R. & JORDON CREEK Project No: IM-035-2(364)67--13-77 County: POLK Type of Work: PCC PAVEMENT - NEW Route: I-35 Length: 3.62 miles Location: FROM WARREN CO. LINE N. TO I-80/235(SBL) Project No: IM-035-2(367)67--13-77 County: POLK Type of Work: LIGHTING Route: I-35 Length: 0.00 miles Location: IN THE CITY OF WEST DES MOINES AT THE GRAND AVE. INTERCHANGE Project No: BRFIM-035-2(369)69--05-77 County: POLK Type of Work: BRIDGE REPLACEMENT - PPCB Route: I-35 Length: 0.00 miles Location: IN THE CITY OF WEST DES MOINES OVER IAIS R.R.(SBL)

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Project No: BRFIM-035-2(371)69--05-77 County: POLK Type of Work: BRIDGE REPLACEMENT - PPCB Route: I-35 Length: 0.00 miles Location: IN THE CITY OF WEST DES MOINES OVER GRAND AVE.(SBL) Project No: IM-035-2(384)69--13-77 County: POLK Type of Work: BRIDGE NEW - PPCB Route: I-35 Length: 0.00 miles Location: IN THE CITY OF WEST DES MOINES AT THE GRAND AVE. INTERCHANGE (SB ENTRANCE RAMP D OVER IAIS R.R.) Project No: IM-035-2(411)69--13-77 County: POLK Type of Work: RCB CULVERT NEW - SINGLE BOX Route: I-35 Length: 0.00 miles Location: IN THE CITY OF WEST DES MOINES AT THE GRAND AVE. INTERCHANGE(3 LOCATIONS) _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS IM-035-2(329)67--13-77 2403-0100000 STRUCT CONC (MISCELLANEOUS) 36 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 5,806 LB SECTION NO. 0002 DESIGN NO. 0413; 441'-0 X 59'- 5 1/2 PPCB BRIDGE BRFIM-035-2(351)72--05-77 2403-0100010 STRUCT CONC (BRIDGE) 37 CY 2404-7775000 REINFORC STEEL 2404-7775005 REINFORC STEEL, EPOXY COATED 139,018 LB 277,106 LB SECTION NO. 0004 ROADWAY ITEMS IM-035-2(364)67--13-77 2102-2625000 EMBANKMENT-IN-PLACE 124 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 237,253 CY 2301-1003090 STD/S-F PCC PAV'T, QM-C CL 3, 9" 14,712 SY 2301-1004115 STD/S-F PCC PAV'T, QM-C CL 3I, 11.5" 111,349 SY 2303-0043502 HMA (3M ESAL) SURF, 1/2", FRIC L-2 877 TON 2303-0143503 HMA (3M ESAL) SURF, 1/2", FRIC L-3 882 SY SECTION NO. 0005 ALTERNATE 'AA' OPTION 1: PCC SHOULDER BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (364) 2122-5190007 PAVED SHLD, PCC, 7" 4,353 SY SECTION NO. 0011 DESIGN NO. 0213; 194'-0 X 48'-0 PPCB BRIDGE BRFIM-035-2(369)69--05-77 2403-0100010 STRUCT CONC (BRIDGE) 144 CY 2404-7775000 REINFORC STEEL 39,438 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 117,185 LB SECTION NO. 0013 DESIGN NO. 0313; 284'-0 X 49'-7 PPCB BRIDGE BRFIM-035-2(371)69--05-77

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)		
SECTION NO. 0013		
DESIGN NO. 0313; 284'-0 X 49'-7 PPCB BRIDGE		
BRFIM-035-2(371)6905-77		
2403-0100010 STRUCT CONC (BRIDGE)	168	CY
	21,965	LB
2404-7775005 REINFORC STEEL, EPOXY COATED	160,797	LB
SECTION NO. 0015		
DESIGN NO. 0113; A 194'-0 X 26'-0 PPCB BRIDGE		
IM-035-2(384)6913-77		
2403-0100010 STRUCT CONC (BRIDGE)	419	-
2404-7775000 REINFORC STEEL	20,420	
2404-7775005 REINFORC STEEL, EPOXY COATED	72,588	LB
SECTION NO. 0017	-	
DESIGN NO. 0713; 12'-0 X 12'-0 RCB CULVERT EXTENSION	N	
IM-035-2(411)6913-77	0.0	
2403-0100020 STRUCT CONC (RCB CULV)	86	
2404-7775000 REINFORC STEEL SECTION NO. 0018	10,662	ΓВ
DESIGN NO. 0813; 12'-0 X 12'-0 X 292'-0 RCB CULVERT		
IM-035-2(411)6913-77		
2403-0100020 STRUCT CONC (RCB CULV)	810	CV
2404-7775000 REINFORC STEEL	140,270	-
SECTION NO. 0019	140,270	О
DESIGN NO. 1013; 14'-0 X 10'-0 X 64'-0 RCB CULVERT		
IM-035-2(411)6913-77		
2403-0100020 STRUCT CONC (RCB CULV)	189	CY
2404-7775000 REINFORC STEEL	31,173	LB
SECTION NO. 0021		
CONTRACT ITEMS		
2528-5160000 NO EXCUSE ROAD OPENING BONUS,	Lump Sum	LUMP

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 107 Proposal ID: 77-8260-624-A Proposed Contract Period: Late Start Date of 04/01/13 with 120 WORK DAYS Site 01: TO COMPLETE STAGE 2A & 2B WORK SHOWN ON PLAN SHEET J.1. No Start Date Specified with 20 WORK DAYS Site 02: CONSTRUCTION OF THE S. 1ST STREET CUL-DE-SAC. Specified Start Date of 06/03/13 with 45 WORK DAYS Site 03: CLOSURE OF SIDE ROAD 1 BETWEEN SWC AND BWD. No Start Date Specified with 15 WORK DAYS Proposal Note: *** CONTRACT AWARD LIMIT *** PER SECTION 09009.04 OF THE DEVELOPMENTAL SPECIFICATIONS FOR ADDED OPTIONS BIDDING, THE CONTRACT AWARD LIMIT FOR THIS PROPOSAL IS \$2,500,000.00 Project(s): Project No: STP-U-8260(624)--70-77 County: POLK Type of Work: PCC PAVEMENT - GRADE AND NEW Route: SW CONNECTOR Length: 0.50 miles Location: IN THE CITY OF WEST DES MOINES FROM INT WITH BROWNS WOODS DR TO IA-28 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 2301-1033060 STD/S-F PCC PAV'T, CL C CL 3, 6" 76,122 CY 210 CY 990 SY 2301-1033070 STD/S-F PCC PAV'T, CL C CL 3, 7" 1,090 SY 2301-1033095 STD/S-F PCC PAV'T, CL C CL 3, 9.5" 1,610 SY 2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10" 6,430 SY 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 1,560 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 108 Proposal ID: 82-0587-634 Proposed Contract Period: Approx Start Date of 07/08/13 with 60 WORK DAYS Project(s): Project No: STP-E-0587(634)--8V-82 County: SCOTT Type of Work: PCC SIDEWALK/TRAIL Route: MIDDLE RD REC TRAIL Length: 1.54 miles Location: IN THE CITY OF BETTENDORF FROM DUCK CREEK TO DEVILS GLEN ROAD _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 TRAIL ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 4,280 CY 2511-0302500 RECREATIONAL TRAIL, PCC, 5" 7,728 SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 109 Proposal ID: 97-0296-222-A Proposed Contract Period: Late Start Date of 04/01/13 with 20 WORK DAYS Proposal Note: REFER TO 656.0183 FOR THE FOLLOWING INFORMATION: *** WORK PRIOR TO THE SPECIFIED START DATE (SITE 01) *** *** WORKING DAYS *** *** INCENTIVE/DISINCENTIVE *** *** NO EXCUSE ROAD OPENING BONUS *** Project(s): Project No: MB-020-3(502)1--77-97 County: WOODBURY Type of Work: DECK JOINT REPAIR Route: U.S. 20 Length: 0.0 Location: IN THE CITY OF SIOUX CITY ON-RAMP Length: 0.00 miles OVER IA. 376(S. HILLS DR.) & UP R.R. Project No: IM-NHS-029-6(176)142--03-97 County: WOODBURY Type of Work: TRAFFIC SIGNS Route: I-29 Length: 0.00 miles Location: IN THE CITY OF SIOUX CITY FROM HARBOR DR. OUTFALL N. TO 0.25 MILE S. OF BN/SF R.R. Project No: IM-NHS-029-6(222)143--03-97 County: WOODBURY Type of Work: PCC PAVEMENT - GRADE AND NEW Route: I-29 Length: 4.21 miles Location: IN THE CITY OF SIOUX CITY FROM HARBOR DR. OUTFALL N. TO 0.25 MILE S. OF BN/SF R.R. (NBL/RAMPS) Project No: IM-NHS-029-6(231)142--03-97 County: WOODBURY Type of Work: RCB CULVERT NEW - TWIN BOX Route: I-29 Length: 0.00 miles Location: IN THE CITY OF SIOUX CITY OVER THE AIRPORT OUTFALL (NBL) _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 DESIGN NO. 0613; REPAIRS TO A 339'-6 X VARIES CWPG BRIDGE MB-020-3(502)1--77-97 2403-0100000 STRUCT CONC (MISCELLANEOUS) 14 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 1,358 LB SECTION NO. 0002 ROADWAY ITEMS MB-020-3(502)1--77-97 2122-5190008 PAVED SHLD, PCC, 8" 924 SY SECTION NO. 0004

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) ROADWAY ITEMS	
IM-NHS-029-6(222)14303-97	
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	187,058 CY
	•
2301-1004110 STD/S-F PCC PAV'T, QM-C CL 3I, 11"	184,327 SY
2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10"	15,915 SY
2303-0101000 HMA WEDGE/LEVEL/STRENGTH	594 SY
2403-0100000 STRUCT CONC (MISCELLANEOUS)	157 CY
2404-7775005 REINFORC STEEL, EPOXY COATED	19,807 LB
2511-0302500 RECREATIONAL TRAIL, PCC, 5"	1,227 SY
2511-0302600 RECREATIONAL TRAIL, PCC, 6"	102 SY
SECTION NO. 0006	
CONTRACT ITEMS	
2528-5160000 NO EXCUSE ROAD OPENING BONUS,	Lump Sum LUMP
2528-5160100 CRITICAL CLOSURE ACTIVITY I/D	50 CDAY
2528-5160100 CRITICAL CLOSURE ACTIVITY I/D	10 CDAY
2528-5160100 CRITICAL CLOSURE ACTIVITY I/D	10 CDAY
2528-5160100 CRITICAL CLOSURE ACTIVITY I/D	20 CDAY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 151 Proposal ID: 09-8190-629 Proposed Contract Period: Specified Start Date of 06/10/13 with 45 WORK DAYS Project(s): Project No: STP-U-8190(629)--70-09 County: BREMER Type of Work: HMA PAVEMENT - REPLACE Route: 16TH STREET Length: 0.30 miles Location: IN THE CITY OF WAVERLY FROM W. BREMER AVE. (IA 3)TO 4TH AVE. SW _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEM 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,526 CY 2303-0031750 HMA (1M ESAL) BASE, 3/4" 1,163 TON 2303-0032750 HMA (1M ESAL) INTERMEDIATE, 3/4" 786 TON 2303-0033500 $\,$ HMA (1M ESAL) SURF, 1/2", NO FRIC 589 TON

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 152 Proposal ID: 35-0356-120 Proposed Contract Period: Late Start Date of 04/01/13 with 130 WORK DAYS Project(s): Project No: MP-003-2(704)172--76-35 County: FRANKLIN Type of Work: HMA RESURFACING Route: IOWA 3 Length: 0.98 miles Location: OVER I-35 Project No: IMX-035-6(120)166--02-35 County: FRANKLIN Type of Work: HMA RESURFACING WITH MILLING Route: I-35 Length: 5.90 miles Location: FROM IA. 3 INTERCHANGE N. TO 1.4 MILES N. OF THE CO. RD. C-25 INTERCHANGE(NBL/SBL) Project No: IMX-035-8(46)217--02-98 County: WORTH Type of Work: HMA RESURFACING Route: I-35 Length: 2.00 miles Location: FROM 1.82 MILES N. OF CO. RD. 105 N. TO MINNESOTA STATE LINE (NBL/SBL) _____ Item No. Item Description Ouantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS MP-3-2(704)172--76-35 2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 1,500 TON 2303-0033504 HMA (1M ESAL) SURF, 1/2", FRIC L-4 1,490 TON SECTION NO. 0003 ROADWAY ITEMS IMX-35-6(120)166--02-35 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 6,887 CY 2303-0031500 HMA (1M ESAL) BASE, 1/2" 15,829 TON 2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 5,435 TON 2303-0033504 HMA (1M ESAL) SURF, 1/2", FRIC L-4 5,395 TON 2303-0062500 HMA (30M ESAL) INTERMEDIATE, 1/2" 24,339 TON 2303-0063502 HMA (30M ESAL) SURF, 1/2", FRIC L-2 24,072 TON 2303-7000510 HMA MIX INCORPORATED W/ ANTI-STRIP AGENT 53,807 TON SECTION NO. 0008 ROADWAY ITEMS IMX-35-8(46)217--02-98 2303-0031500 HMA (1M ESAL) BASE, 1/2" 6,686 TON 2303-0062500 HMA (30M ESAL) INTERMEDIATE, 1/2" 10,820 TON 2303-0063502 HMA (30M ESAL) SURF, 1/2", FRIC L-2 8,179 TON 2303-7000510 HMA MIX INCORPORATED W/ ANTI-STRIP AGENT 18,741 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 153 Proposal ID: 73-C073-116 Proposed Contract Period: Late Start Date of 09/03/13 with 40 WORK DAYS Project(s): Project No: FM-C073(116)--55-73 County: PAGE Type of Work: HMA PAVEMENT (MISCELLANEOUS) Route: VARIOUS Length: 9.93 miles Location: 2 & 34 MAINTENANCE OVERLAY OF PREVIOUSLY SEAL COATED ROADS J32, M41, T AVE _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 154 Proposal ID: 80-C080-056 Proposed Contract Period: Late Start Date of 07/08/13 with 35 WORK DAYS Project(s): Project No: FM-C080(56)--55-80 County: RINGGOLD Type of Work: HMA RESURFACING WITH MILLING Route: P33 Length: 6.66 miles Location: STATE HIGHWAY 2 TO SCL OF DIAGONAL _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2303-0032750 HMA (1M ESAL) INTERMEDIATE, 3/4" 10,891 TON

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 155 Proposal ID: 82-0671-134 Proposed Contract Period: Late Start Date of 09/16/13 with 20 WORK DAYS Project(s): Project No: HSIPX-067-1(134)--3L-82 County: SCOTT Type of Work: HMA PAVED SHOULDER - NEW Route: U.S. 67 Length: 3.83 miles Location: FROM LE CLAIRE TO PRINCETON _____ Item No. Item Description Quantity/Unit SECTION NO. 0001 ROADWAY ITEMS 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 39 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 156 Proposal ID: 84-0101-077 Proposed Contract Period: Late Start Date of 05/20/13 with 100 WORK DAYS Project(s): Project No: STPN-003-1(87)--2J-75 County: PLYMOUTH Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING Route: IOWA 3 Length: 12.74 miles Location: FROM SOUTH DAKOTA STATE LINE E. TO S. JCT. IA.12 & FROM N. JCT. IA. 12 E. TO S. JCT. CO. RD. K-22 Project No: HSIPX-010-1(77)--3L-84 County: SIOUX Type of Work: HMA PAVED SHOULDER - NEW Route: IOWA 10 Length: 2.35 miles Location: FROM SOUTH DAKOTA STATE LINE S. TO HAWARDEN _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS STPN-003-1(87)--2J-75 2102-2625000 EMBANKMENT-IN-PLACE 245 CY 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 17,406 TON 2303-0043503 HMA (3M ESAL) SURF, 1/2", FRIC L-3 15,756 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 213 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 12 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 157 Proposal ID: 84-0181-072 Proposed Contract Period: Late Start Date of 07/08/13 with 60 WORK DAYS Project(s): Project No: NHSX-018-1(72)--3H-84 County: SIOUX Type of Work: PCC PAVEMENT WIDENING / HMA RESURFACING Route: U.S. 18 Length: 0.52 miles Location: FROM 0.3 MILE E. OF CO. RD. K-24 E. TO 0.6 MILE W. OF CO. RD. K-30 IN ROCK VALLEY _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 2303-0043503 HMA (3M ESAL) SURF, 1/2", FRIC L-3 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 30,529 CY 1,476 TON 1,466 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 158 Proposal ID: 93-0651-029 Proposed Contract Period: Late Start Date of 04/15/13 with 120 WORK DAYS Project(s): Project No: NHSX-065-1(29)--3H-93 County: WAYNE Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING Route: U.S. 65 Length: 12.89 miles Location: FROM MISSOURI STATE LINE N. TO IA. 2 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 1,961 CY 19,235 TON 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 21,205 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 231 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 13 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 159 Proposal ID: 94-C094-099 Proposed Contract Period: Late Start Date of 07/29/13 with 35 WORK DAYS Project(s): Project No: FM-C094(99)--55-94 County: WEBSTER Type of Work: HMA RESURFACING Route: P59 Length: 3.50 miles Location: HWY 20 TO D20 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC 10,729 TON 10,729 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 160 Proposal ID: 99-C099-071 Proposed Contract Period: Late Start Date of 07/22/13 with 50 WORK DAYS Project(s): Project No: STP-S-C099(71)--5E-99 County: WRIGHT Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: VARIOUS ROUTES Length: 14.88 miles Location: HWY 69 TO FRANKLIN COUNTY LINE AND FROM S. CL OF BELMOND TO CO.RD. C25 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2303-0001000 HMA WEDGE/LEVEL/STRENGTH 723 TON 2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 13,819 TON 13,819 TON

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 201 Proposal ID: 03-0762-707 Proposed Contract Period: Late Start Date of 08/05/13 with 35 WORK DAYS Project(s): Project No: MP-052-2(702)123--76-03 County: ALLAMAKEE Type of Work: SLURRY SEAL Route: U.S. 52 Length: 16.76 miles Location: FROM WEST OF POSTVILLE, NORTH TO THE JCT. OF IOWA 24/IOWA 150 IN CALMAR. Project No: MP-076-2(707)9--76-03 County: ALLAMAKEE Type of Work: SLURRY SEAL Route: IOWA 76 Length: 18.15 miles Location: FROM N. OF THE YELLOW RIVER NEAR EFFIGY MOUNDS NW TO DUNDEE ROAD. Project No: MP-018-2(705)264--76-33 County: FAYETTE Type of Work: SLURRY SEAL Route: U.S. 18 Length: 16.64 miles Location: FROM IOWA 150 IN WEST UNION, EAST TO U.S. 52 WEST OF POSTVILLE. _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS ALLAMAKEE COUNTY MP-52-2(702)123--76-03 2303-0033504 HMA (1M ESAL) SURF, 1/2", FRIC L-4 453 TON SECTION NO. 0003 ROADWAY ITEMS FAYETTE COUNTY MP-18-2(705)264--76-33 490 TON 2303-0033504 HMA (1M ESAL) SURF, 1/2", FRIC L-4

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 202 Proposal ID: 52-0806-290 Proposed Contract Period: Late Start Date of 09/16/13 with 20 WORK DAYS Project(s): Project No: IMN-080-6(302)205--0E-48 County: IOWA Type of Work: PCC PATCHING Route: I-80 Length: 33.70 miles Location: FROM THE POWESHIEK CO. LINE, EAST TO WEST OF I-380. Project No: IMN-080-6(290)240--0E-52 County: JOHNSON Type of Work: PCC PATCHING Route: I-80 Length: 15.08 miles Location: FROM W. OF I-380 E. TO CEDAR CO. LINE _____ Item Description Item No. Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS IOWA COUNTY IMN-80-6(302)205--0E-48 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 485 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 46 EACH SECTION NO. 0002 ROADWAY ITEMS JOHNSON COUNTY IMN-080-6(290)240--0E-52 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 544 SY 2529-5070111 PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT) 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 110 SY 47 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 203 Proposal ID: 57-0136-717 Proposed Contract Period: Late Start Date of 07/22/13 with 40 WORK DAYS Project(s): Project No: MP-052-6(713)50--76-31 County: DUBUQUE Type of Work: HMA JOINT & CRACK SEALING Route: U.S. 52 Length: 22.50 miles Location: FROM SAGEVILLE WEST TO IOWA 136 IN LUXEMBURG. (VARIOUS LOCATIONS) Project No: MP-001-6(711)89--76-52 County: JOHNSON Type of Work: HMA JOINT & CRACK SEALING Route: IOWA 1 Length: 9.29 miles Location: FROM I-80, NORTHEAST TO SOLON. Project No: MP-013-6(717)12--76-57 County: LINN Type of Work: HMA JOINT & CRACK SEALING Route: IOWA 13 Length: 8.09 miles Location: FROM 0.7 MILE NORTH OF COUNTY HOME ROAD TO 0.5 MILE NORTH OF CENTRAL CITY Project No: MP-067-6(717)15--76-82 County: SCOTT Type of Work: HMA JOINT & CRACK SEALING Route: U.S. 67 Length: 0.45 miles Location: IN THE CITY OF LECLAIRE FROM EWING ST. TO MAY ST. _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 204 Proposal ID: 58-0615-706 Proposed Contract Period: Late Start Date of 10/07/13 with 15 WORK DAYS Project(s): Project No: MP-061-5(706)68--76-58 County: LOUISA Type of Work: HMA PATCHING Route: U.S. 61 Length: 4.00 miles Location: FROM THE NCL OF WAPELLO TO 2 MILES SOUTH OF THE IOWA 92 JCT. AT GRANDVIEW _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 326 SY 23 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 205 Proposal ID: 58-0705-701 Proposed Contract Period: Late Start Date of 09/09/13 with 10 WORK DAYS Project(s): Project No: MP-070-5(701)2--76-58 County: LOUISA Type of Work: MICROSURFACING Route: IOWA 70 Length: 14.82 miles Location: FROM THE JCT. OF IOWA 92 IN COLUMBUS JUNCTION, NORTH TO THE JCT. OF IOWA 22 IN NICHOLS. _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 206 Proposal ID: 68-1375-701 Proposed Contract Period: Late Start Date of 08/26/13 with 15 WORK DAYS Project(s): Project No: MP-137-5(701)0--76-68 County: MONROE Type of Work: MICROSURFACING Route: IOWA 137 Length: 13.12 miles Location: FROM IOWA 5 IN ALBIA NORTH & EAST TO THE WAPELLO COUNTY LINE NEAR EDDYVILLE. _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 207 Proposal ID: 75-0753-713 Proposed Contract Period: Late Start Date of 08/12/13 with 25 WORK DAYS Project(s): Project No: MP-075-3(713)101--76-75 County: PLYMOUTH Type of Work: MICROSURFACING Route: U.S. 75 Length: 4.23 miles Location: FROM 0.2 MILE NORTH OF C80, NORTH TO THE SCL OF HINTON. (NB LANES.) _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 208 Proposal ID: 81-0713-710 Proposed Contract Period: Late Start Date of 09/09/13 with 10 WORK DAYS Project(s): Project No: MP-071-3(710)142--76-81 County: SAC Type of Work: MICROSURFACING Route: U.S. 71 Length: 3.50 miles Location: FROM THE SOUTH JCT OF IOWA, 175 NORTH TO THE SOUTH APPROACH OF THE BOYER RIVER BRIDGE. _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 209 Proposal ID: 90-0165-702 Proposed Contract Period: Late Start Date of 04/01/13 with 50 WORK DAYS Project(s): Project No: MP-001-5(702)0--76-89 County: VAN BUREN Type of Work: HMA CRACK FILLING Route: IOWA 1 Length: 14.44 miles Location: FROM THE JCT. OF IOWA 2, NORTH TO NEAR BIRMINGHAM. Project No: MP-016-5(702)0--76-90 County: WAPELLO Type of Work: HMA CRACK FILLING Route: IOWA 16 Length: 22.58 miles Location: FROM U.S. 34 TO SELMA AND FROM THE S. JCT. OF IOWA 1 TO NEAR HILLSBORO. _____ Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 210 Proposal ID: 92-0225-704 Proposed Contract Period: Late Start Date of 10/07/13 with 15 WORK DAYS Project(s): Project No: MP-022-5(704)29--76-92 County: WASHINGTON Type of Work: HMA PATCHING Length: 6.32 miles Route: IOWA 22 Location: FROM WELLMAN TO KALONA. _____ Item No. Quantity/Unit Item Description _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 301 Proposal ID: 56-0029-026 Proposed Contract Period: Late Start Date of 09/23/13 with 25 WORK DAYS Project(s): Project No: STPN-002-9(26)--2J-56 County: LEE Type of Work: SLIDE REPAIR Route: IOWA 2 Length: 0.00 miles Location: 2 MILES E. OF FARMINGTON _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 5,334 CY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 302 Proposal ID: 77-2352-636 Proposed Contract Period: Late Start Date of 09/16/13 with 25 WORK DAYS Site 01: TO CONSTRUCT WB 31ST STREET ENTRANCE RAMP. No Start Date Specified with 5 WORK DAYS Site 02: TO CONSTRUCT WB NORTH SIDE CD SYSTEM, E. 6TH TO E. 14TH. No Start Date Specified with 15 WORK DAYS Project(s): Project No: IMN-235-2(636)8--0E-77 County: POLK Type of Work: STORM SEWER/INTAKES Route: I-235 Length: 0.00 miles Location: IN THE CITY OF DES MOINES FROM 44TH ST. PEDESTRIAN BRIDGE E. TO E. 14TH ST. _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 351 Proposal ID: 34-C034-087 Proposed Contract Period: Late Start Date of 07/15/13 with 50 WORK DAYS Project(s): Project No: FM-C034(87)--55-34 County: FLOYD Type of Work: PAVEMENT MARKINGS Route: VARIOUS ROUTES Length: 0.00 miles Location: PAVEMENT MARKINGS, VARIOUS ROADS _____ Item No. Quantity/Unit Item Description _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 352 Proposal ID: 36-0291-108 Proposed Contract Period: Late Start Date of 08/19/13 with 50 WORK DAYS Project(s): Project No: IMN-029-1(108)0--0E-36 County: FREMONT Type of Work: TRAFFIC SIGNS Route: I-29 Length: 0.00 miles Location: MISSOURI STATE LINE N. TO HARRISON CO. LINE (SIDE ROAD. INTERCHANGES) _____ Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 401 Proposal ID: 31-0522-128 Proposed Contract Period: Approx Start Date of 03/18/13 with 20 WORK DAYS Project(s): Project No: NHSN-052-2(128)--2R-31 County: DUBUQUE Type of Work: SALVAGE AND REMOVAL Route: U.S. 52 Length: 0.00 miles Location: 15518 RT. 52 NORTH PARCEL NO. 1 _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 402 Proposal ID: 78-0801-426 Proposed Contract Period: Approx Start Date of 03/18/13 with 20 WORK DAYS Project(s): Project No: IMN-080-1(426)3--0E-78 County: POTTAWATTAMIE Type of Work: SALVAGE AND REMOVAL Route: I-80 Length: 0.00 miles Location: IN THE CITY OF COUNCIL BLUFFS AT 2818 S. 8TH ST. PARCEL NO. 319B & 205 E. 29TH AVE. PARCEL NO. 350 _____ Item No. Item Description Quantity/Unit

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 501 Proposal ID: 09-0637-046 Proposed Contract Period: Late Start Date of 03/04/13 with 80 WORK DAYS Project(s): Project No: NHSN-063-7(46)--2R-09 County: BREMER Type of Work: EROSION CONTROL Route: U.S. 63 Length: 2.89 miles Location: FROM IA. 3 N. TO CO. RD. C-38(SBL) Project No: NHSN-218-8(119)--2R-09 County: BREMER Type of Work: EROSION CONTROL Route: U.S. 218 Length: Location: AT CO. RD. C-50 IN JANESVILLE Length: 1.57 miles _____ Item Description Item No. Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS NHSN-063-7(46)--2R-09 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 200 CY SECTION NO. 0002 ROADWAY ITEMS NHSN-218-8(119)--2R-09 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 50 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 502 Proposal ID: 82-0741-203 Proposed Contract Period: Late Start Date of 04/01/13 with 30 WORK DAYS Project(s): Project No: IMN-074-1(203)1--0E-82 County: SCOTT Type of Work: EROSION CONTROL Route: I-74 Length: 0.00 miles Location: IN THE CITY OF DAVENPORT AT THE 53RD ST. INTERCHANGE _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 50 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 503 Proposal ID: 84-0181-076 Proposed Contract Period: Late Start Date of 07/22/13 with 20 WORK DAYS Project(s): Project No: NHSN-018-1(76)--2R-84 County: SIOUX Type of Work: WETLAND MITIGATION Route: U.S. 18 Length: 0.00 miles Location: ABMA II WETLAND MITIGATION SITE 1 MILE NE OF ROCK VALLEY _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 504 Proposal ID: 97-0298-033 Proposed Contract Period: Late Start Date of 03/04/13 with 70 WORK DAYS Project(s): Project No: IMN-029-8(33)150--0E-97 County: WOODBURY Type of Work: EROSION CONTROL Route: I-29 Length: 2.40 miles Location: IN THE CITY OF SIOUX CITY FROM 1.5 MILES S. OF RIVERSIDE BLVD. INTERCHANGE N. TO BIG SIOUX RIVER _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 50 CY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 601 Proposal ID: 31-0618-101 Proposed Contract Period: Approx Start Date of 04/01/13 with 100 WORK DAYS Proposal Note: *** DEFINITION OF MAINTENANCE BRIDGE NUMBERS *** THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED $\{ \ \}$ PORTIONS OF THE NUMBER ARE DEFINED BELOW.) . {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) $5210.90{380}$ 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: . 3120.1S020 3190.2S061 3191.8S061 Project(s): Project No: BRFN-020-9(190)--39-31 County: DUBUQUE Type of Work: BRIDGE CLEANING Route: U.S. 20 Length: 0.00 miles Location: IN THE CITY OF DUBUQUE OVER THE MISSISSIPPI RIVER JULEN DUBUQUE BRIDGE Project No: MB-061-6(522)190--77-31 County: DUBUQUE Type of Work: BRIDGE CLEANING Route: U.S. 61 Length: 0.00 miles Location: IN THE CITY OF DUBUQUE OVER PEOSTA CHANNEL (PEOSTA CHANNEL BRIDGE) Project No: BRFN-061-8(101)--39-31 County: DUBUQUE Type of Work: BRIDGE PAINTING Route: U.S. 61 Length: 0.00 miles Location: IN THE CITY OF DUBUQUE OVER THE MISSISSIPPI RIVER (CITY ISLAND BRIDGE) Project No: BRFN-061-8(122)--39-31 County: DUBUQUE Type of Work: BRIDGE CLEANING Route: U.S. 61 Length: 0.00 miles Location: IN THE CITY OF DUBUOUE OVER THE MISSISSIPPI RIVER (CITY ISLAND BRIDGE)

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Item No.	Item Description	Quantity/Unit

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 602 Proposal ID: 50-0061-500 Proposed Contract Period: Late Start Date of 07/08/13 with 25 WORK DAYS Proposal Note: *** DEFINITION OF MAINTENANCE BRIDGE NUMBERS *** THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED $\{ \ \}$ PORTIONS OF THE NUMBER ARE DEFINED BELOW.) . {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: . 5077.7S006 Project(s): Project No: MB-006-1(500)178--77-50 County: JASPER Type of Work: BRIDGE PAINTING Route: U.S. 6 Length: 0.00 miles Location: OVER NORTH SKUNK RIVER 1.3 MILES EAST OF IOWA 224. _____ Item No. Item Description Quantity/Unit _____

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 603 Proposal ID: 77-2351-509 Proposed Contract Period: Late Start Date of 05/06/13 with 60 WORK DAYS Proposal Note: *** DEFINITION OF MAINTENANCE BRIDGE NUMBERS *** THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED $\{ \ \}$ PORTIONS OF THE NUMBER ARE DEFINED BELOW.) . $\{52\}10.90380$ County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: . 7705.30235 7705.70235 7705.40235 7705.5P235 . 7706.50235 7705.9P235 Project(s): Project No: MBIN-235-1(509)7--0M-77 County: POLK Type of Work: BRIDGE PAINTING Route: I-235 Length: 0.00 miles Location: IN THE CITY OF DES MOINES AT 31ST ST., 42ND ST., POLK BLVD., 40TH ST. PEDESTRIAN BRIDGE & 44TH ST. PEDESTRIAN BRIDGE Item Description Item No. Quantity/Unit _____

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: January 16, 2013 10:00 A.M. Proposed Bid Order: 604 Proposal ID: 82-0741-175 Proposed Contract Period: Approx Start Date of 05/06/13 with 30 WORK DAYS Proposal Note: *** DEFINITION OF MAINTENANCE BRIDGE NUMBERS *** THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED $\{ \ \}$ PORTIONS OF THE NUMBER ARE DEFINED BELOW.) . $\{52\}10.90380$ County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: . 8205.0L074 8205.0R074 8204.3A074 8204.2A074 . 8204.4A074 Project(s): Project No: IMN-074-1(175)5--0E-82 County: SCOTT Type of Work: BRIDGE CLEANING Route: I-74 Length: 0.00 miles Location: IN THE CITY OF BETTENDORF OVER THE MISSISSIPPI RIVER (NBL & SBL) _____ Item Description Item No. Quantity/Unit _____