

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: January 16, 2013
Date of Addendum: January 8, 2013

| B.O. | Proposal ID | Proposal Work Type | County | Project Number | Addendum |
|------|-------------|--------------------|--------|--|--------------|
| 106 | 77-0352-364 | PCC PAVEMENT - NEW | POLK | IM-035-2(329)67--13-77 BRFIM-035-2(351)72--05-77 IM-035-2(364)67--13-77 IM-035-2(367)67--13-77 BRFIM-035-2(369)69--05-77 BRFIM-035-2(371)69-05-77 IM-035-2(384)69--13-77 IM-035-2(411)69--13-77 | 16JAN106.A04 |

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the Standard Specifications for Highway and Bridge Construction, Series 2012:

*****REVISIONS TO THE STANDARD SPECIFICATION*****

- .>>> Delete Article 1102.17, E, 3, b, 3) Bidders with History of Utilizing DBE's.
- .>>> Replace the first sentence of Article 1102.17, E, 3, b, 4), b) with the following:
 - . Within 2 business days after the deadline for bid submittal, the Department will use the two
 - . Good Faith Effort methods to determine which bidders have made a Good Faith Effort to
 - . meet the DBE goal on each proposal for which bids were received.

The intent of this addendum is that Annual Good Faith Effort Points will not be used to determine contract award.

Make the following change to Plan Sheet C.2 on Project Number IM-035-2(364)67--13-77:

Add the following note to the reference notes for the item 2528-8400157, TEMPORARY FLOODLIGHT LUMINAIRE:

Temporary floodlighting is to be used at both ends of the project to illuminate the shift in to/out of the median. This will be used in all stages and will be removed upon completion of the work.

The other areas of floodlighting are at ramps (at Mills Civic Parkway and the SB on ramp to 35 from I-80). These will be used in stages 2 and 3.

Make the following change to the Plan Sheet C.9 on Project Number IM-035-2(364)67--13-77:

Replace Tab. 108-27 TEMPORARY FLOODLIGHT LUMINAIRES with the attached Tab 108-27 TEMPORARY FLOODLIGHT LUMINAIRES.

Make the following change to the Plan Sheet P.2 on Project Number IM-035-2(411)69--13-77:

Delete the following sentence from the METER PEDESTAL SPECIFICATION:

“LOAD CENTER PORTION SHALL CONSIST OF A 120/240 VAC, SINGLE-PHASE, 3-WIRE, 100A, 2-POLE MAIN CIRCUIT BREAKER WITH 100A MAIN BUS AND SHORT CIRCUIT CURRENT WITHSTAND RATING OF 10,000A RMS SYMETRICAL.”

Replace the above sentence with the following:

“LOAD CENTER PORTION SHALL CONSIST OF A 120/240 VAC, SINGLE-PHASE, 3-WIRE, 100A MAIN LUGS, AND 100A LOAD CENTER DISTRIBUTION BUS WITH SIX BRANCH CIRCUIT SPACES. THE ASSEMBLY SHALL HAVE A SHORT CIRCUIT CURRENT WITHSTAND RATING OF 10,000A RMS SYMETRICAL.”

This addendum also corrects a technical problem in Expedite.

Electronic grading files for Project No. IM-035-2(364)67--13-77 are available and located at the following link:

<http://www.iowadot.gov/contracts/biddocuments/january2013.html>

Then go to page 3 for B.O. 106

TEMPORARY FLOODLIGHTING LUMINAIRES

This Data Entry Sheet fills Tab 108-27 effective 10-16-12

| No. | Location Station | Offset | Number Lumin. | Remarks |
|-----|------------------|--------|---------------|---------|
| | 1355+00.00 | 85 | 1 | |
| | 1435+00.00 | 85 | 1 | |
| | 1441+00.00 | 90 | 1 | |
| | 1469+50.00 | 110 | 1 | |
| | 1478+00.00 | 85 | 1 | |
| | 1545+00.00 | 85 | 1 | |
| | 1555+00.00 | 85 | 1 | |
| | | | | |
| | | | | |
| | | Total: | 7 | |