

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: January 16, 2013
Date of Addendum: January 11, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
109	97-0296-222-A	PCC PAVEMENT - GRADE AND NEW	WOODBURY	MB-020-3(502)1-77-97 IM-NHS-029-6(176)142--03-97 IM-NHS-029-6(222)143--03-97 IM-NHS-029-6(231)142--03-97	16JAN109.A05

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Delete Proposal Line No. 1410 2512-1950000 CURB, DOWELLED P.C. CONCRETE, AS PER PLAN, LF, 1,394.000

Add Proposal Line No. 2091 2512-1725256 CURB AND GUTTER, P.C. CONCRETE, 2.5 FT., LF, 1,394.000

If the above changes are not made, they will be made as shown here.

Make the following change to Plan Sheet B.18 on Project No. IM-NHS-029-6(222)143--03-97:

Change the following notes in Typical 7156:

From: 6" HMA Paved Shoulder at guardrail. 7" PCC may be substituted with the following jointing layout:

To: 11" PCC Paved Shoulder at guardrail.

Delete: Compaction of HMA is required to face of guardrail post. Hand compaction will be allowed under guardrail. Removal & reinstallation of guardrail will be allowed with no additional payment.

Delete: Refer to Shoulder tabulation (112-9) for quantities.

Make the following change to Plan Sheet C.6 on Project No. IM-NHS-029-6(222)143--03-97:

Add the following note to the reference notes for the item 2512-1725256 CURB AND GUTTER, P.C. CONCRETE, 2.5 FT.:

Refer to Typical 6135 in the B Sheets.

Includes 1394 LF from Sta. 5001+30 to 5004+29 and Sta. 5018+43 to 5022+41.