

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: March 19, 2013
Date of Addendum: March 6, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
011	65-5341-091	BRIDGE REPLACEMENT - PPCB	MILLS	NHSX-534-1(91)--3H-65	19MAR011.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the plan set:

Replace plan sheet J.1 with attached plan sheet J.1.

Note: Tabulation 102-15 and Tabulation 111-01 had changes.

188-261
08-01-08

STAGING NOTES

STAGE 1
<p>TRAFFIC: Maintain I-29 traffic on existing lanes except during bridge removal and beam setting operations, requiring lane closure, using TC-418, TC-420, or TC-454 Maintain U.S. 34 traffic 2 lane - 2 way on new EB lanes and bridge</p> <p>Construction: Remove existing bridge Construction new bridge</p>
STAGE 2
<p>Traffic Maintain I-29 traffic on existing lanes except during TBR removal operations, requiring lane closure, using TC-418 and TC-420 Maintain U.S. 34 Traffic 2 lane - 2 way on new EB lanes and bridge</p> <p>Construction Remove TBR</p>
STAGE 3
<p>Traffic Maintain I-29 traffic on existing lanes Maintain U.S. 34 traffic 2 lane - 2 way on new EB lanes and bridge</p> <p>Construction Project complete U.S. 34 NB bridge Safety Closures to remain in place</p>

102-11
08-01-08

TABULATION OF SPECIAL EVENTS

Event	Location	Date
College World Series	Omaha, Ne	6/19/13 to 6/28/13
2011 US Senior Open Golf Championship	Omaha, Ne	7/8/13 to 7/14/13
Missouri County Fair	Alvord, Mo	7/15/13 to 7/21/13
Kan County Fair	Glenn, Mo	8/24/13 to 8/25/13
Cass County Festival	Plattsburgh, Ne	9/5/13 to 9/8/13
AppleJack Festival	Nebraska City, Ne	9/28/13 to 9/22/13

111-01
04-17-12

COORDINATED OPERATIONS

Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with these of other contractors working within the same area.

Project	Type of Work
NHSX-534-1(81)--3H-65	Grade and Pave
NHSX-534-1(84)--3H-65	Bridge
NHSX-534-1(85)--3H-65	Grade and Pave
NHSX-534-1(92)--3H-65	Signaling
NHSX-534-1(93)--3H-65	Lighting
MB-034-4(082)8--77-65	Bridge Repair
MB-023-1(80)9--0E-30	PCC Patching

Design No. 1211
File No. 30336