

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: February 19, 2013
Date of Addendum: January 25, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
101	07-0636-088	PCC Pavement - Grade and New	Black Hawk	NHSX-063-6(88)--3H-07	19feb101.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the PROPOSAL SPECIAL PROVISIONS LIST AND TEXT:

Add the following:

660.26

*** SPECIALTY ITEM ***

The item 'TRAFFIC SIGNALIZATION' and/or 'TRAFFIC SIGNAL INSTALLATION' is considered a specialty item for this project.

When performed by subcontract, the cost of the specialty item/s so performed by subcontract may be deducted from the total cost before computing the amount of work required to be performed by the Prime Contractor with his/her own organization. Refer to Article 1108.01 of the Standard Specifications.

Make the following change to the SPECIAL PROVISIONS:

SP-122001 FOR BRICK PAVERS FEBRUARY 19, 2013

Section 2.05: Delete Paragraph 2.05.D.3.

SP-122003 FOR LIMESTONE FEBRUARY 19, 2013

Section 2.04D: Add the following section:

4. As an alternative to completing the Graffiti Control sealant in the field, the work described in Paragraphs 1-3 may be completed in the shop prior to shipping the limestone to the project site.

Make the following change to Plan:

SHEET NUMBER C.3:

Move Item Number 155 2599-9999005 PEDESTRAIN LIGHT FIXTURE, EACH, 61 from Division 2 column to Division 4 column.

SHEET NUMBER J.1:

TRAFFIC CONTROL PLAN Tab 108-23A

Add the following to 3. “..with the drop off exceeding the existing pavement thickness”

SHEET NUMBER U.1

GENERAL NOTES

6. Replace (1/2-INCH FOR SEEDING AREAS) with (ROCKS LARGER THAN 1-INCH TO BE REMOVED FOR SEEDING AREA)

SHEET NUMBER U.10

PLANT QUANTITIES LISTING Tab 100-20

No. 4 GIN GINKGO BILOBA 2.5” to 3”

SHEET U.12

TYPICAL TREE PLANTING

Delete “IF PERCOLATION TEST FINDS POOR DRAINING SOIL,” replace with “APPLY TO ALL TREES,”...