

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: April 16, 2013
Date of Addendum: April 4, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
109	78-0292-078	PCC PAVEMENT - GRADE & REPLACE	POTTAWATTAMIE	IMX-029-2(78)44--02-78	16APR109.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to plan sheet J.1:

Replace plan sheet J.1 with attached plan sheet J.1.

Note: Tabulation 102-15 was revised. Tabulation 111-01 was added.

102-15
08-04-06

TRAFFIC CONTROL PLAN

INTERSTATE 29 SHALL REMAIN OPEN TO TRAFFIC AT ALL TIMES. CONSTRUCTION STAGING REQUIRES THE USE OF THE TC-61 STANDARD ROAD PLAN TO SWITCH TRAFFIC TO TWO-LANE, TWO-WAY OPERATIONS TO ACCOMMODATE CLOSING THE SOUTHBOUND LANES DURING THEIR RECONSTRUCTION AND THE NORTHBOUND LANES DURING THEIR RECONSTRUCTION.

THE CONTRACTOR SHALL UTILIZE STANDARD ROAD PLAN TC-402 DURING CONSTRUCTION OF THE MEDIAN CROSSOVER AT STA. 210+84.

108-26A
08-01-06

STAGING NOTES

STAGE 1A
CONSTRUCT MEDIAN CROSSOVER AT STA. 210+84
PREPARE EXISTING MEDIAN CROSSOVER AT STA 69+25 FOR TRAFFIC.
REMOVE AND INSTALL PAVEMENT MARKING FOR STAGE 1B RECONSTRUCTION.
INSTALL TC-420 AT THE SB ENTRANCE RAMP FROM HWY 92.

STAGE 1B
SWITCH TRAFFIC TO TWO-LANE, TWO-WAY OPERATION IN THE NORTHBOUND LANES.
RECONSTRUCT SOUTHBOUND LANES.
REMOVE 3' OF MEDIAN CROSSOVER PAVEMENT ADJACENT TO THE SOUTHBOUND LANES AT STA. 69+25 TO ACCOMMODATE SLIPFORM PAVING.
REMOVE 3' OF MEDIAN CROSSOVER PAVEMENT ADJACENT TO THE SOUTHBOUND LANES AT STA. 69+25 TO ACCOMMODATE SLIPFORM PAVING.
PERFORM BRIDGE WORK ON PIPE UNDER THE NORTHBOUND JONY CREEK BRIDGE, STA. 78+61.
EXTEND MEDIAN PIPES UNDER SOUTHBOUND LANES AND PIPE AT STA. 107+86.
INSTALL ALL SOUTHBOUND GUARDRAIL AND THE HIGH TENSION CABLE GUARDRAIL AT STA.109+92 LT.
COMPLETE EROSION CONTROL AND STABILIZING SEEDING ADJACENT TO THE SOUTHBOUND LANES.

STAGE 2A
REMOVE AND INSTALL PAVEMENT MARKING FOR STAGE 2 RECONSTRUCTION.
INSTALL TC-61, SHIFTING TRAFFIC TO THE NEWLY CONSTRUCTED SOUTHBOUND LANES.

STAGE 2B
SWITCH TRAFFIC TO TWO-LANE, TWO-WAY OPERATION IN THE SOUTHBOUND LANES.
RECONSTRUCT NORTHBOUND LANES.
REMOVE 3' OF MEDIAN CROSSOVER PAVEMENT ADJACENT TO THE NORTHBOUND LANES AT STA. 69+25 TO ACCOMMODATE SLIPFORM PAVING.
PERFORM BRIDGE WORK ON PIPE UNDER THE NORTHBOUND JONY CREEK BRIDGE, STA. 78+61.
INSTALL NORTHBOUND GUARDRAIL AND THE REMAINING HIGH TENSION CABLE GUARDRAIL.
COMPLETE EROSION CONTROL AND STABILIZING SEEDING ADJACENT TO THE NORTHBOUND LANES.

102-15
08-04-06

TABULATION OF SPECIAL EVENTS

Event	Location	Date
COLLEGE WORLD SERIES	OWAHA, NEBRASKA	JUNE 14-28, 2013
FIREWORKS DISPLAY	OWAHA, NEBRASKA	JULY 4, 2013
WRESTLING CON	OWAHA, NEBRASKA	JULY 4, 2013
2013 US SENIOR OPEN GOLF CHAMPIONSHIP	OWAHA, NEBRASKA	JULY 8 - 14, 2013
RED, WHITE AND QUE	BELLEVUE, NEBRASKA	JULY 19 - 24, 2013
WESTFAIR	COUNCIL BLUFFS, IOWA	JULY 24-29, 2013
SIDNEY RODEO	SIDNEY, IOWA	JULY 30 - AUGUST 3, 2013
KEG CREEK DAYS	GLENWOOD, IOWA	AUGUST, 2013
ARROWS TO AEROSPACE	BELLEVUE, NEBRASKA	AUGUST 15 - 17, 2013
ARMED AND DANGEROUS	OWAHA, NEBRASKA	AUGUST 15 - 17, 2013
SEPTEMBERFEEST	OWAHA, NEBRASKA	AUG 30-31, SEPT 1-2, 2013
APPLE/JACK FESTIVAL	NEBRASKA CITY, NEBRASKA	SEPTEMBER 20 - 22, 2013
RIVERCITY ROUNDUP	OWAHA, NEBRASKA	SEPTEMBER 26-29, 2013
HOMECOMING REUNION	GLENWOOD, IOWA	OCTOBER, 2013
MID-AMERICA MOTORPLEX	PACIFIC JUNCTION, IOWA	WEEKENDS

111-01
04-17-12

COORDINATED OPERATIONS

Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.

Project	Type of Work
	MULTIPLE ON-GOING PROJECTS AND LANE RESTRICTIONS WITHIN THE CB CORRIDOR