

A d d e n d u m

Iowa Department of Transportation

Date of Letting: April 16, 2013

Office of Contracts

Date of Addendum: April 9, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
985	67-0373-709	Clearing and Grubbing	Monona	MP-037-3(709)10--76-67	16apr985.a01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the PLAN, Sheet Number C.1:

Add ESTIMATE REFERENCE INFORMATION, ITEM 1 CLEARING & GRUBBING:

See STANDARD PLAN NOTE 232-3A.

Add the STANDARD PLAN NOTE 232-3A

EROSION CONTROL (RURAL Seeding) dated 10-16-12.

Following the completion of work in a disturbed area, place seed, fertilizer, and mulch on the disturbed area lying 10 feet adjacent to shoulder as follows:

SEEDING:

3 lbs. of Tall Fescue (Fawn) per 1000 sq. ft.

FERTILIZER:

17 lbs. of 13-13-13 (or equivalent) commercial fertilizer per 1000 sq. ft.

MULCH:

70 lbs. of dry cereal straw per 1000 sq. ft. For areas disturbed, but not seeded by September 30th, scarify to a 3 inch depth and mulch. Consolidate all mulch into the soil with a mulch stabilizer.

Use Certified Noxious Weed Seed Free Mulch as determined by the Iowa Crop Improvement Association or adjacent state's Crop Improvement Association.

Preparing the seedbed and furnishing and applying seed, fertilizer, and mulch is incidental to mobilization and will not be paid for separately.