

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: April 16, 2013
Date of Addendum: April 12, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
106	57-0307-159	PCC PAVEMENT - GRADE & REPLACE	LINN	STP-A-030-7(159)--86-57	19APR106.A02

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Delete Proposal Line No. 0620 2524-9276010 PERFORATED SQUARE STEEL TUBE POST;
570.000 LF

Delete Proposal Line No. 0670 2527-9263180 PAVEMENT MARKINGS REMOVED; 444.300
STA

Change Proposal Line No. 0680:

From: 2527-9263600 REMOVABLE, NONREFLECTIVE, PREFORMED TAPE

To: 2527-9263131 WET RETROREFLECTIVE REMOVABLE TAPE MARKINGS

Change Proposal Line No. 0700 2528-8445113 FLAGGERS:

From: 270.000 EACH

To: 50.000 EACH

Change Proposal Line No. 0710 2528-8445115 PILOT CARS:

From: 135.000 EACH

To: 20.000 EACH

If the above changes are not made, they will be made as shown here.

The following applies to this Project:

For pavement removal areas on Highway 30 and Highway 1 the existing pavement consists of approximately 10 inches of PCC overlaid with approximately 8" of Asphalt. Other areas are 5" to 7" PCC.