

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: May 21, 2013
Date of Addendum: May 14, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
107	27-0351-147	PCC PAVEMENT - GRADE & REPLACE	DECATUR	IMX-035-1(147)12--02-27 IMX-035-1(150)12--02-27	21MAY107.A02

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the Plan Sheet C.5 for Project No. IMX-035-1(147)12--02-27:

Add the following note to Tab. 102-5 EXISTING PAVEMENT:

The original 8" shoulders were the chip and seal when the mainline paving was PCC surface, but since then it has all been overlaid as HMA. Some of it has been milled and relayed but a lot of it is still the original overlay. There are no PCC shoulders except small amounts at bridge ends placed for construction purposes.