

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: May 21, 2013
Date of Addendum: April 22, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
982	63-1633-055	CLEARING AND GRUBBING	MARION	NHSN-063-3(92)--2R-62 NHSN-163-3(55)--2R-63	21MAY982.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Add Proposal Line No. 0051 2125-2225050 RESHAPING DITCHES; 3.750 STA

Add Proposal Line No. 0052 2602-0000020 SILT FENCE; 50.000LF

Add Proposal Line No. 0053 2602-0010010 MOBILIZATIONS, EROSION CONTROL; 1.0 EACH

If the above changes are not made, they will be made as shown here.

Make the following changes to the plan:

Add the following Bid Item Reference Information to plan sheet C.1:

2125-2225050 RESHAPING DITCHES; 3.750 STA

This is located along US 63, southbound lanes, outside ditch, near Milepost 58, From Sta. 1304+25 to 1308+00. Positive ditch drainage is to be attained. Incidental items for this work is:

- the removal and disposal of excess class 13 excavation material, approx. 50 CY
- Seeding and mulching of the reshaped ditch per note 232-3A, approx. .06 Acre

2602-0000020 SILT FENCE; 50.000LF

The quantity includes estimated locations for placement of silt fence to address erosion to be encountered during construction. Verify the specific locations with the Engineer prior to beginning placement. Also refer to Standard Road Plan EC-201.

2602-0010010 MOBILIZATIONS, EROSION CONTROL; 1.0 EACH

As per current Standard Specifications and Road Plans

ADD the following Road Standard to Tabulation 105-4, on plan sheet C.1:
EC-201 Silt Fence 04-20-10