MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 001 Proposal ID: 03-0099-060 Proposed Contract Period: Late Start Date of 07/22/13 with 100 WORK DAYS Project(s): Project No: BRFN-009-9(60)--39-03 County: ALLAMAKEE Type of Work: STRUCTURES (MISCELLANEOUS) Route: IOWA 9 Length: 0.00 miles Location: NEW BRIDGE DOLPHIN AND BRIDGE DOLPHIN REHABILITATION FOR BLACKHAWK BRIDGE (IA 9) OVER THE MISSISSIPPI RIVER _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 DESIGN NO. 0412; A NEW BRIDGE DOLPHIN 345 CY 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 40,606 LB SECTION NO. 0002 DESIGN NO. 0512; A BRIDGE DOLPHIN REHABILITATION 2403-0100010 STRUCT CONC (BRIDGE) 159 CY 2404-7775000 REINFORC STEEL 24,088 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 002 Proposal ID: 04-C004-085 Proposed Contract Period: Late Start Date of 08/05/13 with 60 WORK DAYS Project(s): Project No: BROS-C004(85)--8J-04 County: APPANOOSE Type of Work: BRIDGE REPLACEMENT - PPCB Route: DEWEY ROAD Length: 0.09 miles Location: 260TH AVENUE W 0.4 MI OVER HICKORY CREEK _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEMS FOR A 105'-0 X 24'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 1,430 CY 159 CY 2404-7775000 REINFORC STEEL 38,479 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 003 Proposal ID: 07-C007-131 Proposed Contract Period: Late Start Date of 08/26/13 with 40 WORK DAYS Project(s): Project No: FM-C007(131)--55-07 County: BLACK HAWK Type of Work: BRIDGE DECK OVERLAY Route: FINCHFORD RD. Length: 0.10 miles Location: WINSLOW RD. N 0.25 MI _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEMS FOR REPAIRS TO A 175'-0 X 28' CONTINUOUS I-BEAM BRIDGE 2404-7775005 REINFORC STEEL, EPOXY COATED 2413-0698067 DECK OVERLAY (CL HPC-O PCC) 665 LB 550 SY 2413-0698074 DECK REPAIR, CL A 148 SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 004 Proposal ID: 07-2187-227 Proposed Contract Period: Approx Start Date of 09/16/13 with 120 WORK DAYS Proposal Note: *** APPROXIMATE START DATE *** THE US 218 BRIDGE IN LA PORTE CITY IS A PART OF THE EMERGENCY DETOUR ROUTE FOR THE I-380 RECONSTRUCTION PROJECT, IMX-380-7(117)64--02-07, AND THE IOWA DOT DOES NOT WANT ANY WORK BEING STARTED UNTIL AFTER THE COMPLETION OF I-380. Project(s): Project No: BRF-218-7(227)--38-07 County: BLACK HAWK Type of Work: BRIDGE AND APPROACHES - PPCB Route: U.S. 218 Length: 0.00 miles Location: IN THE CITY OF LA PORTE CITY OVER WOLF CREEK _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 DESIGN NO. 0111; A 279'-0 X 47'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 651 CY 2404-7775000 REINFORC STEEL 68,867 LB 161,065 LB 2404-7775005 REINFORC STEEL, EPOXY COATED SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 2301-1033120 STD/S-F PCC PAV'T, CL C CL 3, 12" 2,576 CY 217 CY 62 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 005 Proposal ID: 14-C014-145 Proposed Contract Period: Late Start Date of 07/29/13 with 60 WORK DAYS Project(s): Project No: BROS-C014(145)--8J-14 County: CARROLL Type of Work: BRIDGE REPLACEMENT - CCS Route: WILLOW AVENUE Length: 0.00 miles Location: OVER WILLOW CREEK NEAR THE CENTER OF SECTION 23-82-33 _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ITEMS FOR A 70' X 30' CONTINUOUS CONCRETE SLAB BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 157 CY 40,072 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 006 Proposal ID: 30-C030-046 Proposed Contract Period: Late Start Date of 07/22/13 with 65 WORK DAYS Project(s): Project No: BRS-C030(46)--60-30 County: DICKINSON Type of Work: BRIDGE REPLACEMENT - CCS Route: M27 Length: 0.00 miles Location: OVER STONEY CREEK _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEMS FOR A 110'-0 X 40'-6 CONTINUOUS CONCRETE SLAB BRIDGE 333 CY 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 84,677 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 1,385 CY 2301-1032080 STD/S-F PCC PAV'T, CL C CL 2, 8" 421 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 007 Proposal ID: 31-0522-125 Proposed Contract Period: Late Start Date of 10/21/13 with 10 WORK DAYS Project(s): Project No: BRFN-052-2(125)--39-31 County: DUBUQUE

Type of Work: PERMANENT SCOUR COUNTERMEASURES Route: U.S. 52 Length: 0.00 miles Location: OVER SIDE ROAD DITCH 0.2 MILE N. OF IA. 32

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 008 Proposal ID: 35-C035-072 Proposed Contract Period: Late Start Date of 08/19/13 with 45 WORK DAYS Project(s): Project No: BRS-C035(72)--60-35 County: FRANKLIN Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: S25 Location: 70TH STREET TO 80TH STREET

_____ Item No. Quantity/Unit Item Description _____ SECTION NO. 0001 ITEMS FOR A TWIN 10' X 8' X 60'-0 REINFORCED CONCRETE BOX CULVERT 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 390 CY 2303-0031500 HMA (1M ESAL) BASE, 1/2" 128 TON 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 35 TON 2403-0100020 STRUCT CONC (RCB CULV) 216 CY 2404-7775000 REINFORC STEEL 28,035 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 009 Proposal ID: 36-FEMA-14 Proposed Contract Period: Late Start Date of 07/29/13 with 65 WORK DAYS Project(s): Project No: L-FEMA-14--73-36 County: FREMONT Type of Work: BRIDGE REPLACEMENT - CCS Route: 235TH ST Length: 0.00 miles Location: OVER MULE SLOUGH _____ Item No. Quantity/Unit Item Description _____ SECTION NO. 0001 ITEMS FOR 100'-0 X 24'-0 CONTINUOUS CONCRETE SLAB BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 2,400 CY 186 CY 48,751 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 010 Proposal ID: 51-0012-028 Proposed Contract Period: Late Start Date of 09/23/13 with 15 WORK DAYS Project(s): Project No: BRFN-005-1(59)--39-04 County: APPANOOSE Type of Work: PERMANENT SCOUR COUNTERMEASURES Route: IOWA 5 Length: 0.00 miles Location: OVER D.D. 0.4 MILE N. OF CO. RD. T-30 Project No: BRFN-001-2(28)--39-51 County: JEFFERSON Type of Work: PERMANENT SCOUR COUNTERMEASURES Route: IOWA 1 Length: 0.00 miles Location: OVER SIDE RD. DITCH 2.9 MILES N. OF VAN BUREN CO. LINE _____ Item Description Item No. Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 011 Proposal ID: 52-0015-102 Proposed Contract Period: Late Start Date of 09/23/13 with 30 WORK DAYS Project(s): Project No: BRFN-001-5(102)--39-52 County: JOHNSON Type of Work: PERMANENT SCOUR COUNTERMEASURES Route: IOWA 1 Length: 0.00 miles Location: OVER OLD MANS CREEK 4.4 MILES S. OF US 218 Project No: MB-001-6(712)78--77-52 County: JOHNSON Type of Work: BRIDGE REPAIR Route: IOWA 1 Length: 0.00 miles Location: FROM 5.3 MILES W. OF US 218 TO 3.3 MILES W. OF US 218 (3 LOCATIONS) _____ Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 012 Proposal ID: 53-C053-072 Proposed Contract Period: Late Start Date of 07/22/13 with 35 WORK DAYS Project(s): Project No: BHOS-C053(72)--5N-53 County: JONES Type of Work: BRIDGE DECK OVERLAY Route: X28 Length: 0.06 miles Location: OVER WAPSIPINICON RIVER _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEMS FOR REPAIRS TO A 261.5' X 30' 4-SPAN PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 4 CY 2403-0100000 STRUCT CONC (MISCELLANEOUS) 2404-7775005 REINFORC STEEL, EPOXY COATED 871 LB 2413-0698067 DECK OVERLAY (CL HPC-O PCC) 932 SY 2413-0698074 DECK REPAIR, CL A 73 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 013 Proposal ID: 54-C054-091 Proposed Contract Period: Late Start Date of 07/22/13 with 75 WORK DAYS Project(s): Project No: BRS-C054(91)--60-54 County: KEOKUK Type of Work: BRIDGE REPLACEMENT - PPCB Route: 318TH AVE Length: 0.12 miles Location: OVER S FORK ENGLISH RIVER _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ITEMS FOR A 243'-0 X 24'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 356 CY 2403-0100010 STRUCT CONC (BRIDGE) 2404-7775000 REINFORC STEEL 78,505 LB SECTION NO. 0002 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 6,849 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 014 Proposal ID: 75-0752-088 Proposed Contract Period: Late Start Date of 09/23/13 with 30 WORK DAYS Project(s): Project No: BRFN-075-2(88)--39-75 County: PLYMOUTH Type of Work: PERMANENT SCOUR COUNTERMEASURES Route: U.S. 75 Length: 0.00 miles Location: FROM 1.3 MILES N. OF CO. RD. C-70 TO 0.6 MILE S. OF CO. RD. C-60(4 LOCATIONS) _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 015 Proposal ID: 75-0752-089 Proposed Contract Period: Late Start Date of 09/30/13 with 25 WORK DAYS Project(s): Project No: BRFN-075-2(89)--39-75 County: PLYMOUTH Type of Work: PERMANENT SCOUR COUNTERMEASURES Route: U.S. 75 Length: 0.00 miles Location: FROM 3.0 MILES N. OF CO. RD. C-60 TO 1.2 MILES S. OF CO. RD. C-44(4 LOCATIONS) _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 016 Proposal ID: 77-C077-193 Proposed Contract Period: Late Start Date of 07/29/13 with 70 WORK DAYS Project(s): Project No: BROS-C077(193)--8J-77 County: POLK Type of Work: BRIDGE REPLACEMENT - PPCB Route: SE 20 AVE. Length: 0.00 miles Location: OVER MUD CREEK, 0.3 MILES EAST OF SE 100TH ST. _____ Item Description Quantity/Unit Item No. _____ SECTION NO. 0001 ITEMS FOR A 151'-4 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 7,193 CY 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 231 TON 2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC 225 TON 2403-0100010 STRUCT CONC (BRIDGE) 238 CY 2404-7775000 REINFORC STEEL 3,734 LB 2404-7775005 REINFORC STEEL, EPOXY COATED 53,809 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 017 Proposal ID: 78-0801-428 Proposed Contract Period: Late Start Date of 09/23/13 with 20 WORK DAYS Project(s): Project No: IM-NHS-080-1(428)0--03-78 County: POTTAWATTAMIE Type of Work: RCB CULVERT EXTENSION - SINGLE BOX Route: I-80 Length: 0.00 miles Location: IN THE CITY OF COUNCIL BLUFFS AT THE W. 1-29/80 INTERCHANGE JUST E. OF THE MISSOURI RIVER BRIDGE _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 DESIGN NO. 1013; A 8'-0 X 6'-0 RCB CULVERT EXTENSION 2102-2625000 EMBANKMENT-IN-PLACE 800 CY 2403-0100020 STRUCT CONC (RCB CULV) 73 CY 2404-7775000 REINFORC STEEL 13,615 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 018 Proposal ID: 97-3761-009 Proposed Contract Period: Late Start Date of 10/14/13 with 15 WORK DAYS Project(s): Project No: BRFN-376-1(9)--39-97 County: WOODBURY Type of Work: PERMANENT SCOUR COUNTERMEASURES Route: IOWA 376 Length: 0.00 miles Location: IN THE CITY OF SIOUX CITY OVER FLOYD RIVER 1.1 MILES S. OF CO. RD. D-12 _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 101 Proposal ID: 00-000S-610

- - -

Proposed Contract Period: Late Start Date of 08/05/13 with 50 WORK DAYS

Project(s):
 Project No: NHSN-000-S(610)--2R-00
 County: STATEWIDE
 Type of Work: PCC SIDEWALK/TRAIL
 Route: VARIOUS Length: 0.00 miles
 Location: VARIOUS LOCATIONS IN DISTRICT 1(ADA COMPLIANCE)

Item No.Item DescriptionQuantity/UnitSECTION NO. 0001
SIDEWALK ITEMSSIDEWALK ITEMS2102-2710070EXCAVATION, CL 10, RDWY+BORROW40 CY2529-5070110PATCH, FULL-DEPTH FINISH, BY AREA56 SY2529-5070120PATCH, FULL-DEPTH FINISH, BY COUNT6 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 102 Proposal ID: 00-000S-611 Proposed Contract Period: Late Start Date of 07/22/13 with 75 WORK DAYS Project(s): Project No: NHSN-000-S(611)--2R-00 County: STATEWIDE Type of Work: PCC SIDEWALK/TRAIL Route: VARIOUS Length: 0.00 miles Location: VARIOUS LOCATIONS IN DISTRICT 2(ADA COMPLIANCE) _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 SIDEWALK ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 141 CY 425 SY 45 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposal ID: 07-2432-611 Proposed Bid Order: 103 Proposed Contract Period: Late Start Date of 09/16/13 with 25 WORK DAYS Project(s): Project No: SRTS-U-2432(611)--8U-07 County: BLACK HAWK Type of Work: PCC SIDEWALK/TRAIL Route: GRAND BLVD SIDEWALK Length: 0.33 miles Location: IN THE CITY OF EVANSDALE _____ Item No. Quantity/Unit Item Description _____ SECTION NO. 0001 SIDEWALK ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 402 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 104 Proposal ID: 21-7170-623 Proposed Contract Period: Late Start Date of 08/12/13 with 60 WORK DAYS Project(s): Project No: STP-E-7170(623)--8V-21 County: CLAY Type of Work: PCC SIDEWALK/TRAIL Route: PCC TRAIL Length: 1.29 miles Location: IN THE CITY OF SPENCER TRAIL & BRIDGE OVER OCHEYEDAN RIVER _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 PCC TRAIL ITEMS 650 CY 2102-2625000 EMBANKMENT-IN-PLACE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 256 CY 2403-0100010 STRUCT CONC (BRIDGE) 7 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 990 LB 2511-0302500 RECREATIONAL TRAIL, PCC, 5" 6,916 SY 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 79 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 105 Proposal ID: 25-0063-069 Proposed Contract Period: Late Start Date of 09/23/13 with 20 WORK DAYS Project(s): Project No: TSF-006-3(69)--92-25 County: DALLAS Type of Work: PCC PAVEMENT - GRADE AND NEW Route: U.S. 6 Length: 0.00 miles Location: LEFT TURN LANE IMPROVEMENTS ON US 6 AT WARRIOR LANE/ ALICE'S RD./156TH ST./142ND ST./128TH ST. _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033105 STD/S-F PCC PAV'T, CL C CL 3, 10.5" 1,199 CY 3,679 SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 106 Proposal ID: 65-5341-085 Proposed Contract Period: Specified Start Date of 04/07/14 with 100 WORK DAYS Proposal Note: ***WORK RESTRICTION*** THE 24 INCH CULVERT AT STA. 456+50 SHALL BE INSTALLED AFTER JULY 31, 2014. Project(s): Project No: NHSX-534-1(85)--3H-65 County: MILLS Type of Work: PCC PAVEMENT - GRADE AND NEW Route: IOWA 534 Length: 3.84 miles Location: FROM MISSOURI RIVER EAST TO JUST EAST OF BN/SF R.R. (WBL) Project No: NHSX-534-1(92)--3H-65 County: MILLS Type of Work: TRAFFIC SIGNS Route: IOWA 534 Length: 0.00 miles Location: FROM MISSOURI RIVER EAST TO JUST EAST OF BN/SF R.R. Project No: NHSN-534-1(93)--2R-65 County: MILLS Type of Work: LIGHTING Route: IOWA 534 Length: 0.00 miles Location: INTERCHANGE OF I-29 AND RELOCATED U.S. 34 AND INTERCHANGE OF I-29 AND IA 978 _____ Item No. Item Description Ouantity/Unit SECTION NO. 0001 ROADWAY ITEMS - NHSX-534-1(85)--3H-65 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 296,680 CY 2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 633 CY 2108-5025000 OVERHAUL 1,290,480 ST-Y 2122-5190010 PAVED SHLD, PCC, 10" 517 SY 2301-1003100 STD/S-F PCC PAV'T, QM-C CL 3, 10" 73,997 SY SECTION NO. 0002 ALTERNATE 'AA' OPTION 1: PCC PAVED SHOULDER-RAMPS BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN-(85) 2122-5190007 PAVED SHLD, PCC, 7" 9,108 SY SECTION NO. 0004 ALTERNATE 'BB' OPTION 1: PCC PAVED SHOULDER-ML BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN-(85) 2122-5190006 PAVED SHLD, PCC, 6" 19,291 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 77-0801-504

Proposed Contract Period: By individual sites.

Proposal Note:

*** HOURLY LIQUIDATED DAMAGES *** DUE TO THE HIGH VOLUME OF TRAFFIC THE LIQUIDATED DAMAGES FOR THIS CONTRACT HAVE BEEN INCREASED AND WILL BE ASSESSED ON AN HOURLY BASIS. THE HOURLY LIQUIDATED DAMAGES SHALL APPLY TO THIS PROJECT WITH THE FOLLOWING CONDITIONS:

HOURLY LIQUIDATED DAMAGES RATE: \$165.00/HOUR

THE HOURLY LIQUIDATED DAMAGES RATE WAS CALCULATED BY DIVIDING THE DAILY ROAD USER COST BY 24.

THE DOLLAR AMOUNT ''LIQUIDATED DAMAGES'' FOR THE SITES SHOWN ABOVE IS EQUAL TO THE DAILY ROAD USER COST. THE LIQUIDATED DAMAGES WILL BE ASSESSED ON AN HOURLY BASIS IF WORK IS NOT COMPLETED WITHIN THE TIMES SHOWN IN THE STAGING NOTES ON SHEET J.1 OF THE PLANS.

*** SITE NUMBER 01 AND 02 / NO EXCUSE ROAD OPENING BONUS FOR STAGE 1 AND 2 *** THE CONTRACTOR WILL BE PAID THE PREDETERMINED LUMP SUM AMOUNT SHOWN IN THE PROPOSAL SCHEDULE OF PRICES FOR THE BID ITEMS 'NO EXCUSE ROAD OPENING BONUS' FOR COMPLETING CONSTRUCTION OF STAGE 1 AND/OR STAGE 2 AS SHOWN ON PLAN SHEET J.1 WITHIN THE CONTRACT PERIODS SHOWN ABOVE IN SITE NUMBERS 01 AND 02. COMPLIANCE REQUIRES THAT THE CONTRACTOR MUST HAVE ALL EASTBOUND LANES/SHOULDERS AND ALL WESTBOUND LANES/SHOULDERS OPEN TO TRAFFIC. ANY OTHER DELAYS DUE TO WEATHER, UTILITY DELAYS, OR ANY OTHER DELAYS WILL NOT BE CONSIDERED AS JUSTIFICATION TO MODIFY THE PAYMENT OF THE BONUSES.

Project(s):				
Project No:	MBIN-080-1(504)1390M-77			
County:	POLK			
Type of Work:	BRIDGE APPROACH REPAIR			
Route:	I-80	Length:	0.00 miles	
Location:	OVER FOUR MILE CREEK	1.4 MILES	E. OF I-35	

Item No. Item Description Quantity/Unit SECTION NO. 0001 DESIGN NO. 2813; 188'-4 X 56'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE - EASTBOUND 2403-0100000 STRUCT CONC (MISCELLANEOUS) 10 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 1,228 LB SECTION NO. 0002 DESIGN NO. 3613; 188'-4 X 56'-0 PRETENSIONED PRESTRESSED

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT				
(for information only)				
CONCRETE BEAM BRIDGE - WESTBOUND				
2403-0100000 STRUCT CONC (MISCELLANEOUS)	10 CY			
2404-7775005 REINFORC STEEL, EPOXY COATED	1,228 LB			
SECTION NO. 0003				
ROADWAY ITEMS				
2102-2625000 EMBANKMENT-IN-PLACE	600 CY			
SECTION NO. 0004				
BONUS ITEMS				
2528-5160000 NO EXCUSE ROAD OPENING BONUS,	Lump Sum LUMP			
2528-5160000 NO EXCUSE ROAD OPENING BONUS,	Lump Sum LUMP			

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 108 Proposal ID: 77-1945-746 Proposed Contract Period: Late Start Date of 08/05/13 with 180 WORK DAYS Project(s): Project No: STP-U-1945(746)--70-77 County: POLK Type of Work: PCC PAVEMENT - GRADE & REPLACE Route: EAST INDIANOLA AVE Length: 0.63 miles Location: IN THE CITY OF DES MOINES FROM EAST MCKINLEY AVENUE SOUTHEASTERLY _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 37,437 CY 2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10" 26,510 SY 2303-0031750 HMA (1M ESAL) BASE, 3/4" 242 TON 2303-0033500 $\,$ HMA (1M ESAL) SURF, 1/2", NO FRIC 182 TON 2511-0301600 RECREATIONAL TRAIL, HMA, 6" 4,908 SY 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 1,734 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 109 Proposal ID: 82-0069-079 Proposed Contract Period: Late Start Date of 07/29/13 with 60 WORK DAYS Project(s): Project No: STP-U-006-9(79)--70-82 County: SCOTT Type of Work: PCC PAVEMENT WIDENING Route: U.S. 6 Length: 0.00 miles Location: IN THE CITY OF DAVENPORT WITH FOREST RD. AND LORTON AVE INTERSEC _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1034100 STD/S-F PCC PAV'T, CL C CL 3I, 10" 5,859 CY 4,714 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 110 Proposal ID: 91-0653-061 Proposed Contract Period: Late Start Date of 09/30/13 with 25 WORK DAYS Project(s): Project No: HSIPX-065-3(61)--3L-91 County: WARREN Type of Work: PCC PAVEMENT - GRADE & REPLACE Route: U.S. 65 Length: 0.00 miles Location: SCOTCH RIDGE RD. INTERSECTION 2.5 MILES S. OF IA. 5/US 65/US 69 INTERCHANGE _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 2,425 CY 1,357 SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 111 Proposal ID: 97-0121-030 Proposed Contract Period: By individual sites. Site 01: ALL ADA RAMPS & SIDEWALKS AT IA. 12 AND STONE, REFER TO J.1. Late Start Date of 07/29/13 with 10 WORK DAYS Site 02: ALL REMAINING ADA RAMPS AND SIDEWALKS, REFER TO J.1. Late Start Date of 07/29/13 with 40 WORK DAYS Project(s): Project No: NHSN-012-1(30)--2R-97 County: WOODBURY Type of Work: PCC SIDEWALK/TRAIL Route: IOWA 12 Length: 0.00 miles Location: IN THE CITY OF SIOUX CITY FROM US 20/75 W. TO VIADUCT _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 SIDEWALK ITEMS 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 4 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 1 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 151 Proposal ID: 11-7422-613 Proposed Contract Period: Late Start Date of 07/29/13 with 45 WORK DAYS Project(s): Project No: STP-U-7422(613)--70-11 County: BUENA VISTA Type of Work: HMA RESURFACING WITH MILLING Route: WEST FIFTH STREET Length: 1.20 miles Location: IN THE CITY OF STORM LAKE, FROM VISTA DRIVE TO LAKE AVENUE _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 4,787 TON 514 SY 95 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 25-0802-230

Proposed Contract Period: Late Start Date of 08/19/13 with 65 WORK DAYS

Project(s): Project No: IMX-080-2(230)99--02-25 County: DALLAS Type of Work: HMA PAVED SHOULDER - NEW Route: I-80 Leng

Route: I-80 Length: 0.00 miles Location: FROM 0.5 MILE E. OF DEXTER E. TO 2 MILES W. OF POLK CO. LINE

 Item No.
 Item Description
 Quantity/Unit

 SECTION NO. 0001
 ROADWAY ITEMS
 18,997 CY

 2102-2625000
 EMBANKMENT-IN-PLACE
 18,997 CY

 2122-5190007
 PAVED SHLD, PCC, 7"
 516 SY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 153 Proposal ID: 25-1694-706 Proposed Contract Period: Late Start Date of 08/05/13 with 15 WORK DAYS Proposal Note: Project(s): Project No: MP-169-4(706)89--76-25 County: DALLAS Type of Work: HMA RESURFACING Route: U.S. 169 Length: 0.75 miles Location: N. OF ADEL BETWEEN THE RACCOON RIVER MILL RACE BRIDGE & . THE N. RACCOON RIVER BRIDGE _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 826 TON 2303-0043503 HMA (3M ESAL) SURF, 1/2", FRIC L-3 1,634 TON

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 154 Proposal ID: 31-0522-117 Proposed Contract Period: Late Start Date of 08/12/13 with 45 WORK DAYS Project(s): Project No: NHSX-052-2(117)--3H-31 County: DUBUQUE Type of Work: HMA RESURFACING Route: U.S. 52 Length: 15.09 miles Location: FROM BOY SCOUT RD. W. TO IA. 136 IN LUXEMBURG(VAR. LOC.) Project No: NHSN-136-3(41)--2R-31 County: DUBUQUE Type of Work: HMA RESURFACING Route: IOWA 136 Length: 0.47 miles Location: IN THE CITY OF NEW VIENNA FROM JEFFERSON ST. N. TO NCL _____ Item Description Item No. Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS NHSX-052-2(117)--3H-31 2303-0033504 HMA (1M ESAL) SURF, 1/2", FRIC L-4 8,348 TON SECTION NO. 0003 ROADWAY ITEMS NHSN-136-3(41)--2R-31 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 714 TON 2303-0043504 HMA (3M ESAL) SURF, $1/2"\,,$ FRIC L-4 734 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 156 SY 18 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 155 Proposal ID: 45-C045-069 Proposed Contract Period: Late Start Date of 09/09/13 with 25 WORK DAYS Project(s): Project No: FM-C045(69)--55-45 County: HOWARD Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: B16 Length: 4.94 miles Location: FROM 0.28 MILES EAST OF RIDGEWAY AVENUE, EAST TO WINNESHIEK COUNTY LINE _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 10,912 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 156 Proposal ID: 57-1187-769 Proposed Contract Period: Late Start Date of 09/03/13 with 35 WORK DAYS Project(s): Project No: STP-E-1187(769)--8V-57 County: LINN Type of Work: HMA SIDEWALK/TRAIL Route: HMA TRAIL Length: 0.63 miles Location: IN THE CITY OF CEDAR RAPIDS, BOAT RAMPS TO EDGEWOOD RD. NW _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 TRAIL ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033060 STD/S-F PCC PAV'T, CL C CL 3, 6" 2511-0301500 RECREATIONAL TRAIL, HMA, 5" 4,359 CY 100 SY 3,460 SY 2511-0302500 RECREATIONAL TRAIL, PCC, 5" 185 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 157 Proposal ID: 63-C063-110 Proposed Contract Period: Late Start Date of 09/30/13 with 15 WORK DAYS Project(s): Project No: FM-C063(110)--55-63 County: MARION Type of Work: HMA RESURFACING Route: RUTLEDGE STREET Length: 1.00 miles Location: MELCHER CL TO 42ND _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS
 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 620 CY

 2303-0023500
 HMA (300K ESAL) I-S, 1/2", NO FRIC
 2,100 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 158 Proposal ID: 63-C063-111 Proposed Contract Period: Late Start Date of 09/16/13 with 25 WORK DAYS Project(s): Project No: FM-C063(111)--55-63 County: MARION Type of Work: HMA RESURFACING Route: T-23 AND G-71 Length: 2.50 miles Location: HWY 5 TO BUSSEY _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ROADWAY ITEMS 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 7,590 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 159 Proposal ID: 77-C077-196 Proposed Contract Period: Late Start Date of 09/09/13 with 20 WORK DAYS Project(s): Project No: STP-S-C077(196)--5E-77 County: POLK Type of Work: HMA RESURFACING Route: S27 Length: 5.94 miles Location: I-80 TO SKUNK RIVER & US HWY 65 TO NE 13 4 AVE _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC 11,620 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 160 Proposal ID: 78-C078-180 Proposed Contract Period: Late Start Date of 08/19/13 with 15 WORK DAYS Project(s): Project No: FM-C078(180)--55-78 County: POTTAWATTAMIE Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: 310TH STREET Length: 0.70 miles Location: ARROWHEAD PARK ENTRANCE TO INTERSTATE 80 RAMPS Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 161 Proposal ID: 78-0921-068 Proposed Contract Period: Late Start Date of 07/22/13 with 60 WORK DAYS Project(s): Project No: STPN-092-1(68)--2J-78 County: POTTAWATTAMIE Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING Route: IOWA 92 Length: 5.91 miles Location: FROM 0.2 MILES E. OF STATE ORCHARD RD. E. TO KEG CREEK _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS
 2102-2625000
 EMBANKMENT-IN-PLACE

 2303-0042500
 HMA (3M ESAL) INTERMEDIATE, 1/2"

 2303-0043503
 HMA (3M ESAL) SURF, 1/2", FRIC L-3
 855 CY 8,073 TON 11,382 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 162 Proposal ID: 82-1301-029 Proposed Contract Period: Late Start Date of 07/15/13 with 80 WORK DAYS Project(s): Project No: STPN-130-1(29)--2J-82 County: SCOTT Type of Work: HMA RESURFACING WITH MILLING Route: IOWA 130 Length: 14.05 miles Location: FROM THE CEDAR COUNTY LINE SOUTHEASTERLY TO COUNTY ROAD Y-52 _____ Quantity/Unit Item No. Item Description _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 2303-0001000 HMA WEDGE/LEVEL/STRENGTH 2,840 CY 519 TON 2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 17,389 TON 2303-0033504 HMA (1M ESAL) SURF, 1/2", FRIC L-4 17,086 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 277 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 2 EACH

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 163 Proposal ID: 85-0155-679 Proposed Contract Period: Late Start Date of 09/09/13 with 30 WORK DAYS Proposal Note: *** SITE NUMBER 01 *** DARTMOOR ROAD SHALL BE CLOSED TO TRAFFIC DURING GUARDRAIL INSTALLATION ON DARTMOOR RD. DARTMOOR ROAD SHALL BE REOPENED TO TRAFFIC UPON COMPLETION OF GUARDRAIL INSTALLATION. DARTMOOR ROAD SHALL BE CLOSED TO THROUGH TRAFFIC FOR NO MORE THAN 7 CALENDAR DAYS. THE OWNER'S REPRESENTATIVE SHALL BE GIVEN 72 HOUR ADVANCE ROAD CLOSURE NOTIFICATION. Project(s): Project No: STP-U-0155(679)--70-85 County: STORY Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING Route: STATE AVE. Length: 0.88 miles Location: IN THE CITY OF AMES, FROM OAKWOOD RD. TO NORTH OF THE US 30 OVERPASS Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 786 CY 2303-0001000 HMA WEDGE/LEVEL/STRENGTH 179 TON 2303-0031500 HMA (1M ESAL) BASE, 1/2" 2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 1,723 TON 1,788 TON 1,864 TON 2303-0131500 HMA (1M ESAL) BASE, 1/2" 836 SY 2303-0132500 HMA (1M ESAL) INTERMEDIATE, 1/2" 836 SY 2303-0133500 HMA (1M ESAL) SURF, 1/2", NO FRIC 836 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 164 Proposal ID: 92-8140-610 Proposed Contract Period: Late Start Date of 09/09/13 with 30 WORK DAYS Project(s): Project No: STP-U-8140(610)--70-92 County: WASHINGTON Type of Work: HMA RESURFACING WITH MILLING Route: SOUTH IOWA AVE. Length: 0.80 miles Location: IN THE CITY OF WASHINGTON WEST MADISON STREET TO CITY LIMITS _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 255 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC 2,300 TON 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 84 SY 7 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 201 Proposal ID: 10-7040-012 Proposed Contract Period: Late Start Date of 09/09/13 with 20 WORK DAYS Project(s): Project No: DHS-704-0(12)--7H-10 County: BUCHANAN Type of Work: PCC PATCHING Route: ENTRANCE ROAD Length: 0.00 miles Location: INDEPENDENCE MENTAL HEALTH INSTITUTE-VARIOUS ROADS _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS - DIVISION 1 2529-5070110PATCH, FULL-DEPTH FINISH, BY AREA2529-5070120PATCH, FULL-DEPTH FINISH, BY COUNT 460 SY 65 EACH SECTION NO. 0002 ROADWAY ITEMS - DIVISION II 2403-0100000 STRUCT CONC (MISCELLANEOUS) 5 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 670 LB 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 152 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 10 EACH

	IOWA DEPARTMENT OF TRANSPORTATION
	MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)
Proposed Letting	g Date: June 18, 2013 10:00 A.M.
Proposed Bid Or	rder: 202 Proposal ID: 85-0351-704
Proposed Contr	ract Period: Late Start Date of 10/07/13 with 10 WORK DAYS
Proposal Note	e:
Project(s):	
Project No:	MPIN-035-1(704)1180N-85
Project No: County:	STORY
Project No: County:	STORY PAVEMENT PLANING/GROOVING
Project No: County: Type of Work: Route:	STORY PAVEMENT PLANING/GROOVING

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 301 Proposal ID: 05-C005-056 Proposed Contract Period: Late Start Date of 09/16/13 with 30 WORK DAYS Project(s): Project No: FM-C005(56)--55-05 County: AUDUBON Type of Work: GRANULAR SURFACING OF ROADWAY Route: MULTIPLE ROUTES Length: 185.00 miles Location: VARIOUS LOCATIONS - SEE MAP OF FM ROADS _____ Quantity/Unit Item No. Item Description _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 302 Proposal ID: 22-1624 Proposed Contract Period: Late Start Date of 09/30/13 with 20 WORK DAYS Project(s): Project No: L-1624--73-22 County: CLAYTON Type of Work: AGGREGATE FOR SHOULDERS Route: HILTON ROAD(C7X) Length: 9.50 miles Location: IOWA 3 NORTH TO X3C _____ Item No. Quantity/Unit Item Description _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 303 Proposal ID: 25-0803-176 Proposed Contract Period: Late Start Date of 10/14/13 with 15 WORK DAYS Project(s): Project No: IMN-080-3(176)112--0E-25 County: DALLAS Type of Work: REVETMENT Route: I-80 Length: 0.00 miles Location: OVER N. RACCOON RIVER 2.3 MILES E. OF US 169 _____ Item No. Quantity/Unit Item Description _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 304 Proposal ID: 94-C094-091 Proposed Contract Period: Late Start Date of 08/12/13 with 60 WORK DAYS Project(s): Project No: NRT-C094(091)--9G-94 County: WEBSTER Type of Work: GRADING Route: . Length: 0.00 miles Location: IN WEBSTER COUNTY GYPSUM CITY OHV PARK CAMPGROUND _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 35,554 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 305 Proposal ID: 97-6890-608 Proposed Contract Period: Late Start Date of 08/12/13 with 40 WORK DAYS Project(s): Project No: SRTS-U-6890(608)--8U-97 County: WOODBURY Type of Work: STORM SEWER/INTAKES Route: PORT NEAL RD Length: 0.46 miles Location: IN THE CITY OF SERGEANT BLUFF PORT NEAL RD FROM WARRIOR RD S. TO DRAINAGE DITCH _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 3,145 CY

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 351 Proposal ID: 00-000S-551 Proposed Contract Period: By individual sites. Site 01: TO COMPLETE DIVISION 1- STANDARD TIME FRAME Late Start Date of 09/30/13 with 25 WORK DAYS Site 02: TO COMPLETE DIVISION 2 - ACCELERATED TIME FRAME Late Start Date of 07/29/13 with 5 WORK DAYS Project(s): Project No: NHSN-000-S(551)--2R-00 County: STATEWIDE Type of Work: TRAFFIC SIGNS Route: MULTIPLE ROUTES Length: 0.00 miles Location: VARIOUS LOCATIONS STATEWIDE _____ _____ Item No. Item Description Quantity/Unit _____

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 352 Proposal ID: 25-000S-614 Proposed Contract Period: By individual sites. Site 01: TO INSTALL #659, #662, AND #56 Late Start Date of 09/09/13 with 45 WORK DAYS Site 02: TO INSTALL #122 Approx Start Date of 04/28/14 with 15 WORK DAYS Proposal Note: ***WORK RESTRICTION*** NO WORK SHALL BE PERMITTED AT SITE #122 IN 2013. Project(s): Project No: ITS-000-S(614)--25-25 County: DALLAS Type of Work: DYNAMIC MESSAGE SIGNS Route: I-80 & I-235 Length: 0.00 miles Location: I-80/ALICE'S RD. & I-235/63RD ST. IN DES MOINES _____ Item Description Item No. Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 56 CY 2122-5190007 PAVED SHLD, PCC, 7" 63 SY 2403-0100000 STRUCT CONC (MISCELLANEOUS) 166 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 20,046 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 353 Proposal ID: 73-0591-030 Proposed Contract Period: Late Start Date of 07/15/13 with 30 WORK DAYS Project(s): Project No: STP-059-1(30)--2C-73 County: PAGE Type of Work: TRAFFIC SIGNALS Route: U.S. 59 Length: 1.00 miles Location: IN THE CITY OF SHENANDOAH TRAFFIC SIGNAL/STROM SEWER REPLACEMENT _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 106 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 354 Proposal ID: 77-0354-189-A Proposed Contract Period: Late Start Date of 10/14/13 with 10 WORK DAYS Project(s): Project No: IMN-035-4(189)90--0E-77 County: POLK Type of Work: TRAFFIC SIGNS Route: I-35 Length: 0.00 miles Location: IN THE CITY OF ANKENY AT THE IA. 160(ORALABOR RD.) INTERCHAN NB OFF RAMP _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 355 Proposal ID: 97-0296-239-A Proposed Contract Period: Late Start Date of 08/19/13 with 40 WORK DAYS Project(s): Project No: IMN-029-6(239)147--0E-97 County: WOODBURY Type of Work: FIBER OPTIC INSTALLATION Route: I-29 Length: 0.00 miles Location: IN THE CITY OF SIOUX CITY ON GORDON DR. (PLACEMENT OF CONDUIT) _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 401 Proposal ID: 78-0292-081 Proposed Contract Period: Approx Start Date of 08/26/13 with 10 WORK DAYS Project(s): Project No: IMN-029-2(81)48--0E-78 County: POTTAWATTAMIE Type of Work: SALVAGE AND REMOVAL Length: 0.00 miles Route: I-29 Location: IN THE CITY OF COUNCIL BLUFFS AT 250 29TH AVE. PARCEL NO. 346 _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 402 Proposal ID: 82-0741-238 Proposed Contract Period: Approx Start Date of 08/26/13 with 10 WORK DAYS Project(s): Project No: IMN-074-1(238)5--0E-82 County: SCOTT Type of Work: SALVAGE AND REMOVAL Route: I-74 Length: 0.00 miles Location: IN THE CITY OF BETTENDORF AT 1523 GRANT ST. PARCEL NO. 340 _____ Item No. Item Description Quantity/Unit _____

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 451 Proposal ID: 04-FE08-076 Proposed Contract Period: Late Start Date of 07/22/13 with 85 WORK DAYS Project(s): Project No: RPD-FE08(76)--8B-04 County: APPANOOSE Type of Work: MISCELLANEOUS Route: . Length: 0.00 miles Location: IMPROVEMENTS AND REHABILITATION TO RAIL AND BRIDGES ON THE APPANOOSE COUNTY COM _____ Item No. Item Description Quantity/Unit _____ SECTION NO. 0004 ARTICLE 5 - APNC MOULTON SPUR EXTENSION 282 CY 2102-2713070 EXCAVATION, CL 13, RDWY+BORROW

IOWA DEPARTMENT OF TRANSPORTATION MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Proposed Letting Date: June 18, 2013 10:00 A.M. Proposed Bid Order: 601 Proposal ID: 97-0772-015 Proposed Contract Period: Late Start Date of 07/22/13 with 40 WORK DAYS Proposal Note: *** DEFINITION OF MAINTENANCE BRIDGE NUMBERS *** THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE: . BRIDGE NO. 5210.90380: . (BRACKETED $\{ \ \}$ PORTIONS OF THE NUMBER ARE DEFINED BELOW.) . $\{52\}10.90380$ County no. where the bridge is located . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9 (ACTUAL MILEPOST COULD BE 110.9 OR 210.9) . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE (ALPHA VALUES; O = OVER, R = RIGHT, L = LEFT, A = RAMP, S = SINGLE) . 5210.90{380} 3-DIGIT ROUTE THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE FOLLOWING BRIDGES: . 9700.0S077 Project(s): Project No: BRFN-077-2(15)--39-97 County: WOODBURY Type of Work: BRIDGE CLEANING Route: U.S. 77 Length: 0.00 miles Location: IN THE CITY OF SIOUX CITY OVER THE MISSOURI RIVER _____ Item No. Item Description Quantity/Unit _____

IOWA DEPARTMENT OF TRANSPORTATION			
MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)			
Proposed Letting Date: June 18, 2013 10:00 A.M.			
Proposed Bid Order: 981 Proposal ID: 35-0352-717			
Proposed Contract Period: Late Start Date of 09/23/13 with 10 WORK DAYS			
Proposal Note:			
Project(s): Project No: MPIN-035-2(717)1600N-35 County: FRANKLIN Type of Work: PCC PATCHING Route: I-35 Length: 0.00 miles Location: DOWS REST AREA			
Item No. Item Description Quantity/Unit			
SECTION NO. 0001			
PATCHING ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 84 CY			
2122-5190007 PAVED SHLD, PCC, 7" 433 SY			
2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 135 SY			
2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 4 EACH			

IOWA DEPARTMENT OF TRANSPORTATION				
MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)				
Proposed Letting Date: June 18, 2013 10:00 A.M.				
Proposed Bid Order: 982 Proposal ID: 77-4151-713				
Proposed Contract Period: Late Start Date of 10/07/13 with 15 WORK DAYS				
Proposal Note:				
Project(s): Project No: MP-415-1(713)176-77 County: POLK Type of Work: GUARDRAIL Route: IOWA 415 Length: 0.00 miles Location: IN THE CITY OF DES MOINES JUST N. OF THE UP R.R THE FIRESTONE PLANT.				
Item No. Item Description	Quantity/Unit			
SECTION NO. 0001 ROADWAY ITEMS 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	373 CY			