

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: September 17, 2013
Date of Addendum: August 21, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
502	25-0803-177	LANDSCAPING	DALLAS	IMN-80-3(177)--0E-25	17SEP502.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to Plan Sheet C.2:

Add the following note to the reference notes for the item 2601-2633100 MOWING:

Double shrub rows: Mow a 3 feet wide strip adjacent to the mulch area.

Native Grass Seeding Areas: if Native Grass Seeding is not accomplished by May 31, 2014; the Contractor shall mow 1 week prior to the initial seeding in spring 2015. This mowing will not be measured for payment.

Add the following note to the reference notes for the item 2601-2636015 NATIVE GRASS SEEDING:

Seed shall be mixed off-site by a seed conditioner approved by the Iowa Crop Improvement Association. Grasses and wildflowers shall be mixed together.

No seeding will be allowed after May 31, 2014. Seed the areas not completed with a stabilizing crop of Oats 50 lbs.PLS/acre and Grain rye 50 lbs.PLS/acre by June 15, 2014. Furnish an additional percentage of PLS lbs. of Source Identified Class (Yellow Tag) Source G0-Iowa native grass and wildflower seed as specified below to replace loss in germination. Seed the furnished native grass and wildflower mixture and the contractor furnished additional seed during the following spring seeding dates.

Percent supplemental seed/total lbs. /species

Native grasses (except Prairie dropseed, and Prairie cordgrass) 10%, Prairie dropseed 80%, and Prairie cordgrass 100%

Wildflowers @ 40%:

White sage, Tall boneset, Rough blazingstar, Prairie blazingstar, Smooth blue aster, New England aster, Prairie spiderwort, Ironweed

Wildflowers @ 80%:

Stiff goldenrod, Showy goldenrod

Furnishing supplemental native grass and wildflower seed will not be measured for payment.

Furnishing seed for cover crop and related activities will not be measured for payment.

Add the following note to the reference notes for the item 2611-0000200 TREES, FURNISH AND INSTALL:

Install white corrugated resin tree guards to all deciduous trees prior to completion of the initial installation. Tree guards shall measure 3 inch diameter and cover the length of the trunk from the mulch line up to the first tier of branches. Tree guards, installation and related activities will not be measured for payment. Tree guards will remain at the end of the project.

Make the following change to the Plan Sheet C.3:

Tab 100-20 PLANTING QUANTITIES LISTING

No.5 C-1 American Hornbeam J.N.Strain (*Carpinus caroliniana* J.N.Strain)

Add:

Alternate size: 6' BB shrub form