

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: October 15, 2013  
Date of Addendum: September 27, 2013

| <b>B.O.</b> | <b>Proposal ID</b> | <b>Proposal Work Type</b> | <b>County</b> | <b>Project Number</b>  | <b>Addendum</b> |
|-------------|--------------------|---------------------------|---------------|------------------------|-----------------|
| 154         | 57-3806-293        | HMA RESURFACING           | LINN          | IMX-380-6(293)16-02-57 | 15OCT154.A01    |

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to Plan Sheet B.6:

Add the following note to Typical 7307M and 7308M:

Construct a temporary HMA runout at each milled surface notch prior to opening to traffic. The length of temporary runout shall be 10' per 1" of thickness. The temporary runout shall be removed prior to placement of the surface course. Placement of the runout is incidental to the milling.