

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: September 17, 2013
Date of Addendum: September 11, 2013

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
104	78-0801-364-A	PCC PAVEMENT - GRADE & REPLACE	POTTAWATTAMIE	IM-NHS-080-1(364)3--03-78 IM-NHS-080-1(365)3--03-78 IM-NHS-080-1(419)3--03-78	17SEP104.A03

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following change to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 0210 2301-1033100 STANDARD OR SLIP FORM PORTLAND CEMENT CONCRETE PAVEMENT, CLASS C, CLASS 3 DURABILITY, 10 IN.:

From: 6,995.700 SY

To: 7,019.300 SY

Change Proposal Line No. 0230 2301-4875006 MEDIAN, P.C.CONCRETE, 6 IN.:

From: 284.600 SY

To: 94.900 SY

If the above changes are not made, they will be made as shown here.

Make the following changes to IM-NHS-080-1(365)3--03-78:

Plan Sheet C.1, Add the following ESTIMATE REFERENCE INFORMATION for Item Code 2423-0001010 DYNAMIC MESSAGE SIGN (D.M.S.) INSTALLATION:

D.M.S. to be stored at Council Bluffs Maintenance yard located at 3538 S. Expressway, Council Bluffs, IA.

Plan Sheet C.2, Add the following ESTIMATE REFERENCE INFORMATION for Item Code 2524-9276010 PERFORATED SQUARE STEEL TUBE POSTS:

PSST posts shall be 2.5 inch width, 12 gauge.

Plan Sheet C.5, Tabulation STS SIGN TRUSS STANDARDS:

Change the date on the following standards:

SOST-18-11 From: 03-13 To: 06-13

The current standards can be found at the following internet site:

<http://www.iowadot.gov/bridge/standards/english/SteelOverheadSignTruss.pdf>