

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: December 17, 2013  
Date of Addendum: December 10, 2013

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
028	82-0741-234	BRIDGE REPLACEMENT - PPCB	SCOTT	BRFIM-074-1(153)0--05-82 IM-074-1(234)0--13-82	17DEC028.A02

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following changes to plan IM-074-1(234)0--13-82:

Plan Sheet C.1:

For Item Code STORM SEWER GRAVITY MAIN WITH CASING PIPE,  
TRENCHLESS, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 24 IN.,  
add the following to the Estimate Reference Information:

Casing pipe shall be a minimum 40 inch diameter pipe with a minimum wall thickness of 0.375 inches. Manufactured casing spacers shall be used to position the carrier pipe in casing. Flowable mortar or other annular fill will not be required.

Plan Sheet C.11:

Delete the following Standard Notes:

232-3A	10-16-12
232-3B	10-16-12
232-11	10-16-12