

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: February 18, 2014  
Date of Addendum: February 11, 2014

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
010	43-1912-007	BRIDGE REPLACEMENT - CCS	HARRISON	BRFN-191-2(7)--39-43	18FEB010.A03

---

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

---

Make the following change to Plan Sheet Number 3:

Add the following to the GENERAL NOTES:

THE DETOUR ROADWAY WILL OVERTOP FOR FLOODS EXCEEDING THE 2-YR EVENT.  
WHEN THE DETOUR CULVERTS ARE INSTALLED, THE CONTRACTOR SHALL NOTIFY THE IDOT PRELIMINARY BRIDGE DESIGN OFFICE AT 515-239-1487 SO A FLOOD MANAGEMENT PLAN CAN BE DEVELOPED IN ADVANCE OF THE DETOUR BEING PLACED INTO SERVICE.  
UPON NOTIFICATION, THE BRIDGE OFFICE WILL ADD THIS SITE TO THE BRIDGE WATCH MANAGEMENT PLAN FOR MONITORING.

CONCRETE BARRIER RAILING WILL BE USED ON THIS BRIDGE PROJECT.  
ANY REFERENCE TO OPEN RAIL THAT WAS USED ON SHEET NUMBER 7 AND 8 IS NOT APPLICABLE.”