

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: May 19, 2014
Date of Addendum: May 19, 2014

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
301	90-1491-070	PIPE CULVERTS	WAPELLO	STPN-149-1(70)--2J-90	19MAY301.A02

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Delete Proposal Line No. 0070 2506-4984000 FLOWABLE MORTAR; 150.000 CY

Add Proposal Line No. 0181 2402-0425040 FLOODED BACKFILL; 162.500 CY

If the above changes are not made, they will be made as shown here.

Add the following to the PROPOSAL SPECIAL PROVISIONS TEXT and the PROPOSAL SPECIAL PROVISIONS LIST:

SS-12008 December 17, 2013

SUPPLEMENTAL SPECIFICATION FOR BACKFILLING AND COMPACTION OF
PIPE AND REINFORCED BOX CULVERTS BY FLOODING

Make the following change to the PLAN:

SHEET C.1:

Add the following note to the ESTIMATE REFERENCE INFORMATION for the item 2402-0425040, FLOODED BACKFILL:

- A. Includes 150 cu. yds. of floodable backfill and 12.5 cu. yds. of porous backfill.
- B. Flooded Backfill shall be placed above the porous backfill and directly under the Modified Subbase. Omit 6" of Flowable Mortar as shown on Standard Road Plan RF-30A.