

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 15-0801-409

Proposed Contract Period: Late Start Date of 08/18/14 with 50 WORK DAYS

Project(s):

Project No: IMN-080-1(409)52--0E-15

County: CASS

Type of Work: RECONSTRUCTION - BRIDGE DECK REPLACEMENT

Route: I-80 Length: 0.00 miles

Location: OVER I-80

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0213; REPAIRS TO A 223'-9 X 30'-0 PRETENSIONED		
PRESTRESSED CONCRETE BEAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	239 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	69,678 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	280 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 16-0806-503

Proposed Contract Period: Late Start Date of 08/04/14 with 25 WORK DAYS

Project(s):

Project No: MBIN-080-6(503)266--0M-16

County: CEDAR

Type of Work: BRIDGE REPAIR

Route: I-80 Length: 0.00 miles

Location: OVER THE CEDAR RIVER 1 MILE W. OF W. JCT. IA. 38(EBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0314; REPAIRS TO A 1181'-0 X 56'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2413-0698074	DECK REPAIR, CL A	374 SY
SECTION NO. 0002		
DESIGN NO. 0314; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2413-0698066	DECK OVERLAY (CL O PCC)	374 SY
SECTION NO. 0003		
DESIGN NO. 0314; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	374 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 20-C020-094

Proposed Contract Period: Late Start Date of 07/28/14 with 70 WORK DAYS

Project(s):

Project No: STP-S-C020(94)--5E-20

County: CLARKE

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: H45 Length: 0.00 miles

Location: APPROX. 3/4 MI. E. OF HOPEVILLE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 120'-0 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,721 CY
2403-0100010	STRUCT CONC (BRIDGE)	198 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	48,193 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 23-C023-098

Proposed Contract Period: Late Start Date of 08/11/14 with 50 WORK DAYS

Project(s):

Project No: ER-C023(98)--58-23

County: CLINTON

Type of Work: RCB CULVERT REPLACEMENT - TRIPLE BOX

Route: Y-4E Length: 0.00 miles

Location: Y4E: OVER CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TRIPLE 12' X 9' X 42' REINFORCED CONCRETE BOX		
CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,432 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	290 SY
2403-0100020	STRUCT CONC (RCB CULV)	301 CY
2404-7775000	REINFORC STEEL	45,713 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 26-C026-084

Proposed Contract Period: Late Start Date of 07/21/14 with 75 WORK DAYS

Project(s):

Project No: ER-C026(84)--58-26

County: DAVIS

Type of Work: BRIDGE AND APPROACHES - PPCB

Route: DRIFTWOOD BLVD Length: 0.00 miles

Location: DRIFTWOOD BLVD: OVER TRIBUTARY OF FOX RIVER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 135'-0 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,261 CY
2403-0100010	STRUCT CONC (BRIDGE)	215 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	49,891 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 26-C026-085

Proposed Contract Period: Late Start Date of 04/01/15 with 75 WORK DAYS

Project(s):

Project No: BROS-C026(85)--8J-26

County: DAVIS

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: IRIS BLVD Length: 0.00 miles

Location: ON IRIS BLVD, BRIDGE REPLACEMENT, 0.7 MILES TO SOUTH OF 180TH STREET - SOUTH OF DRAKESVILLE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR 163'-10 X 24'-6 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	279 CY
2404-7775000	REINFORC STEEL	51,829 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,027 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 35-C035-076

Proposed Contract Period: Late Start Date of 08/11/14 with 50 WORK DAYS

Project(s):

Project No: BROS-C035(76)--5F-35

County: FRANKLIN

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: C33 Length: 0.50 miles

Location: FROM 160TH STREET TO 160TH STREET

Project No: BROS-C035(81)--8J-35

County: FRANKLIN

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: VIOLET AVE Length: 0.40 miles

Location: 50 FOOT NORTH OF 220TH STREET OVER SMALL STREAM

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	ITEMS FOR A 12'-0 X 12'-0 X 49'-0 PRECAST CONCRETE BOX	
	CULVERT - BROS-C033(76)--5F-35	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	835 CY
SECTION NO. 0002		
	ITEMS FOR A 12'-0 X 8'-0 X 40'-0 PRECAST CONCRETE BOX	
	CULVERT - BROS-C035(81)--8J-35	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	63 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 41-C041-113

Proposed Contract Period: Late Start Date of 09/15/14 with 20 WORK DAYS

Project(s):

Project No: BROS-C041(113)--8J-41

County: HANCOCK

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: 220TH ST. Length: 0.00 miles

Location: FROM DEER AVENUE TO ECHO AVENUE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 49-C049-058

Proposed Contract Period: Late Start Date of 07/28/14 with 60 WORK DAYS

Project(s):

Project No: BROS-C049(58)--5F-49

County: JACKSON

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 140TH AVE. Length: 0.15 miles

Location: OTTER CREEK TWP SEC. 21

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 100'-0 X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,158 CY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	5 CY
2403-0100010	STRUCT CONC (BRIDGE)	227 CY
2404-7775000	REINFORC STEEL	392 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	59,275 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 53-C053-071

Proposed Contract Period: Late Start Date of 07/21/14 with 65 WORK DAYS

Project(s):

Project No: BROS-C053(71)--5F-53

County: JONES

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: 42ND STREET Length: 0.10 miles

Location: OVER SIBLES CREEK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 110'-0 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	9,598 CY
2403-0100010	STRUCT CONC (BRIDGE)	196 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	47,625 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 57-1187-775

Proposed Contract Period: Late Start Date of 07/21/14 with 85 WORK DAYS

Project(s):

Project No: STP-U-1187(775)--70-57

County: LINN

Type of Work: BRIDGE NEW - PPCB

Route: EDGEWOOD ROAD Length: 0.48 miles

Location: IN THE CITY OF CEDAR RAPIDS ON EDGEWOOD ROAD SW, FROM PRAIRIE VALLEY COURT SW TO 37TH AVENUE SW

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 14'-0 X 257'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	26,410 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,187 CY
2122-5190010	PAVED SHLD, PCC, 10"	211 SY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	297 SY
2310-5151040	PCC OVERLAY, FURN ONLY	13 CY
2310-5151051	PCC OVERLAY, PLACE ONLY (BONDED)	224 SY
2403-0100010	STRUCT CONC (BRIDGE)	259 CY
2404-7775000	REINFORC STEEL	6,438 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	37,726 LB
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	2,094 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 86-C086-089

Proposed Contract Period: Late Start Date of 08/25/14 with 45 WORK DAYS

Project(s):

Project No: BROS-C086(89)--8J-86

County: TAMA

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: K AVENUE Length: 0.01 miles

Location: BETWEEN HWY D65 AND 100TH STREET

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 12'-0 X 12'-0 X 51'-0 REINFORCED CONCRETE		
BOX CULVERT		
2102-2625000	EMBANKMENT-IN-PLACE	3,124 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,264 CY
2403-0100020	STRUCT CONC (RCB CULV)	313 CY
2404-7775000	REINFORC STEEL	46,461 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 86-C086-090

Proposed Contract Period: Late Start Date of 08/25/14 with 45 WORK DAYS

Project(s):

Project No: BROS-C086(90)--8J-86

County: TAMA

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: W AVENUE Length: 0.00 miles

Location: BETWEEN 200TH STREET AND 210TH STREET

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 12'-0 X 8'-0 X 40'-0 REINFORCED CONCRETE		
BOX CULVERT		
2102-2625000	EMBANKMENT-IN-PLACE	3,347 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	950 CY
2403-0100020	STRUCT CONC (RCB CULV)	273 CY
2404-7775000	REINFORC STEEL	41,148 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 97-0201-105

Proposed Contract Period: Late Start Date of 04/20/15 with 115 WORK DAYS

Proposal Note:

*** WORK RESTRICTION ***

THE CONTRACTOR SHALL LIMIT REMOVAL OF FOREST COVER TO THOSE
AREAS WHICH ARE ABSOLUTELY NECESSARY FOR THE CONSTRUCTION OF
THE WORK. CUTTING SHALL BE PERFORMED BETWEEN OCTOBER 1ST
AND MARCH 31ST.

Project(s):

Project No: BRFN-020-1(105)--39-97

County: WOODBURY

Type of Work: BRIDGE REPLACEMENT - STEEL GIRDER

Route: U.S. 20 Length: 0.00 miles

Location: OVER ELLIOTT CREEK 6 MILES W. OF IA. 140 (EBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 3214; 180'-0 X 40' ROLLED STEEL BEAM BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	310 CY
2404-7775000	REINFORC STEEL	5,610 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	81,229 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	1,108 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,202 CY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	2,074 SY
SECTION NO. 0004		
ALTERNATE 'AA' OPTION 2: PCC SHOULDERS		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2122-5190007	PAVED SHLD, PCC, 7"	938 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 015 Proposal ID: 97-0201-128

Proposed Contract Period: Late Start Date of 04/01/15 with 125 WORK DAYS

Proposal Note:

*** WORK RESTRICTION ***

THE CONTRACTOR SHALL LIMIT REMOVAL OF FOREST COVER TO THOSE
AREAS WHICH ARE ABSOLUTELY NECESSARY FOR THE CONSTRUCTION OF
THE WORK. CUTTING SHALL BE PERFORMED BETWEEN OCTOBER 1ST
AND MARCH 31ST.

Project(s):

Project No: BRFN-020-1(128)--39-97

County: WOODBURY

Type of Work: BRIDGE REPLACEMENT - STEEL GIRDER

Route: U.S. 20 Length: 0.00 miles

Location: OVER W. FORK LITTLE SIOUX RIVER 0.1 MILE W. OF IA. 140 (EBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 3114; 220'-0 X 40' ROLLED STEEL BEAM BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	561 CY
2404-7775000	REINFORC STEEL	30,540 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	96,125 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	1,521 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,182 CY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	691 SY
SECTION NO. 0003		
ALTERNATE 'AA' OPTION 1: PCC SHOULDERS		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2122-5190007	PAVED SHLD, PCC, 7"	445 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 016 Proposal ID: 97-0867-601

Proposed Contract Period: Late Start Date of 07/21/14 with 75 WORK DAYS

Project(s):

Project No: BRS-0867(601)--60-97

County: WOODBURY

Type of Work: BRIDGE AND APPROACHES - CCS

Route: 210TH STREET Length: 0.16 miles

Location: D-38 APPROX 1/4 MILE SE OF K42.BRONSON TWP. SECTION 5.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 150'-0 X 30'-6 CONTINUOUS CONCRETE BRIDGE		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	942 CY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	1,598 SY
2403-0100010	STRUCT CONC (BRIDGE)	540 CY
2403-0100020	STRUCT CONC (RCB CULV)	125 CY
2404-7775000	REINFORC STEEL	18,941 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	95,363 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 06-7872-602

Proposed Contract Period: Late Start Date of 08/11/14 with 40 WORK DAYS

Project(s):

Project No: STP-U-7872(602)--70-06

County: BENTON

Type of Work: PCC PAVEMENT (MISCELLANEOUS)

Route: UNION AVENUE Length: 0.00 miles

Location: IN THE CITY OF URBANA, UNION ST (D-66): FROM WOOD ST TO CITY LIMITS

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	936 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	477 SY
2303-0031750	HMA (1M ESAL) BASE, 3/4"	235 TON
2303-0032750	HMA (1M ESAL) INTERMEDIATE, 3/4"	120 TON
2303-0033380	HMA (1M ESAL) SURF, 3/8", NO FRIC	120 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	118 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	1 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 07-C007-129

Proposed Contract Period: Late Start Date of 08/18/14 with 45 WORK DAYS

Project(s):

Project No: FM-TSF-C007(129)--5B-07

County: BLACK HAWK

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: V37 Length: 1.38 miles

Location: FROM 0.25 MI SOUTH OF D38 TO ORANGE RD.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	6,909 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	7,720 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	10,254 SY
2303-0031750	HMA (1M ESAL) BASE, 3/4"	41 TON
2310-5151600	PCC OVERLAY, QM-C, FURN ONLY	2,805 CY
2310-5151630	PCC OVERLAY, QM-C, PLACE ONLY(WHITE TOP)	12,624 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 11-7422-616

Proposed Contract Period: Late Start Date of 08/04/14 with 50 WORK DAYS

Project(s):

Project No: STP-E-7422(616)--8V-11

County: BUENA VISTA

Type of Work: PCC SIDEWALK/TRAIL

Route: LAKE AVE Length: 0.77 miles

Location: LAKE AVE TRAIL: ALONG LAKE AVENUE FROM 10TH ST TO COUNTY ROA
D C-49 IN THE CITY OF STORM LAKE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,926 CY
2511-0302400	RECREATIONAL TRAIL, PCC, 4"	2,440 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	297 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	96 SY
2511-0302800	RECREATIONAL TRAIL, PCC, 8"	525 SY
2511-0302800	RECREATIONAL TRAIL, PCC, 8"	120 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 18-7020-015

Proposed Contract Period: Late Start Date of 08/04/14 with 30 WORK DAYS

Project(s):

Project No: DHS-702-0(15)--7H-18

County: CHEROKEE

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: FUEL STATION ROAD Length: 0.00 miles

Location: CHEROKEE MENTAL HEALTH INSTITUTE - FUEL STATION RD.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	167 CY
2301-1022080	STD/S-F PCC PAV'T, CL B CL 2, 8"	385 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	192 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	10 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 49-0520-602

Proposed Contract Period: Late Start Date of 08/18/14 with 40 WORK DAYS

Project(s):

Project No: TAP-R-0520(602)--8T-49

County: JACKSON

Type of Work: PCC SIDEWALK/TRAIL

Route: RIVERVUE TRAIL Length: 1.46 miles

Location: IN THE CITY OF BELLEVUE, BELLEVUE RIVERVUE TRAIL-PH II: FROM
JEFFERSON AVE NORTHERLY ON THE W SIDE OF US 52 TO 395TH AVE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,829 CY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	25 CY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	7,300 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 106 Proposal ID: 54-1495-710

Proposed Contract Period: Late Start Date of 09/22/14 with 30 WORK DAYS

Project(s):

Project No: MP-149-5(710)31--76-54

County: KEOKUK

Type of Work: PCC PAVEMENT - REPLACE

Route: IOWA 149 Length: 0.30 miles

Location: NEAR THE SKUNK RIVER BRIDGE, NORTH FROM MP 30.9 TO MP 31.3.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2301-1083090	STD/S-F PCC PAV'T, CL M CL 3, 9"	3,444 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	53 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 77-C077-198

Proposed Contract Period: Late Start Date of 06/15/15 with 85 WORK DAYS

Project(s):

Project No: STP-ES-C077(198)--8I-77

County: POLK

Type of Work: PCC SIDEWALK/TRAIL

Route: TRAIL Length: 5.75 miles

Location: CHICHAQUA VALLEY TRAIL CONNECTOR FROM POLK COUNTY'S NE 29TH STREET TO 800' WEST OF GRANT STREET IN BONDURANT

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	17,800 CY
2303-0131750	HMA (1M ESAL) BASE, 3/4"	588 SY
2303-0132750	HMA (1M ESAL) INTERMEDIATE, 3/4"	588 SY
2303-0133500	HMA (1M ESAL) SURF, 1/2", NO FRIC	588 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	34,899 SY
2511-0302800	RECREATIONAL TRAIL, PCC, 8"	80 SY
SECTION NO. 0002		
STRUCTURE ITEMS		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	2 CY
2403-0100010	STRUCT CONC (BRIDGE)	42 CY
2404-7775000	REINFORC STEEL	1,114 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 108 Proposal ID: 78-0801-438

Proposed Contract Period: Late Start Date of 09/15/14 with 30 WORK DAYS

Project(s):

Project No: IMN-080-1(438)6--0E-78

County: POTTAWATTAMIE

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: I-80 Length: 0.21 miles

Location: IN COUNCIL BLUFFS JUST N OF MADISON AVE INTERCHANGE (WB)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2122-5190012	PAVED SHLD, PCC, 12"	1,937 SY
2301-1034120	STD/S-F PCC PAV'T, CL C CL 3I, 12"	3,148 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 109 Proposal ID: 78-6802-157

Proposed Contract Period: Late Start Date of 09/15/14 with 35 WORK DAYS

Project(s):

Project No: IMN-680-2(157)21--0E-78

County: POTTAWATTAMIE

Type of Work: BRIDGE APPROACH REPAIR

Route: I-680 Length: 0.00 miles

Location: CO RD L34 (EB/WB)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0002		
	DESIGN NO. 0814; 146'-8 X VAR. PRETENSIONED PRESTRESSED	
	CONCRETE BEAM BRIDGE	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	2 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	500 LB
SECTION NO. 0003		
	DESIGN NO. 0914; 146'-8 X VAR. PRETENSIONED PRESTRESSED	
	CONCRETE BEAM BRIDGE	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	2 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	500 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 110 Proposal ID: 97-0121-031

Proposed Contract Period: Late Start Date of 09/08/14 with 25 WORK DAYS

Project(s):

Project No: NHSN-012-1(31)--2R-97

County: WOODBURY

Type of Work: PCC SIDEWALK/TRAIL

Route: IOWA 12 Length: 0.00 miles

Location: IN THE CITY OF SIOUX CITY FROM US 20/75 W. TO VIADUCT

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
SIDEWALK ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	19 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 48-C048-068

Proposed Contract Period: Late Start Date of 07/21/14 with 45 WORK DAYS

Project(s):

Project No: STP-S-C048(68)--5E-48

County: IOWA

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: V-77 Length: 6.00 miles

Location: ON V77, FROM WILLIAMSBURG NCL TO US HWY 6, AT S15 T80 R10

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0031750	HMA (1M ESAL) BASE, 3/4"	17,768 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	7,826 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 75-1402-017

Proposed Contract Period: Late Start Date of 04/06/15 with 140 WORK DAYS

Proposal Note:

*** WORK RESTRICTION ***

THE CONTRACTOR SHALL LIMIT REMOVAL OF FOREST COVER TO THOSE
AREAS WHICH ARE ABSOLUTELY NECESSARY FOR THE CONSTRUCTION OF
THE WORK. CUTTING SHALL BE PERFORMED BETWEEN OCTOBER 1ST
AND MARCH 31ST.

Project(s):

Project No: STPN-140-2(17)--2J-75

County: PLYMOUTH

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 140 Length: 15.72 miles

Location: FROM MAIN ST. IN KINGSLEY N. TO IA. 3

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	1,762 CY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	21,110 TON
2303-0033503	HMA (1M ESAL) SURF, 1/2", FRIC L-3	20,784 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	73 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH
SECTION NO. 0002		
DESIGN NO. 1213; REPAIRS TO A 30'-0 X 28' CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	294 LB
SECTION NO. 0003		
DESIGN NO. 1113; REPAIRS TO A 75'-0 X 28' CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	294 LB
SECTION NO. 0004		
DESIGN NO. 1013; REPAIRS TO A 175'-0 X 28'-0 CONTINUOUS I-BEAM BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	294 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 77-1425-624

Proposed Contract Period: Late Start Date of 09/08/14 with 25 WORK DAYS

Project(s):

Project No: STP-U-1425(624)--70-77

County: POLK

Type of Work: HMA RESURFACING

Route: NW 142ND STREET Length: 0.69 miles

Location: IN THE CITY OF CLIVE, NW 142ND ST: FROM HAWTHORN DR TO PINNA
CLE POINTE DR

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0031500	HMA (1M ESAL) BASE, 1/2"	617 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	1,669 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,669 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 79-0806-378

Proposed Contract Period: Specified Start Date of 09/03/14 with 110 WORK DAYS

Proposal Note:

*** WORK RESTRICTION ***

THE CONTRACTOR SHALL NOT WORK FROM MAY 22, 2015 TO SEPTEMBER 7, 2015. GOAL IS TO COMPLETE THE PROJECT BY THE END OF THE 2015 CONSTRUCTION SEASON.

CONTRACTOR CAN WORK AFTER LABOR DAY 2014 TO THE END OF THE CONSTRUCTION SEASON IN 2014, FROM 4-1-2015 TO FRIDAY 5-22-2015 AT NOON, AND THEN FROM SEPTEMBER 8, 2015 TO THE END OF THE 2015 CONSTRUCTION SEASON.

CONTRACTOR MAY ONLY CLOSE A LANE IN ONE DIRECTION. SINGLE LANE CLOSURES WILL NOT BE ALLOWED IN BOTH THE EASTBOUND AND WESTBOUND DIRECTION ON I-80 AT THE SAME TIME DURING THE PROJECT.

Project(s):

Project No: IMX-080-6(378)193--02-79

County: POWESHIEK

Type of Work: HMA PAVED SHOULDER - NEW

Route: I-80 Length: 0.00 miles

Location: FROM 1.1 MILE E. OF US 63 E. TO 0.35 MILE W. OF CO. RD. V38
(OUTSIDE EBL/WBL)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 155 Proposal ID: 82-1301-030

Proposed Contract Period: Late Start Date of 07/21/14 with 60 WORK DAYS

Project(s):

Project No: STPN-130-1(30)--2J-82
County: SCOTT
Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING
Route: IOWA 130 Length: 3.09 miles
Location: FROM CO. RD. Y-52 SE TO 83RD ST. IN DAVENPORT

Project No: STPN-130-1(31)--2J-82
County: SCOTT
Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING
Route: IOWA 130 Length: 0.65 miles
Location: IN THE CITY OF DAVENPORT FROM 83RD ST. SE
TO 76TH ST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
	STPN-130-1(30)--2J-82	
2102-2625000	EMBANKMENT-IN-PLACE	125 CY
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	7,522 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	6,209 TON
SECTION NO. 0002		
ROADWAY ITEMS		
	STPN-130-1(31)--2J-82	
2102-2625000	EMBANKMENT-IN-PLACE	320 CY
2303-0062500	HMA (30M ESAL) INTERMEDIATE, 1/2"	2,697 TON
2303-0063502	HMA (30M ESAL) SURF, 1/2", FRIC L-2	2,802 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	106 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	8 EACH
SECTION NO. 0003		
DESIGN NO. 0213; REPAIRS TO A 300'-0 X 30' CONTINUOUS		
	I-BEAM BRIDGE	STPN-130-1(31)--2J-82
2403-0100000	STRUCT CONC (MISCELLANEOUS)	3 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	577 LB
SECTION NO. 0004		
DESIGN NO. 0113; REPAIRS TO A 300'-0 X 30 CONTINUOUS		
	I-BEAM BRIDGE	STPN-130-1(31)--2J-82
2403-0100000	STRUCT CONC (MISCELLANEOUS)	3 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	577 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 156 Proposal ID: 86-0631-708

Proposed Contract Period: Late Start Date of 09/08/14 with 25 WORK DAYS

Proposal Note:

Project(s):

Project No: MP-063-1(708)139--76-86

County: TAMA

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 63 Length: 0.60 miles

Location: IN THE CITY OF TRAER, FROM THE SCL NORTH TO NCL.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	3,676 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	3,981 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 157 Proposal ID: 92-0782-008

Proposed Contract Period: Late Start Date of 10/06/14 with 20 WORK DAYS

Project(s):

Project No: STPN-078-2(8)--2J-92

County: WASHINGTON

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 78 Length: 0.68 miles

Location: FROM WCL OF BRIGHTON E. TO 400' E. OF IA.1

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	1,118 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	1,100 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	2 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	1 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 00-000S-736

Proposed Contract Period: Late Start Date of 08/11/14 with 50 WORK DAYS

Project(s):

Project No: HSIPX-000-S(736)--3L-00

County: STATEWIDE

Type of Work: MILLED RUMBLE STRIPS

Route: VARIOUS LOCATIONS Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 3

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 00-0003-714

Proposed Contract Period: By individual sites.

Project(s):

Project No: MP-000-3(714)0--76-00

County: STATEWIDE

Type of Work: PCC PATCHING

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS - WEST HALF OF DISTRICT 3.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,369 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	136 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 203 Proposal ID: 00-0003-715

Proposed Contract Period: By individual sites.

Project(s):

Project No: MP-000-3(715)0--76-00

County: STATEWIDE

Type of Work: PCC PATCHING

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS - EAST HALF OF DISTRICT 3.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	904 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	98 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 204 Proposal ID: 01-0254-703

Proposed Contract Period: Late Start Date of 08/25/14 with 45 WORK DAYS

Project(s):

Project No: MP-025-4(703)57--76-01

County: ADAIR

Type of Work: HMA CRACK FILLING

Route: IOWA 25 Length: 16.56 miles

Location: FROM IOWA 92 IN GREENFIELD TO THE E. JCT. OF F-65.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 205 Proposal ID: 04-0025-705

Proposed Contract Period: Late Start Date of 08/25/14 with 40 WORK DAYS

Project(s):

Project No: MP-002-5(705)174--76-04

County: APPANOOSE

Type of Work: HMA PATCHING

Route: IOWA 2 Length: 7.70 miles

Location: FROM 2 MI. EAST OF THE ECL OF CENTERVILLE TO THE JCT.
OF IOWA 202.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 206 Proposal ID: 04-0055-709

Proposed Contract Period: Late Start Date of 09/08/14 with 15 WORK DAYS

Project(s):

Project No: MP-005-5(709)0--76-04

County: APPANOOSE

Type of Work: SLURRY SEAL

Route: IOWA 5 Length: 3.92 miles

Location: FROM THE MISSOURI STATE LINE TO THE WCL OF CINCINNATI.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 207 Proposal ID: 14-0713-704

Proposed Contract Period: Late Start Date of 08/25/14 with 15 WORK DAYS

Proposal Note:

Project(s):

Project No: MP-071-3(704)98--76-14

County: CARROLL

Type of Work: MICROSURFACING

Route: U.S. 71 Length: 3.21 miles

Location: FROM SOUTH OF THE WEST JCT. OF IOWA 141, EAST TO NORTH
OF THE EAST JCT. OF IOWA 141.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 208 Proposal ID: 56-2185-705

Proposed Contract Period: Late Start Date of 10/13/14 with 15 WORK DAYS

Project(s):

Project No: MP-218-5(705)9--76-56

County: LEE

Type of Work: PCC PATCHING

Route: U.S. 218 Length: 7.85 miles

Location: FROM THE NORTH JCT. OF US 61 TO 0.5 MI. NORTH OF
CO. RD. J-62.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
MP-1-5(709)45--76-92		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	604 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)	347 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	32 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 209 Proposal ID: 58-0613-075

Proposed Contract Period: Late Start Date of 08/04/14 with 55 WORK DAYS

Project(s):

Project No: HSIPX-061-3(75)--3L-58

County: LOUISA

Type of Work: HMA PATCHING

Route: U.S. 61 Length: 11.00 miles

Location: FROM THE DES MOINES CO. LINE N. TO WAPELLO'S SCL AND
CONTINUING FROM WAPELLO'S NCL TO 2 MILES S. OF THE IA 92 JCT

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 210 Proposal ID: NOTUSED; 14/06

Project(s):

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 211 Proposal ID: 77-0691-713

Proposed Contract Period: Late Start Date of 09/22/14 with 20 WORK DAYS

Proposal Note:

Project(s):

Project No: MP-069-1(713)81--76-77

County: POLK

Type of Work: PCC PATCHING

Route: U.S. 69

Length: 4.70 miles

Location: IN THE CITY OF DES MOINES FROM ARMY POST RD. NORTH TO I-235.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	965 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	75 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 212 Proposal ID: 78-0064-712

Proposed Contract Period: Late Start Date of 08/18/14 with 50 WORK DAYS

Proposal Note:

Project(s):

Project No: MP-006-4(712)3--76-78

County: POTTAWATTAMIE

Type of Work: PCC PATCHING

Route: U.S. 6 Length: 3.50 miles

Location: IN THE CITY OF COUNCIL BLUFFS, FROM JUST WEST OF 8TH STREET,
EAST TO RAILROAD AVENUE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	3,099 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)	186 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	380 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 213 Proposal ID: 80-1694-704

Proposed Contract Period: Approx Start Date of 08/11/14 with 25 WORK DAYS

Proposal Note:

Project(s):

Project No: MP-169-4(704)0--76-80

County: RINGGOLD

Type of Work: MICROSURFACING

Route: U.S. 169

Length: 15.15 miles

Location: FROM THE MISSOURI STATE LINE TO THE WEST JCT. OF IOWA 2.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 214 Proposal ID: 83-0444-708

Proposed Contract Period: Late Start Date of 09/22/14 with 20 WORK DAYS

Proposal Note:

Project(s):

Project No: MP-044-4(708)21--76-83

County: SHELBY

Type of Work: PCC PATCHING

Route: IOWA 44 Length: 1.59 miles

Location: IN THE CITY OF HARLAN, FROM U.S. 59 EAST TO THE ECL.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,627 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)	133 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	124 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 215 Proposal ID: 87-1484-710

Proposed Contract Period: Late Start Date of 07/21/14 with 85 WORK DAYS

Proposal Note:

Project(s):

Project No: MP-148-4(703)31--76-02

County: ADAMS

Type of Work: SLURRY SEAL

Route: IOWA 148 Length: 18.85 miles

Location: FROM 15TH ST. IN CORNING, NORTH TO IOWA 92.

Project No: MP-141-4(706)133--76-25

County: DALLAS

Type of Work: SLURRY SEAL

Route: IOWA 141 Length: 12.00 miles

Location: FROM JUST EAST OF U.S. 169 TO JUST NORTH OF GRANGER.
(EASTBOUND LANES)

Project No: MP-148-4(710)15--76-87

County: TAYLOR

Type of Work: SLURRY SEAL

Route: IOWA 148 Length: 15.56 miles

Location: FROM GRAVITY TO SCL OF CORNING.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
ADAMS COUNTY MP-148-4(703)31--76-02		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	373 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	20 EACH
SECTION NO. 0003		
ROADWAY ITEMS		
TAYLOR COUNTY MP-148-4(710)15--76-87		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	304 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(>=50 FT)	133 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	10 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 216 Proposal ID: 97-0293-711

Proposed Contract Period: Late Start Date of 09/29/14 with 15 WORK DAYS

Proposal Note:

Project(s):

Project No: MPIN-029-3(711)146--0N-97

County: WOODBURY

Type of Work: PCC PATCHING

Route: I-29 Length: 3.38 miles

Location: FROM JUST SOUTH OF FLOYD BLVD. INTERCHANGE TO JUST NORTH OF
HAMILTON BLVD. INTERCHANGE. (NB & SB)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	126 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	428 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	43 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 217 Proposal ID: 97-0313-709

Proposed Contract Period: Late Start Date of 08/18/14 with 15 WORK DAYS

Proposal Note:

Project(s):

Project No: MP-183-3(705)44--76-43

County: HARRISON

Type of Work: SLURRY SEAL

Route: IOWA 183 Length: 7.10 miles

Location: FROM NCL OF PISGAH, NORTHEASTERLY TO OAK STREET
IN MOORHEAD.

Project No: MP-031-3(709)0--76-97

County: WOODBURY

Type of Work: SLURRY SEAL

Route: IOWA 31 Length: 4.50 miles

Location: FROM THE JCT. OF IOWA 141 IN SMITHLAND, NORTH TO DRIFTWOOD
STREET IN CORRECTIONVILLE. (VARIOUS LOCATIONS.)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 03-0762-052

Proposed Contract Period: Late Start Date of 08/04/14 with 60 WORK DAYS
Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.
Completion Date of 09/30/14

Proposal Note:

*** SITE 01, WORK RESTRICTION FOR ER-076-2(52)--28-03 ***
THE FOLLOWING DESCRIBES THE SEPTEMBER 30, 2014 COMPLETION
DATE RESTRICTION BY THE DNR. ALL CONSTRUCTION ACTIVITIES
WILL NEED TO BE COMPLETED BY SEPTEMBER 30, 2014 TO MINIMIZE
IMPACT ON SPAWNING TROUT.

Project(s):

Project No: ER-076-2(51)--28-03
County: ALLAMAKEE
Type of Work: SLIDE REPAIR
Route: IOWA 76 Length: 0.00 miles
Location: 1 MILE S. OF MINERAL CREEK BRIDGE

Project No: ER-076-2(52)--28-03
County: ALLAMAKEE
Type of Work: SLIDE REPAIR
Route: IOWA 76 Length: 0.00 miles
Location: ALONG WATERLOO CREEK 0.9 MILE N. OF CO. RD. A-26
(2 LOCATIONS)

Project No: ER-013-3(44)--28-22
County: CLAYTON
Type of Work: REVETMENT
Route: IOWA 13 Length: 0.00 miles
Location: OVER ROBERTS CREEK 0.6 MILE S. OF IA. 128

Project No: ER-013-3(45)--28-22
County: CLAYTON
Type of Work: REVETMENT
Route: IOWA 13 Length: 0.00 miles
Location: IA. 13 APPROX. 7 MILES S. OF ELKADER(2 LOCATIONS)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0003		
ROADWAY ITEMS		
ER-076-2(52)--28-03		
2102-2625000	EMBANKMENT-IN-PLACE	770 CY
SECTION NO. 0008		
DESIGN NO. 0314; SCOUR COUNTERMEASURE AT BOX CULVERT OUTLET		
ER-013-3(45)--28-22		
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	33 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 18-0032-068

Proposed Contract Period: Late Start Date of 08/18/14 with 20 WORK DAYS

Project(s):

Project No: ER-003-2(68)--28-18

County: CHEROKEE

Type of Work: REVETMENT

Route: IOWA 3 Length: 0.00 miles

Location: OVER MAPLE RIVER 0.5 MILE W. OF IA. 7

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 28-C028-085

Proposed Contract Period: Late Start Date of 09/15/14 with 30 WORK DAYS

Project(s):

Project No: STP-S-C028(85)--5E-28

County: DELAWARE

Type of Work: LONGITUDINAL SUBDRAINS

Route: C64 Length: 7.10 miles

Location: C-64: FROM GREELEY TO PETERSBURG

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 304 Proposal ID: 38-C038-092

Proposed Contract Period: Late Start Date of 09/29/14 with 10 WORK DAYS

Project(s):

Project No: ER-C038(92)--58-38

County: GRUNDY

Type of Work: REVETMENT

Route: D17 Length: 0.02 miles

Location: D-17: FROM T-19 0.2 MI EAST TO NORTH FORK OF BEAVER CREEK

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 305 Proposal ID: 47-0202-122

Proposed Contract Period: Late Start Date of 08/11/14 with 25 WORK DAYS

Project(s):

Project No: ER-020-2(122)--28-47

County: IDA

Type of Work: REVETMENT

Route: U.S. 20 Length: 0.00 miles

Location: MAPLE RIVER 4.1 MILES E OF US 59

Project No: ER-059-6(42)--28-47

County: IDA

Type of Work: REVETMENT

Route: U.S. 59 Length: 0.00 miles

Location: OVER THE MAPLE RIVER IN IDA GROVE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 306 Proposal ID: 57-0131-057

Proposed Contract Period: Approx Start Date of 10/06/14 with 25 WORK DAYS

Project(s):

Project No: ER-013-1(57)--28-57

County: LINN

Type of Work: REVETMENT

Route: IOWA 13 Length: 0.00 miles

Location: OVER HEATON'S CREEK 2.6 MILES S. OF CO. RD. D62

Project No: ER-013-1(58)--28-57

County: LINN

Type of Work: REVETMENT

Route: IOWA 13 Length: 0.00 miles

Location: OVER NUGENTS CREEK (NORTH CROSSING)
0.8 MILE N. OF N. JCT CO. RD. D62

Project No: ER-013-1(61)--28-57

County: LINN

Type of Work: REVETMENT

Route: IOWA 13 Length: 0.00 miles

Location: OVER NUGENTS CREEK (SOUTH CROSSING)
1.1 MILES N. OF S. JCT CO. RD. D62

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 307 Proposal ID: 77-3163-011

Proposed Contract Period: Late Start Date of 09/15/14 with 35 WORK DAYS

Project(s):

Project No: BRFN-316-3(11)--39-77

County: POLK

Type of Work: REVETMENT

Route: IOWA 316 Length: 0.00 miles

Location: OVER DES MOINES RIVER 3.9 MILES N. OF IA. 5

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 308 Proposal ID: 91-1105-607

Proposed Contract Period: Late Start Date of 09/08/14 with 160 WORK DAYS

Project(s):

Project No: EDP-1105(607)--7Y-91

County: WARREN

Type of Work: GRADING

Route: SUMMERSET TRAIL Length: 3.30 miles

Location: CONNECTION OF SUMMERSET TRAIL IN THE CITY OF CARLISLE, SCOTC
H RIDGE NATURE TRAIL, FROM SUMMERSET TRAIL IN CARLISLE TO SC

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	7,010 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	78,030 CY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	232 SY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	60 CY
2403-0100010	STRUCT CONC (BRIDGE)	135 CY
2404-7775000	REINFORC STEEL	5,037 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	12,255 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 309 Proposal ID: 97-0296-257

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE STAGES 1 THROUGH 5 AS SHOWN ON PLAN SHEET J.1.
Completion Date of 04/30/15

Site 02: TO COMPLETE STAGE 6 AS SHOWN ON PLAN SHEET J.1.
Completion Date of 06/30/15

Proposal Note:

FOLLOWING IS THE ANTICIPATED CONSTRUCTION TIMELINE REFER TO
THE J SHEETS IN THE PLANS FOR FURTHER DETAILS:

STAGE 1:

JULY 2014- SEPTEMBER 2014; MH BENCHES AND SIPHON DOWNSTREAM
PORTION

STAGE 2:

JULY 2014 - SEPTEMBER 2014; SIPHON DUAL BARREL SYSTEM = WORK
WILL BE PERFORMED CONCURRENTLY WITH STAGE 1.
SEPTEMBER 2014 - FEBRUARY 2015; SIPHON STRUCTURES

STAGE 3:

SEPTEMBER 2014; FLOYD BLVD.

STAGE 4:

SEPTEMBER 2014 - OCTOBER 2014; DACE AVE.

STAGE 5:

FEBRUARY 2015; FLOYD RIVER LIFT STATION CONNECTION AND STOP
LOGS

SUBSTANTIAL COMPLETION - APRIL 30, 2015 - SANITARY
SEWER/SIPHON IN OPERATION. REFER TO SITE NUMBER 01 ABOVE.

STAGE 6:

FEBRUARY 2015 - JUNE 2015; REMOVALS/ABANDONMENT/SURFACE
RESTORATION

FINAL COMPLETION - JUNE 30, 2015 - SEEDING COMPLETE. REFER
TO
SITE NUMBER 02 ABOVE.

Project(s):

Project No: IM-NHS-029-6(257)147--03-97

County: WOODBURY

Type of Work: SANITARY SEWER

Route: I-29 Length: 0.00 miles

Location: I-29 INTERCEPTOR FLOYD RIVER SIPHON &
CONNECTION TO FLOYD LIFT STATION

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0001

SANITARY SEWER ITEMS

2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,500 CY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,213 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 351 Proposal ID: 00-000S-672

Proposed Contract Period: Late Start Date of 07/21/14 with 65 WORK DAYS

Project(s):

Project No: NHSN-000-S(672)--2R-00

County: STATEWIDE

Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 3

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 00-000S-673

Proposed Contract Period: Late Start Date of 07/21/14 with 65 WORK DAYS

Project(s):

Project No: NHSN-000-S(673)--2R-00

County: STATEWIDE

Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 4

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 353 Proposal ID: 00-000S-729

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE DIVISION 1 SIGNS

Late Start Date of 10/06/14 with 25 WORK DAYS

Site 02: TO COMPLETE DIVISION 2 SIGNS

Late Start Date of 07/28/14 with 5 WORK DAYS

Project(s):

Project No: NHSN-000-S(729)--2R-00

County: STATEWIDE

Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS STATEWIDE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 354 Proposal ID: 57-1187-772

Proposed Contract Period: Late Start Date of 08/11/14 with 55 WORK DAYS
Site 01: TO COMPLETE PHASE 1 AND 2 AS SHOWN ON J.01-J.03
Completion Date of 09/05/14

Proposal Note:

SITE 01

WORK INCLUDES GRADING AND STORM SEWER IMPROVEMENTS SOUTH OF
42ND STREET N.E. WORK ALSO INCLUDES NB I-380 OFF RAMP RIGHT
TURN LANE PAVEMENT WIDENING. REFER TO PHASES 1-2 SHOWN ON
PLAN SHEETS J.01-J.03. THE RIGHT TURN LANE PAVEMENT SHALL
BE OPEN TO TRAFFIC BY THE COMPLETION DATE.

Project(s):

Project No: STP-U-1187(772)--70-57

County: LINN

Type of Work: TRAFFIC SIGNALS

Route: 42ND STREET Length: 0.08 miles

Location: IN THE CITY OF CEDAR RAPIDS, 42ND STREET NE: FROM I-380 NB O
N RAMP TO EAST OF THE CEDAR RIVER TRAIL

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,383 CY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	774 SY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	117 SY
2303-0041500	HMA (3M ESAL) BASE, 1/2"	53 TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	15 TON
2511-0301500	RECREATIONAL TRAIL, HMA, 5"	231 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 355 Proposal ID: 57-3806-262

Proposed Contract Period: Late Start Date of 08/04/14 with 70 WORK DAYS

Project(s):

Project No: IMN-380-6(262)20--0E-57

County: LINN

Type of Work: LIGHTING

Route: I-380 Length: 0.00 miles

Location: I-380 IN CEDAR RAPIDS AT VARIOUS LOCATIONS

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 356 Proposal ID: 77-1945-805

Proposed Contract Period: Approx Start Date of 08/18/14 with 40 WORK DAYS

Project(s):

Project No: STP-A-1945(805)--86-77

County: POLK

Type of Work: ITS EQUIPMENT

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: IN THE CITY OF DES MOINES, DOWNTOWN DES MOINES: UPGRADE 10
EXISTING CCTV AND INSTALL 4 CMS WAYFINDING SIGNS

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 401 Proposal ID: 78-0801-444

Proposed Contract Period: Approx Start Date of 07/21/14 with 30 WORK DAYS

Proposal Note:

Project(s):

Project No: IMN-080-1(444)3--0E-78

County: POTTAWATTAMIE

Type of Work: SALVAGE AND REMOVAL

Route: I-80 Length: 0.00 miles

Location: IN THE CITY OF COUNCIL BLUFFS AT 1124 S. 8TH ST. PARCEL 386
& 1205 S. 8TH ST. PARCEL 386A

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 402 Proposal ID: 82-0741-252

Proposed Contract Period: Approx Start Date of 08/25/14 with 20 WORK DAYS

Proposal Note:

Project(s):

Project No: IMN-074-1(252)5--0E-82

County: SCOTT

Type of Work: SALVAGE AND REMOVAL

Route: I-74

Length: 0.00 miles

Location: IN THE CITY OF BETTENDORF AT 411 14TH ST.
PARCEL NO. 355

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 403 Proposal ID: 91-0925-057

Proposed Contract Period: Approx Start Date of 08/25/14 with 15 WORK DAYS

Proposal Note:

Project(s):

Project No: NHSN-092-5(57)--2R-91

County: WARREN

Type of Work: SALVAGE AND REMOVAL

Route: IOWA 92

Length: 0.00 miles

Location: 8535 HWY 92 INDIANOLA-PARCEL NO. 14

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 07-2187-219

Proposed Contract Period: Late Start Date of 08/11/14 with 50 WORK DAYS

Project(s):

Project No: STPN-218-7(219)--2J-07

County: BLACK HAWK

Type of Work: WETLAND MITIGATION

Route: U.S. 218 Length: 0.00 miles

Location: WOLF CREEK WETLAND MITIGATION SITE
ONE MILE NE OF LA PORTE CITY

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: June 17, 2014 10:00 A.M.

Proposed Bid Order: 981 Proposal ID: 97-0293-710

Proposed Contract Period: Late Start Date of 08/18/14 with 20 WORK DAYS

Proposal Note:

Project(s):

Project No: MPIN-029-3(710)139--0N-97

County: WOODBURY

Type of Work: FENCING

Route: I-29 Length: 2.02 miles

Location: FROM SOUTH OF THE SERGEANT BLUFF REST AREA TO SOUTH OF THE
SERGEANT BLUFF INTERCHANGE. (SOUTHBOUND)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

