

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: June 17, 2014
Date of Addendum: June 12, 2014

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
308	91-1105-607	GRADING	WARREN	EDP-1105(607)--7Y-91	17JUN308.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Add the following notes to the plans:

SHEET NUMBER C.05 - Estimate Reference Information

ITEM CODE: 68 2599-9999001 WETLAND MICROGRADING

A. PRIOR TO TOPSOIL PLACEMENT, GRADE BOTTOM OF WETLAND AREAS TO PROVIDE AN IRREGULAR SURFACE CONSISTING OF MOUNDED/RIDGED AND DISHED/RUTTED AREAS SPACED SO THAT THERE IS VARIATION OF PLUS SIX (+6) INCHES TO MINUS SIX (-6) INCHES IN SURFACE ELEVATION OVER A HORIZONTAL DISTANCE OF FIVE (5) FEET, OR AS DIRECTED BY THE ENGINEER.

UTILIZE A SMALL TRACK HOE, TRACK EXCAVATOR OR SIMILAR EQUIPMENT TO MINIMIZE SOIL COMPACTION.

SUBSEQUENT TOPSOIL SPREADING IN MICRO-GRADED AREAS SHALL BE PLACED IN A MANNER AS TO NOT DISRUPT SUB-GRADE MICRO-GRADING.

B. MEASUREMENT FOR THE WETLAND MICRO-GRADING BID ITEM WILL BE PER THE ACRE OF GRADED AREA. THE UNIT PRICE SHALL BE PAID PER THE ACRE OF GRADED AREA, AND SHALL BE CONSIDERED COMPENSATION FOR ALL LABOR, EQUIPMENT, AND MATERIALS REQUIRED TO COMPLETE THE WETLAND MICRO-GRADING BID ITEM.

ITEM CODE: 69 2599-9999005 APRON GUARD (RF-26)

A. APRON GUARD REQUIRED ON ALL CONCRETE APRONS.

- B. REFER TO STANDARD ROAD PLAN RF-26 FOR DETAILS.
- C. APRON GUARDS WILL BE COUNTED BY THE ENGINEER. THIS SHALL BE FULL COMPENSATION FOR FURNISHING ALL TOOLS, EQUIPMENT, LABOR AND MATERIAL NECESSARY FOR INSTALLING APRON GUARD AS SHOWN IN THE DETAIL.