

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 06-1506-500

Proposed Contract Period: Late Start Date of 09/14/15 with 15 WORK DAYS

Project(s):

Project No: MB-150-6(500)2--77-06

County: BENTON

Type of Work: DECK JOINT REPAIR

Route: IOWA 150 Length: 0.00 miles

Location: IN THE CITY OF VINTON OVER THE CEDAR RIVER 1 MILE S. OF  
CO. RD. E16

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0215; 807'-0 X 32'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	0 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 07-3807-120

Proposed Contract Period: Late Start Date of 06/01/15 with 20 WORK DAYS

Proposal Note:

\*\*\* SITE NUMBER 01 - INCENTIVE/DISINCENTIVE \*\*\*  
SECTION 1111 OF THE STANDARD SPECIFICATIONS FOR  
INCENTIVE/DISINCENTIVE (I/D) FOR EARLY COMPLETION SHALL  
APPLY TO THIS PROJECT WITH THE FOLLOWING CONDITIONS:  
SITE NUMBER 01: 120 CLOSURE DAYS/CALENDAR DAYS  
I/D RATE \$10,000.00 PER DAY  
MAXIMUM INCENTIVE: NONE  
THIS SITE REQUIRES THE COMPLETION OF ALL WORK THAT REQUIRES  
A LANE/SHOULDER/RAMP CLOSURE. THE SITE WILL BE CONSIDERED  
COMPLETE WHEN TRAFFIC IS RESTORED WITH NO FURTHER LANE  
CLOSURES. WINTER WEATHER WILL NOT BE CONSIDERED AS  
JUSTIFICATION FOR ADDITIONAL CLOSURE DAYS OR TO SUSPEND THE  
COUNT OF CLOSURE DAYS.

\*\*\* NO EXCUSE ROAD OPENING BONUS FOR CONTRACT \*\*\*  
THE CONTRACTOR WILL BE PAID THE PREDETERMINED LUMP SUM  
AMOUNT SHOWN IN THE PROPOSAL SCHEDULE OF PRICES FOR THE BID  
ITEM 'NO EXCUSE ROAD OPENING BONUS' FOR COMPLETING  
CONSTRUCTION SO THAT I-380 IS OPEN TO TRAFFIC ON OR BEFORE  
THE CALENDAR DATE SHOWN. COMPLIANCE REQUIRES THAT THE  
CONTRACTOR MUST HAVE ALL OF I-380 OPEN TO TRAFFIC WITH NO  
FURTHER LANE CLOSURES. ANY OTHER DELAYS DUE TO WEATHER,  
CHANGE ORDERS, OVERRUNS OF QUANTITIES, UTILITY DELAYS, OR  
ANY OTHER DELAYS WILL NOT BE CONSIDERED AS JUSTIFICATION TO  
MODIFY THE CALENDAR DATE.

Project(s):

Project No: IMN-380-7(120)71--0E-07  
County: BLACK HAWK  
Type of Work: DECK JOINT REPAIR  
Route: I-380 Length: 0.00 miles  
Location: I-380 IN THE CITY OF WATERLOO OVER CEDAR RIVER/STREET/R.R.  
APPROX. 0.4 MILES S. OF JCT. US 20

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0114; REPAIRS TO A 1532'-11 X VAR. CONTINUOUS WELDED PLATE GIRDER BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	57 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	4,900 LB
SECTION NO. 0002		
	DESIGN NO. 0214; REPAIRS TO A 1532'-11 X VAR. CONTINUOUS WELDED PLATE GIRDER BRIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	34 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	2,989 LB
SECTION NO. 0003		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

DESIGN NO. 0314; REPAIRS TO A 1521'-4 X VAR. CONTINUOUS  
WELDED PLATE GIRDER BRIDGE

2403-0100010	STRUCT CONC (BRIDGE)	69 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	5,615 LB

SECTION NO. 0004

DESIGN NO. 0514; REPAIRS TO A 1521'-4 X VAR. CONTINUOUS  
WELDED PLATE GIRDER BRIDGE

2403-0100010	STRUCT CONC (BRIDGE)	17 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,618 LB

SECTION NO. 0005

ROADWAY ITEMS

2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	1,715 CY
--------------	---	----------

SECTION NO. 0006

CONTRACT ITEMS

2528-5160000	NO EXCUSE ROAD OPENING BONUS, _____	Lump Sum	LUMP
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	30	CDAY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 18-0313-008

Proposed Contract Period: Late Start Date of 07/20/15 with 65 WORK DAYS

Project(s):

Project No: BRFN-031-3(8)--39-18

County: CHEROKEE

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: IOWA 31 Length: 0.00 miles

Location: FOUR MILE CREEK 1.1 MILES S OF CO RD L51

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
DESIGN NO. 0115; TWIN 12' X 12' X 107'-0 REINFORCED		
CONCRETE BOX CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	553 CY
2404-7775000	REINFORC STEEL	82,363 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	2,561 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,369 CY
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	208 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 20-C020-094-A

Proposed Contract Period: Late Start Date of 07/06/15 with 80 WORK DAYS

Project(s):

Project No: STP-S-C020(94)--5E-20

County: CLARKE

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: H45 Length: 0.00 miles

Location: APPROX. 3/4 MI. E. OF HOPEVILLE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 120'-0 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE		
BEAM BRIDGE		
2102-2625000	EMBANKMENT-IN-PLACE	567 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	5 CY
2403-0100010	STRUCT CONC (BRIDGE)	198 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	48,193 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 24-C024-103

Proposed Contract Period: Late Start Date of 08/17/15 with 45 WORK DAYS

Project(s):

Project No: BROS-C024(103)--5F-24

County: CRAWFORD

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: E35 Length: 0.00 miles

Location: NEAR 3546 L AVE TO

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A TWIN 12' X 10' X 72' REINFORCED CONCRETE BOX		
CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,851 CY
2403-0100020	STRUCT CONC (RCB CULV)	336 CY
2404-7775000	REINFORC STEEL	50,890 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 24-C024-105

Proposed Contract Period: Late Start Date of 06/01/15 with 60 WORK DAYS

Project(s):

Project No: BRS-C024(105)--60-24

County: CRAWFORD

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 140TH ST Length: 0.00 miles

Location: L51 NEAR 2330 140TH SST TO

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A TWIN 12' X 12' X 50' REINFORCED CONCRETE BOX		
CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	948 CY
2403-0100020	STRUCT CONC (RCB CULV)	342 CY
2404-7775000	REINFORC STEEL	49,674 LB
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)	317 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 29-0612-089

Proposed Contract Period: Late Start Date of 06/15/15 with 105 WORK DAYS

Project(s):

Project No: BRFN-061-2(89)--39-29

County: DES MOINES

Type of Work: RECONSTRUCTION - BRIDGE WIDENING

Route: U.S. 61 Length: 0.00 miles

Location: US 61 OVER SPRING CREEK 3.7 MILES N. OF LEE CO. LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0112; REPAIRS TO A 150'-0 X 40'-0 STEEL BEAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	217 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	63,389 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	1,982 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,320 CY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	1,657 SY
SECTION NO. 0004		
ALTERNATE 'AA' OPTION 2: PCC SHOULDER		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2122-5190007	PAVED SHLD, PCC, 7"	1,258 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 32-0046-028

Proposed Contract Period: Specified Start Date of 06/15/15 with 5 WORK DAYS  
Site 02: SEE SITE NUMBER 02 DESCRIPTION BELOW.  
No Start Date Specified with 0 WORK DAYS  
Site 03: A + B RAILROAD FLAGGERS  
Cost Plus Time Site (A + B). Road User Cost per Day: \$ 1,300.00

Proposal Note:

\*\*\*PRE-BID MEETING\*\*\*

A PRE-BID MEETING WILL BE HELD ON THURSDAY DECEMBER 4, 2014  
AT 10:30 AM. THE LOCATION WILL BE THE WEST MATERIALS  
CONFERENCE ROOM IN THE CENTRAL COMPLEX OF THE DOT IN AMES.

\*\*\* SITE NUMBER CONTRACT \*\*\*

WORKING DAYS ARE FOR ITEMS THAT DO NOT REQUIRE THE DETOUR.  
THIS WORK INCLUDES EROSION CONTROL AND SEEDING.

\*\*\* SITE NUMBER 01 - INCENTIVE/DISINCENTIVE \*\*\*

THIS SITE IS FOR THE DETOUR TO REMOVE BRIDGES, CONSTRUCT THE  
CULVERTS AND REBUILD THE ROAD.

AS WE DISCUSSED, THE CONTRACTOR CANNOT START BEFORE JUNE 15  
(THIRD MONDAY IN JUNE). (THE DETOUR USED FOR THE PROJECT  
CAN NOT START UNTIL JUNE 15 SINCE THE ROUTE IS EMBARGOED BY  
THE COUNTY EACH SPRING. THE DETOUR AGREEMENT ALLOWS FOR THE  
DETOUR TO START ON JUNE 15, 2015.) IN ADDITION, THE  
DISTRICT AND THE COUNTY HAS CONCERN ON KEEPING TRAFFIC ON  
THE DETOUR MORE THAN REQUIRED. BECAUSE OF THIS THE DISTRICT  
IS REQUESTING THE USE OF CALENDAR DAYS AND AN ACCELERATED  
WORK SCHEDULE (ALREADY MENTIONED. THE LIQUIDATED DAMAGES  
WORKSHEET IS ATTACHED. IT INDICATES A VALUE OF LD/CLOSURE  
DAYS OF \$10,136. THE DISTRICT IS REQUESTING A VALUE OF  
\$5,000 PER CLOSURE DAY. THE DISTRICT ESTIMATED 56 CLOSURE  
DAYS. (PLEASE PROVIDE AN INDEPENDENT CHECK, NOTE WE ASSUMED  
A SEPARATE CREW FOR EACH BRIDGE AND ADDED A WEEK FOR WEATHER  
DELAYS.)

\*\*\* SITE NUMBER 02 \*\*\*

THIS SITE IS FOR CLOSURE OF THE RR TRACKS FOR BOTH PROJECTS.  
A SINGLE CLOSURE OF 90 HOURS WILL BE ALLOWED. THE START OF  
THE 90 HOURS WILL BEGIN WHEN THE UP RR COMPLETES THE CUTS OF  
THE RR TRACKS. BOTH RR BRIDGES MUST BE REMOVED, THE NEW  
CULVERT INSTALLED, AND THE BACKFILL AND SUBBALLAST PLACED  
FOR THE WORK TO BE COMPLETED. THE LIQUIDATED DAMAGES FOR  
THIS WORK WILL BE ASSESSED AT \$1,600.00/HOUR WHICH EQUATES  
TO THE \$38,400.00 DAILY LIQUIDATED DAMAGES SHOWN ABOVE. THE  
CLOSURE MUST

Project(s):

Project No: BRFN-004-6(28)--39-32  
County: EMMET

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX  
Route: IOWA 4 Length: 0.00 miles  
Location: OVER DD # 94, 2.5 MILES N. OF CO. RD. B-14

Project No: BRFN-004-6(29)--39-32  
County: EMMET  
Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX  
Route: IOWA 4 Length: 0.00 miles  
Location: OVER DD #2, 1.6 MILES N. OF CO. RD. B-14

Item No.	Item Description	Quantity/Unit
SECTION NO. 0002		
ROADWAY ITEMS		
BRFN-004-6(28)--39-32		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,153 CY
2301-1033095	STD/S-F PCC PAV'T, CL C CL 3, 9.5"	591 SY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	600 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	272 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	47 EACH
SECTION NO. 0003		
DESIGN NO. 0215; DUAL SINGLE 12X12 PRECAST RCB		
WITH CAST IN PLACE FLUME AND BASIN BRFN-004-6(29)--39-32		
2403-0100020	STRUCT CONC (RCB CULV)	233 CY
2404-7775000	REINFORC STEEL	41,593 LB
SECTION NO. 0004		
ROADWAY ITEMS		
BRFN-004-6(29)--39-32		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,049 CY
2301-1033095	STD/S-F PCC PAV'T, CL C CL 3, 9.5"	544 SY
SECTION NO. 0005		
INCENTIVE/DISINCENTIVE ITEM FOR CONTRACT		
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	1 CDAY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 40-0173-034

Proposed Contract Period: Late Start Date of 08/03/15 with 35 WORK DAYS

Project(s):

Project No: BRFN-017-3(34)--39-40

County: HAMILTON

Type of Work: BRIDGE DECK OVERLAY

Route: IOWA 17 Length: 0.00 miles

Location: IA 17 AT E. JCT. US 20

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0115; 264'-6 X 44'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2413-0698074	DECK REPAIR, CL A	104 SY
SECTION NO. 0002		
DESIGN NO. 0115; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2413-0698066	DECK OVERLAY (CL O PCC)	1,307 SY
SECTION NO. 0003		
DESIGN NO. 0115; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	1,307 SY
SECTION NO. 0004		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	400 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 40-3875-601

Proposed Contract Period: Late Start Date of 07/27/15 with 55 WORK DAYS

Project(s):

Project No: BRS-3875(601)--60-40

County: HAMILTON

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: D41 Length: 0.06 miles

Location: COUNTY ROAD D41 OVER UNNAMED CREEK;SECTION 2, T87N, R25W

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	273 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,176 CY
2403-0100020	STRUCT CONC (RCB CULV)	338 CY
2404-7775000	REINFORC STEEL	45,778 LB
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	366 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 43-0301-144

Proposed Contract Period: Late Start Date of 06/01/15 with 80 WORK DAYS

Project(s):

Project No: NHSN-030-1(144)--2R-43  
 County: HARRISON  
 Type of Work: BRIDGE DECK OVERLAY  
 Route: U.S. 30 Length: 0.00 miles  
 Location: OVER MISSOURI RIVER E. OF BLAIR NEBRASKA

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0115; REPAIRS TO A 1977'-6 X 40'-0 STEEL GIRDER AND PPC BEAM BRIDGE		
2102-2625000	EMBANKMENT-IN-PLACE	13 CY
2413-0698074	DECK REPAIR, CL A	440 SY
SECTION NO. 0002		
DESIGN NO. 0115; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2413-0698066	DECK OVERLAY (CL O PCC)	8,755 SY
SECTION NO. 0003		
DESIGN NO. 0115; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	8,755 SY
SECTION NO. 0004		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	39 CY
2122-5190012	PAVED SHLD, PCC, 12"	91 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 44-C044-075

Proposed Contract Period: Late Start Date of 07/13/15 with 75 WORK DAYS

Project(s):

Project No: BROS-C044(75)--5F-44

County: HENRY

Type of Work: BRIDGE AND APPROACHES - CCS

Route: X13 Length: 0.25 miles

Location: ON X13 (MARSH AVENUE), OVER SOUTH BIG CREEK, S31 T72 R05

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A 120'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE		
3 SPAN		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,081 CY
2403-0100010	STRUCT CONC (BRIDGE)	293 CY
2404-7775000	REINFORC STEEL	3,162 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	66,849 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 46-0032-708

Proposed Contract Period: Late Start Date of 11/02/15 with 10 WORK DAYS

Project(s):

Project No: MP-003-2(708)137--76-46

County: HUMBOLDT

Type of Work: RCB CULVERT - REPAIR

Route: IOWA 3 Length: 0.00 miles

Location: 8.1 MI EAST OF U.S. 169

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	40 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 48-0066-045

Proposed Contract Period: Late Start Date of 05/25/15 with 85 WORK DAYS

Project(s):

Project No: BRFN-006-6(45)--39-48

County: IOWA

Type of Work: BRIDGE DECK OVERLAY

Route: U.S. 6 Length: 0.00 miles

Location: OVER IAIS R.R. 1.6 MILES E. OF IA. 21

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0115; REPAIRS TO A 328'-0 X 28'-0 CONTINUOUS I-BEAM BRIDGE		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	26 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	3,643 LB
2413-0698074	DECK REPAIR, CL A	153 SY
SECTION NO. 0002		
DESIGN NO. 0115; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2413-0698066	DECK OVERLAY (CL O PCC)	1,011 SY
SECTION NO. 0003		
DESIGN NO. 0115; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	1,011 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 015 Proposal ID: 57-1006-501

Proposed Contract Period: Late Start Date of 08/24/15 with 50 WORK DAYS

Project(s):

Project No: MB-100-6(501)3--77-57

County: LINN

Type of Work: BRIDGE REHABILITATION

Route: IOWA 100 Length: 0.00 miles

Location: IN THE CITY OF CEDAR RAPIDS OVER I-380 AND R.R. 2.7 MILES  
W. OF US 151

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 2015; 708'-0 X 84'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	38 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,366 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 016 Proposal ID: 71-C071-076

Proposed Contract Period: Late Start Date of 07/06/15 with 65 WORK DAYS

Project(s):

Project No: BROS-C071(76)--5F-71

County: OBRIEN

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: L40 Length: 0.10 miles

Location: L40: NW COR SEC 7 S 0.75 MI

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A TWIN 12' X 8' X 46' REINFORCED CONCRETE BOX CULVERT		
2102-2625000	EMBANKMENT-IN-PLACE	444 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	520 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	500 SY
2403-0100020	STRUCT CONC (RCB CULV)	205 CY
2404-7775000	REINFORC STEEL	33,491 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 017 Proposal ID: 77-1631-087

Proposed Contract Period: Late Start Date of 06/01/15 with 40 WORK DAYS

Project(s):

Project No: BRFN-163-1(87)--39-77  
 County: POLK  
 Type of Work: BRIDGE DECK OVERLAY  
 Route: IOWA 163 Length: 0.00 miles  
 Location: IA 163 OVER FOUR MILE CREEK  
 1.7 MILES W. OF US 65

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0315; REPAIRS TO A 253'-0 X 56'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	2 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	171 LB
2413-0698074	DECK REPAIR, CL A	159 SY
SECTION NO. 0002		
	DESIGN NO. 0315; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN	
2413-0698066	DECK OVERLAY (CL O PCC)	1,593 SY
SECTION NO. 0003		
	DESIGN NO. 0315; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	1,593 SY
SECTION NO. 0004		
	ROADWAY ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	150 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 018 Proposal ID: 77-1945-811

Proposed Contract Period: Late Start Date of 07/20/15 with 60 WORK DAYS

Project(s):

Project No: BROS-1945(811)--8J-77

County: POLK

Type of Work: RCB CULVERT NEW - SINGLE BOX

Route: E. PAYTON AVE. Length: 0.00 miles

Location: IN THE CITY OF DES MOINES: E. PAYTON AVE. FROM 120' WEST OF  
SE 31ST ST. TO 580' EAST OF SE 31ST ST., INCLUDING 1

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	3,386 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	212 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	1,745 SY
2511-0301600	RECREATIONAL TRAIL, HMA, 6"	153 SY
SECTION NO. 0002		
ITEMS FOR A: 12' X 8' X 87' REINFORCED CONCRETE BOX CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	177 CY
2404-7775000	REINFORC STEEL	33,475 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 019 Proposal ID: 79-3127-626

Proposed Contract Period: Late Start Date of 07/13/15 with 70 WORK DAYS

Project(s):

Project No: STP-E-3127(626)--8V-79

County: POWESHIEK

Type of Work: RCB CULVERT NEW - SINGLE BOX

Route: US HWY 6 Length: 0.22 miles

Location: IN THE CITY OF GRINNELL, HWY 6: BOX CULVERT UNDERPASS BENEAT  
H HWY 6 AND TRAIL EXTENSION

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 12' X 10' X 90' REINFORCED CONCRETE BOX CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,149 CY
2403-0100020	STRUCT CONC (RCB CULV)	244 CY
2404-7775000	REINFORC STEEL	42,626 LB
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	2,135 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)	311 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 020 Proposal ID: 82-0066-502

Proposed Contract Period: Late Start Date of 08/17/15 with 25 WORK DAYS

Project(s):

Project No: MB-006-6(502)301--77-82

County: SCOTT

Type of Work: BRIDGE REPAIR

Route: U.S. 6 Length: 0.00 miles

Location: I-280 0.8 MI E OF I-80

Project No: MB-061-6(506)124--77-82

County: SCOTT

Type of Work: BRIDGE REPAIR

Route: U.S. 61 Length: 0.00 miles

Location: ICE RR 0.8 MI N OF I-80 (NBL / SBL)

Project No: MB-061-6(507)124--77-82

County: SCOTT

Type of Work: BRIDGE REPAIR

Route: U.S. 61 Length: 0.00 miles

Location: 210TH ST / CO RD F55 1.1 MI N OF I-80  
(NBL / SBL / NB - WB RAMP)

Project No: MBIN-080-6(505)297--0M-82

County: SCOTT

Type of Work: BRIDGE REPAIR

Route: I-80 Length: 0.00 miles

Location: JERSEY RIDGE RD 0.70 MILES W OF I-74 INTERCHANGE

Project No: MBIN-080-6(506)299--0M-82

County: SCOTT

Type of Work: BRIDGE REPAIR

Route: I-80 Length: 0.00 miles

Location: CO RD Z16 / UTICA RIDGE RD 0.95 MILES E OF I-74 INTERCHANGE

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 021 Proposal ID: 82-0741-196

Proposed Contract Period: Completion Date of 11/20/15

Proposal Note:

THE INTENT OF SITES 1 THRU 4 IS TO ALLOW LANE AND RAMP CLOSURES IN ADDITION TO THOSE ALLOWED ON SHEET J.1 OF IMN-074-1(237)5--0E-82 WHICH ALLOWS WORK ON WEEKENDS AND AT NIGHT.  
CALENDAR DAY CHARGES WILL ONLY BE MADE FOR WORK OCCURRING FROM 6 AM MONDAY THRU 7 PM FRIDAY.

\*\*\*SITE 01\*\*\*

6 DAYS FOR WESTBOUND MAINLINE LANE CLOSURES WILL BE ALLOWED FROM 6 AM MONDAY TO 7 PM FRIDAY. CLOSURES CAN BE USED FOR WB STAGE 1 WORK

\*\*\*SITE 02\*\*\*

6 DAYS OF EASTBOUND MAINLINE LANE CLOSURES WILL BE ALLOWED FROM 6 AM MONDAY TO 7 PM FRIDAY. THE CLOSURES CAN BE USED FOR EB STAGE 1 & 2 WORK. RAMP A MUST BE CLOSED FOR THIS WORK. RAMP A WORK CAN OCCUR WITH THIS SITE WORK OR IN SITE 4.

\*\*\*SITE 03\*\*\*

10 DAYS OF WESTBOUND RAMP C LANE CLOSURES WILL BE ALLOWED FROM 6 AM MONDAY TO 7 PM FRIDAY. THE CLOSURES CAN BE USED FOR RAMP C STAGE 3 & 4 WORK.

\*\*\*SITE 04\*\*\*

5 DAYS OF EASTBOUND RAMP A CLOSURE WILL BE ALLOWED FROM 6 AM MONDAY TO 7 PM FRIDAY. THE CLOSURE CAN BE USED FOR RAMP A OVERLAY WORK AND IS INDEPENDENT OF THE RAMP A CLOSURES THAT ARE FOR THE MAINLINE WORK NEAR THE RAMP AREA. RAMP A OVERLAY WORK CAN BE DONE IN EITHER THIS SITE OR SITE 2.

\*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\*

THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS AS SHOWN FOR THE FOLLOWING EXAMPLE:

. BRIDGE NO. 5210.90380:  
. (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)  
. {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED  
. 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9  
. (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)

Project(s):

Project No: IMN-074-1(195)5--0E-82  
County: SCOTT  
Type of Work: BRIDGE CLEANING  
Route: I-74 Length: 0.00 miles  
Location: I-74 MISSISSIPPI RIVER BRIDGE IN BETTENDORF  
(NBL & SBL)

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Project No: IMN-074-1(196)5--0E-82  
 County: SCOTT  
 Type of Work: BRIDGE REHABILITATION  
 Route: I-74 Length: 0.00 miles  
 Location: I-74 MISSISSIPPI RIVER BRIDGE IN BETTENDORF  
 (IOWA AND ILLINOIS BOUND)

Project No: IMN-074-1(233)5--0E-82  
 County: SCOTT  
 Type of Work: LIGHTING  
 Route: I-74 Length: 0.00 miles  
 Location: IN THE CITY OF BETTENDORF OVER THE MISSISSIPPI RIVER  
 (NBL & SBL)

Project No: IMN-074-1(237)5--0E-82  
 County: SCOTT  
 Type of Work: BRIDGE DECK OVERLAY  
 Route: I-74 Length: 0.00 miles  
 Location: OVER DME RR AND CITY STREETS  
 (FRA NO. 865645Y)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0003		
	DESIGN NO. 0116; I-74 BRIDGE OVER MISSISSIPPI RIVER (IOWA BOUND) IMN-074-1(196)5--0E-82	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775000	REINFORC STEEL	404 LB
SECTION NO. 0004		
	DESIGN NO. 0216; I-74 BRIDGE OVER MISSISSIPPI RIVER (ILLINOIS BOUND) IMN-074-1(196)5--0E-82	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	2 CY
2404-7775000	REINFORC STEEL	418 LB
SECTION NO. 0007		
	DESIGN NO. 0714; REPAIRS TO A 3,033'-0 X VARIABLE CONTINUOUS WELDED PLATE GIRDER BRIDGE IMN-074-1(237)5--0E-82	
2413-0698074	DECK REPAIR, CL A	430 SY
SECTION NO. 0008		
	DESIGN NO. 0714; ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (237)	
2413-0698066	DECK OVERLAY (CL O PCC)	2,149 SY
SECTION NO. 0009		
	DESIGN NO. 0714; ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN (237)	
2413-0698067	DECK OVERLAY (CL HPC-O PCC)	2,149 SY
SECTION NO. 0010		
	DESIGN NO. 0814; REPAIRS TO A 3104'-0 X VARIABLE CONTINUOUS WELDED PLATE GIRDER BRIDGE IMN-074-1(237)5--0E-82	
2413-0698074	DECK REPAIR, CL A	162 SY
SECTION NO. 0011		
	DESIGN NO. 0814; ALTERNATE 'BB' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN (237)	
2413-0698066	DECK OVERLAY (CL O PCC)	812 SY
SECTION NO. 0012		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

DESIGN NO. 0814; ALTERNATE 'BB' OPTION 2: CLASS HPC-O PCC  
BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN (237)  
2413-0698067 DECK OVERLAY (CL HPC-O PCC) 812 SY  
SECTION NO. 0013  
DESIGN NO. 0914; REPAIRS TO A 150' X VARIABLE CONTINUOUS  
WELDED PLATE GIRDER BRIDGE IMN-074-1(237)5--0E-82  
2413-0698074 DECK REPAIR, CL A 65 SY  
SECTION NO. 0014  
DESIGN NO. 0914; ALTERNATE 'CC' OPTION 1: CLASS O PCC  
BID THIS SECTION IF ALTERNATE 'CC' OPTION 1 IS CHOSEN (237)  
2413-0698066 DECK OVERLAY (CL O PCC) 326 SY  
SECTION NO. 0015  
DESIGN NO. 0914; ALTERNATE 'CC' OPTION 2: CLASS HPC-O PCC  
BID THIS SECTION IF ALTERNATE 'CC' OPTION 2 IS CHOSEN (237)  
2413-0698067 DECK OVERLAY (CL HPC-O PCC) 326 SY  
SECTION NO. 0016  
DESIGN NO. 1014; REPAIRS TO A 374' X VARIABLE CONTINUOUS  
WELDED PLATE GIRDER BRIDGE IMN-074-1(237)5--0E-82  
2413-0698074 DECK REPAIR, CL A 267 SY  
SECTION NO. 0017  
DESIGN NO. 1014; ALTERNATE 'DD' OPTION 1: CLASS O PCC  
BID THIS SECTION IF ALTERNATE 'DD' OPTION 1 IS CHOSEN (237)  
2413-0698066 DECK OVERLAY (CL O PCC) 1,336 SY  
SECTION NO. 0018  
DESIGN NO. 1014; ALTERNATE 'DD' OPTION 2: CLASS HPC-O PCC  
BID THIS SECTION IF ALTERNATE 'DD' OPTION 2 IS CHOSEN (237)  
2413-0698067 DECK OVERLAY (CL HPC-O PCC) 1,336 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 022 Proposal ID: 85-C085-119

Proposed Contract Period: Late Start Date of 07/27/15 with 55 WORK DAYS

Project(s):

Project No: BROS-C085(119)--5F-85

County: STORY

Type of Work: RCB CULVERT REPLACEMENT - TRIPLE BOX

Route: 640TH AVENUE Length: 0.01 miles

Location: 640TH AVE. OVER EAST INDIAN CREEK

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
ITEMS FOR A 12' X 10' X 56' TRIPLE REINFORCED CONCRETE BOX		
CULVERT		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	656 CY
2403-0100020	STRUCT CONC (RCB CULV)	414 CY
2404-7775000	REINFORC STEEL	63,009 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 023 Proposal ID: 85-C085-128

Proposed Contract Period: Late Start Date of 09/08/15 with 30 WORK DAYS

Project(s):

Project No: FM-C085(128)--55-85

County: STORY

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: 650TH AVE Length: 0.10 miles

Location: S27: OVER SMALL STREAM

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	ITEMS FOR A 10' X 8' X 84' PRECAST CONCRETE BOX CULVERT	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,047 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 024 Proposal ID: 90-C090-079

Proposed Contract Period: Late Start Date of 06/29/15 with 60 WORK DAYS

Project(s):

Project No: BHS-C090(79)--63-90

County: WAPELLO

Type of Work: BRIDGE DECK OVERLAY

Route: ELDON FLORIS RD(J15) Length: 0.09 miles

Location: OVER DES MOINES RIVER, S27 T71 R12

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR REPAIRS TO A 1,240'-5 X 24'-0 CONTINUOUS STEEL I-BEAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	10 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	1,846 LB
2413-0698081	DECK REPAIR, CL A, SPECIAL	330 SY
SECTION NO. 0002		
ITEMS FOR ALTERNATE 'AA' OPTION 1: CLASS O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN		
2413-0698041	DECK O-DEPTH OVERLAY (CL O PCC)	1,220 SY
SECTION NO. 0003		
ITEMS FOR ALTERNATE 'AA' OPTION 2: CLASS HPC-O PCC BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN		
2413-0698051	DECK O-DEPTH OVERLAY (CL HPC-O)	1,220 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 025 Proposal ID: 92-0014-043

Proposed Contract Period: Late Start Date of 04/27/15 with 130 WORK DAYS

Project(s):

Project No: BRF-001-4(43)--38-92  
County: WASHINGTON  
Type of Work: BRIDGE REPLACEMENT - PPCB  
Route: IOWA 1 Length: 0.00 miles  
Location: IA 1 OVER W. FORK CROOKED CREEK  
1.3 MILES SOUTH OF IA 92

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
DESIGN NO. 0216; 254'-0 X 44'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	1,047 CY
2404-7775000	REINFORC STEEL	77,765 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	113,304 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	3,419 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	703 CY
2301-1033090	STD/S-F PCC PAV'T, CL C CL 3, 9"	493 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 026 Proposal ID: 99-C099-077

Proposed Contract Period: Late Start Date of 07/13/15 with 70 WORK DAYS

Project(s):

Project No: BROS-C099(77)--5F-99

County: WRIGHT

Type of Work: BRIDGE REPLACEMENT - CCS

Route: 150TH STREET Length: 0.50 miles

Location: ON 150TH STREET, OVER DRAINAGE DITCH, NW S32 T92N R25W

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 110'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2625000	EMBANKMENT-IN-PLACE	752 CY
2403-0100010	STRUCT CONC (BRIDGE)	237 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	63,656 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 081 Proposal ID: 54-C054-090-A

Proposed Contract Period: Late Start Date of 09/21/15 with 30 WORK DAYS

Site 01: A+B RAILROAD FLAGGERS

Cost Plus Time Site (A + B). Road User Cost per Day: \$ 1,300.00

Project(s):

Project No: HRRR-C054(90)--5R-54

County: KEOKUK

Type of Work: ALTERNATE PAVEMENT TYPES-MAINLINE PAVING

Route: W15 Length: 10.60 miles

Location: W15: 314TH STREET TO 277TH STREET

Item No.	Item Description	Quantity/Unit
	SECTION NO. 0003	
	ALTERNATE 'AA' OPTION 2: PCC SHOULDER	
	BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN	
2122-5190006	PAVED SHLD, PCC, 6"	24,130 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 04-1210-611

Proposed Contract Period: Late Start Date of 04/13/15 with 40 WORK DAYS

Project(s):

Project No: STP-U-1210(611)--70-04

County: APPANOOSE

Type of Work: PCC PAVEMENT - NEW

Route: 5TH STREET Length: 0.00 miles

Location: W STATE ST IN THE CITY OF CENTERVILLE - WEST STATE STREET -  
FROM THE WEST LINE OF 5TH STREET TO THE WEST LINE OF 10TH ST

---

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,445 CY
2301-1033060	STD/S-F PCC PAV'T, CL C CL 3, 6"	6,064 SY
2301-1083060	STD/S-F PCC PAV'T, CL M CL 3, 6"	251 SY

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 30-7185-602-A

Proposed Contract Period: Late Start Date of 05/19/15 with 45 WORK DAYS

Project(s):

Project No: SRTS-U-7185(602)--8U-30

County: DICKINSON

Type of Work: PCC SIDEWALK/TRAIL

Route: HILL AVE Length: 0.00 miles

Location: IN THE CITY OF SPIRIT LAKE, SIDEWALK ALONG HILL AVE FROM 30TH ST TO 36TH ST.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 57-1187-774

Proposed Contract Period: Late Start Date of 07/06/15 with 25 WORK DAYS

Project(s):

Project No: SRTS-U-1187(774)--8U-57

County: LINN

Type of Work: PCC SIDEWALK/TRAIL

Route: OAKLAND RD. Length: 0.00 miles

Location: IN THE CITY OF CEDAR RAPIDS, FROM GOLF STREET  
TO GOLFPVIEW DRIVE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
SIDEWALK ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	290 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 57-2382-602

Proposed Contract Period: Late Start Date of 07/13/15 with 40 WORK DAYS

Project(s):

Project No: STP-E-2382(602)--8V-57

County: LINN

Type of Work: PCC SIDEWALK/TRAIL

Route: HOOVER NATURE TRAIL Length: 0.43 miles

Location: IN THE CITY OF ELY, FROM ELY CITY PARK TO COMMUNITY CENTER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
TRAIL ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	400 CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	36 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	25 TON
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	1,201 SY
2511-0302800	RECREATIONAL TRAIL, PCC, 8"	66 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 64-3301-503

Proposed Contract Period: Late Start Date of 06/01/15 with 105 WORK DAYS

Project(s):

Project No: MP-065-1(703)98--76-50  
 County: JASPER  
 Type of Work: BRIDGE APPROACH REPAIR  
 Route: U.S. 65 Length: 0.00 miles  
 Location: OVER INDIAN CREEK 0.2 MILE S. OF IA. 117

Project No: MB-330-1(502)8--77-64  
 County: MARSHALL  
 Type of Work: BRIDGE APPROACH REPAIR  
 Route: IOWA 330 Length: 0.00 miles  
 Location: OVER CLEAR CREEK 1.8 MILES S. OF S. JCT. CO. RD. S-52

Project No: MB-330-1(503)11--77-64  
 County: MARSHALL  
 Type of Work: BRIDGE APPROACH REPAIR  
 Route: IOWA 330 Length: 0.00 miles  
 Location: OVER N. SKUNK RIVER 0.9 MILE N. OF N. JCT. CO. RD. S-52

Item No.	Item Description	Quantity/Unit
SECTION NO. 0004		
	DESIGN NO. 0115; REPAIRS TO A 221'-0 X 40' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE MP-065-1(703)98--76-50	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	173 LB
SECTION NO. 0008		
	DESIGN NO. 0115; REPAIRS TO A 154'-0 X 44' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE MB-330-1(502)8--77-64	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	190 LB
SECTION NO. 0012		
	DESIGN NO. 0215; REPAIR TO A 214.895' X 39.370' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE MB-330-1(503)11--77-64	
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	241 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 106 Proposal ID: 66-C066-049

Proposed Contract Period: Late Start Date of 06/01/15 with 75 WORK DAYS

Project(s):

Project No: STP-S-C066(049)--5E-66

County: MITCHELL

Type of Work: PCC OVERLAY - UNBONDED

Route: A23 Length: 12.00 miles

Location: A23: 31-100-16 TO 34-100-15

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2310-5151040	PCC OVERLAY, FURN ONLY	14,537 CY
2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	115,849 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 67-0295-236

Proposed Contract Period: Late Start Date of 04/06/15 with 140 WORK DAYS

Project(s):

Project No: IMX-029-5(236)101--02-67

County: MONONA

Type of Work: PCC PAVEMENT - GRADE AND NEW

Route: I-29 Length: 0.62 miles

Location: OVER ABAND. R.R. 5.1 MILES N. OF CO. RD. F-20  
(REMOVE BRIDGES)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	5,543 CY
2122-5190007	PAVED SHLD, PCC, 7"	10,117 SY
2301-1034110	STD/S-F PCC PAV'T, CL C CL 3I, 11"	18,789 SY
2403-0100020	STRUCT CONC (RCB CULV)	40 CY
2404-7775000	REINFORC STEEL	5,629 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 108 Proposal ID: 81-1961-021

Proposed Contract Period: Late Start Date of 03/16/15 with 10 WORK DAYS

Project(s):

Project No: BRFN-196-1(14)--39-81  
 County: SAC  
 Type of Work: BRIDGE REPLACEMENT - PPCB  
 Route: IOWA 196 Length: 0.00 miles  
 Location: OVER CEDAR CREEK 0.2 MILE S. OF  
 CO. RD. D-36

Project No: BRFN-196-1(15)--39-81  
 County: SAC  
 Type of Work: BRIDGE REPLACEMENT - PPCB  
 Route: IOWA 196 Length: 7.13 miles  
 Location: OVER RACCOON RIVER 1.1 MILES N. OF US 71

Project No: STPN-196-1(21)--2J-81  
 County: SAC  
 Type of Work: PCC PAVEMENT - GRADE & REPLACE  
 Route: IOWA 196 Length: 10.20 miles  
 Location: FROM US 71 N. TO CO. RD. D-36

Project No: STPN-196-1(24)--2J-81  
 County: SAC  
 Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX  
 Route: IOWA 196 Length: 7.13 miles  
 Location: APPROX. 5.2 MILES S. OF RELOC. US 20

Project No: STPN-196-1(26)--2J-81  
 County: SAC  
 Type of Work: TRAFFIC SIGNS  
 Route: IOWA 196 Length: 0.00 miles  
 Location: FROM JCT US 71/IA 193 TO JCT US 20/US 71

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0113; FOR A 262'-0 X 60' PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	BRFN-196-1(14)--39-81
2403-0100010	STRUCT CONC (BRIDGE)	1,105 CY
2404-7775000	REINFORC STEEL	71,612 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	165,107 LB
SECTION NO. 0002		
	DESIGN NO. 0115; FOR A 268'-0 X 44'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE	BRFN-16-1(15)--39-81
2403-0100010	STRUCT CONC (BRIDGE)	680 CY
2404-7775000	REINFORC STEEL	29,412 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	116,684 LB
SECTION NO. 0003		
ROADWAY ITEMS		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

STPN-196-1(21)--2J-81

2102-2624980	CONTRACTOR FURNISH SELECT TREATMENT	79,881	CY
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	444,471	CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	432,651	CY
2122-5190095	PAVED SHLD, PCC, 9.5"	1,244	SY
2301-1003095	STD/S-F PCC PAV'T, QM-C CL 3, 9.5"	145,593	SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	392	SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	29	EACH

SECTION NO. 0004

ALTERNATE 'AA' OPTION 1: PCC SHOULDER

BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (021)

2122-5190006	PAVED SHLD, PCC, 6"	37,078	SY
--------------	---------------------	--------	----

SECTION NO. 0008

ALTERNATE 'BB' OPTION 1: RCB CULVERT

BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN (024)

2403-0100020	STRUCT CONC (RCB CULV)	412	CY
2404-7775000	REINFORC STEEL	77,824	LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 109 Proposal ID: 82-0741-226

Proposed Contract Period: Late Start Date of 04/06/15 with 210 WORK DAYS

Project(s):

Project No: IM-074-1(226)5--13-82  
County: SCOTT

Type of Work: PCC PAVEMENT - GRADE & REPLACE  
Route: I-74 Length: 0.48 miles  
Location: IN THE CITY OF BETTENDORF, US 67 FROM 10TH STREET  
TO 17TH STREET

Project No: IM-074-1(227)5--13-82  
County: SCOTT

Type of Work: TRAFFIC SIGNS  
Route: I-74 Length: 0.00 miles  
Location: IN THE CITY OF BETTENDORF ON LOCAL ROADS

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
IM-074-1(226)5--13-82		
2102-2625000	EMBANKMENT-IN-PLACE	7,178 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	49,757 CY
2301-1032080	STD/S-F PCC PAV'T, CL C CL 2, 8"	25,937 SY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	29,674 SY
2301-1034110	STD/S-F PCC PAV'T, CL C CL 3I, 11"	2,556 SY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	13 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	3,584 LB
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,076 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT)	428 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	27 EACH
SECTION NO. 0002		
SIGNING ITEMS		
IM-074-1(227)5--13-82		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	193 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	23,760 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 110 Proposal ID: 85-0155-688

Proposed Contract Period: Late Start Date of 06/15/15 with 70 WORK DAYS

Project(s):

Project No: STP-U-0155(688)--70-85

County: STORY

Type of Work: PCC PAVEMENT - REPLACE

Route: VARIOUS ROUTES Length: 0.54 miles

Location: IN THE CITY OF AMES: 24TH ST. FROM UPRR TO NORTHWESTERN AVE.  
& BLOOMINGTON RD. FROM EISENHOWER AVE. TO 500' WEST.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	322 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	12,092 SY
2303-0041750	HMA (3M ESAL) BASE, 3/4"	363 TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	218 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 01-C001-083

Proposed Contract Period: Late Start Date of 08/24/15 with 40 WORK DAYS

Project(s):

Project No: STP-S-C001(83)--5E-01

County: ADAIR

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: G61 Length: 5.75 miles

Location: ON N72, FROM FROM G61 NORTH 5.7 MILES TO SCL FONTANELLE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	18,966 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	211 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 04-C004-068

Proposed Contract Period: Late Start Date of 09/08/15 with 30 WORK DAYS

Project(s):

Project No: STP-S-C004(68)--5E-04

County: APPANOOSE

Type of Work: HMA RESURFACING

Route: T61 Length: 5.50 miles

Location: T-61: FROM 34-70-16 TO 34-69-16

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	10,600 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	7,900 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 09-8190-631

Proposed Contract Period: Late Start Date of 08/03/15 with 50 WORK DAYS

Project(s):

Project No: STP-U-8190(631)--70-09

County: BREMER

Type of Work: HMA RESURFACING WITH MILLING

Route: 2ND AVE Length: 0.38 miles

Location: IN THE CITY OF WAVERLY, 2ND AVE SW: FROM 4TH ST. SW TO 10TH  
ST. SW

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	545 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	4,173 CY
2301-1033070	STD/S-F PCC PAV'T, CL C CL 3, 7"	95 SY
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	793 TON
2303-0031750	HMA (1M ESAL) BASE, 3/4"	1,664 TON
2303-0032750	HMA (1M ESAL) INTERMEDIATE, 3/4"	809 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 14-1414-028

Proposed Contract Period: Late Start Date of 04/06/15 with 140 WORK DAYS

Project(s):

Project No: STPN-141-4(28)--2J-14

County: CARROLL

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: IOWA 141 Length: 9.18 miles

Location: FROM 0.2 MILE EAST OF 4TH ST. IN DEDHAM, EAST TO  
0.4 MILE EAST OF N50

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	438 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	107 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	9,811 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	9,676 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 155 Proposal ID: 15-0922-041

Proposed Contract Period: Late Start Date of 06/01/15 with 90 WORK DAYS

Project(s):

Project No: STPN-092-2(41)--2J-15

County: CASS

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 92 Length: 14.83 miles

Location: US 71 TO ADAIR CO. LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	850 CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	19,291 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	21,173 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	21,323 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	224 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	8 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 156 Proposal ID: 32-C032-047

Proposed Contract Period: Late Start Date of 08/31/15 with 20 WORK DAYS

Project(s):

Project No: FM-C032(47)--55-32

County: EMMET

Type of Work: HMA RESURFACING WITH MILLING

Route: P12 Length: 2.87 miles

Location: ON P12, FROM PALO COUNTY LINE NORTH 3 MILES TO IA HWY 15

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	140 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	8,095 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 157 Proposal ID: 45-0639-024

Proposed Contract Period: Late Start Date of 09/28/15 with 10 WORK DAYS

Project(s):

Project No: NHSN-063-9(24)--2R-45

County: HOWARD

Type of Work: HMA PAVED SHOULDER - NEW

Route: U.S. 63 Length: 0.00 miles

Location: NEAR 175TH ST TO MN STATE LINE (VARIOUS LOCATIONS)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	754 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 158 Proposal ID: 50-0850-338

Proposed Contract Period: Late Start Date of 06/15/15 with 75 WORK DAYS  
Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.  
Specified Start Date of 09/13/15 with 35 WORK DAYS

Proposal Note:

\*\*\* SITE NUMBER 01 \*\*\*  
TO COMPLETE ALL WORK SHOWN ON DETAIL 2 ON SHEET B.1 AND  
DETAIL 4 ON SHEET B.2.

\*\*\* SITE NUMBER 02 - LANE RENTAL (A+B BIDDING WITH  
INCENTIVE/DISINCENTIVE) \*\*\*  
THIS SITE IS FOR THE MAINLINE I-80 LANE CLOSURES. THESE LANE  
CLOSURES WILL OCCUR DURING THE SITE NUMBER 01 INTERMEDIATE  
CONTRACT PERIOD SHOWN ABOVE. THE NUMBER OF CALENDAR DAYS BID  
EQUALS THE NUMBER OF RENTAL DAYS THE CONTRACTOR REQUIRES FOR  
LANE CLOSURES. MULTIPLE RENTAL DAYS ARE POSSIBLE DURING ANY  
SINGLE WORKING DAY. REFER TO DS-12029 DEVELOPMENTAL  
SPECIFICATIONS FOR LANE RENTAL (A+B BIDDING WITH  
INCENTIVE/DISINCENTIVE) FOR MORE INFORMATION.

Project(s):

Project No: IMX-080-5(338)155--02-50  
County: JASPER  
Type of Work: HMA PAVED SHOULDER - NEW  
Route: I-80 Length: 0.00 miles  
Location: W OF IA 117 TO E OF IOWA SPEEDWAY DR  
(EB & WB SHOULDERS)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	846 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 159 Proposal ID: 56-C056-091

Proposed Contract Period: Late Start Date of 08/17/15 with 30 WORK DAYS

Project(s):

Project No: STP-S-C056(91)--5E-56

County: LEE

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: J72 Length: 5.80 miles

Location: J72: HWY 218 TO 180TH AVE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	5,791 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	5,754 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 160 Proposal ID: 57-1001-085

Proposed Contract Period: Late Start Date of 07/06/15 with 60 WORK DAYS

Project(s):

Project No: NHSX-100-1(85)--3H-57

County: LINN

Type of Work: HMA RESURFACING

Route: IOWA 100 Length: 1.62 miles

Location: IN CEDAR RAPIDS FROM W. OF COUNCIL ST. E. TO E. OF NORTHLAND  
AVE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0031500	HMA (1M ESAL) BASE, 1/2"	2,125 TON
2303-0052500	HMA (10M ESAL) INTERMEDIATE, 1/2"	5,577 TON
2303-0053503	HMA (10M ESAL) SURF, 1/2", FRIC L-3	5,763 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 161 Proposal ID: 63-C063-118

Proposed Contract Period: Late Start Date of 09/14/15 with 25 WORK DAYS

Project(s):

Project No: FM-C063(118)--55-63

County: MARION

Type of Work: HMA RESURFACING

Route: T22 Length: 3.50 miles

Location: HWY T 22 , FROM HWY T 14 ALONG 228TH PLACE AND 240TH PLACE ,  
TO THE WEST LINE OF SECTION 13, T 77N, R18W

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	160 CY
2303-0021500	HMA (300K ESAL) BASE, 1/2"	805 TON
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	6,709 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 162 Proposal ID: 64-C064-122

Proposed Contract Period: Late Start Date of 09/21/15 with 15 WORK DAYS

Project(s):

Project No: FM-C064(122)--55-64

County: MARSHALL

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: E41 Length: 1.70 miles

Location: ON E41 / MARSHALLTOWN BLVD, FROM IA HWY 330 EAST 1.7 MILES T  
O WEST CITY LIMITS OF MARSHALLTOWN, S6 T83 R18

---

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0021750	HMA (300K ESAL) BASE, 3/4"	3,597 TON
2303-0023750	HMA (300K ESAL) I-S, 3/4", NO FRIC	2,993 TON

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 163 Proposal ID: 78-C078-168

Proposed Contract Period: Late Start Date of 05/04/15 with 100 WORK DAYS

Project(s):

Project No: HRRR-C078(168)--5R-78

County: POTTAWATTAMIE

Type of Work: HMA PAVEMENT - NEW

Route: L55

Length: 0.49 miles

Location: L55: US6 S 0.5 MI

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
POTTAWATTAMIE COUNTY - L55		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	34,025 CY
2303-0041500	HMA (3M ESAL) BASE, 1/2"	1,942 TON
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	936 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	654 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 164 Proposal ID: 85-0355-107

Proposed Contract Period: Late Start Date of 08/10/15 with 40 WORK DAYS

Project(s):

Project No: IMN-035-5(107)113--0E-85

County: STORY

Type of Work: HMA RESURFACING WITH MILLING

Route: I-35 Length: 5.25 miles

Location: 13TH ST INTERCHANGE IN AMES TO CO RD D65 INTERCHANGE AT  
RANDALL (VARIOUS LOCATIONS)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	14 CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	5,526 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	5,580 TON
2303-0062500	HMA (30M ESAL) INTERMEDIATE, 1/2"	1,250 TON
2303-0063502	HMA (30M ESAL) SURF, 1/2", FRIC L-2	1,554 TON



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

SECTION NO. 0004

ROADWAY ITEMS

STPN-069-5(107)--2J-85

2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	3,040 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	224 SY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	147 TON
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	147 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 166 Proposal ID: 89-C089-085

Proposed Contract Period: Late Start Date of 07/13/15 with 45 WORK DAYS

Project(s):

Project No: STP-S-C089(85)--5E-89

County: VAN BUREN

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING

Route: W40 Length: 7.75 miles

Location: W40: FROM IA HWY 16 TO BONAPARTE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	8,721 TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	8,417 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 167 Proposal ID: 91-0653-045

Proposed Contract Period: Late Start Date of 06/15/15 with 65 WORK DAYS

Project(s):

Project No: NHSN-065-3(45)--2R-91

County: WARREN

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: U.S. 65 Length: 3.45 miles

Location: S JCT CO RD G58 TO US 69

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
US 65 STATE, RURAL		
2102-2625000	EMBANKMENT-IN-PLACE	531 CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	8,678 TON
2303-0043504	HMA (3M ESAL) SURF, 1/2", FRIC L-4	6,361 TON
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)	3,267 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	17 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 168 Proposal ID: 97-0201-164

Proposed Contract Period: Late Start Date of 08/03/15 with 50 WORK DAYS

Project(s):

Project No: NHSX-020-1(164)--3H-97

County: WOODBURY

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING

Route: U.S. 20 Length: 6.80 miles

Location: DETOUR FOR US 20/CO. RD. L21/CO. RD. D22/IA. 31

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	54 TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	7,971 TON
2303-0033503	HMA (1M ESAL) SURF, 1/2", FRIC L-3	8,025 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	293 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	8 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 01-0804-712-A

Proposed Contract Period: Late Start Date of 08/10/15 with 25 WORK DAYS

Proposal Note:

Project(s):

Project No: MPIN-080-4(712)73--0N-01

County: ADAIR

Type of Work: MICROSURFACING

Route: I-80 Length: 12.43 miles

Location: FROM THE CASS COUNTY LINE, EAST TO IOWA 25 INTERCHANGE.  
(WB LANES)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 11-0073-708

Proposed Contract Period: Late Start Date of 04/06/15 with 30 WORK DAYS

Project(s):

Project No: MP-007-3(708)21--76-11

County: BUENA VISTA

Type of Work: HMA CRACK FILLING

Route: IOWA 7 Length: 24.54 miles

Location: FROM THE SOUTH JCT. U.S. 71, EAST TO THE NORTH JCT IOWA 4.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 203 Proposal ID: 24-C024-106

Proposed Contract Period: Late Start Date of 08/31/15 with 25 WORK DAYS

Project(s):

Project No: FM-C024(106)--55-24

County: CRAWFORD

Type of Work: PAVEMENT PLANING/GROOVING

Route: E16 Length: 6.00 miles

Location: ON E16, FROM MONONA COUNTY LINE EAST 5 MILES TO INTERSECTIO  
N WITH COUNTY ROAD L51

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	378 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	18 EACH



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 205 Proposal ID: 30-C030-049

Proposed Contract Period: Late Start Date of 06/22/15 with 35 WORK DAYS

Project(s):

Project No: L-630--73-30

County: DICKINSON

Type of Work: SEAL COAT

Route: VARIOUS ROUTES Length: 3.14 miles

Location: MONTGOMERY 195TH AVE., 153RD ST., STATELINE GRADE 100TH ST.

Project No: FM-C030(49)--55-30

County: DICKINSON

Type of Work: SEAL COAT

Route: VARIOUS ROUTES Length: 20.00 miles

Location: M27, A18, A31, N16 100TH ST FROM OSCEOLA CO. EAST 4 MILES,  
130TH ST. FROM OSCEOLA CO EAST TO LAKE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------



IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 207 Proposal ID: 35-0352-719

Proposed Contract Period: Late Start Date of 05/04/15 with 95 WORK DAYS

Proposal Note:

\*\*\* SITE NUMBER 01 - LANE RENTAL (A+B BIDDING WITH INCENTIVE/DISINCENTIVE) \*\*\*  
THIS SITE IS FOR THE MAINLINE I-35 LANE CLOSURES. THESE LANE CLOSURES WILL OCCUR DURING THE SITE NUMBER CONTRACT SHOWN ABOVE. THE NUMBER OF CALENDAR DAYS BID EQUALS THE NUMBER OF RENTAL DAYS THE CONTRACTOR REQUIRES FOR LANE CLOSURES. MULTIPLE RENTAL DAYS ARE POSSIBLE DURING ANY SINGLE WORKING DAY. REFER TO DS-12029 DEVELOPMENTAL SPECIFICATIONS FOR LANE RENTAL (A+B BIDDING WITH INCENTIVE/DISINCENTIVE) FOR MORE INFORMATION.

Project(s):

Project No: MPIN-035-2(508)178--0N-17  
County: CERRO GORDO  
Type of Work: MICROSURFACING  
Route: I-35 Length: 8.11 miles  
Location: FROM THE FRANKLIN CO LINE, NORTH 8.11 MILES (NBL)

Project No: MPIN-035-2(723)186--0N-17  
County: CERRO GORDO  
Type of Work: HMA PAVED SHOULDER - FOG SEAL  
Route: I-35 Length: 18.34 miles  
Location: FROM 1 MI NORTH OF B55, NORTH TO 0.5 MI SOUTH OF A15 IN WORTH COUNTY. (VARIOUS LOCATIONS)

Project No: MPIN-035-2(719)166--0N-35  
County: FRANKLIN  
Type of Work: MICROSURFACING  
Route: I-35 Length: 28.42 miles  
Location: FROM IOWA 3 NORTH TO NEAR A27. (VARIOUS LOCATIONS)

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 208 Proposal ID: 48-0806-307

Proposed Contract Period: Late Start Date of 08/24/15 with 40 WORK DAYS

Project(s):

Project No: IMN-080-6(307)205--0E-48  
 County: IOWA  
 Type of Work: PCC PATCHING  
 Route: I-80 Length: 0.00 miles  
 Location: FROM POWESHIEK CO. LINE EAST TO I-380

Project No: IMN-080-6(308)240--0E-52  
 County: JOHNSON  
 Type of Work: PCC PATCHING  
 Route: I-80 Length: 0.00 miles  
 Location: FROM I-380 EAST TO CEDAR CO. LINE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
IOWA COUNTY IMN-080-6(307)205--0E-48		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	478 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	28 EACH
SECTION NO. 0002		
ROADWAY ITEMS		
JOHNSON COUNTY IMN-080-6(308)240--0E-52		
2303-0043503	HMA (3M ESAL) SURF, 1/2", FRIC L-3	536 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	506 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	30 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 209 Proposal ID: 57-0131-063

Proposed Contract Period: Late Start Date of 08/17/15 with 25 WORK DAYS

Project(s):

Project No: NHSN-013-1(63)--2R-57

County: LINN

Type of Work: PAVEMENT PLANING/GROOVING

Route: IOWA 13 Length: 7.46 miles

Location: FROM N. OF CENTRAL CITY N. TO DELAWARE CO. LINE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 210 Proposal ID: 60-0091-046

Proposed Contract Period: Late Start Date of 07/20/15 with 35 WORK DAYS

Project(s):

Project No: STPN-009-1(46)--2J-60  
 County: LYON  
 Type of Work: MICROSURFACING  
 Route: IOWA 9 Length: 7.44 miles  
 Location: CO. RD. L26 TO 0.9 MILE E. OF CO. RD. L40

Project No: STPN-010-1(79)--2J-84  
 County: SIOUX  
 Type of Work: MICROSURFACING  
 Route: IOWA 10 Length: 5.89 miles  
 Location: FROM E. OF US 75 TO ALBANY AVE IN ORANGE CITY

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
STPN-009-1(46)--2J-60		
2102-2625000	EMBANKMENT-IN-PLACE	110 CY
2303-0001000	HMA WEDGE/LEVEL/STRENGTH	12 TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	31 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2 EACH
SECTION NO. 0002		
ROADWAY ITEMS		
STPN-010-1(79)--2J-84		
2102-2625000	EMBANKMENT-IN-PLACE	90 CY
2301-1032100	STD/S-F PCC PAV'T, CL C CL 2, 10"	16 SY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	53 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH





IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 213 Proposal ID: 87-0024-705

Proposed Contract Period: Late Start Date of 10/05/15 with 25 WORK DAYS

Project(s):

Project No: MP-002-4(705)69--76-87

County: TAYLOR

Type of Work: HMA CRACK FILLING

Route: IOWA 2 Length: 0.00 miles

Location: FROM THE CITY OF BEDFORD, EAST TO THE RINGGOLD COUNTY LINE.

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	374 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	32 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: NOTUSED; 15/01

Project(s):

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 16-0382-033

Proposed Contract Period: Late Start Date of 06/01/15 with 70 WORK DAYS

Project(s):

Project No: BRFN-038-2(33)--39-16

County: CEDAR

Type of Work: GRADING

Route: IOWA 38 Length: 0.00 miles

Location: APPROX 3 MILES N OF I-80 (6 LOCATIONS)

Item No.	Item Description	Quantity/Unit
-----		
SECTION NO. 0001		
DESIGN NO. 0114; 10' X 6' REINFORCED CONCRETE BOX CULVERT		
EXTENSION		
2403-0100020	STRUCT CONC (RCB CULV)	72 CY
2404-7775000	REINFORC STEEL	11,150 LB
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	2,819 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,413 CY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	85 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	7 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 22-C022-076

Proposed Contract Period: Late Start Date of 06/15/15 with 95 WORK DAYS

Project(s):

Project No: FM-C022(076)--55-22

County: CLAYTON

Type of Work: LONGITUDINAL SUBDRAINS

Route: X56 Length: 13.19 miles

Location: X56: FROM GUTTENBERG NCL TO KING RD

Project No: FM-C022(079)--55-22

County: CLAYTON

Type of Work: PCC PAVEMENT - GRADE & REPLACE

Route: X56 Length: 0.39 miles

Location: PIKES PEAK RD: FROM GREAT RIVER RD TO STATE PARK

Item No.	Item Description	Quantity/Unit
SECTION NO. 0002		
ROADWAY ITEMS		
		FM-C022(079)--55-22
2102-2625000	EMBANKMENT-IN-PLACE	4,520 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	8,181 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 304 Proposal ID: 78-0293-102

Proposed Contract Period: Completion Date of 05/25/17  
Site 01: STAGE 2A TRAFFIC  
Completion Date of 07/31/15  
Site 02: STAGE 3A TRAFFIC  
Completion Date of 11/13/15  
Site 03: STAGE 4A CONSTRUCTION  
Completion Date of 06/30/16  
Site 04: STAGE 4B TRAFFIC  
Completion Date of 09/30/16

Proposal Note:

SEE 656.0195  
\*\*\*SITE 01 (STAGE 2A)\*\*\*  
\*\*\*SITE 02 (STAGE 3A)\*\*\*  
\*\*\*SITE 03 (STAGE 4A)\*\*\*  
\*\*\*SITE 04 (STAGE 4B)\*\*\*  
\*\*\*SITE 05 (STAGE 5)\*\*\*  
\*\*\*SITE 06 (STAGE 5)\*\*\*  
\*\*\*WORK RESTRICTION\*\*\*  
\*\*\* INCENTIVE/DISINCENTIVE/SITE 05 AND 06 \*\*\*  
\*\*\*CRITICAL CLOSURE ACTIVITY\*\*\*

Project(s):

Project No: IM-NHS-029-3(102)48--03-78  
County: POTTAWATTAMIE  
Type of Work: GRADING  
Route: I-29 Length: 1.28 miles  
Location: US 275 INTERCHANGE

Project No: IM-NHS-029-3(103)48--03-78  
County: POTTAWATTAMIE  
Type of Work: TRAFFIC SIGNS  
Route: I-29 Length: 0.00 miles  
Location: I-29/80 IN COUNCIL BLUFFS - I-29/US 275 INTERCHANGE

Project No: IM-NHS-029-3(104)48--03-78  
County: POTTAWATTAMIE  
Type of Work: TRAFFIC SIGNALS  
Route: I-29 Length: 0.00 miles  
Location: I-29/80 IN COUNCIL BLUFFS - I-29/US 275 INTERCHANGE

Project No: IM-029-3(105)48--13-78  
County: POTTAWATTAMIE  
Type of Work: BRIDGE REPLACEMENT - PPCB  
Route: I-29 Length: 0.00 miles  
Location: I-29/80 IN COUNCIL BLUFFS - EB IA 92 OVER I-29

Project No: NHS-029-3(106)48--11-78  
County: POTTAWATTAMIE  
Type of Work: BRIDGE REPLACEMENT - PPCB  
Route: I-29 Length: 0.00 miles

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Location: I-29/80 IN COUNCIL BLUFFS - EB IA 92 OVER MOSQUITO CREEK

Project No: IM-NHS-029-3(110)48--03-78  
 County: POTTAWATTAMIE  
 Type of Work: LIGHTING  
 Route: I-29 Length: 0.00 miles  
 Location: I-29/80 IN COUNCIL BLUFFS - I-29/US 275 INTERCHANGE

Project No: IM-NHS-029-3(122)48--03-78  
 County: POTTAWATTAMIE  
 Type of Work: RCB CULVERT EXTENSION - SINGLE BOX  
 Route: I-29 Length: 0.00 miles  
 Location: US 275 INTERCHANGE

Project No: IM-NHS-029-3(146)48--03-78  
 County: POTTAWATTAMIE  
 Type of Work: BRIDGE REPLACEMENT - STEEL GIRDER  
 Route: I-29 Length: 0.00 miles  
 Location: I-29 SOUTHBOUND RAMP D OVER MOSQUITO CREEK AND  
 BNSF/CBEC R.R. IN THE CITY OF COUNCIL BLUFFS

Project No: IM-NHS-080-1(416)3--03-78  
 County: POTTAWATTAMIE  
 Type of Work: RECONSTRUCTION - BRIDGE WIDENING  
 Route: I-29 Length: 0.00 miles  
 Location: I-29 NB OVER I-80 EB TEMPORARY BRIDGE WIDENING  
 IN THE CITY OF COUNCIL BLUFFS

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
IM-NHS-029-3(102)48--03-78		
2102-2625000	EMBANKMENT-IN-PLACE	1,874 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	783,706 CY
2301-1003100	STD/S-F PCC PAV'T, QM-C CL 3, 10"	30,580 SY
2301-1004115	STD/S-F PCC PAV'T, QM-C CL 3I, 11.5"	87,980 SY
2303-0053502	HMA (10M ESAL) SURF, 1/2", FRIC L-2	529 TON
2511-0301800	RECREATIONAL TRAIL, HMA, 8"	794 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	1,026 SY
SECTION NO. 0002		
ALTERNATE 'AA' OPTION 1: PCC SHOULDERS		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN(102)		
2122-5190008	PAVED SHLD, PCC, 8"	2,990 SY
SECTION NO. 0004		
ALTERNATE 'BB' OPTION 1: PCC SHOULDERS		
BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN(102)		
2122-5190007	PAVED SHLD, PCC, 7"	4,140 SY
SECTION NO. 0011		
SIGNING ITEMS (NP)		
IM-NHS-029-3(103)48--03-78		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	171 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	20,664 LB
SECTION NO. 0014		
DESIGN NO. 0114; 476'-0 X VARIES PRETENSIONED PRESTRESSED		

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

CONCRETE BEAM BRIDGE IM-029-3(105)48--13-78		
2403-0100010	STRUCT CONC (BRIDGE)	870 CY
2404-7775000	REINFORC STEEL	98,504 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	269,428 LB
SECTION NO. 0016		
DESIGN NO. 214; A 1056'-0 X 38'-0 PRETENSIONED PRESTRESSED		
CONCRETE BEAM BRIDGE NHS-029-3(106)48--11-78 (RR)		
2403-0100010	STRUCT CONC (BRIDGE)	633 CY
2404-7775000	REINFORC STEEL	633,602 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	433,814 LB
SECTION NO. 0018		
LIGHTING ITEMS		
IM-NHS-029-3(110)48--03-78		
2404-7775000	REINFORC STEEL	16,964 LB
SECTION NO. 0019		
DESIGN NO. 1112;10' X 10' REINFORCED CONCRETE BOX CULVERT		
IM-NHS-29-3(122)48--03-78		
2403-0100020	STRUCT CONC (RCB CULV)	163 CY
2404-7775000	REINFORC STEEL	32,493 LB
SECTION NO. 0020		
ROADWAY ITEMS		
IM-NHS-29-3(122)48--03-78		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	675 CY
SECTION NO. 0021		
DESIGN NO. 0414; A 122'-5 X 26'-0 SIMPLE SPAN WELDED PLATE		
GIRDER BRIDGE IM-NHS-029-3(146)48--03-78		
2404-7775000	REINFORC STEEL	8,520 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	44,553 LB
SECTION NO. 0022		
DESIGN NO. 0414; ALTERNATE 'DD' OPTION 1: REINFORCING STEEL		
BID THIS SECTION IF ALTERNATE 'DD' OPTION 1 IS CHOSEN(146)		
2404-7775000	REINFORC STEEL	38,770 LB
SECTION NO. 0025		
DESIGN NO. 215; A 243'-0 X 39'-0 CONTINUOUS ROLLED STEEL		
BEAM BRIDGE IM-NHS-080-1(416)3--03-78		
2403-0100010	STRUCT CONC (BRIDGE)	134 CY
2404-7775000	REINFORC STEEL	45,983 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	41,758 LB
SECTION NO. 0026		
ROADWAY ITEMS		
IM-NHS-080-1(416)3--03-78		
2102-2625000	EMBANKMENT-IN-PLACE	41 CY
SECTION NO. 0027		
ALTERNATE 'EE' OPTION 1: PCC PAVED SHOULDERS		
BID THIS SECTION IF ALTERNATE 'EE' OPTION 1 IS CHOSEN(416)		
2122-5190009	PAVED SHLD, PCC, 9"	203 SY
SECTION NO. 0029		
INCENTIVE/DISINCENTIVE ITEM FOR CONTRACT		
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	1 CDAY
2528-5160100	CRITICAL CLOSURE ACTIVITY I/D	1 CDAY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 351 Proposal ID: 42-7140-013

Proposed Contract Period: Completion Date of 08/31/15

Proposal Note:

\*\*\* CONTRACTING AUTHORITY REQUEST / WORK RESTRICTIONS \*\*\*  
THE SCHOOL HAS REQUESTED THAT LIGHTING BE DONE AS SOON AS  
POSSIBLE, AND THAT THE PAVEMENT REPAIR WORK (PATCHING AND  
STEAM TUNNELS) BE COMPLETED BETWEEN JUNE 1 AND AUGUST 31.  
THEY ARE HAVING AN ACCREDITATION REVIEW IN MAY WHICH LIMITS  
THE START DATE, AND NEED TO HAVE THE STEAM TUBING  
(HEATING SYSTEM) OPERATIONAL BY SEPTEMBER WHICH CONSTRAINS  
THE COMPLETION DATE.

Project(s):

Project No: DHS-714-0(13)--7H-42

County: HARDIN

Type of Work: LIGHTING

Route: INSTITUTIONAL ROAD Length: 0.00 miles

Location: STATE TRAINING SCHOOL FOR BOYS

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	1 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	212 LB
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)	695 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	3 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 57-3806-298

Proposed Contract Period: Late Start Date of 09/08/15 with 10 WORK DAYS

Project(s):

Project No: IMN-380-6(298)19--0E-57

County: LINN

Type of Work: PAVEMENT MARKINGS

Route: I-380 Length: 2.97 miles

Location: IN CEDAR RAPIDS FROM 15TH AVE. SW TO "J" AVE. NE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 353 Proposal ID: 85-C085-124

Proposed Contract Period: Late Start Date of 08/31/15 with 15 WORK DAYS

Project(s):

Project No: HSIP-S-C085(124)--6C-85

County: STORY

Type of Work: PAVEMENT MARKINGS

Route: VARIOUS LOCATIONS Length: 28.48 miles

Location: ON VARIOUS ROUTES, 28.48 MILES

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 354 Proposal ID: 95-C095-062-A

Proposed Contract Period: Late Start Date of 09/14/15 with 35 WORK DAYS

Project(s):

Project No: HSIP-S-C095(62)--6C-95

County: WINNEBAGO

Type of Work: PAVEMENT MARKINGS

Route: MULTIPLE ROUTES Length: 50.00 miles

Location: VARIOUS LOCATIONS IN WINNEBAGO COUNTY

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY/PAVEMENT MARKING ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	416 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 27-0351-170

Proposed Contract Period: Late Start Date of 03/02/15 with 10 WORK DAYS

Project(s):

Project No: IMN-035-1(170)0--0E-27

County: DECATUR

Type of Work: CLEARING AND GRUBBING

Route: I-35 Length: 24.31 miles

Location: MISSOURI STATE LINE TO S OF THE DECATUR CO  
REST AREA (SBL)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 502 Proposal ID: 79-0634-048

Proposed Contract Period: Completion Date of 03/31/15

Project(s):

Project No: NHSN-063-4(48)--2R-79

County: POWESHIEK

Type of Work: CLEARING AND GRUBBING

Route: U.S. 63 Length: 10.80 miles

Location: NCL OF MONTEZUMA TO 2 MI N OF I-80

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 601 Proposal ID: 17-0652-501

Proposed Contract Period: Late Start Date of 07/13/15 with 40 WORK DAYS

Project(s):

Project No: MB-065-2(501)196--77-17

County: CERRO GORDO

Type of Work: BRIDGE PAINTING

Route: U.S. 65 Length: 0.00 miles

Location: IN THE CITY OF MASON CITY OVER WILLOW CREEK 0.1 MILE N. OF  
IOWA 122

---

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

---

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 602 Proposal ID: 23-1361-069

Proposed Contract Period: By individual sites.

Site 01: BRFN-136-1(65)--39-23 BRIDGE CLEANING  
Late Start Date of 04/20/15 with 10 WORK DAYS

Site 02: BRFN-136-1(69)--39-23 BRIDGE PAINTING  
Late Start Date of 07/06/15 with 80 WORK DAYS

Project(s):

Project No: BRFN-136-1(65)--39-23

County: CLINTON

Type of Work: BRIDGE CLEANING

Route: IOWA 136 Length: 0.00 miles

Location: OVER MISSISSIPPI RIVER IN CLINTON.

Project No: BRFN-136-1(69)--39-23

County: CLINTON

Type of Work: BRIDGE PAINTING

Route: IOWA 136 Length: 0.00 miles

Location: OVER THE MISSISSIPPI RIVER IN CLINTON.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 603 Proposal ID: 29-0345-504

Proposed Contract Period: Late Start Date of 07/13/15 with 40 WORK DAYS

Project(s):

Project No: MB-034-5(504)264--77-29

County: DES MOINES

Type of Work: BRIDGE PAINTING

Route: U.S. 34 Length: 0.00 miles

Location: IN THE CITY OF BURLINGTON OVER CITY STREETS  
0.4 MILE W. OF ILLINOIS STATE LINE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 604 Proposal ID: 31-0209-198

Proposed Contract Period: Approx Start Date of 04/06/15 with 40 WORK DAYS

Proposal Note:

\*\*\* DEFINITION OF MAINTENANCE BRIDGE NUMBERS \*\*\*  
THE NAMING CONVENTION FOR THE MAINTENANCE BRIDGE NUMBERS IS  
AS SHOWN FOR THE FOLLOWING EXAMPLE:

- . BRIDGE NO. 5210.90380:
- . (BRACKETED { } PORTIONS OF THE NUMBER ARE DEFINED BELOW.)
- . {52}10.90380 COUNTY NO. WHERE THE BRIDGE IS LOCATED
- . 52{10.9}0380 MILEPOST LOCATION - SHOWN ONLY UP TO 99.9
- . (ACTUAL MILEPOST COULD BE 110.9 OR 210.9)
- . 5210.9{0}380 LOCATION OF BRIDGE RELATIVE TO THE ROUTE
- . (ALPHA VALUES;
- . O = OVER, R = RIGHT, L = LEFT,
- . A = RAMP, S = SINGLE)
- . 5210.90{380} 3-DIGIT ROUTE

THIS PROPOSAL/CONTRACT INCLUDES WORK TO BE DONE ON THE  
FOLLOWING BRIDGES:

3120.1S020 3190.2S061 3191.8S061

Project(s):

Project No: BRFN-020-9(198)--39-31  
 County: DUBUQUE  
 Type of Work: BRIDGE CLEANING  
 Route: U.S. 20 Length: 0.00 miles  
 Location: OVER THE MISSISSIPPI RIVER IN DUBUQUE  
 JULEN DUBUQUE BRIDGE

Project No: MB-061-6(524)190--77-31  
 County: DUBUQUE  
 Type of Work: BRIDGE CLEANING  
 Route: U.S. 61 Length: 0.00 miles  
 Location: OVER THE PEOSTA CHANNEL IN DUBUQUE  
 (PEOSTA CHANNEL BRIDGE)

Project No: BRFN-061-8(125)--39-31  
 County: DUBUQUE  
 Type of Work: BRIDGE CLEANING  
 Route: U.S. 61 Length: 0.00 miles  
 Location: (U.S. 151) OVER THE MISSISSIPPI RIVER IN DUBUQUE.  
 (CITY ISLAND BRIDGE)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 605 Proposal ID: 43-0294-508

Proposed Contract Period: Late Start Date of 07/13/15 with 40 WORK DAYS

Project(s):

Project No: MBIN-029-4(508)73--0M-43

County: HARRISON

Type of Work: BRIDGE PAINTING

Route: I-29 Length: 0.00 miles

Location: OVER BOYER RIVER, 0.4 MILE N. OF POTTAWATTAMIE CO. LINE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 606 Proposal ID: 61-0924-500

Proposed Contract Period: Late Start Date of 07/13/15 with 40 WORK DAYS

Project(s):

Project No: MB-092-4(500)94--77-61

County: MADISON

Type of Work: BRIDGE PAINTING

Route: IOWA 92 Length: 0.00 miles

Location: OVER MIDDLE RIVER, 1.5 MILES EAST OF ADAIR CO. LINE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 607 Proposal ID: 85-0301-503

Proposed Contract Period: Late Start Date of 07/13/15 with 40 WORK DAYS

Project(s):

Project No: MB-030-1(503)150--77-85

County: STORY

Type of Work: BRIDGE PAINTING

Route: U.S. 30 Length: 0.00 miles

Location: OVER SOUTH SKUNK RIVER, 1.2 MILES WEST OF I-35.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT  
(for information only)

Proposed Letting Date: January 21, 2015 10:00 A.M.

Proposed Bid Order: 981 Proposal ID: 07-0002-746

Proposed Contract Period: Late Start Date of 10/19/15 with 10 WORK DAYS

Proposal Note:

Project(s):

Project No: MP-000-2(746)0--76-07

County: BLACK HAWK

Type of Work: FENCING

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS ALONG U.S. 218, I-380, IOWA 27, & U.S. 20  
IN WATERLOO

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

