

# A d d e n d u m

Iowa Department of Transportation  
Office of Contracts

Date of Letting: January 21, 2015  
Date of Addendum: January 8, 2015

<b>B.O.</b>	<b>Proposal ID</b>	<b>Proposal Work Type</b>	<b>County</b>	<b>Project Number</b>	<b>Addendum</b>
108	81-1961-021	PCC PAVEMENT - GRADE AND REPLACE	SAC	BRFN-196-1(14)--39-81 BRFN-196-1(15)--39-81 STPN-196-1(21)--2J-81 STPN-196-1(24)--2J-81	21JAN108.A06

Make the following change to the PLAN: STPN-196-1(21)--2J-81

REPLACE TAB 110-1 on SHEET NUMBER C.9 with the attached TAB-110-1

# REMOVAL OF PAVEMENT

Refer to Tabulation 102-5

\* Not a Bid Item

Begin Station	End Station	Side	Pavement Type	Area		Saw Cut*	Remarks
				SY	LF		
<b>DIVISION 1:</b>							
<b>Mainline Iowa 196</b>							
666+06.00	720+57.50	Both	HMA	14537.3		24.0	
722+20.10	1070+84.60	Both	HMA	92972.0		0.0	
1073+27.20	1078+82.70	Both	HMA	1481.3		300.0	
1079+22.50	1088+40.00	Both	HMA	2446.7		769.0	
<b>Sideroads</b>							
<b>Iowa 175</b>							
1665+89.80	1676+79.80	Both	HMA/PCC	2906.7		24.0	
<b>300th Street/Co. Rd. D46</b>							
4832+50.00	4835+79.00	Both	PCC	804.2		22.0	
4836+03.00	4839+80.00	Both	PCC	921.6		22.0	
<b>280th Street/Co. Rd. D42</b>							
6945+40.00	6947+17.00	Both	PCC	432.7		22.0	
<b>255th Street/Co. Rd. D36</b>							
86+25.00	95+30.00	Both	HMA/PCC	2413.3		48.0	
<b>U.S. 71</b>							
518+42.50	542+37.00	Both	HMA/PCC	4263.4		48.0	
<b>Detour Runarounds</b>							
<b>Detour 1</b>							
1506+47.94	1527+90.94	Both	Detour	4983.9		227.0	
<b>Detour 2</b>							
2531+92.88	2554+31.30	Both	Detour	5380.5		237.0	
<b>Division 1 Total:</b>				<b>133543.6</b>		<b>1743.0</b>	
<b>DIVISION 2:</b>							
<b>Sideroad</b>							
<b>280th Street/Co. Rd. D42</b>							
6944+00.00	6945+40.00	Both	PCC	1088.8		220.0	
<b>Division 2 Total:</b>				<b>1088.8</b>		<b>220.0</b>	