

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: February 17, 2015
Date of Addendum: February 12, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
115	77-0805-329	PCC PAVEMENT - NEW	POLK	IMX-080-5(329)143--02-77	17FEB115.A01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 0030 2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISHED:

From: 37,573.300 CY

To: 37,663.700 CY

Change Proposal Line No. 0040 2102-2713070 EXCAVATION, CLASS 13, ROADWAY AND BORROW:

From: 46,183.600 CY

To: 58,131.800 CY

If the above changes are not made, they will be made as shown here.

Make the following change to the PLAN:

SHEET B.1:

Detail 1 and Detail 2: Revise details to clarify existing shoulder section and class 13 excavation. Replace Sheet B.1 with the attached Sheet B.1.

SHEET C.3 AND C.4:

Tabulation 112-9 PCC PAVEMENT: quantities in the Class 13 Excavation column and in the Embankment-in-Place column have been revised. The total for Class 13 Excavation and Embankment-in-Place have been revised. A note has been added to the remarks column to clarify the meaning of the asterisk. Replace Sheet C.3 and Sheet C.4 with the attached Sheet C.3 and C.4.

SHEET J.1:

Tabulation 108-23A TRAFFIC CONTROL PLAN:

Add note 10 as follows: 10. Contractor may transfer material over Temporary Barrier Rail from the work zone when a lane closure is in place. Any spilled materials must be removed, a clean/swept surface is required on the closed lane prior to it being opened to traffic.

SHEET J.3

Typical 2: Remove anchored requirement from all lines in the Temporary Barrier Rail tabulation. Add circle note 6 in the “Anchored” column. Add note 6 as follows:


Temporary Barrier Rail to be anchored a minimum of 500 ft ahead and 100 ft beyond any guardrail installation and bridge rail work. Replace Sheet J.3 with the attached Sheet J.3.

DETAIL 1

- ① Pay Limits of Paving Work Trench Treatment
- ② Prepare and Compact Subgrade Per Specification Section 2107, Type A Compaction, Incidental to Class 13 Excavation
- ③ Refer to Tabulation 112-9 for Details Regarding Embankment-In-Place
- ④ Strip, Salvage and Respread 6" of Existing Topsoil within Embankment-In-Place Limits.

PCC Paved Shoulder - New

- ① Pay Limit of Shoulder Work Trench Treatment.
- ② Width will Vary at Guardrail Installations. Refer to Tab. 112-9 for Locations and Specific Dimensions.
- ③ Modify Grading at Guardrail Installations. Refer to Tab. 107-23 and 107-24 for Locations.
- ④ Modified Subbase in RE-19F Trench. Refer to Tab 104-3.
- ⑤ Refer to Tabulation 112-9 for Details Regarding Embankment-In-Place



ENGLISH	IOWA DOT	DESIGN TEAM
SNYDER AND ASSOCIATES, INC.		

IMX-80-5(329)143--02-77

SHEET NUMBER **B.1**

9:50:02 AM 2/12/2015 V81_ID0TRoadJ:\2014_Projects\114.0800K\Cadd\Design PCC\77080329b01.sht

PCC PAVEMENT																
Road Identification	Location	Station to Station	Side	P	G	L	Quantities					Embankment-in-Place			Remarks	
							Class 13 Excavation	PCC Pavement	Shoulder	Modified Subbase	Existing Fore Slope		Proposed Fore Slope			Volume
											CY	FT	Width	Depth		
Interstate 80	EB	1437+29.00	1438+00.00	10.0	10.0	111.0	74.7	123.3	240.0	45.2	6.1	4.1	4.8	-	3.9	Includes Quantity for High Tension Cable Guardrail
	EB	1438+40.00	1445+60.00	10.0	10.0	720.0	517.6	800.0	16.7	333.3	2.5	2.1	4.4	-	104.3	Includes Quantity for High Tension Cable Guardrail
	EB	1445+60.00	1446+20.00	10.0	10.0	60.0	42.7	66.7	16.7	27.2	3.1	4.1	18	3	1	Includes Quantity for High Tension Cable Guardrail
	EB	1446+20.00	1450+00.00	10.0	10.0	380.0	255.6	422.2		154.8	4.1	4.1	24.1	-	20.9	Includes Quantity for High Tension Cable Guardrail
	EB	1450+00.00	1451+60.00	10.0	10.0	276.0	187.6	306.7		126.7	4.1	4.1	1.7	-	3.5	Includes Quantity for Steel Beam Guardrail
	EB	1451+60.00	1461+36.00	10.0	10.0	364.2	244.9	406.7	85.3	1483.8	6.1	4.1	4.8	-	128.1	
	EB	1461+36.00	1469+00.00	10.0	10.0	340.0	94.2	155.6		57.0	4.1	4.1	18	3	1	Includes Quantity for Steel Beam Guardrail
	EB	1469+00.00	1500+40.00	10.0	10.0	340.0	228.7	377.8		138.5	3.1	4.1	18	3	1	
	EB	1500+40.00	1503+80.00	10.0	10.0	200.0	134.5	222.2		81.5	4.1	4.1	20	-	81.5	
	EB	1503+80.00	1505+00.00	10.0	10.0	2480.0	1668.2	2755.6		1010.4	6.1	4.1	4.8	-	24.4	
	EB	1505+00.00	1510+00.00	10.0	10.0	180.0	67.3	111.1		46.7	4.1	4.1	12	-	24.4	
	EB	1510+00.00	1531+60.00	10.0	10.0	370.0	248.9	411.1		156.7	6.1	4.1	4.8	-	13.0	
	EB	1531+60.00	1535+00.00	10.0	10.0	60.0	40.4	66.7		35.9	4.1	4.1	16	-	19.6	
	EB	1535+00.00	1536+78.00	10.0	10.0	88.0	59.2	97.8		24.4	3.1	4.1	18	3	1	Includes Quantity for High Tension Cable Guardrail
	EB	1536+78.00	1540+00.00	10.0	10.0	400.0	287.6	444.4	133.3	185.2	3.1	2.1	4.4	-	23.9	
	EB	1540+00.00	1542+80.00	10.0	10.0	202.0	135.9	224.4		82.3	3.1	4.1	18	3	1	Includes Quantity for High Tension Cable Guardrail
	EB	1542+80.00	1544+00.00	10.0	10.0	210.0	141.3	233.3		442.0	4.1	4.1	1.7	-	265.2	
	EB	1544+00.00	1549+00.00	10.0	10.0	180.0	79.8	120.6		101.9	6.1	4.1	4.8	-	6.8	
	EB	1549+00.00	1558+25.00	10.0	10.0	1085.0	729.8	1205.6		442.0	4.1	4.1	12	-	265.2	
	EB	1558+25.00	1564+47.00	10.0	10.0	622.0	418.4	691.1		253.4	6.1	4.1	4.8	-	21.9	
	EB	1564+47.00	1567+20.00	10.0	10.0	273.0	195.6	303.3	86.2	125.6	4.1	2.1	1.7	-	3.4	
	EB	1567+20.00	1581+00.00	10.0	10.0	1366.0	918.8	1517.8		556.5	6.1	4.1	4.8	-	48.1	
	EB	1581+00.00	1587+60.00	10.0	10.0	570.0	383.4	633.3		231.2	4.1	4.1	4.8	-	232.2	
	EB	1587+60.00	1603+70.00	10.0	10.0	1034.0	695.5	1148.9		446.7	6.1	4.1	4.8	-	24.4	
	EB	1603+70.00	1604+70.00	10.0	10.0	100.0	67.3	111.1		46.7	4.1	4.1	18	-	24.4	
	EB	1604+70.00	1607+30.00	10.0	10.0	260.0	174.9	288.9		105.9	6.1	4.1	4.8	-	9.1	
	EB	1607+30.00	1622+40.00	10.0	10.0	490.0	329.6	544.4		199.6	6.1	4.1	4.8	-	17.2	
	EB	1622+40.00	1646+04.00	10.0	10.0	2364.0	1590.1	2626.7	133.3	963.1	4.1	4.1	18	3	1	Includes Quantity for High Tension Cable Guardrail
	EB	1646+04.00	1650+63.00	10.0	10.0	400.0	287.6	444.4		185.2	4.1	2.1	1.7	-	5.0	
	EB	1650+63.00	1658+00.00	10.0	10.0	59.0	39.7	65.6		24.9	4.1	4.1	16	3	1	Includes Quantity for High Tension Cable Guardrail
	EB	1658+00.00	1662+36.00	10.0	10.0	144.0	96.9	160.0		93.7	4.1	4.1	16	-	75.0	
	EB	1662+36.00	1668+26.00	10.0	10.0	716.0	481.6	795.6		291.7	6.1	4.1	4.8	-	25.2	
	EB	1671+52.00	1673+25.00	12 to 6	12 to 6	173.0	41.1		169.0	28.2	6.1	2.1	1.7	-	1.6	Includes Quantity for Steel Beam Guardrail at NE 112th Street Brk.
	EB	1684+00.00	1702+30.00	10.0	10.0	1830.0	1230.9	2033.3		745.6	6.1	4.1	4.8	-	64.4	
	EB	1702+30.00	1704+00.00	10.0	10.0	150.0	100.9	166.7		61.1	4.1	4.1	20	-	61.1	
	EB	1704+00.00	1704+30.00	10.0	10.0	50.0	35.9	55.6	16.7	24.9	4.1	4.1	16	-	9.7	
	EB	1704+30.00	1710+00.00	10.0	10.0	570.0	409.8	633.3	190.0	263.9	2.5	2.1	8.6	-	82.5	
	EB	1710+00.00	1714+00.00	10.0	10.0	100.0	69.6	111.1	16.7	43.5	4.1	4.1	20	-	13.3	
	EB	1714+00.00	1723+42.00	10.0	10.0	1242.0	835.4	1380.0		506.0	6.1	4.1	4.8	-	43.7	
	EB	1723+42.00	1724+10.00	10.0	10.0	68.0	50.9	75.6	36.9	33.9	6.1	2.1	1.7	-	0.9	Includes Quantity for Steel Beam Guardrail
	EB	1724+10.00	1725+35.00	10.0	10.0	125.0	91.1	138.9	50.2	59.3	4.1	2.1	1.7	-	1.6	Includes Quantity for Steel Beam Guardrail
	EB	1725+35.00	1725+88.00	10.0	10.0	53.0	36.2	58.9	4.2	22.3	3.1	2.1	4.4	-	3.2	Includes Quantity for Steel Beam Guardrail
	EB	1727+50.00	1736+75.00	10.0	10.0	125.0	87.2	138.9		107.8	4.1	4.1	20	-	134.0	
	EB	1736+75.00	1738+00.00	10.0	10.0	1150.0	773.9	1277.8	22.7	1171.3	6.1	4.1	4.8	-	101.2	
	EB	1738+00.00	1746+25.00	10.0	10.0	2875.0	1931.9	3194.4		468.5	4.1	4.1	12	-	281.1	
	EB	1746+25.00	1758+75.00	10.0	10.0	1150.0	773.9	1277.8		468.5	4.1	4.1	12	-	281.1	
	EB	1758+75.00	1794+00.00	10.0	10.0	1575.0	1059.4	1750.0		641.7	3.1	4.1	18	3	1	Includes Quantity for High Tension Cable Guardrail
	EB	1794+00.00	1797+40.00	10.0	10.0	300.0	201.8	333.3		122.2	4.1	4.1	16	-	97.8	
	EB	1797+40.00	1807+75.00	10.0	10.0	1075.0	723.1	1194.4		438.0	6.1	4.1	4.8	-	37.8	
	EB	1807+75.00	1843+65.00	10.0	10.0	3590.0	2414.8	3988.9		1462.6	4.1	4.1	24	-	1755.1	
	EB	1843+65.00	1847+00.00	10.0	10.0	335.0	225.3	372.2		126.8	2.5	2.1	8.6	3	1	Includes Quantity for Steel Beam Guardrail
	EB	1847+00.00	1856+95.00	10.0	10.0	995.0	669.3	1105.6		298.9	4.1	4.1	18	2.5	1	Includes Quantity for Steel Beam Guardrail
	EB	1856+95.00	1859+64.00	10.0	10.0	269.0	195.3	298.9		126.8	2.5	2.1	8.6	-	39.0	
	EB	1859+64.00	1860+75.00	8.0	8.0	1640.0	570.0		1553.2	805.5	4.1	3.1	1	-	6.1	Includes Quantity for Steel Beam Guardrail
	EB	1860+75.00	1876+60.00	8.0	8.0	7540.0	2559.9		6702.2	3630.4	4.1	3.1	1	-	27.9	
	EB	1881+10.00	1956+50.00	8.0	8.0	2946.0	1000.2		2618.7	1418.4	4.1	3.1	1	-	10.9	
	EB	1958+00.00	1957+46.00	10.0	10.0	1322.0	889.2	1468.9		538.6	4.1	4.1	20	-	538.6	
Interstate 80	WB	1425+08.00	1438+30.00	10.0	10.0	1322.0	889.2	1468.9		538.6	4.1	4.1	20	-	538.6	
	WB	1438+30.00	1442+30.00	10.0	10.0	400.0	269.1	444.4		163.0	3.1	4.1	18	3	1	Includes Quantity for High Tension Cable Guardrail
	WB	1442+30.00	1445+90.00	10.0	10.0	360.0	258.8	400.0	120.0	166.7	3.1	2.1	4.4	-	21.5	
	WB	1445+90.00	1448+80.00	10.0	10.0	290.0	195.1	322.2	118.1	118.1	4.1	4.1	20	-	118.1	
	WB	1448+80.00	1460+32.00	10.0	10.0	1152.0	774.9	1280.0		469.3	6.1	4.1	4.8	-	48.5	
	WB	1460+32.00	1464+25.00	10.0	10.0	260.0	186.3	288.9	82.4	119.7	6.1	4.1	4.8	-	3.3	Includes Quantity for Steel Beam Guardrail
	WB	1464+25.00	1484+25.00	10.0	10.0	1755.0	1180.5	1950.0		715.0	6.1	4.1	4.8	-	61.8	
	WB	1484+25.00	1489+20.00	10.0	10.0	740.0	497.8	822.2		73.3	4.1	4.1	16	-	24.5	
	WB	1489+20.00	1490+75.00	10.0	10.0	980.0	659.2	1088.9		399.3	6.1	4.1	4.8	-	34.5	
	WB	1490+75.00	1500+75.00	10.0	10.0	175.0										

112-9
Modified

	Location	Quantities
for further information,		

* Refers to circle note 5 above

