

Asphalt Rubber Cement Concrete Webster County

Final Report
Iowa Department of Transportation
Office of Materials
Project HR-555

April 2003

Highway Division



**Iowa Department
Of Transportation**

Asphalt Rubber Cement Concrete Webster County

Final Report
for
Iowa Department of Transportation
Project HR-555

by
Edward J. Engle, P.E.
Office of Materials
Highway Division
Iowa Department of Transportation
Ames, Iowa 50010

April 2003

Disclaimer

The contents of this report reflect the views of the author and do not necessarily reflect the official views of the Iowa Department of Transportation. This report does not constitute any standard, specification or regulation.

TECHNICAL REPORT TITLE PAGE

1. REPORT NO.	2. REPORT DATE
HR-555	April 2003

3. TITLE AND SUBTITLE	4. TYPE OF REPORT & PERIOD COVERED
Asphalt Rubber Cement Concrete Webster County	Final Report, 4-92 to 2-93

5. AUTHOR(S)	6. PERFORMING ORGANIZATION ADDRESS
Edward Engle, P.E. Secondary Road Research Coordinator	Iowa Department of Transportation Office of Materials 800 Lincoln Way Ames, IA 50010

7. ACKNOWLEDGMENT OF COOPERATING ORGANIZATIONS/INDIVIDUALS

8. ABSTRACT

Discarded tires have become a major disposal problem in the U.S. Different techniques of recycling these discarded tires have been tried. The state of Iowa has evaluated the use of discarded tires ground into crumb rubber and blending it with asphalt to make asphalt rubber cement (ARC). This was the sixth project using this process. The project is located on US 169 from the east junction of IA 175 west and north to US 20.

Only the binder course was placed during this research with the surface course to be let at a later date. There were four test sections, two sections with conventional mixtures and two with ARC mixtures.

There were no significant differences in placement or performance between the two mix types. The cost of the ARC mixture was significantly higher.

9. KEY WORDS	10. NO. OF PAGES
Ground crumb rubber, Recycled tires, Asphalt rubber cement, Crumb rubber modifier, Asphalt concrete	20

TABLE OF CONTENTS

Introduction	1
Objective	1
Contractors.....	1
Project Location	1
Preconstruction Survey	1
Materials.....	2
Mix Design	2
Plant Operation	2
Paving Operation	3
Construction Testing	3
Performance Monitoring.....	3
Cracking.....	3
Rutting.....	4
Structure.....	5
Cost Comparison	6
Conclusions.....	6
Appendices	
Appendix A – Project Location Map.....	7
Appendix B – Mix Designs.....	9
Appendix C – Lab Test Results	12

INTRODUCTION

Recycling discarded tires into asphalt rubber cement (ARC) has been evaluated in several research projects by the Iowa DOT and others. The process used in this project involved blending the crumb rubber with AC-5 before mixing it with the aggregates (this is the so-called "wet process").

Only the binder (lower) course was completed as part of this research. There were areas of reconstruction and finally an overlay of the entire project at a later date. The project contained two test sections with ARC and two control sections with conventional asphalt cement concrete (ACC). The control sections were placed on August 13, 1992 and the test sections later on August 24, 1992.

OBJECTIVE

The objective of this project was to compare the cost and performance of ARC to conventional ACC.

CONTRACTORS

Mathy Construction Company of Onalaska, Wisconsin was the contractor on this project. Rouse Rubber Products of Vicksburg, Mississippi furnished the reactor and the crumb rubber for the project.

PROJECT LOCATION

The project was located on US 169 from the east junction with IA 175 west and north to the junction with US 20. Test sections are shown in Table 1 below. A map is provided in Appendix A.

<u>Test Section</u>	<u>Stations (Mileposts)</u>	<u>Type</u>
1	221+00 (137.76) to 247+00 (138.25)	Conventional
2	303+50 (139.32) to 383+50 (140.84)	ARC binder
3	430+00 (141.72) to 510+00 (143.23)	ARC binder
4	565+00 (144.27) to 590+00 (144.75)	Conventional

PRECONSTRUCTION SURVEY

The original road was a 24-foot wide by 7-inch thick Portland cement concrete (PCC) pavement built in 1930. It had been overlaid with three inches of ACC in 1960. The 1991 traffic volume was 2550 VPD with 12 percent trucks.

A preliminary crack and patch survey was conducted and the Road Rater was used to test the structural rating of the test sections prior to construction. Portions of the test sections had been milled. The road had a large number of reflective cracks and was showing signs of distress.

MATERIALS

The ground tire rubber provided by Rouse Rubber Products was listed as GF-50 rubber. Course aggregate was furnished by Martin-Marietta, Fort Dodge Mine, Webster County, Iowa. The crushed limestone, manufactured sand was produced by Martin-Marietta, Hodges, Humboldt County, Iowa. Finally, the natural sand was produced by Northwest Limestone, Yates, Webster County. AC-5 and AC-10 were supplied by Bituminous Materials of Algona, Iowa.

MIX DESIGNS

Low lab voids were a problem with both the conventional mixtures and the ARC mixtures. The mix design for the conventional sections was changed twice and a new mix design adopted for the last two days of production. The asphalt content was reduced from 5.1 to 4.9 percent. Even with the new mix design, including an aggregate interchange and reduced asphalt content, the lab voids remained below three percent.

The ARC mix had low lab voids (1.5 percent on the first day). The asphalt/rubber content was reduced from 6.5 to 6.1 percent. This did increase the lab voids to 3.6 percent.

The ARC mix contained 15 percent crumb rubber. This amounted to one percent of the ACC mixture. All of the mix designs are shown in Appendix B.

PLANT OPERATION

This was the first time a drum plant was used for producing an ARC mixture in Iowa (usually a batch plant was used). It worked satisfactorily with approximately 250 tons per hour being produced. Normally this particular drum plant (Bituma Drum Plant) would be expected to produce 350 tons per hour with conventional mixtures.

Past production of ARC using a Rouse reactor resulted in 150 tons per hour. The lower production was due to difficulties in maintaining temperature in the reaction unit, resulting in longer reaction times. Between 1991 and 1992, Rouse Rubber added an auxiliary heater to the reactor which increased production.

PAVING OPERATION

There were no construction problems with the conventional mix and segregation was minimal.

The ARC mix seemed to handle well, but the mix appeared rather dry. The appearance seemed to improve after the first 1500 feet. There was a minor problem with tearing of the mat when the finish roller was working. Mathy backed the finish roller off some behind the paving operation which helped reduce the problem. This same problem had occurred in previous ARC projects such as the one for HR-330 in Muscatine county. With both the Muscatine project and this one, the tearing was not apparent by the next day. The temperature of the mat behind the paver was between 275 °F and 300 °F with the conventional mixture and approximately 290 °F with the ARC.

Mathy used a Blaw-Knox PF-180H paver and a Dynapac vibratory roller with a steel finish roller on this project.

CONSTRUCTION TESTING


A sample of the GF-50 rubber was tested for gradation. The rubber and AC-5 were tested for viscosity. Finally, samples of the mix were subjected to creep and resilient modulus testing. These laboratory results are provided in Appendix C.

PERFORMANCE MONITORING

This road was evaluated approximately annually from just before the construction until 2001. The results of this testing are shown below.

CRACKING


Crack surveys were performed six times over the course of this project. Figure 1 shows the results of these surveys.



The data in this graph have been normalized. That is to say that because almost all of the cracks in the overlay are reflective, the cracks in the underlying pavement have a strong effect on the number of cracks in the overlay. These data were normalized by dividing the cracks-per-hundred feet by the original (pre-construction) cracks-per-hundred feet. As can be seen from the figure, there are no significant differences apparent between the ARC sections and the control sections.

RUTTING


Rutting measurements were made using a standard four-foot straight edge in each wheel track. Figure 2 shows the results of rut measurements between 1992 and 2001. The level of rutting was not significant within the accuracy of the measurements.



STRUCTURE

The structural support of the road – a measure of its strength was measured using the Iowa DOT's Road Rater. This device non-destructively determines the thickness, and strength of pavement by measuring its stiffness. It accomplishes this by vibrating a large mass resonantly against the surface and measuring the deflection of the pavement in response. The values obtained are structural numbers (bigger is better) which can be correlated with equivalent thicknesses of various types of pavement.

Figure 3 shows the results of Road Rater testing for this project. Once again the data have been normalized. This is because the structural number is strongly affected by the strength and moisture content of the subgrade. Under certain conditions, such as a wet spring, the structural numbers are lower across the board. Because this research was mostly concerned with comparison between ARC and control sections, it was assumed that the subgrade values were similar for all of the projects. So the structural numbers were normalized to a fixed average. This makes the data inappropriate for absolute measures but useable for comparison purposes.



The data for the control sections straddle the data for the ARC sections. As a result, there is no indication of a significant difference between the two.

COST COMPARISON

A major difference between conventional mixtures and the ARC mixtures was the cost. On this project, the asphalt cement was bid at \$84.00 per ton while the bid for ARC was \$190.00 per ton. The cost of the conventional ACC and ARC mix are shown in Table 2 below.

<u>Conventional Mix</u>		<u>ARC Mix</u>	
Aggregate	\$14.53	Aggregate	\$14.53
4.9 % AC-10	\$ 4.12	6.1% ARC	\$11.59
Total	\$18.65 per ton mix	Total	\$26.12 per ton mix


CONCLUSIONS

1. The ARC mixture can be constructed with little or no difference from that of a conventional mixture.
2. The performance of the two mixes was very similar in terms of cracking, rutting and strength.
3. The cost of ARC mix was significantly higher than that of conventional mixes (this could change with improved technology and possible patent issues).
4. Under the conditions of this research project there is insufficient benefit of using ARC to outweigh the higher cost.

APPENDIX A
Project Location Map

STA. 1035+00
END PROJECT
M.P. 153.17
R-28W

R-29W



STA. 219+00
BEGIN PROJECT
M.P. 137.72

APPENDIX B
Mix Designs

ABD2-0183
BD

MIX DESIGN

IOWA DEPARTMENT OF TRANSPORTATION
OFFICE OF MATERIALS
TEST REPORT - ASPHALT MIX DESIGN
LAB LOCATION - AMES

LAB NO.: ABD2-0183

MATERIAL.....:TYPE A ARC
INTENDED USE.....:BINDER
PROJECT NO.....:IHS-169-6(43)--19-94
COUNTY.....:WEBSTER
SPEC NO.....:5040.00
SAMPLED BY.....:
DATE SAMPLED: DATE RECEIVED: DATE REPORTED: 08/21/92
PROJ. LOCATION: FROM E. JCT. IOWA 175 TO U.S. 20

CONTRACTOR: MATHY
SIZE.....: 3/4
SENDER NO.:

AGG. SOURCES: CR. LST. & CHIPS - MARTIN MARIETTA, FORT
DODGE MINE, WEBSTER CO.; MAN. SAND - MARTIN MARIETTA,
HODGES, HUMBOLDT CO.; SAND - NORTHWEST LST., YATES, WEBSTER
CO./ 15% RUBBER ADDED TO AC.

JOB MIX FORMULA-COMB. GRADATION

1 1/2" 1" 3/4" 1/2" 3/8" NO.4 NO.8 NO.16 NO.30 NO.50 NO.100 NO.200
100.0 92.0 79.0 56.0 45.0 33.0 22.0 11.0 5.3 4.0

TOLERANCE /100 :

98 7 7 7 5 4 2

MATERIAL MIX	A94002	A94002	A46006	A94502	
% AGGR. PROP.	52.50	12.50	10.00	25.00	0.00
% ASPHALT IN MIX		5.25	6.25	7.25	0.00
NUMBER OF MARSHALL BLOWS		50	50	50	0
MARSHALL STABILITY - LBS.		1933	1777	1600	0
FLOW - 0.01 IN.		9	12	13	0
SP GR BY DISPLACEMENT (LAB DENS)		2.332	2.338	2.354	0.000
BULK SP. GR. COMB. DRY AGG.		2.697	2.697	2.697	0.000
SP. GR. ASPH. @ 77 F.		1.022	1.022	1.022	0.000
CALC. SOLID SP. GR.		2.497	2.459	2.423	0.000
% VOIDS - CALC.		6.60	4.94	2.85	0.00
RICE SP. GR.		2.469	2.438	2.405	0.000
% VOIDS - RICE		5.55	4.10	2.12	0.00
% WATER ABSORPTION - AGGREGATE		0.47	0.47	0.47	0.00
% VOIDS IN MINERAL AGGREGATE		18.07	18.73	19.05	0.00
% V.M.A. FILLED WITH ASPHALT		63.47	73.65	85.04	0.00
CALC. ASPH. FILM THICK. MICRONS		10.41	12.48	14.56	0.00
FILLER/BITUMEN RATIO		0.00	0.62	0.00	0.00

A CONTENT OF 6.5% BINDER IS RECOMMENDED TO START THE JOB.
TARGET VOIDS 3.5%

COPIES TO:

CENTRAL LAB
D. HEINS
DIST. 1

R. MONROE
MATHY
JEFFERSON RES.

J. ADAM
W. OPPELAL

DISPOSITION:

SIGNED: ORRIS J. LANE, JR.
TESTING ENGINEER

AB02-0182
00

MIX DESIGN

IOWA DEPARTMENT OF TRANSPORTATION
OFFICE OF MATERIALS
TEST REPORT - ASPHALT MIX DESIGN
LAB LOCATION - AMES

LAB NO.....:AB02-0182

MATERIAL.....:TYPE A
INTENDED USE.....:BINDER
PROJECT NO.....:NMS-169-6(43)--19-94
COUNTY.....:WEBSTER
SPEC NO.....:5040.00
SAMPLED BY.....:
DATE SAMPLED: DATE RECEIVED: DATE REPORTED: 08/20/92
PROJ. LOCATION: FROM E. JCT. IOWA 175 TO U.S. 20
CONTRACTOR:MATHY
SIZE.....:3/4
SENDER NO.:

AGG. SOURCES: CR.LST. & CHIPS - MARTIN MARIETTA, FORT DODGE
MINE, WEBSTER CO.; MAN. SAND - MARTIN MARIETTA, HODGES,
HUMBOLOTT CO.; SAND - NORTHWEST LST., YATES, WEBSTER CO.

JOB MIX FORMULA-COMB. GRADATION											
1 1/2"	1"	3/4"	1/2"	3/8"	NO.4	NO.8	NO.16	NO.30	NO.50	NO.100	NO.200
100.0	92.0	79.0	56.0	45.0	33.0	22.0	11.0	5.3	4.0		

TOLERANCE /100 :	98	7	7	7	5	4	2

MATERIAL MIX	A94002	A94002	A46006	A94502	
% AGGR. PROP.	52.50	12.50	10.00	25.00	0.00

	ALGONA			
ASPHALT SOURCE AND APPROXIMATE VISCOSITY POISES	0929			
% ASPHALT IN MIX	4.50	5.50	0.00	0.00
NUMBER OF MARSHALL BLOWS	50	50	0	0
MARSHALL STABILITY - LBS.	2482	2390	0	0
FLOW - 0.01 IN.	6	8	0	0
SP GR BY DISPLACEMENT (LAB DENS)	2.376	2.395	0.000	0.000
BULK SP. GR. COMB. DRY AGG.	2.697	2.697	0.000	0.000
SP. GR. ASPH. @ 77 F.	1.023	1.023	0.000	0.000
CALC. SOLID SP. GR.	2.526	2.488	0.000	0.000
% VOIDS - CALC.	5.94	3.73	0.00	0.00
RICE SP.GR.	2.497	2.462	0.000	0.000
% VOIDS - RICE	4.85	2.72	0.00	0.00
% WATER ABSORPTION - AGGREGATE	0.47	0.47	0.00	0.00
% VOIDS IN MINERAL AGGREGATE	15.87	16.08	0.00	0.00
% V.M.A. FILLED WITH ASPHALT	62.59	76.84	0.00	0.00
CALC. ASPH. FILM THICK. MICRONS	8.85	10.93	0.00	0.00
FILLER/BITUMEN RATIO	0.00	0.78	0.00	0.00

A CONTENT OF 5.1% AC 10 IS RECOMMENDED TO START THE JOB.
TARGET VOIDS 3.5%

COPIES TO:

CENTRAL LAB	R. MONROE	J. ADAM
D. HEINS	MATHY	DIST. 1
JEFFERSON RES.		

DISPOSITION:

SIGNED: ORRIS J. LANE, JR.
TESTING ENGINEER

APPENDIX C
Lab Test Results

TEST SECTION WORKSHEET

①

TEST SECTION WORKSHEET

DATE: 8/26/92 STATE: Indiana COUNTY: Webster

PROJECT NUMBER: _____ HIGHWAY: 20-169

MARKER: _____ % RUBBER: 15%

TYPE RUBBER: GFSDA UNIT RPM: 40

TOTAL RUBBER USED/DAY: 48,375 ASPHALT TEMP: 352°F
 $21.5 \text{ SK. IN. @ } 2250 \text{ IT} = 48,375$

BROOKSFIELD DATA

TIME	TEMP	SPINDLE	10 RPM - B/F READING	FACTOR	OPS VISCOSITY
8:30	350	3	2.25	200	1000
11:30	350	3	6	200	1200
1:30	350	3	5.5	200	1100
2:00	350	3	7	200	1400
made 2750 Tons Asphalt concrete etc					
8/27/92					
8:00	355	3	10 RPM 6	200	1200
10:00	350	3	8	200	1600
12:00	350	3	8.5	200	1700
3:00	347	3	10.0	200	2000
3:00	345	3	5.5	200	1200

Rubber used = 21.5 SK. IN. @ 2250 48,375
 Made 2750 TONS Asphalt concrete.



Iowa Department of Transportation

DAILY PLANT REPORT
BITUMINOUS TREATED BASE, ASPHALT TREATED BASE, ASPHALT CONCRETE

County Webster
Project W-169-6(43) 17-44
Contract No. 34399
Date 8-24-92

Contractor Matly Construction
Plant Location 5 miles south Fort Dodge on Hwy 169
Plant Type Drum
Make Bituma
Size 3/4"
Crushed Aggr. Sources Martin, Maricetta
Asphalt Source & Grade Bituminous AC-05
Sand Sources Hodges, Yates
Plant Operated 7:45 A.M. to 6:30 P.M.
Mix No. A802-0162

SIEVE ANALYSIS OF COMBINED AGGREGATES table with columns for Sieve No., % Passing, and Samples Submitted.

DENSITY RECORD table with columns for Course Laid, Station, g Factor, Date Laid, Density, % Density, % Voids, Time, and Temperature Record.

PRODUCTION AND PLACEMENT RECORD table with columns for Side, Course Laid, From Station to Station, Tons Today, and Tons To Date.

COMMENTS: started rubber mix today

Acceptance fines/bitumen Ratio = 4.6/5.6 = 0.82
COMMENTS: Delays, Breakdowns, Corrective Action, etc.
Signed: [Signature]
Inspector: [Signature]

MATERIALS OFFICE - RECORDS CENTER COPY

14



Iowa Department of Transportation

DAILY PLANT REPORT
BITUMINOUS TREATED BASE, ASPHALY TREATED BASE, ASPHALY CONCRETE

County Webster
Project MHS 169-6(43)-9-99
Contract No. 37398
Date 8-26-92
Report No. 13

Contractor Maty Construction Plant Location Smiles south Fort Dodge on Hwy. 169
Plant Type Drum Make Bituma Pollution Equipment bag house Resident Engineer Ken DeBok
Mix Type A Class Bituminous Size 3/4" Crushed Aggr. Sources Martin Marietta Recycle Source
Asphalt Source & Grade AC-05 Sand Sources Hodges, Yates Plant Operator 6:45 A.M. to 6:30 P.M. Mix No. AB03-0162

SIEVE ANALYSIS OF COMBINED AGGREGATES

SAMPLE	SIEVE NO. - % PASSING													SAMPLES SUBMITTED				SAMPLES SUBMITTED			
	20	30	40	50	60	75	100	150	200	250	300	425	60	75	100	150	200	250	300		
KE-B3 AMYES	100	92	91	57	45	35	25	14	7.1	5.0			34" Type A	8-26-1	AC-5	AC-05-099					
													34" Type A	8-26-2	AC-5	AC-05-099					
													34" Type A	8-26-3	AC-5	AC-05-099					
													AC-5	AC-05							
	Intended Added 5.1 % A.C. Tank Meas. 5.37 % A.C.																				
	Intended Total 6.1 % A.C. Total % A.C.																				

LAB. DEN.	DENSITY RECORD				SOLID DEN.				TEMPERATURE RECORD					MATERIALS DELIVERIES				
	Course Laid	Station	4 Refer	Date Laid	(1) Density	% Density	4 Refer	Time	7	9	11	1	3	5	Type	Ticket No.	Quantity	
Binder	504r 46	5' RT	8-26-92	2.28	2.342	98.735	4.2	Air	54	58	59	67	76	75	AC-5	3006	25.39	
	469r 77	1' RT		1.28	2.318	97.723	5.2	A.C.	328	337	329	323	324	333	AC-5	3008	25.62	
	441r 24	9' RT		2.24	2.364	99.663	3.3	Aggr.	315	310	330	320	316	310	AC-5	3012	25.68	
	505r 78	11' LT		2.28	2.303	97.091	5.8	Mix	310	305	315	310	305	AC-5	3019	25.38		
	490r 72	3' LT		2.24	2.299	96.585	6.4	Mel	300	305	330	315	310	305	AC-5	3022	25.64	
	489r 71	1' LT		2.28	2.374	100.084	2.90											
	447r 42	1' LT		2.28	2.300	96.863	5.9											
RECYCLED MIX ONLY																		
	AC-5																3027	25.40
Total RAP Used Tons																		
Total Aggr. Used Tons																		
RAP Used %																		
Aggr. Used %																		

Avg. Field Density Lot #1	PRODUCTION AND PLACEMENT RECORD											
	Side	Course Laid	From Station to Station	Tons Today	Tons To Date							
3.327	RT	517+60 to 429+00										
	RT	Binder	517+60 to 429+00	1368.17								
	LT	Binder	515+00 to 429+00	1362.74								
			2730.91	34399.76								
Acceptance Cold Feed												
(Certified Projects Only)												
			100	91	80	57	45	35	25	13	1.6	4.5

COMMENTS: 22 ton road waste
Rubber Mix

Acceptance Finer/Bitumen Ratio = $\frac{4.5}{5.37} = 0.84$
COMMENTS: Delays, Breakdowns, Corrective Action, etc.
Thickness: (1) Actual; (2) Intended
Bituminous Treated Base: Enter % Moisture in % Volair Column

M.T. Signed Ken J. Ellis 318
Inspector

MATERIALS OFFICE - RECORDS CENTER COPY



Iowa Department of Transportation

DAILY PLANT REPORT
BITUMINOUS TREATED BASE, ASPHALT TREATED BASE, ASPHALT CONCRETE

County Webster
Project WHS-169-G(43)-19-94
Contract No. 34398
Date 8-25-92

Contractor Matth Construction Plant Location Smiles south Fort Dodge on Hwy. 169
Plant Type Drum Make Bitumar Pollution Equipment Bag House Resident Engineer Rca DeBok
Mix Type A Class Bituminous Size 3/4 Crushed Aggr. Source Martha Marietta Recycle Source
Asphalt Source & Grade Bituminous AC-05 Sand Sources Hodges, Yates Plant Operated 7:00 AM to 10:30 PM Mix No. AB02-0162

SIEVE ANALYSIS OF COMBINED AGGREGATES												SAMPLES SUBMITTED							
SIEVE NO. - % PASSING												Materials	Senders No.	Materials	Senders No.				
JOB MIX FORMULA - LIMITS	92-100 85-99 72-96 49-63 40-50 18-36 20-10											3/4" Type A	8-25-1	AC-5	ACC-02				
Spl. ID	Temp	Comp	1/2"	3/8"	1/2"	3/4"	1"	1 1/2"	2"	3"	4.75"	60	100	200	3/4" Type A	8-25-2	AC-5	ACC-03	
KE-BIL AM	75%	✓	100	92	79	57	44	33	23	12	6.5	4.5		3/4" Type A	8-25-3	AC-5	ACC-04		
														AC-5	ACC-04	AC-5	ACC-02, 03		
														Intended Added	5.1	% A.C.	Task Mess.	5.94	% A.C.
														Intended Total	6.1	% A.C. Total			% A.C.

LAB. DEN. <u>2.362</u> DENSITY RECORD										SOLID DEN. <u>2.450</u>					TEMPERATURE RECORD					MATERIALS DELIVERIES		
Course Laid	Station	Depth	Date Laid	Temp	Density	% Density	% Voids	Time	Temp	Temp	Temp	Temp	Temp	Type	Ticket No.	Quantity						
Binder	474+63	3" LT.	8-25-92	57	2.331	98.635	4.9	Air	59	62				AC-5	3003	25.55						
	469+80	7" LT.			2.282	96.782	6.7	Aggr.	310	316												
	463+05	5" LT.			2	2.276	96.359	7.1	Mix	305	310											
	452+46	9" LT.			2.242	96.629	5.9	Hot	310	310												
	449+55	11" LT.			2.220	93.772	4.9															
	442+80	5" LT.			1.78	2.270	96.103	7.3														
	432+31	9" LT.																				

Avg. Field Density Lot #1 <u>2.305</u>										PRODUCTION AND PLACEMENT RECORD									
Avg. Field Density Lot #2										(1)	Side	Course Laid	From Station to Station	Tons Today	Tons to Date				
Advisory - Fines/Bitumen Ratio = $\frac{4.5}{5.31} = 0.84$										LT.	Binder	478+56 to 451+25	900.99	31668.95					
Ave. % Fines Voids = <u>5.9</u>																			
Lab % Voids = <u>3.6</u>																			
O.I. (Density) = $\frac{97.593 - 95.0}{1.189} = 2.18$																			

COMMENTS										1	2	3	4	8	16	30	50	100	200
Rained out at 10:30 A.C. changed to 5.1% from 5.5%										100	94	82	59	45	34	34	12	7.9	4.6

Acceptance Fines/Bitumen Ratio = $\frac{4.5}{5.31} = 0.86$

COMMENTS: Delays, Breakdowns, Corrective Action, etc.
 (1) - concrete; (2) - Actual; (3) - Intended
 Bituminous Treated Base: Enter % Moisture in % Voids Column

Signed MT Inspector Rca DeBok 3/18 Cert. No.

MATERIALS OFFICE - RECORDS CENTER COPY



Iowa Department of Transportation

DAILY PLANT REPORT

BITUMINOUS TREATED BASE, ASPHALT TREATED BASE, ASPHALT CONCRETE

County Webster
Project W-112-167-6 (v3)-19-99
Contract No. 34398
Date 8-27-92

Contractor Matty Construction Plant Location 5 miles south Fort Dodge on Hwy 169
Plant Type Drum Make Bituma Paving Equipment bag house Resident Engineer Ron DeBok
Mix Type A Class Bituminous Size 3/4" Crushed Aggr. Source Martin Marietta Recycle Source
Asphalt Source & Grade Bituminous AC-0.5 Sand Source Hedges, Pates Plant Operation 6:45 A.M. to 6:00 P.M. Mix No. AB02-0162

SIEVE ANALYSIS OF COMBINED AGGREGATES

Table with columns for SAMPLE, SIEVE NO. - % PASSING, and SAMPLES SUBMITTED. Includes sieve sizes from 3/8" to 200 and material details like 3/4" Type A and AC-5.

Table with columns for LAB. DEN., DENSITY RECORD, SOLID DEN., TEMPERATURE RECORD, and MATERIALS DELIVERIES. Includes data for Binder, Station, Date Laid, Density, and various material tickets.

Table with columns for PRODUCTION AND PLACEMENT RECORD. Includes columns for Side, Course Laid, From Station to Station, Tons Today, and Tons To Date.

COMMENTS: Finished job
Acceptance Cold Feed (Certified Protests Only) 100 93 82 60 45 39 23 12 7.1 9.5
Advisory - Fines/Bluffon Ratio = 4.5 / 5.21 = 0.85
Avg. % Field Voids = 6.9
Lab % Voids = 3.3
C.I. (Density) = (96.186 - 95.0) / 0.669 = 1.77

Signed Kevin J. P... Inspector
MATERIALS OFFICE - RECORDS CENTER COPY
318 Cert. No.

TEST SECTION WORKSHEET

(2)

TEST SECTION WORK SHEET

DATE: 8/24/92 STATE: IOWA COUNTY: webster

PROJECT NUMBER: _____ HIGHWAY: IA 169

MARKER: _____ % RUBBER: 15%

TYPE RUBBER: GF-50A UNIT RPM: 80

TOTAL RUBBER USED/DAY: 19 pallets ASPHALT TEMP: 340-360°F
 @ 2250 # each = 40,750 #

BROOKSFIELD DATA

TIME	TEMP	SRPM			CPS	
		SPINDLE	(BF READING)	FACTOR	VISCOSITY	
11:00	350	3	5	400	2000	
1:00	360	3	8	400	3200	
3:00	350	3	6	400	2400	
5:30	360	3	8	400	3200	
8/25/92						
7:30	340	3	4.5	400	1800	310
9:00	345	3	5	400	2000	310
11:00	375	3	6	400	2400	310
(1) used (6) pallet @						
2250 #/pallet = 10,150						
(3) made						

10 RPM

340 - 1200
CPS

350 - 1200
CPS

345 - 1400
CPS

AAT2-0449
A

IOWA DEPARTMENT OF TRANSPORTATION
OFFICE OF MATERIALS
TEST REPORT - BITUMINOUS AGGREGATES
LAB LOCATION - AMES

LAB NO.: AAT2-0449

MATERIAL.....:GF 50 CRUMB RUBBER
INTENDED USE....:A.R.C. BINDER
PRODUCER.....:ROUSH
PROJECT NO.....:NHS-169-6(43) --19-94
COUNTY.....:WEBSTER
UNIT OF MATERIAL:GF - 50 RUBBER GRANULES
SAMPLED BY.....:C. ANDERSON
DATE SAMPLED: 08/24/92 DATE RECEIVED: 08/27/92 DATE REPORTED: 08/27/92

CONTRACTOR: MATHY CONST.

SENDER NO.: CA2-123

SIEVE NO. 10 - 100.0

LAB NUMBER	AAT2-0449
SIEVE ANALYSIS %	
#30	98.0
#50	33.0

COPIES TO:
CENTRAL LAB

GEOLOGY

V. MARKS

DISPOSITION:

SIGNED: ORRIS J. LANE, JR.
TESTING ENGINEER

Marshall Stability, Creep and Resilient Modulus Testing

<u>Test</u>	<u>Material</u>	<u>Conventional</u>	<u>ARC</u>
Marshall Stability	¾ - inch binder, 50 blows	2,436	1,790
Creep	¾ - inch binder, 50 blows	88	77
Resilient Modulus	¾ - inch binder, 50 blows	710,000	580,000