

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: July 21, 2015
Date of Addendum: July 16, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
304	97-0296-258	SANITARY SEWER	WOODBURY	IM-NHS-029-6(258)147--03-97	21JUL304.A02

Make the following change to the PROPOSAL DETAILS, Page 2:

Replace PROPOSAL DETAILS, Page 2 with the attached.

REPLACE Plan:

PLAN sheet J.1:

Replace Plan Sheet J.1 with the attached Plan Sheet J.1 to account for changes to the amount of work scheduled to be completed in Stage 1 of construction.

PROPOSAL DETAILS

Proposal ID No.:	97-0296-258	Bid Order No.:	304
Primary Work Type:	SANITARY SEWER	Letting Date:	July 21, 2015 10:00 A.M.

Site Number	Contract Period/ Site Description	Liquidated Damages
CONTRACT	LATE START DATE: 08/24/15 180 WORKING DAYS	\$ 2,000.00
01	COMPLETION DATE: 11/15/15 REFER TO SITE NUMBER 01 DESCRIPTION BELOW.	\$ 2,000.00
02	NO START DATE SPECIFIED 30 WORKING DAYS REFER TO SITE NUMBER 02 DESCRIPTION BELOW.	\$ 1,000.00

PROPOSAL NOTES

*** SITE NUMBER 01 ***
 COMPLETE ALL WORK AS CALLED TO BE EXPEDITED IN STAGE 1
 STAGING NOTES (TAB. 108-26A) ON PLAN SHEET J.1

*** SITE NUMBER 02 ***
 TO COMPLETE THE WORK INVOLVING THE CLOSURE OF PARKING LOT A
 AND THE MISSOURI RIVER RECREATION TRAIL DURING STAGE 2.

108-26A
08-01-08

TRAFFIC CONTROL PLAN

Refer to Tab. 108-26A for traffic control specifics.

Contractor is not allowed access from I-29 or I-29 ramps.

- Larsen Park Road:
- Road will be closed to thru traffic while it is under construction.

Parking Lots:

- As much as possible, access will be maintained via at least one driveway while the permanent roadway is being constructed.

108-26A
08-01-08

STAGING NOTES

(Sanitary Sewer) - shall be expedited in Stage 1 and complete prior to winter (see Proposal)

- Install elements within limits of Stage 1 shown on sheets UTL.4 -UTL.8, including service connections and connections to existing mains. Complete the Excavation and backfill in the sheets prior to completing the sanitary sewer pipe.
- Coordinate all construction activities in Stage 1 with the existing sanitary sewer pipe.
- Once P-753031 is connected to the existing sanitary sewer, install plug in the manhole on the north side of I-29 as noted on sheet UTL.8. This will divert flow into the proposed Stage 1 sanitary sewer system. The plug in the existing manhole and installation is incidental to the project. No flow shall be allowed past this plug in the existing manhole north of I-29. This plug will need to be left in place until the Stage 2 sanitary sewer is installed and flow is diverted out of existing system.
- Install sand bags on other means to keep the sanitary sewer from P-753031 from flowing into P-753016.
- Complete Sanitary Sewer Removal and Abandonment as shown for Stage 1, per tabulations.

(Storm Sewer) - shall be expedited in Stage 1 and complete prior to winter (see Proposal)

- Install structures 853051, 853052, and 853053 as shown on sheet M.10.
- Install pipes P-853051, P-853052, and P-853052a as shown on sheets M.7 and M.10.
- Abandon structure AS-106 as shown on sheet U.11 and tabulated on sheet C.18.
- Remove pipe RP-135 as shown on sheet U.14 and as tabulated on sheet C.15.

-Completion of the storm sewer work described above is necessary for future project work on I-29 scheduled to begin in 2016. Other Stage 1 work, not described above but shown in the Stage 1 plans, should be completed prior to winter if possible but is allowed to occur concurrently with Stage 2 work.

(Recreation Trail) - shall be expedited in Stage 1 and complete prior to winter (see Proposal)

- Construct recreation trail nearest the Missouri River above storm sewer pipe P-853052.

(Water Main)

- Coordinate shut down of existing 6" water main with the City of Sioux City one week in advance. During this shut down install new tees, fittings, valve, and thrust block on existing water main North of I-29 and East of Floyd Blvd. This will allow the existing water main to remain in service during construction.
- Coordinate closure of the existing valve with the City of Sioux City at Sta. 719d14.
- Connect proposed water main into the existing water main at approximately Sta. 731+50.
- Complete installation of water main as shown for Stage 1, per tabulations.

(Other)

- Begin lighting, roadway, and other construction within the limits of Stage 1.

STAGE 2

Traffic:

- Close Larsen Park Road and all parking lot entrances from Sta. 711+00 to Sta. 731+75.
- Maintain access to parking lots D, E, F, G, H, I, J and K via driveway accesses from Larsen Park Road east of Sta. 731+75, except during replacement. Closure of recreation trail along the Missouri River associated with 'Pearl Outfall' construction shall not coincide with recreation trail closure along Larsen Park Road.
- Paving Lot A shall be closed only during construction of P-853048. Parking lots shall be re-opened after pipe installation and pavement replacement. Closure of recreation trail along the Missouri River associated with 'Pearl Outfall' construction shall not coincide with recreation trail closure along Larsen Park Road.
- Maintain access to parking Lots D, E, F, G, H, I, J and K via driveway accesses from Larsen Park Road east of Sta. 731+75, except during times when remaining Stage 1 work prevents such access.
- Limit duration of recreation trail closure from Sta. 716+00 to Sta. 725+50 to maintain conng 2 elements and remaining Stage 1 elements not previously completed.

Construction:

(Water Main)

- Water shut downs shall be coordinated with the City of Sioux City one week in advance. Water shut downs shall be limited to 6 hours.
- Existing water main between Sta. 725+50 and 739+14 shall remain in service while the proposed water main is being installed and tested.

(Other)

- Construct other Stage 2 elements and remaining Stage 1 elements not previously completed.

STAGE 3

Traffic:

- Open Larsen Park Road, all parking lots, and all recreation trails for use.

Construction:

-None

108-26A
08-01-08

113-2
04-16-13

PEDESTRIAN PATH CLOSURES

Refer to TC-601.

*Assumes 6 foot wide barricade, closures may need to be removed and re-established.

Stage	Location	Side	Type III Barricades+ No.	Remarks
Stage 1	Missouri River Recreational Trail - Sta. 710+76.92 to 713+39.54	RT	2	Pearl Outfall (240' RT offset)
	Larsen Park Road Recreational Trail - Sta. 731+00 to 742+60	RT	2	Roadway/Utility construction
Stage 2	Missouri River Recreational Trail - Sta. 710+76.92 to 713+39.54	RT	2	Pearl Outfall (240' RT offset)
	Larsen Park Road Recreational Trail - Sta. 712+19.34 to 712+64.38	RT	2	Pearl Outfall (25.5' RT offset)
	Pierce Street Underpass - Sta. 717+75	LT	2	Roadway/Utility construction
	Larsen Park Road Recreational Trail - Sta. 716+00 to 725+54.87	RT	2	Roadway/Utility construction
	Larsen Park Road Recreational Trail - Sta. 729+04.73 to 731+00	RT	2	Roadway/Utility construction

111-01
04-17-12

COORDINATED OPERATIONS

Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.

Project	Type of Work
IM-NHS-029-7(48)149--03-97	GRADE AND PAVE
IM-NHS-029-7(49)149--03-97	GRADE AND PAVE
IM-NHS-029-6(241)147--03-97	GRADE AND PAVE

108-26A
08-01-08

STAGING NOTES

Except as otherwise noted below, it is anticipated that some Stage 1 work will be completed concurrently with Stage 2 work. However, the Contractor shall be advised that the intent of this staging plan is to complete as much Stage 1 work as possible prior to winter.

STAGE 1

Traffic:

- Close Larsen Park Road and all parking lot entrances from Sta. 729+25 to Sta. 747+00.
- Close parking lots H and J and adjacent recreation trails shall be closed during construction of P-853052 and east of Sta. 747+00.
- Close parking lots H and J and adjacent recreation trails shall be closed during construction of P-853052 (part of 'Virginia Outfall' network). Closure of recreation trail along the Missouri River associated with 'Virginia Outfall' construction shall not coincide with recreation trail closure along Larsen Park Road. Recreation trail along the Missouri River shall be re-opened prior to winter.

Construction:

FILE NO. 2:22:11 PM ENGLISH DESIGN TEAM Tymkowicz\HR Green

WOODBURY COUNTY PROJECT NUMBER IM-NHS-029-6(258)147--03-97 SHEET NUMBER J.1

7/16/2015 \\hrcma\hrcma\cadd\1548_Seg2\108092583\CAD\Info\1080925831.x15