

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 33-C033-096

Proposed Contract Period: Late Start Date of 04/25/16 with 50 WORK DAYS

Project(s):

Project No: BROS-C033(96)--8J-33

County: FAYETTE

Type of Work: BRIDGE REPLACEMENT - CCS

Route: S AVENUE Length: 0.00 miles

Location: S AVENUE OVER VOLGA RIVER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 110' X 30'-6 CONTINUOUS CONCRETE SLAB BRIDGE		
2403-0100010	STRUCT CONC (BRIDGE)	257 CY
2404-7775000	REINFORC STEEL	63,933 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 35-C035-086

Proposed Contract Period: Late Start Date of 08/22/16 with 30 WORK DAYS

Project(s):

Project No: BROS-C035(86)--8J-35

County: FRANKLIN

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: INDIGO AVENUE Length: 0.00 miles

Location: 92210402: FROM C25 TO 200TH STREET

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
2102-2710070	ITEMS FOR A TWIN 12' X 8' X 44' PRECAST CONCRETE BOX CULVERT EXCAVATION, CL 10, RDWY+BORROW	917 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 003 Proposal ID: 45-C045-075

Proposed Contract Period: Late Start Date of 07/05/16 with 75 WORK DAYS

Project(s):

Project No: BROS-C045(75)--5F-45

County: HOWARD

Type of Work: BRIDGE REPLACEMENT - CCS

Route: RIVER ROAD Length: 0.00 miles

Location: RIVER RD: OVER BRANCH UPPER IOWA RIVER

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ITEMS FOR A 110'-0 X 30'-0 CONTINUOUS CONCRETE SLAB BRIDGE		
2102-2625000	EMBANKMENT-IN-PLACE	530 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	74 CY
2403-0100010	STRUCT CONC (BRIDGE)	284 CY
2404-7775000	REINFORC STEEL	64,431 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 73-C073-127

Proposed Contract Period: Late Start Date of 07/18/16 with 40 WORK DAYS

Project(s):

Project No: BHS-C073(127)--63-73

County: PAGE

Type of Work: BRIDGE DECK OVERLAY

Route: J31 Length: 0.00 miles

Location: ON J31, OVER EAST NODAWAY RIVER, AT E1/4 S13 T69 R36

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
BRIDGE DECK OVERLAY ITEMS		
2413-0698051	DECK O-DEPTH OVERLAY (CL HPC-O)	672 SY
2413-0698081	DECK REPAIR, CL A, SPECIAL	448 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 97-0296-246

Proposed Contract Period: Specified Start Date of 04/04/16 with 140 WORK DAYS
Site 01: TO COMPLETE ALL WORK IN STAGE 4, REFER TO PLAN SHEET J.1.
No Start Date Specified with 30 WORK DAYS

Proposal Note:

*** WORK PRIOR TO THE SPECIFIED START DATE ***
TO ENCOURAGE THE CONTRACTOR TO START EARLY, NO WORKING DAYS
WILL BE CHARGED FOR WORK DONE PRIOR TO THE SPECIFIED START
DATE OF 04/04/2016. LANE AND SHOULDER CLOSURES WILL NOT BE
ALLOWED PRIOR TO THE SPECIFIED START DATE.

Project(s):

Project No: BRFIMX-029-6(246)134--14-97
County: WOODBURY
Type of Work: BRIDGE REPLACEMENT - STEEL GIRDER
Route: I-29 Length: 0.00 miles
Location: COUNTY RD. K-25 OVER I-29
SALIX INTERCHANGE

Project No: BRFIMX-029-6(251)134--14-97
County: WOODBURY
Type of Work: TRAFFIC SIGNS
Route: I-29 Length: 0.00 miles
Location: CO. RD. K-25(SALIX) INTERCHANGE

Project No: BRFIMX-029-6(252)134--14-97
County: WOODBURY
Type of Work: LIGHTING
Route: I-29 Length: 0.00 miles
Location: CO. RD. K-25(SALIX) INTERCHANGE

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
	DESIGN NO. 0715; A 403'-0 X 40' WELDED GIRDER BRIDGE	
	BRIDGE	BRFIMX-029-6(246)134--14-97
2403-0100010	STRUCT CONC (BRIDGE)	1,429 CY
2404-7775000	REINFORC STEEL	80,079 LB
2404-7775005	REINFORC STEEL, EPOXY COATED	272,669 LB
SECTION NO. 0003		
	ROADWAY ITEMS	
		BRFIMX-029-6(246)134--14-97
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	70,951 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	17,661 CY
2122-5190007	PAVED SHLD, PCC, 7"	7,493 SY
2122-5190010	PAVED SHLD, PCC, 10"	256 SY
2301-1004100	STD/S-F PCC PAV'T, QM-C CL 3I, 10"	19,493 SY
2303-0053502	HMA (10M ESAL) SURF, 1/2", FRIC L-2	406 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 91-0352-354

Proposed Contract Period: Completion Date of 11/18/16
Site 01: TO COMPLETE STAGE 1
Completion Date of 11/20/15

Proposal Note:

*** NO EXCUSE ROAD OPENING BONUS ***
THE CONTRACTOR WILL BE PAID THE PREDETERMINED LUMP SUM AMOUNT SHOWN IN THE PROPOSAL SCHEDULE OF PRICES FOR THE BID ITEM 'NO EXCUSE ROAD OPENING BONUS' FOR COMPLETING CONSTRUCTION SO THAT ALL LANES NB AND SB ON I-35 ARE OPEN TO TRAFFIC ON OR BEFORE THE CALENDAR DATE SHOWN. COMPLIANCE REQUIRES THAT THE CONTRACTOR MUST HAVE ALL LANES NB AND SB ON I-35 OPEN TO TRAFFIC WITH NO FURTHER LANE CLOSURES. ANY OTHER DELAYS DUE TO WEATHER, CHANGE ORDERS, OVERRUNS OF QUANTITIES, UTILITY DELAYS, OR ANY OTHER DELAYS WILL NOT BE CONSIDERED AS JUSTIFICATION TO MODIFY THE CALENDAR DATE.

Project(s):

Project No: IM-NHS-035-2(354)56--03-91
County: WARREN
Type of Work: PCC PAVEMENT - GRADE & REPLACE
Route: I-35 Length: 0.00 miles
Location: FROM CLANTON CREEK APPROX. 2 MILES S. OF IA. 92 N. THROUGH THE IA. 92 INTERCHANGE (NBL)

Project No: IM-035-2(379)56--13-91
County: WARREN
Type of Work: TRAFFIC SIGNS
Route: I-35 Length: 0.00 miles
Location: FROM CLANTON CREEK APPROX. 2 MILES S. OF IA. 92 N. THROUGH THE IA. 92 INTERCHANGE (NBL)

Project No: IM-035-2(380)56--13-91
County: WARREN
Type of Work: LIGHTING
Route: I-35 Length: 0.00 miles
Location: FROM CLANTON CREEK APPROX. 2 MILES S. OF IA. 92 N. THROUGH THE IA. 92 INTERCHANGE (NBL)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
IM-NHS-035-2(354)56--03-91		
2102-2624980	CONTRACTOR FURNISH SELECT TREATMENT	95,238 CY
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	170,797 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	381,838 CY
2301-1003095	STD/S-F PCC PAV'T, QM-C CL 3, 9.5"	15,863 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

SECTION NO. 0001		
ROADWAY ITEMS		
IM-NHS-035-2(354)56--03-91		
2301-1004115	STD/S-F PCC PAV'T, QM-C CL 3I, 11.5"	92,069 SY
SECTION NO. 0002		
ALTERNATE 'AA' OPTION 1: PCC SHOULDER		
BID THIS SECTION IF ALTERNATE 'AA' OPTION IS CHOSEN (354)		
2122-5190007	PAVED SHLD, PCC, 7"	17,096 SY
SECTION NO. 0004		
DESIGN NO. 0215; 10' X 10' RCB EXTENSION WITH FLUME		
IM-NHS-035-2(354)56--03-91		
2403-0100020	STRUCT CONC (RCB CULV)	194 CY
2404-7775000	REINFORC STEEL	39,400 LB
SECTION NO. 0005		
DESIGN NO. 0315; 42" RCP EXTENSION WITH FLUME		
IM-NHS-035-2(354)56--03-91		
2403-0100020	STRUCT CONC (RCB CULV)	36 CY
2404-7775000	REINFORC STEEL	5,404 LB
SECTION NO. 0006		
DESIGN NO. 0415; 48" RCP WITH FLUME		
IM-NHS-035-2(354)56--03-91		
2403-0100020	STRUCT CONC (RCB CULV)	44 CY
2404-7775000	REINFORC STEEL	7,029 LB
SECTION NO. 0007		
DESIGN NO. 0515; 8'-0 X 6'-0 REINFORCED CONCRETE BOX		
CULVERT WITH FLUME IM-NHS-035-2(354)56--03-91		
2403-0100020	STRUCT CONC (RCB CULV)	183 CY
2404-7775000	REINFORC STEEL	27,800 LB
SECTION NO. 0009		
TRAFFIC SIGNS		
IM-035-2(379)56--13-91		
2403-0100000	STRUCT CONC (MISCELLANEOUS)	18 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	2,903 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 29-0349-218

Proposed Contract Period: Late Start Date of 09/21/15 with 20 WORK DAYS

Project(s):

Project No: NHSN-034-9(218)--2R-29

County: DES MOINES

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 34 Length: 2.06 miles

Location: E OF CO RD X30 TO W OF 135TH ST

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2303-0053502	HMA (10M ESAL) SURE, 1/2", FRIC L-2	4,171 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 38-C038-097

Proposed Contract Period: Late Start Date of 07/25/16 with 65 WORK DAYS

Project(s):

Project No: FM-C038(96)--55-38
County: GRUNDY

Type of Work: HMA RESURFACING
Route: T25 Length: 3.00 miles
Location: T25: FROM D17 NORTH TO BUTLER CO. LINE

Project No: STP-S-C038(97)--5E-38
County: GRUNDY

Type of Work: HMA RESURFACING
Route: T13 Length: 13.00 miles
Location: T-13/D-17: FROM IA 57 SOUTH AND EAST TO IA 14

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
FM-C038(96)--55-38		
2303-0032750	HMA (1M ESAL) INTERMEDIATE, 3/4"	3,850 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	3,100 TON
SECTION NO. 0002		
ROADWAY ITEMS		
STP-S-C038(97)--5E-38		
2303-0032750	HMA (1M ESAL) INTERMEDIATE, 3/4"	16,900 TON
2303-0033504	HMA (1M ESAL) SURF, 1/2", FRIC L-4	13,700 TON

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 43-C043-078

Proposed Contract Period: Late Start Date of 09/21/15 with 15 WORK DAYS

Project(s):

Project No: FM-TSF-C043(78)--5B-43

County: HARRISON

Type of Work: HMA PAVED SHOULDER - NEW

Route: L20 Length: 3.07 miles

Location: ON L20, FROM POTT CO. LINE NORTH 3.38 MILES TO UP RR CROSSIN
G IN MO VALLEY, IN S34 T78 R44

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	1,155 CY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 58-C058-046

Proposed Contract Period: Late Start Date of 09/21/15 with 30 WORK DAYS

Project(s):

Project No: SB-IA-C058(046)--7T-58

County: LOUISA

Type of Work: HMA PAVED SHOULDER - NEW

Route: X 61 Length: 12.50 miles

Location: INTERSECTION OF X61 AND X99 NORTH TO 162ND STREET

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 07-2187-233

Proposed Contract Period: Approx Start Date of 07/25/16 with 25 WORK DAYS

Project(s):

Project No: NHSN-218-7(233)--2R-07

County: BLACK HAWK

Type of Work: PCC PATCHING

Route: U.S. 218 Length: 0.00 miles

Location: APPROX 0.55 MI W OF AIRPORT BLVD IN WATERLOO TO
IA 27/IA 57/IA 58 INTERCHANGE IN CEDAR FALLS (SB)

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
ROADWAY ITEMS		
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	20 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	1 EACH

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 52-3806-710-A

Proposed Contract Period: Late Start Date of 04/04/16 with 40 WORK DAYS

Project(s):

Project No: MPIN-380-6(710)0--0N-52

County: JOHNSON

Type of Work: HMA CRACK FILLING

Route: I-380 Length: 17.00 miles

Location: FROM I-80, NORTH TO 1 MILE NORTH OF U.S. 30.

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 04-0051-061

Proposed Contract Period: Late Start Date of 10/12/15 with 10 WORK DAYS

Project(s):

Project No: ER-005-1(61)--28-04

County: APPANOOSE

Type of Work: REVETMENT

Route: IOWA 5 Length: 0.00 miles

Location: NORTH CREEK 2.6 MI S OF CO RD T20

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 26-C026-089

Proposed Contract Period: Late Start Date of 04/04/16 with 20 WORK DAYS

Project(s):

Project No: BROS-C026(89)--8J-26

County: DAVIS

Type of Work: PIPE CULVERTS

Route: QUILL AVENUE Length: 0.00 miles

Location: ON QUILL AVE, OVER TRIB S CHEQUEST LAKE CR, FROM QUILL AVE,
1 MILE NORTH OF 195TH ST, ON CTR S11 T69 R13

Item No.	Item Description	Quantity/Unit
SECTION NO. 0001		
BRIDGE REPLACEMENT ITEMS		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	566 CY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	37 CY
2404-7775000	REINFORC STEEL	360 LB

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 78-0801-366

Proposed Contract Period: Completion Date of 01/30/17
 Site 01: . Completion Date of 04/30/16
 Site 02: . Completion Date of 08/02/16

Proposal Note:
SEE NOTE 656.0199

Project(s):

Project No: IMN-029-3(127)48--0E-78
 County: POTTAWATTAMIE
 Type of Work: RCB CULVERT NEW - SINGLE BOX
 Route: I-29 Length: 0.00 miles
 Location: COUNCIL BLUFFS INTERSTATE SYSTEM
 UNDER CBEC R.R.

Project No: IMN-080-1(366)4--0E-78
 County: POTTAWATTAMIE
 Type of Work: GRADING
 Route: I-80 Length: 0.00 miles
 Location: IAIS R.R. IN COUNCIL BLUFFS

Item No.	Item Description	Quantity/Unit

SECTION NO. 0001		
DESIGN NO. 1612; 14' X 8' X 40'-0 REINFORCED CONCRETE BOX		
CULVERT IMN-029-3(127)48--0E-78		
2403-0100020	STRUCT CONC (RCB CULV)	307 CY
2404-7775000	REINFORC STEEL	32,588 LB
SECTION NO. 0002		
DESIGN NO. 1712; TWIN 6'-0 X 4'-0 REINFORCED CONCRETE BOX		
CULVERT EXTENSION IMN-029-3(127)48--0E-78		
2403-0100020	STRUCT CONC (RCB CULV)	323 CY
2404-7775000	REINFORC STEEL	10,598 LB
SECTION NO. 0003		
ROADWAY ITEMS		
IMN-080-1(366)4--0E-78		
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	164,196 CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	3,196 SY
2511-0301600	RECREATIONAL TRAIL, HMA, 6"	1,581 SY
SECTION NO. 0004		
ALTERNATE 'AA' OPTION 1: PCC SHOULDER		
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (366)		
2122-5190007	PAVED SHLD, PCC, 7"	25 SY

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 351 Proposal ID: 00-000S-797

Proposed Contract Period: Late Start Date of 09/28/15 with 25 WORK DAYS

Project(s):

Project No: NHSN-000-S(797)--2R-00

County: STATEWIDE

Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS STATEWIDE

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 42-C042-082

Proposed Contract Period: Late Start Date of 09/21/15 with 30 WORK DAYS

Project(s):

Project No: FM-C042(82)--55-42

County: HARDIN

Type of Work: PAVEMENT MARKINGS

Route: VARIOUS ROUTES Length: 0.00 miles

Location: VARIABLE: FROM VARIES TO VARIES

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 401 Proposal ID: 86-0306-227

Proposed Contract Period: Approx Start Date of 10/26/15 with 20 WORK DAYS

Project(s):

Project No: NHSN-030-6(227)--2R-86

County: TAMA

Type of Work: SALVAGE AND REMOVAL

Route: U.S. 30 Length: 0.00 miles

Location: PARCEL 7, 2287 HIGHWAY 30, TAMA

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 01-0802-237

Proposed Contract Period: Late Start Date of 09/21/15 with 130 WORK DAYS

Project(s):

Project No: IMN-080-2(237)94--0E-01

County: ADAIR

Type of Work: LANDSCAPING

Route: I-80 Length: 0.00 miles

Location: CO RD P28 TO 1 MI E OF CO RD P53

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 502 Proposal ID: 44-2182-147

Proposed Contract Period: Late Start Date of 09/28/15 with 25 WORK DAYS

Project(s):

Project No: NHSN-218-2(147)--2R-44

County: HENRY

Type of Work: LANDSCAPING

Route: U.S. 218 Length: 0.00 miles

Location: 255TH ST INTERCHANGE NORTH TO 220TH ST

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 503 Proposal ID: 48-0806-381

Proposed Contract Period: Late Start Date of 10/12/15 with 25 WORK DAYS

Project(s):

Project No: IMN-080-6(381)208--0E-48

County: IOWA

Type of Work: LANDSCAPING

Route: I-80 Length: 0.00 miles

Location: REST AREA 2.5 MI EAST OF V38 (WB).

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

IOWA DEPARTMENT OF TRANSPORTATION

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT
(for information only)

Proposed Letting Date: August 18, 2015 10:00 A.M.

Proposed Bid Order: 504 Proposal ID: 78-0294-707

Proposed Contract Period: Late Start Date of 09/21/15 with 65 WORK DAYS

Project(s):

Project No: MPIN-029-4(707)67--0N-78

County: POTTAWATTAMIE

Type of Work: CLEARING AND GRUBBING

Route: I-29 Length: 0.00 miles

Location: FROM NORTH OF L19 (HONEY CREEK) INTERCHANGE NORTH TO SOUTH
OF NORTH I-680 INTERCHANGE (SB)

Item No.	Item Description	Quantity/Unit
----------	------------------	---------------

