

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: December 22, 2015
Date of Addendum: December 8, 2015

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
001	97-0297-049	BRIDGE NEW - PPCB	WOODBURY	IM-NHS-029-6(201)147--03-97 IM-NHS-029-6(203)147--03-97 IM-NHS-029-6(205)148--03-97 IM-NHS-029-6(206)147--03-97 IM-NHS-029-7(34)148--03-97 IM-NHS-029-7(35)149--03-97 IM-NHS-029-7(40)149--03-97 IM-NHS-029-7(46)149--03-97 IM-NHS-029-7(49)149--03-97 IM-NHS-029-7(58)149--03-97 IM-NHS-029-7(59)149--03-97	22DEC001.A05

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 5030 2527-9263180 PAVEMENT MARKINGS REMOVED:
From: 2,004.410 STA
To: 765.020 STA

If the above changes are not made, they will be made as shown here.

Make the following changes to the plan: IM-NHS-029-7(49)149--03-97

Replace the TAB 108-22RA on SHEETS C.40, C.41 and C.42 with the attached TAB 108-22RA.

PAVEMENT MARKING REMOVAL LINE TYPES

**BCV4 - Place on the same side of the roadway to match existing markings near the project
 **MNV4 - For estimating purposes only. No Passing Zone Lines will be located in the field. See PN-110
 DCV4: Double Center-Line (Yellow) @ 2.00
 ELV4: Edge Line Left (White) @ 1.00
 ELM4: Edge Line Right (White) @ 1.00
 ELW4: Edge Line Left (Yellow) @ 1.00
 ELR4: Edge Line Right (Yellow) @ 1.00
 ELM4: Edge Line Left (White) @ 3.00
 ELM4: Edge Line Right (White) @ 0.2'
 ELW4: Ramp Edge Line Left (Yellow) @ 1.00
 ELW4: Ramp Edge Line Right (White) @ 1.00
 ELW4: Solid Lane Line (White) @ 1.00
 ELW4: Broken Lane Line (White) @ 0.2'
 ELM4: Median Nose (Yellow) @ 1.00
 ELM4: Median Nose (White) @ 2.00
 ELM4: Dotted Line (White) @ 0.3'
 Length by Line Type (Unfactored):

Road ID	Station to Station	Dir. of Travel	Marking Type	Side			YLM2		DCY4		STM6		BLM4		ELM4		ELV4		RLV4		SLW4		ELW4		CBW6		STY6		MNV4***		CMW8		DLW4		Remarks	
				L	C	R	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA	STA		
ML I-29	524770.00	NB	Removal of Paint	X									4.20				3.11																	Placed in 3A		
ML I-29	528290.00	NB	Removal of Paint		X																													Placed in 3A		
Stage 3A Temp Hamilton Exit Ramp 1			Removal of Paint			X																												Placed in 3A		
ML I-29	523040.00	NB	Removal of Paint										2.14				1.45																	Placed in 3A		
Northbound Frontage Rd 2			Removal of Paint																															Placed in 3A		
ML I-29	523440.00	NB	Removal of Paint			X								0.67			1.57																	Placed in 3A		
Temporary Floyd/Nebraska Exit			Removal of Paint																															Placed in 3A		
ML I-29	430400.00	NB	Removal of Paint																															Reapplied in 3A		
ML I-29	432411.00	NB	Removal of Paint			X																												Reapplied in 3A		
ML I-29	442456.00	NB	Removal of Paint			X																												Placed in 3A		
ML I-29	388479.00	SB	Removal of Paint	X																																
ML I-29	389480.00	SB	Removal of Paint			X																													Reapplied in 3A	
ML I-29	455493.00	SB	Removal of Paint			X								66.13																				Reapplied in 3A		
ML I-29	460400.00	SB	Removal of Paint			X																												Reapplied in 3A		
ML I-29	455493.00	SB	Removal of Paint			X																												Reapplied in 3A		
ML I-29	389480.00	SB	Removal of Paint			X									60.81																			Reapplied in 3A		
ML I-29	455493.00	SB	Removal of Paint			X																												Reapplied in 3A		
ML I-29	452458.00	SB	Removal of Paint			X																												Reapplied in 3A		
ML I-29	454496.00	SB	Removal of Paint			X																												Reapplied in 3A		
Floyd Ramp C			Removal of Paint			X																												Reapplied in 3A		
Floyd Ramp C	3463451.00	SB	Removal of Paint	X																														Reapplied in 3A		
Floyd Ramp C	3452452.00	SB	Removal of Paint			X															9.19													Reapplied in 3A		
Floyd Ramp C	3464462.00	SB	Removal of Paint			X																												Reapplied in 3A		
NBFRNT1	3470405.00	NB	Removal of Removable Tap	X																														Placed in 2		
NBFRNT1	3472451.00	NB	Removal of Removable Tap	X																														Placed in 2		
NBFRNT1	3470405.00	NB	Removal of Removable Tap	X																														Placed in 2		
Floyd Ramp C	3463451.00	SB	Removal of Paint			X															7.47													Placed in 3B		
Floyd Ramp C	3463451.00	SB	Removal of Paint			X																												Placed in 3B		
STAGE 4			Removal of Paint			X																														
Floyd Ramp C	3463451.00	SB	Removal of Paint	X																															Placed in 3C	
Floyd Ramp C	3463451.00	SB	Removal of Paint			X																													Placed in 3C	
Floyd Ramp C	3463451.00	SB	Removal of Paint			X																													Placed in 3C	
ML I-29	463470.00	SB	Removal of Paint			X																													Placed in 3C	
			Factored Total: Removal of Paint						26.74				49.63		183.54		237.54				36.11			0.32		18.60								6.44		
			Factored Total: Removal of Removable Tap						4.66						4.48		2.46								1.44											
			Bid Quantity: Pavement Markings Removal																																	
			Incidental Removal of Removable Tap																																	