

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: January 20, 2016
Date of Addendum: January 19, 2016

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
154	25-C025-102	HMA - PAVEMENT FULL DEPTH RECLAMATION	DALLAS	STP-S-C025(102)--5E-25	20JAN154.A04

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 0010 2102-3240000 WATER FOR EMBANKMENT
CONSTRUCTION:

From: 1,018.390 MGAL
To: 950.660 MGAL

Change Proposal Line No. 0030 2116-0000300 MINERAL STABILIZING AGENT:

From: 8,486.600 TON
To: 7,922.100 TON

If the above changes are not made, they will be made as shown here.

Make the following changes to ESTIMATED PROJECT QUANTITIES on plan sheet C.1:

Ref No. 1, Item code 2102-3240000

Division I	Division II	Division III	Total
670.24 MGAL	149.8 MGAL	130.62 MGAL	950.66 MGAL

Ref No. 3, Item code 2116-0000300

Division I	Division II	Division III	Total
5,585.3 TON	1,248.3 TON	1,088.5 TON	7,922.1 TON

Fly ash estimated quantity based on an assumed average dry density of 115 pcf and adding 15% fly ash. Dallas County will provide a mix design prior to FDR. Percent fly ash and required added water may vary based on mix design.