MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 001 Proposal ID: 01-C001-090

Proposed Contract Period: Late Start Date of 08/15/16 with 55 WORK DAYS

Project(s):

Project No: FM-C001(90)--55-01

County: ADAIR

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 270TH ST Length: 0.10 miles

Location: ON G53, OVER BRANCH OF NINE MILE RUN, FROM STATE HWY 25 EAST

0.3 MILES, NLINE S32 T75 R31

Item No. Item Description Quantity/Unit -----

SECTION NO. 0001

ITEMS FOR A TWIN 12' X 12' REINFORCED CONCRETE BOX CULVERT 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,14 2403-0100020 STRUCT CONC (RCB CULV) 32 2404-7775000 REINFORC STEEL 47,16 327 CY

47,164 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 002 Proposal ID: 01-C001-091

Proposed Contract Period: Late Start Date of 09/19/16 with 30 WORK DAYS

Project(s):

Project No: FM-C001(91)--55-01

County: ADAIR

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX

Route: 270TH ST Length: 0.10 miles

Location: ON G53, OVER BRANCH OF NINE MILE RUN, FROM STATE HWY 25 EAST

1.5 MILES, NLINE S33 T75 R31

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TWIN 12' X 6' X 37' REINFORCED CONCRETE BOX

CULVERT

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 539 CY

 2403-0100020
 STRUCT CONC (RCB CULV)
 170 CY

 2404-7775000
 REINFORC STEEL
 22,898 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposal ID: 05-C005-061 Proposed Bid Order: 003

Proposed Contract Period: Late Start Date of 07/25/16 with 60 WORK DAYS

Project(s):

Project No: BROS-C005(61)--5F-05

County: AUDUBON

2404-7775000 REINFORC STEEL

Type of Work: BRIDGE REPLACEMENT - CCS

Route: KINGBIRD AVE Length: 0.10 miles

Location: ON KINGBIRD AVE., OVER CREEK, ON WLINE S11 T80N R35W

Item Description Quantity/Unit Item No. ______ SECTION NO. 0001 ROADWAY ITEMS 2102-2625000 EMBANKMENT-IN-PLACE 555 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 100 CY SECTION NO. 0002 ITEMS FOR A 80'-0 X 24'-6 CONTINUOUS CONCRETE SLAB BRIDGE 2403-0100010 STRUCT CONC (BRIDGE) 144 CY

39,195 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 004 Proposal ID: 05-0443-032

Proposed Contract Period: Late Start Date of 06/27/16 with 50 WORK DAYS

Project(s):

Project No: BRFN-044-3(32)--39-05

County: AUDUBON

Type of Work: BRIDGE DECK OVERLAY

Route: IOWA 44 Length: 0.00 miles

Location: IA 44 OVER BLUE GRASS CREEK
0.1 MILE EAST OF US 71

Item No. Item Description Quantity/Unit

SECTION NO. 0001

DESIGN NO. 117; ITEMS FOR A 180'-0 X 58'-0 PRETENSIONED

PRESTRESSED CONCRETE BEAM BRIDGE

2403-0100000 STRUCT CONC (MISCELLANEOUS) 103 CY

2404-7775005 REINFORC STEEL, EPOXY COATED 11,254 LB 2413-0698074 DECK REPAIR, CL A 210 SY

2413-0698074 DECK REPAIR, CL A SECTION NO. 0002

DESIGN NO. 117; ALTERNATE 'AA' OPTION 1: CLASS O PCC

BID THIS SECTION IF IF ALTERNATE 'AA' OPTION 1 IS CHOSEN

2413-0698066 DECK OVERLAY (CL O PCC) 1,050 SY

SECTION NO. 0003

DESIGN NO. 117; ALTERNATE 'AA' OPTION 2 HPC-O PCC

BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN

2413-0698067 DECK OVERLAY (CL HPC-O PCC) 1,050 SY

SECTION NO. 0004

ROADWAY ITEMS

2102-2625000 EMBANKMENT-IN-PLACE 35 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 005 Proposal ID: 06-2186-051

Proposed Contract Period: Late Start Date of 06/27/16 with 80 WORK DAYS

Project(s):

Project No: BRFN-218-6(51)--39-06

County: BENTON

2122-5190007 PAVED SHLD, PCC, 7"

Type of Work: BRIDGE REPLACEMENT - CCS

Route: U.S. 218 Length: 0.00 miles

Location: OVER WILD CAT CREEK 2 MILES NORTH OF CO. RD. E44

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
D	DESIGN NO. 0516;90'-0 X 44'-0 CONTINUOUS CONCRETE	SLAB
Е	RIDGE	
2403-0100010	STRUCT CONC (BRIDGE)	277 CY
2404-7775005	REINFORC STEEL, EPOXY COATED	68,844 LB
SECTION	NO. 0002	
F	COADWAY ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	434 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	2,583 CY
SECTION	NO. 0004	
A	LTERNATE 'AA' OPTION 2 PCC SHOULDERS	
Е	ID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHO	SEN

644 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 006 Proposal ID: 11-C011-093

Proposed Contract Period: Late Start Date of 06/27/16 with 80 WORK DAYS

Project(s):

Project No: BROS-C011(93)--5F-11

County: BUENA VISTA

Type of Work: BRIDGE REPLACEMENT - CCS

Route: C43 Length: 0.00 miles

Location: C43: OVER BRANCH RACCOON RIVER

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 140'-0 X 30' CONTINUOUS CONCRETE SLAB BRIDGE

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 1,950 CY

 2303-0001000
 HMA WEDGE/LEVEL/STRENGTH
 31 TON

 2403-0100010
 STRUCT CONC (BRIDGE)
 370 CY

 2404-7775005
 REINFORC STEEL, EPOXY COATED
 87,438 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 007 Proposal ID: 12-C012-093

Proposed Contract Period: Late Start Date of 07/25/16 with 60 WORK DAYS

Project(s):

Project No: BROS-C012(93)--8J-12

County: BUTLER

Type of Work: BRIDGE REPLACEMENT - CCS

Route: CAMP COMFORT RD. Length: 0.00 miles Location: CAMP COMFORT RD: NW CORNER SEC 29 S 0.1 MI

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 100'-0 X 30 CONTINUOUS CONCRETE SLAB BRIDGE

 2102-2625000
 EMBANKMENT-IN-PLACE
 200 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 228 CY

 2404-7775005
 REINFORC STEEL, EPOXY COATED
 59,275 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 008 Proposal ID: 14-0713-500

Proposed Contract Period: Late Start Date of 08/29/16 with 15 WORK DAYS

Project(s):

Project No: MB-071-3(500)112--77-14

County: CARROLL

Type of Work: DECK JOINT REPAIR

Route: U.S. 71 Length: 0.00 miles Location: UP RR AND RD 0.2 MI S OF US 30 IN CARROLL

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 009 Proposal ID: 18-C018-066

Proposed Contract Period: Late Start Date of 08/15/16 with 40 WORK DAYS

Project(s):

Project No: BROS-C018(66)--5F-18

County: CHEROKEE

Type of Work: RCB CULVERT NEW - TRIPLE BOX

Route: L48 Length: 0.00 miles Location: L48: FROM 470TH STREET TO 480TH STREET

 Item No.
 Item Description
 Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TRIPLE 12' X 7' X 46' REINFORCED CONCRETE BOX CULVERT

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 743 CY

 2301-1032100
 STD/S-F PCC PAV'T, CL C CL 2, 10"
 320 SY

 2403-0100020
 STRUCT CONC (RCB CULV)
 259 CY

 2404-7775005
 REINFORC STEEL, EPOXY COATED
 41,396 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 010 Proposal ID: 25-1414-500

Proposed Contract Period: Late Start Date of 08/22/16 with 35 WORK DAYS

Project(s):

Project No: MB-141-4(500)134--77-25

County: DALLAS

Type of Work: BRIDGE REPAIR

Route: IOWA 141 Length: 0.00 miles Location: OVER BEAVER CREEK 1.3 MILES E. OF US 169

Project No: MB-169-4(500)105--77-25

County: DALLAS

Type of Work: BRIDGE REPAIR
Route: U.S. 169 Length: 0.00 mi.
Location: OVER BEAVER CREEK 1 MILE N. OF IA. 141 Length: 0.00 miles

Item Description Quantity/Unit ______

SECTION NO. 0003 ROADWAY ITEMS

MB-169-4(500)105--77-25

360 CY

2102-2625000 EMBANKMENT-IN-PLACE

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 011 Proposal ID: 25-1416-073

Proposed Contract Period: Late Start Date of 06/13/16 with 65 WORK DAYS

Project(s):

Project No: BRFN-141-6(73)--39-25

County: DALLAS

Type of Work: BRIDGE DECK OVERLAY

2102-2625000 EMBANKMENT-IN-PLACE

Route: IOWA 141 Length: 0.00 miles

Location: IA 141 OVER NORTH RACCOON RIVER

1.5 MILES W OF IA 144

Item No. Item Description	Quantity/Unit
SECTION NO. 0001	
DESIGN 117; 420'-0 X 44' CONTINUOUS WELDED PLATE G	IRDER
BRIDGE	
2403-0100000 STRUCT CONC (MISCELLANEOUS)	35 CY
2404-7775005 REINFORC STEEL, EPOXY COATED	5,930 LB
2413-0698074 DECK REPAIR, CL A	408 SY
SECTION NO. 0002	
DESIGN 117; ALTERNATE 'AA' OPTION 1: CLASS O PCC	
BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOS	SEN
2413-0698066 DECK OVERLAY (CL O PCC)	2,039 SY
SECTION NO. 0003	
DESIGN 117; ALTERNATE 'AA' OPTION 2: CLASS HPC-O H	PCC
BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOS	SEN
2413-0698067 DECK OVERLAY (CL HPC-O PCC)	2,039 SY
SECTION NO. 0004	
ROADWAY ITEMS	

188 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 012 Proposal ID: 29-0345-507

Proposed Contract Period: Late Start Date of 07/25/16 with 70 WORK DAYS

Project(s):

Project No: MB-034-5(507)263--77-29

County: DES MOINES Type of Work: BRIDGE REPAIR

Route: U.S. 34 Length: 0.00 miles

Location: IN BURLINGTON AT 8TH ST

Project No: MB-027-5(500)8--77-56

County: LEE

Type of Work: BRIDGE REPAIR
Route: IOWA 27 Length: 0.00 miles
Location: OVER SUGAR CREEK 7.6 MILES N. OF MISSOURI STATE LINE

Project No: MB-022-5(501)59--77-70
County: MUSCATINE
Type of Work: BRIDGE APPROACH REPAIR

Route: IOWA 22 Length: 0.00 miles Location: WAPSINONOC CREEK 1.6 MI E OF W JCT IA 70

Item No. Item Description Quantity/Unit ______

SECTION NO. 0001

DESIGN NO. 0116; 218'-0 X 30'-0 PRETENSIONED PRESTRESSED

MB-034-5(507)263--77-29 CONCRETE BEAM BRIDGE

2403-0100010 STRUCT CONC (BRIDGE) 2404-7775005 REINFORC STEEL, EPOXY COATED 94 CY

8,315 LB

SECTION NO. 0003

ROADWAY ITEMS

MB-027-5 (500) 8--77-56

720 CY

2102-2625000 EMBANKMENT-IN-PLACE

SECTION NO. 0006

DESIGN NO. 0116; 172'-2 X 36'-0 PRETENSIONED PRESTRESSED

CONCRETE BEAM BRIDGE MB-027-5(500)8--77-56

2413-0698074 DECK REPAIR, CL A 6 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 013 Proposal ID: 34-C034-093

Proposed Contract Period: Late Start Date of 07/05/16 with 75 WORK DAYS

Project(s):

Project No: BRS-C034(93)--60-34

County: FLOYD

Type of Work: BRIDGE REPLACEMENT - CCS

Route: B30 Length: 0.00 miles

Location: B30: OVER FLOOD CREEK

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 150' X 30' CONTINUOUS CONCRETE SLAB BRIDGE

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 603 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 391 CY

 2404-7775005
 REINFORC STEEL, EPOXY COATED
 94,902 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 014 Proposal ID: 35-C035-087

Proposed Contract Period: Late Start Date of 07/25/16 with 60 WORK DAYS

Project(s):

Project No: BROS-C035(87)--8J-35

County: FRANKLIN

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: WARBLER AVE Length: 0.50 miles

Location: ON WARBLER AVENUE, OVER SMALL STREAM, FROM 160TH STREET NORT

H 1 MILES TO 170TH STREET, ALONG WLINE S23 T92 R19

Project No: BROS-C035(89)--5F-35

County: FRANKLIN

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX
Route: 115TH ST Length: 0.00 miles
Location: ON 115TH STREET (C51), OVER SMALL STREAM, FROM TULIP AVENUE

EAST THREE FOURTHS MILES TO VIOLET AVENUE, IN S15 T91 R19

Item Description Item No. Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TWIN 12' X 8' X 82'-0 PRECAST CONCRETE BOX

CULVERT BROS-C035(87)--8J-35

2102-2625000 EMBANKMENT-IN-PLACE

572 CY

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW

3,137 CY

SECTION NO. 0002

ITEMS FOR A TWIN 10' X 10' X 48'-0 PRECAST CONCRETE BOX

CULVERT BROS-C035(89)--5F-35

2102-2625000 EMBANKMENT-IN-PLACE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW

1,722 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 015 Proposal ID: 42-C042-079

Proposed Contract Period: Late Start Date of 06/20/16 with 85 WORK DAYS

Project(s):

Project No: BHS-C042(79)--63-42

County: HARDIN

Type of Work: RECONSTRUCTION - BRIDGE DECK REPLACEMENT Route: S27 Length: 0.10 miles

Location: ON S27, OVER SOUTH FORK IOWA RIVER, FROM STATE HIGHWAY 20 N

0.25 MILES, S11 T88 R22

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 167'-6 X 30'-0 PRETENSIONED PRESTRESSED CONCRETE

BEAM BRIDGE

2102-2625000 EMBANKMENT-IN-PLACE 132 CY 2403-0100010 STRUCT CONC (BRIDGE) 177 CY 2404-7775005 REINFORC STEEL, EPOXY COATED 43,048 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 016 Proposal ID: 44-C044-076

Proposed Contract Period: Late Start Date of 06/20/16 with 90 WORK DAYS

Project(s):

Project No: BROS-C044(76)--8J-44

County: HENRY

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: ASH AVE Length: 0.10 miles

Location: ON ASH AVENUE, OVER ROCK CREEK

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 80'-0 X 30'-6 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

 2102-2625000
 EMBANKMENT-IN-PLACE
 1,255 CY

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 997 CY

 2403-0100010
 STRUCT CONC (BRIDGE)
 158 CY

 2404-7775000
 REINFORC STEEL
 38,523 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 017 Proposal ID: 45-C045-076

Proposed Contract Period: Late Start Date of 06/27/16 with 80 WORK DAYS

Project(s):

Project No: EDP-C045(76)--7Y-45

County: HOWARD

Type of Work: BRIDGE NEW - PPCB
Route: WAPSI-GREAT WESTERN Length: 0.00 miles
Location: ON WAPSIE GREAT WESTERN TRAIL - 2 TRAIL BRIDGES

-	Item No.	Item Description	Quantity/Unit
	SECTION	NO. 0001	
	2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	5,300 CY
		STRUCT CONC (BRIDGE) REINFORC STEEL	147 CY 187 LB
	2404-7775005	REINFORC STEEL, EPOXY COATED	27 , 564 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 018 Proposal ID: 53-1362-027

Proposed Contract Period: Late Start Date of 06/27/16 with 60 WORK DAYS

Site 01: TO COMPLETE STAGE 1

Late Start Date of 06/27/16 with 40 WORK DAYS

Proposal Note:

SITE 01

TO COMPLETE STAGE 1 WHEN DETOUR IS IN EFFECT.

WORK RESTRICTIONS

NO ROAD CLOSURES WILL BE ALLOWED PRIOR TO MAY 16, 2016.

Project(s):

Project No: BRFN-136-2(27)--39-53

County: JONES
Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX
Route: IOWA 136 Length: 0.00 miles
Location: OVER SMALL STREAM 1.1 MILES S. OF CO. RD. X-64

Item No. Item Description Quantity/Unit _____

SECTION NO. 0001

DESIGN NO. 0116; TWIN12' X 9' X 82' REINFORCED CONCRETE BOX

CULVERT

2403-0100020 STRUCT CONC (RCB CULV) 282 CY

2404-7775000 REINFORC STEEL 52,874 LB

SECTION NO. 0002

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1033090 STD/S-F PCC PAV'T, CL C CL 3, 9" 1,119 CY

311 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 019 Proposal ID: 57-3806-274-A

Proposed Contract Period: Late Start Date of 06/06/16 with 85 WORK DAYS

Site 01: TO COMPLETE STAGE 1A

Late Start Date of 06/06/16 with 10 WORK DAYS

Proposal Note:

SITE 02

CALENDAR DAYS ARE BASED ON 4 DAYS FOR EACH WEEKEND OF WORK,

FRIDAY NIGHT THROUGH MONDAY MORNING.

LIQUIDATED DAMAGES OF \$5000 FOR NOT OPENING NORTHBOUND LANES

AND ENTRANCE RAMP BY 6:00 AM MONDAY MORNING.

Project(s):

Project No: IMN-380-6(274)17--0E-57

County: LINN

Type of Work: DECK JOINT REPAIR
Route: I-380 Length: 0.00 miles
Location: IN THE CITY OF CEDAR RAPIDS OVER THE CIC R.R. & CITY STREET

(NBL/SBL)

Project No: MBIN-380-6(551)17--0M-57

County: LINN

Type of Work: DECK JOINT REPAIR

Route: I-380 Length: 0.00 miles Location: N.B. / S.B. I-380 OVER UNION PACIFIC R.R.

1.0 MI. N. OF JCT. US 30

Item No. Item Description Ouantity/Unit ______

SECTION NO. 0001

DESIGN NO. 0115; 564'-0 X 52'-0 PRETENSIONED PRESTRESSED

CONCRETE BEAM BRIDGE

IMN--380-6(274)17--0E-57 19 CY

2403-0100000 STRUCT CONC (MISCELLANEOUS) 2404-7775005 REINFORC STEEL, EPOXY COATED

1,943 LB

SECTION NO. 0002

DESIGN NO. 0215; 564'-0 X 52'-0 PRETENSIONED PRESTRESSED

IMN-380-6(274)17--0E-57

CONCRETE BEAM BRIDGE 2403-0100000 STRUCT CONC (MISCELLANEOUS)

19 CY

2404-7775005 REINFORC STEEL, EPOXY COATED

1,975 LB

SECTION NO. 0004

DESIGN NO. 0217; 293'-6 X 52'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE

MBIN-380-6(551)17--0M-57

2403-0100000 STRUCT CONC (MISCELLANEOUS) 2404-7775005 REINFORC STEEL, EPOXY COATED

11 CY 1,231 LB

SECTION NO. 0005

DESIGN NO. 0317; 293'-6 X 52'-0 PRETENSIONED PRESTRESSED

CONCRETE BEAM BRIDGE MBIN-380-6)551)17--0M-57

11 CY

2403-0100000 STRUCT CONC (MISCELLANEOUS) 2404-7775005 REINFORC STEEL, EPOXY COATED

1,246 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 020 Proposal ID: 61-C061-099

Proposed Contract Period: Late Start Date of 05/23/16 with 110 WORK DAYS

Project(s):

Project No: BROS-C061(99)--8J-61

County: MADISON

Type of Work: BRIDGE REPLACEMENT - CCS
Route: LARKSPUR AVE Length: 0.10 miles Location: LARKSPUR AVE.: OVER S FORK CLANTON CREEK

Item No.	Item Description	Quantity/Unit
	NO. 0001 ITEMS 120'-0 X 24'-6 CONTINUOUS CONCRETE SLAB BRIDG	E
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,769 CY
2403-0100000	STRUCT CONC (MISCELLANEOUS)	5 CY
2403-0100010	STRUCT CONC (BRIDGE)	253 CY
2404-7775000	REINFORC STEEL	59,975 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 021 Proposal ID: 75-0031-089

Proposed Contract Period: Late Start Date of 07/05/16 with 70 WORK DAYS

Project(s):

Project No: BRFN-003-1(89)--39-75

County: PLYMOUTH

Type of Work: RCB CULVERT REPLACEMENT - SINGLE BOX Route: IOWA 3 Length: 0.00 miles Location: OVER DITCH 2.6 MILES W. OF CO. RD. K-42

Item No.	Item Description	Quantity,	/Unit
SECTION	NO. 0001		
D	ESIGN NO. 0116; 12' X 12' X 90'-0 REINFORCED C	ONCRETE BOX	
C	CULVERT		
2403-0100020	STRUCT CONC (RCB CULV)	296	CY
2404-7775000	REINFORC STEEL	46,934	LB
SECTION	NO. 0002		
R	COADWAY ITEMS		
2102-2625000	EMBANKMENT-IN-PLACE	2,474	CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	372	CY
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	92	CY
2303-0031500	HMA (1M ESAL) BASE, 1/2"	82	TON
2303-0032500	HMA (1M ESAL) INTERMEDIATE, 1/2"	86	TON
2303-0033503	HMA (1M ESAL) SURF, 1/2", FRIC L-3	130	TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 022 Proposal ID: 82-1827-673

Proposed Contract Period: Late Start Date of 04/18/16 with 130 WORK DAYS

Project(s):

Project No: BHM-1827(673)--8K-82

County: SCOTT

Type of Work: RECONSTRUCTION - BRIDGE DECK REPLACEMENT Route: KIMBERLY ROAD Length: 0.00 miles

Location: IN THE CITY OF DAVENPORT, KIMBERLY RD.: DUCK CREEK

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW

600 CY

SECTION NO. 0002

BRIDGE ITEMS FOR A 170'-0 X 52'-0 CONTINUOUS I-BEAM BRIDGE

2403-0100010 STRUCT CONC (BRIDGE)

271 CY

2404-7775005 REINFORC STEEL, EPOXY COATED

99,244 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 023 Proposal ID: 85-C085-139

Proposed Contract Period: Late Start Date of 07/25/16 with 60 WORK DAYS

Project(s):

Project No: FM-C085(137)--55-85

County: STORY

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 660TH AVE Length: 0.10 miles

Location: 660TH AVE.: 0.23 MI SOUTH OF NW CORNER OF SECTION 23-84-22

OVER DRAINAGE DITCH

Project No: FM-C085(139)--55-85

County: STORY

Type of Work: RCB CULVERT REPLACEMENT - TRIPLE BOX
Route: 305TH ST Length: 0.10 miles
Location: ON 305TH ST., OVER CALAMUS CREEK, IN S18 T82 R22

Project No: FM-C085(140)--55-85

County: STORY

Type of Work: RCB CULVERT REPLACEMENT - TWIN BOX

Route: 580TH AVE Length: 0.10 miles

Location: ON 580TH AVE., OVER SMALL STREAM, ON WLINE S33 T84 R23

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TWIN 12' X 8' X 44' REINFORCED CONCRETE BOX

CULVERT - FM-C085(137)--55-85

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW

SECTION NO. 0002

ITEMS FOR A TRIPLE 10' X 8' X 42' REINFORCED CONCRETE BOX

CULVERT - FM-C085(139)--55-85

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 340 CY

SECTION NO. 0003

ITEMS FOR A TWIN 8' X 5' X 46' REINFORCED CONCRETE BOX

CULVERT - FM-C085(140)--55-85

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 213 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 024 Proposal ID: 91-0653-074

Proposed Contract Period: Late Start Date of 06/13/16 with 90 WORK DAYS

Project(s):

Project No: BRF-065-3(74)--38-91

County: WARREN

2122-5190007 PAVED SHLD, PCC, 7"

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: U.S. 65 Length: 0.00 miles

Location: US 65 OVER MIDDLE RIVER (NBL) 0.4 MILES SOUTH OF CO. RD. G-24

Item No. Item Description	on Quantity/Un:	 it
SECTION NO. 0001		
	A 359'-0 X 44'-0 PRESTRESSED PRETENSIONED	
2403-0100010 STRUCT CONC (BF		
2404-7775000 REINFORC STEEL	76,601 LB	
2404-7775005 REINFORC STEEL,	EPOXY COATED 165,569 LB	
SECTION NO. 0002		
ROADWAY ITEMS		
2102-2710070 EXCAVATION, CL	10, RDWY+BORROW 2,545 CY	
2301-1003100 STD/S-F PCC PAY	7'T, QM-C CL 3, 10" 666 SY	
SECTION NO. 0004		
DESIGN NO. 1016;	ALTERNATE 'AA' OPTION 2: PCC SHOULDER	

BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN

540 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 025 Proposal ID: 93-C093-067

Proposed Contract Period: Late Start Date of 08/15/16 with 50 WORK DAYS

Project(s):

Project No: BROS-C093(67)--5F-93

County: WAYNE

Type of Work: RCB CULVERT NEW - TWIN BOX

Route: S-34 Length: 0.00 miles

Location: ON S34 OVER DUCK CREEK, FROM OVER DUCK CREEK AT NW S29 T68N

R21W

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A TWIN 12' X 10' REINFORCED CONCRETE BOX CULVERT

2403-0100020 STRUCT CONC (RCB CULV) 425 CY 2404-7775000 REINFORC STEEL 62,400 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 026 Proposal ID: 93-C093-078

Proposed Contract Period: Late Start Date of 04/04/16 with 110 WORK DAYS

Project(s):

Project No: FM-C093(78)--55-93

County: WAYNE

Type of Work: BRIDGE DECK OVERLAY

Route: S-60 Length: 0.00 miles

Location: ON S60, OVER WALNUT CREEK, FROM IA HWY 2 SOUTH 1/2 MILES TO

NORTH 1/4 OF S35 T69N R20W, IN SE S26 T69 R20

Project No: FM-C093(79)--55-93

County: WAYNE

Type of Work: BRIDGE DECK OVERLAY
Route: J-22 Length: 0.00 miles
Location: ON J22, OVER DUCK VALLEY CREEK, FROM INT OF 180TH ST AND J22

SE 1/4 MILES TO E LINE OF S23 T70N R21W, IN SE S23 T70 R21

Item Description Ttem No. Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 117'-6 X 28'-0 PRETENSIONED PRESTRESSED CONCRETE BEAM BRIDGE FM-C093(78)--55-93

2102-2625000 EMBANKMENT-IN-PLACE

580 CY

2403-0100010 STRUCT CONC (BRIDGE)

14 CY

2404-7775005 REINFORC STEEL, EPOXY COATED

2,422 LB

2413-0698081 DECK REPAIR, CL A, SPECIAL

SECTION NO. 0002

DECK OVER-DEPTH OVERLAY; ALTERNATE 'AA' OPTION 1: CL. O PCC

BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (78)

2413-0698041 DECK O-DEPTH OVERLAY (CL O PCC)

SECTION NO. 0003

DECK OVER-DEPTH OVERLAY; ALTERNATE 'AA' OPTION 2 CL. HPC-O

BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN (78)

2413-0698051 DECK O-DEPTH OVERLAY (CL HPC-O)

SECTION NO. 0004

ITEMS FOR A 100'-0 X 28'-0 CONTINUOUS CONCRETE SLAB BRIDGE

FM-C093(79)--55-93

2102-2625000 EMBANKMENT-IN-PLACE

580 CY

2413-0698081 DECK REPAIR, CL A, SPECIAL

SECTION NO. 0005

DECK OVER-DEPTH OVERLAY; ALTERNATE 'BB' OPTION 1: CL. O PCC BID THIS SECTION IF ALTERNATE 'BB' OPTION 1 IS CHOSEN (79)

2413-0698041 DECK O-DEPTH OVERLAY (CL O PCC)

SECTION NO. 0006

DECK OVER-DEPTH OVERLAY; ALTERNATE 'BB' OPTION 2: CL. HPC-O

BID THIS SECTION IF ALTERNATE 'BB' OPTION 2 IS CHOSEN (79)

2413-0698051 DECK O-DEPTH OVERLAY (CL HPC-O) 727 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 027 Proposal ID: 97-3761-006

Proposed Contract Period: Specified Start Date of 03/14/16 with 140 WORK DAYS

Project(s):

Project No: BRF-376-1(6)--38-97

County: WOODBURY

SECTION NO. 0002

Type of Work: BRIDGE REPLACEMENT - PPCB

Route: IOWA 376 Length: 0.00 miles

Location: IA 376 N.B. OVER BNSF R.R., CN R.R. & TAFT ST.

0.1 MILE S. OF CO. RD. D-12

Item No. Item Description Quantity/Unit

SECTION NO. 0001

DESIGN NO. 0215; A 562'-7 1/4 X 40'-0 PRETENSIONED

PRESTRESSED CONCRETE BEAM BRIDGE

2403-0100010 STRUCT CONC (BRIDGE) 773 CY

2404-7775000 REINFORC STEEL 85,272 LB

2404-7775005 REINFORC STEEL, EPOXY COATED 260,511 LB

28,164 CY

2,719 SY

ROADWAY ITEMS
2102-2625001 EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH
2301-1033100 STD/S-F PCC PAV'T, CL C CL 3, 10"

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 028 Proposal ID: 97-7057-687

Proposed Contract Period: Late Start Date of 07/18/16 with 90 WORK DAYS

Project(s):

Project No: BHM-7057(687)--8K-97

County: WOODBURY

Type of Work: BRIDGE REHABILITATION

Route: 18TH STREET Length: 0.00 miles

Location: IN THE CITY OF SIOUX CITY, ON 18TH STREET BRIDGE, OVER FLOYD

RIVER

2511-0301500 RECREATIONAL TRAIL, HMA, 5" 2511-0302600 RECREATIONAL TRAIL, PCC, 6"

Item No.	Item Description	Quantity,	/Unit
SECTION	NO. 0001		
	REPAIRS TO A 360'-6 X 48' CONTINUOUS WELDED PLATE		
(GIRDER BRIDGE		
2102-2625000	EMBANKMENT-IN-PLACE	100	CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	50	CY
2403-0100010	STRUCT CONC (BRIDGE)	691	CY
2404-7775000	REINFORC STEEL	1,038	LB
2404-7775005	REINFORC STEEL, EPOXY COATED	224,557	LB
2511-0301500	RECREATIONAL TRAIL, HMA, 5"	240	SY

36 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 029 Proposal ID: 98-C098-071

Proposed Contract Period: Late Start Date of 08/01/16 with 50 WORK DAYS

Project(s):

Project No: BHS-C098(71)--63-98

County: WORTH

Type of Work: RECONSTRUCTION - BRIDGE DECK REPLACEMENT Route: CO RD 105 Length: 0.00 miles Location: ON HWY 105, OVER DD #2, AT SE S26 T100N R21W

Item No. Item Description	Quantity/Unit
SECTION NO. 0001	
ITEMS FOR A 33'-7 3/4 X 30'-0 STEEL I-BEAM BRIDGE	
2403-0100010 STRUCT CONC (BRIDGE)	30 CY
2404-7775005 REINFORC STEEL, EPOXY COATED	12,765 LB
SECTION NO. 0002	
ROADWAY ITEMS	
2102-2625000 EMBANKMENT-IN-PLACE	72 CY
2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	245 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 030 Proposal ID: 99-C099-079

Proposed Contract Period: Late Start Date of 06/06/16 with 100 WORK DAYS

Project(s):

Project No: BROS-C099(79)--5F-99

County: WRIGHT

Type of Work: RCB CULVERT REPLACEMENT - TRIPLE BOX Route: R-65 Length: 0.00 miles

Location: OVER LUICKS CREEK, AT ELINE S32 T93 R23

Item No.	Item Description	Quantity/Unit
SECTION	 NO. 0001 TEMS FOR A TRIPLE 12' X 10' X 74'-0 RCB CULVERT	
2102-2625000	EMBANKMENT-IN-PLACE	883 CY 190 CY
2301-1033080	EXCAVATION, CL 10, RDWY+BORROW STD/S-F PCC PAV'T, CL C CL 3, 8"	571 SY
	STRUCT CONC (RCB CULV) REINFORC STEEL	471 CY 72,483 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 081 Proposal ID: 17-C017-071

Proposed Contract Period: Late Start Date of 06/06/16 with 90 WORK DAYS

Site 01: STAGE 1 TRAIL CLOSURE, REFER TO PLAN SHEET J.01.

No Start Date Specified with 30 WORK DAYS

Site 02: STAGE 4 TRAIL CLOSURE, REFER TO PLAN SHEET J.01.

No Start Date Specified with 20 WORK DAYS

Proposal Note:

THIS PROJECT INCLUDES A \$133,000 ALTERNATIVE DIFFERENTIAL (D) FOR THE ALTERNATIVE BID OF OPTION 1 - PCC ROADWAY (BETTER VALUE ALTERNATIVE) VS. OPTION 2 - HMA ROADWAY (BASE ALTERNATIVE).

Project(s):

Project No: STP-S-C017(71)--5E-17
County: CERRO GORDO

Type of Work: ALTERNATE PAVEMENT TYPES-MAINLINE PAVING
Route: B35
Length: 2.49 miles
Location: ON B-35, FROM NEAR MASON CITY WEST 2.5 MILES TO NEAR CLEAR L

AKE CITY LIMITS

_____ Item No. Item Description Quantity/Unit ______

SECTION NO. 0001

ROADWAY ITEMS

2102-2625000 EMBANKMENT-IN-PLACE 2,873 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 5,265 CY

SECTION NO. 0002

ALTERNATE 'AA' OPTION 1: PCC ROADWAY

BID THIS SECTIONIF ALTERNATE 'AA' OPTION 1 IS CHOSEN

2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 53,762 SY SECTION NO. 0003

ALTERNATE 'AA' OPTION 2: HMA ROADWAY

BID THIS SECTION IF ALTERNATE 'AA' OPTION 2 IS CHOSEN

800 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2303-0141750 HMA (3M ESAL) BASE, 3/4" 53,762 SY 2303-0142750 HMA (3M ESAL) INTERMEDIATE, 3/4" 53,762 SY 53,762 SY 2303-0143500 HMA (3M ESAL) SURF, 1/2", NO FRIC

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 101 Proposal ID: 07-8155-741

Proposed Contract Period: Late Start Date of 07/11/16 with 65 WORK DAYS

Project(s):

Project No: TAP-U-8155(741)--8I-07

County: BLACK HAWK

Type of Work: PCC SIDEWALK/TRAIL

Route: SHAULIS ROAD TRAIL Length: 0.00 miles

Location: IN THE CITY OF WATERLOO, ON SHAULIS RD., FROM IOWA 21 TO

ISLE OF CAPRI BLVD.

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
F	ROADWAY ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	9,987 CY
2301-1082060	STD/S-F PCC PAV'T, CL M CL 2, 6"	298 SY
2301-1082080	STD/S-F PCC PAV'T, CL M CL 2, 8"	106 SY
2511-0302500	RECREATIONAL TRAIL, PCC, 5"	10,280 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	211 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 102 Proposal ID: 31-1363-047

Proposed Contract Period: Late Start Date of 06/06/16 with 20 WORK DAYS

Project(s):

Project No: NHSN-136-3(47)--2R-31

County: DUBUQUE

Type of Work: PCC SIDEWALK/TRAIL

Route: IOWA 136 Length: 0.00 miles

Location: IN NEW VIENNA

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001 OADWAY ITEMS	
	STRUCT CONC (MISCELLANEOUS)	0 CY
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	91 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	8 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 103 Proposal ID: 32-2417-605

Proposed Contract Period: Late Start Date of 07/01/16 with 45 WORK DAYS

Project(s):

Project No: TAP-U-2417(605)--8I-32

County: EMMET

Type of Work: PCC SIDEWALK/TRAIL

Route: TRAIL Length: 0.87 miles

Location: CENTRAL AVENUE: TRAIL FOLLOWS ALONG DES MOINES RIVER CORRIDO

R FROM 375TH AVE SOUTH 1.02 MILES

Item No. Item Description Quantity/Unit

SECTION NO. 0001

TRAIL ITEMS

2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 1,020 CY 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 6,768 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 104 Proposal ID: 40-C040-091

Proposed Contract Period: Late Start Date of 06/20/16 with 85 WORK DAYS

Project(s):

Project No: TAP-R-C040(91)--8T-40

County: HAMILTON

Type of Work: PCC SIDEWALK/TRAIL

Route: JEWELLSWORTH TRAIL Length: 0.00 miles

Location: ON JEWELL TO ELLSWORTH SEGMENT OF LAKE PATH TRAIL, FROM EAST

OF JEWELL EAST 4300 FEET TO JUST WEST OF ELLSWORTH

_		
	Item No. Item Description	Quantity/Unit
	SECTION NO. 0001	
	ROADWAY ITEMS	
	2102-2625000 EMBANKMENT-IN-PLACE	791 CY
	2102-2710070 EXCAVATION, CL 10, RDWY+BORROW	1,446 CY
	2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8"	316 SY
	2511-0302600 RECREATIONAL TRAIL, PCC, 6"	16,946 SY
	2511-0302800 RECREATIONAL TRAIL, PCC, 8"	255 SY
	SECTION NO. 0003	
	ITEMS FOR A 65'-0 X 10'-6 TIMBER BEAM BRIDGE	
	2403-0100010 STRUCT CONC (BRIDGE)	12 CY
	2404-7775000 REINFORC STEEL	880 LB
	SECTION NO. 0004	
	ITEMS FOR A 226'-0 X 10'-6 STEEL GIRDER BRIDGE	
	2403-0100010 STRUCT CONC (BRIDGE)	41 CY
	2404-7775000 REINFORC STEEL	3,070 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 105 Proposal ID: 47-0202-103

Proposed Contract Period: Late Start Date of 04/04/16 with 20 WORK DAYS

Site 01: SEE SITE NUMBER 01 DESCRIPTION BELOW.

Completion Date of 12/01/18

COMPLECTOR Date of 12/01/10

Site 02: SEE SITE NUMBER 02 DESCRIPTION BELOW.

Approx Start Date of 05/16/16 with 60 WORK DAYS

Site 03: SEE SITE NUMBER 03 DESCRIPTION BELOW.

Completion Date of 09/01/16

Proposal Note:

*** SITE NUMBER CONTRACT ***

THIS IS FOR ALL WORK NOT COVERED BY SITE 01. THIS IS FOR EROSION CONTROL AND SEEDING.

*** SITE NUMBER 01 ***

THIS SITE IS FOR THE COMPLETION OF ALL WORK THROUGH STAGE 6 SO THAT ALL OF US 20 MAINLINE, US 20 SHOULDERS, AND COUNTY ROADS ARE OPEN TO TRAFFIC. THIS INCLUDES THE COMPLETION OF ALL SAFETY ITEMS NEEDED TO OPEN THE ROADWAY TO TRAFFIC. THESE SAFETY ITEMS INCLUDE ITEMS SUCH AS GUARDRAIL, PAINT LINES AND REGULATORY SIGNING.

SITE NUMBER 01 ALSO HAS A ROAD OPENING BONUS AS FOLLOWS:

ROAD OPENING BONUS FOR CONTRACT

THE CONTRACTOR WILL BE PAID THE PREDETERMINED AMOUNT SHOWN IN THE PROPOSAL SCHEDULE FOR ROAD OPENING BONUS FOR COMPLETING CONSTRUCTION SO THAT NEW US 20 MAINLINE, US 20 SHOULDERS AND COUNTY ROAD CONNECTIONS ARE OPEN TO TRAFFIC. COMPLIANCE REQUIRES THAT ALL SAFETY ITEMS ARE COMPLETED. THIS INCLUDES ITEMS SUCH AS GUARDRAIL, PAINT LINES AND REGULATORY SIGNING. FAILURE TO OPEN US 20 TO TRAFFIC DUE TO WEATHER, CHANGE ORDERS, CHANGE IN QUANTITIES, UTILITY DELAYS OR ANY OTHER DELAYS WILL NOT BE CONSIDERED AS A JUSTIFICATION TO MODIFY THE DATE OR JUSTIFY PAYMENT OF THE BONUS.

SCHEDULE FOR ROAD OPENING BONUS:

OPENING DATE / BONUS

ON OR BEFORE 11/16/18 --- \$1,500,000

11/17/18 --- \$1,400,000

11/18/18 --- \$1,300,000

11/19/18 --- \$1,200,000

11/20/18 --- \$1,100,000

11/21/18 --- \$1,000,000

11/22/18 --- \$900,000

11/23/18 --- \$800,000

11/24/18 --- \$700,000

11/25/18 --- \$600,000

Project(s):

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only) Project No: NHSN-020-2(103)--2R-47 County: IDA Type of Work: PCC PAVEMENT - GRADE AND NEW Route: U.S. 20 Length: Location: E JCT US 59 TO W OF ADAMS AVE Length: 6.66 miles Project No: NHSN-020-2(118)--2R-47 County: IDA Type of Work: TRAFFIC SIGNS Route: U.S. 20 Length: 7.96 miles Location: E JCT US 59 TO W OF ADAMS AVE Project No: NHSN-020-2(139)--2R-47 County: IDA Type of Work: BRIDGE REPLACEMENT - PPCB Route: U.S. 20 Length: 7.96 miles Location: FRITZ CREEK 3.4 MILES EAST OF E JCT. U.S. 59 Project No: NHSN-020-2(140)--2R-47County: IDA

Type of Work: BRIDGE REPLACEMENT - STEEL GIRDER
Route: U.S. 20 Length: 7.9
Location: US 20 OVER MAPLE RIVER Length: 7.96 miles 4.1 MI EAST OF E. JCT. US 59 Project No: NHSN-020-2(141)--2R-47 County: IDA Type of Work: RCB CULVERT NEW - TRIPLE BOX Route: U.S. 20 Length: 7.96 miles Location: E JCT US 59 TO W OF ADAMS AVE Project No: NHSN-020-2(144)--2R-47 County: IDA
Type of Work: LIGHTING
Route: U.S. 20
Location: E JCT US 59 Length: 7.96 miles ______ Item No. Item Description Quantity/Unit _____ SECTION NO. 0001 ROADWAY ITEMS NHSN-020-2(103)--2R-47 2102-2624980 CONTRACTOR FURNISH SELECT TREATMENT 242,182 CY 2102-2625000 EMBANKMENT-IN-PLACE 178,846 CY 1,242,805 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2301-1003100 STD/S-F PCC PAV'T, QM-C CL 3, 10" 220,740 SY 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2"
2303-0043502 HMA (3M ESAL) SURF, 1/2", FRIC L-2
2529-5070111 PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT) 32 TON 121 TON 281 SY SECTION NO. 0002 ALTERNATE 'AA' OPTION 1: PCC SHOULDER BID THIS SECTION IF ALTERNATE 'AA' OPTION 1 IS CHOSEN (103) 2122-5190006 PAVED SHLD, PCC, 6" 53,471 SY SECTION NO. 0007 DESIGN NO. 0316; 253'-0 X 40 PRETENDSIONED PRESTRESSED

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

(for information only)	
CONCRETE BEAM BRIDGE NHSN-020-2(139)2R-47	
2403-0100010 STRUCT CONC (BRIDGE) 118	CY
2404-7775000 REINFORC STEEL 9,300	LB
2404-7775005 REINFORC STEEL, EPOXY COATED 110,816	LB
SECTION NO. 0008	
DESIGN NO. 0416; 253'-0 X 40' PRETENSIONED PRESTRESSED	
CONCRETE BEAM BRIDGE NHSN-020-2(139)2R-47	
2403-0100010 STRUCT CONC (BRIDGE) 116	CY
2404-7775000 REINFORC STEEL 9,384	
2404-7775005 REINFORC STEEL, EPOXY COATED 110,870	
SECTION NO. 0010	
DESIGN NO. 0616; 340'-0 X 40 ROLLED STEEL BEAM BRIDGE	
NHSN-020-2 (140) 2R-47	
2403-0100010 STRUCT CONC (BRIDGE) 299	CY
2404-7775000 REINFORC STEEL 34,660	
2404-7775005 REINFORC STEEL, EPOXY COATED 138,615	
SECTION NO. 0011	ענד
DESIGN NO. 0716; 340'-0 X 40 ROLLED STEEL BEAM BRIDGE	
NHSN-020-2 (140) 2R-47	
2403-0100010 STRUCT CONC (BRIDGE) 299	CV
2404-7775000 REINFORC STEEL 34,660	
2404-7775005 REINFORC STEEL, EPOXY COATED 138,615	
SECTION NO. 0013	ענד
BID ITEMS FOR A 8'-0 X 6 REINFORCED CONCRETE	
3:1 FLUME AND BASIN NHSN-020-2(141)2R-47	
2403-0100020 STRUCT CONC (RCB CULV) 50	CV
2404-7775000 REINFORC STEEL 9,114	
SECTION NO. 0014	טע
DESIGN NO. 0216; TWIN 8' X 6' REINFORCED CONCRETE BOX	
CULVERT NHSN-020-2 (141) 2R-47	
2102-2625000 EMBANKMENT-IN-PLACE 1,800	CV
2403-0100020 STRUCT CONC (RCB CULV) 373	
2403-0100020 SIROCI CONC (RCB COLV) 373 2404-7775000 REINFORC STEEL 50,686	
SECTION NO. 0015	ПЪ
DESIGN NO. 0516; ALTERNATE 'BB' OPTION 1: CAST IN PLACE	
BID THIS SECTION IF ALTERNATE 'BB' OPTION 1: IS CHOSEN (141) 2403-0100020 STRUCT CONC (RCB CULV) 845	CV
2404-7775000 REINFORC STEEL 139,720	
2404-///3000 REINFORC STEEL 139,/20	ΤВ

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 106 Proposal ID: 57-1001-073

Proposed Contract Period: Late Start Date of 04/04/16 with 300 WORK DAYS

Proposal Note:

*** INCENTIVE/DISINCENTIVE ***

SECTION 1111 OF THE STANDARD SPECIFICATIONS FOR INCENTIVE/DISINCENTIVE (I/D) FOR EARLY COMPLETION SHALL APPLY TO THIS PROJECT WITH THE FOLLOWING CONDITIONS:

SITE NUMBER 01:

PHASES 2A AND 2B (THE STORM SEWER CROSSINGS OF COLLINS ROAD) 14 CLOSURE DAYS/CALENDAR DAYS, I/D RATE \$5,000.00 PER DAY

THERE ARE NO MAXIMUM INCENTIVE OR DISINCENTIVE (LIQUIDATED DAMAGES) AMOUNTS. THE INCENTIVE/DISINCENTIVE AMOUNT WILL BE PAID/COLLECTED BY THE CONTRACTING AUTHORITY UPON COMPLETION OF THE CRITICAL CLOSURE ACTIVITY.

CRITCAL CLOSURE ACTIVITY

WHEN COLLINS ROAD TRAFFIC IS CONFIGURED AS SHOWN ON SHEETS J.16 THROUGH J.19.

WORK RESTRICTIONS

NO WORK THAT AFFECTS TRAFFIC MAY BE PERFORMED FROM NOVEMBER 1 THROUGH DECEMBER 31 IN 2016, 2017, AND 2018.

NO WORK MAY BE PERFOMED ON SUNDAYS ON THE CHIK-FIL-A SITE.

Project(s):

Project No: HDP-100-1(73)--71-57

County: LINN

Type of Work: PCC PAVEMENT - NEW
Route: IOWA 100 Length: 0.43 miles
Location: IN THE CITY OF CEDAR RAPIDS, IA100: E OF NORTHLAND AVE NE TO E OF TWIXT TOWN RD NE AND LINDALE DR: TO APPROX 800 FT N

Item No.	Item Description	Quantity,	/Unit
 SECTION 1	NO. 0001		
R	OADWAY ITEMS		
2102-2625001	EMBANKMENT-IN-PLACE, CONTRACTOR FURNISH	17,786	CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	36 , 658	CY
2301-1033080	STD/S-F PCC PAV'T, CL C CL 3, 8"	2,620	SY
2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	25,449	SY
2303-0031750	HMA (1M ESAL) BASE, 3/4"	1,793	TON
2303-0033500	HMA (1M ESAL) SURF, 1/2", NO FRIC	597	TON
2303-0051750	HMA (10M ESAL) BASE, 3/4"	787	TON
2303-0053503	HMA (10M ESAL) SURF, 1/2", FRIC L-3	262	TON
2310-5151040	PCC OVERLAY, FURN ONLY	20	CY
2310-5151051	PCC OVERLAY, PLACE ONLY (BONDED)	235	SY
2403-0100020	STRUCT CONC (RCB CULV)	3	CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

SECTION NO. 0001

ROADWAY ITEMS

2404-7775000 REINFORC STEEL

2404-7775005 REINFORC STEEL, EPOXY COATED

370 LB 93,006 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 107 Proposal ID: 69-6360-620

Proposed Contract Period: Late Start Date of 08/01/16 with 15 WORK DAYS

Project(s):

Project No: TAP-U-6360(620)--8I-69

County: MONTGOMERY

Type of Work: PCC SIDEWALK/TRAIL

Route: 4TH STREET Length: 0.30 miles

Location: IN THE CITY OF RED OAK, ON WEST SIDE OF 4TH STREET, FROM S.

OF MONTGOMERY CO. FAIRGROUNDS NORTH 1609.5' TO HWY 34.

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 337 CY 2511-0302500 RECREATIONAL TRAIL, PCC, 5" 1,308 SY 2511-0302600 RECREATIONAL TRAIL, PCC, 6" 6 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 108 Proposal ID: 75-C075-137

Proposed Contract Period: Late Start Date of 08/15/16 with 30 WORK DAYS

Project(s):

Project No: FM-C075(137)--55-75

County: PLYMOUTH

Length: 3.00 miles

Type of Work: PCC OVERLAY - UNBONDED
Route: K-42 Len
Location: K42: FROM C38- TO HWY 3

_				
	Item No.	Item Description	Quantity,	/Unit
_	SECTION	NO. 0001 OADWAY ITEMS		
	2301-1033100	STD/S-F PCC PAV'T, CL C CL 3, 10"	586	SY
	2303-0001000	HMA WEDGE/LEVEL/STRENGTH	56	TON
	2310-5151040	PCC OVERLAY, FURN ONLY	7,527	CY
	2310-5151551	PCC OVERLAY PLACE ONLY (WHITE TOPPING)	37 , 377	SY
	2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	29	SY
	2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	2	EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 109 Proposal ID: 85-0155-682

Proposed Contract Period: Late Start Date of 03/14/16 with 55 WORK DAYS

Project(s):

Project No: TAP-U-0155(682)--8I-85

County: STORY

Type of Work: PCC SIDEWALK/TRAIL

Route: SKUNK RIVER TRAIL Length: 0.79 miles

Location: IN THE CITY OF AMES, SKUNK RIVER TRAIL: FROM EAST LINCOLN WA

Y TO S. RIVER VALLEY PARK

 Item No.
 Item Description
 Quantity/Unit

 SECTION NO. 0001

 TRAIL ITEMS

 2102-2625000
 EMBANKMENT-IN-PLACE
 3,859 CY

 2102-2710070
 EXCAVATION, CL 10, RDWY+BORROW
 1,461 CY

 2511-0302500
 RECREATIONAL TRAIL, PCC, 5"
 4,721 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 151 Proposal ID: 09-8190-632

Proposed Contract Period: Late Start Date of 08/29/16 with 20 WORK DAYS

Project(s):

Project No: STP-U-8190(632)--70-09

County: BREMER

Type of Work: HMA PAVEMENT - GRADE AND REPLACE

Route: 16TH ST Length: 0.31 miles

Location: IN THE CITY OF WAVERLY, 16TH ST. SW: FROM 4TH AVE. SW TO MEA

DOW VIEW LN.

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
F	ROADWAY ITEMS	
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	1,542 CY
2303-0023500	HMA (300K ESAL) I-S, 1/2", NO FRIC	484 TON
2303-0031750	HMA (1M ESAL) BASE, 3/4"	1,100 TON
2303-0032750	HMA (1M ESAL) INTERMEDIATE, 3/4"	646 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 152 Proposal ID: 11-C011-097

Proposed Contract Period: Late Start Date of 08/08/16 with 25 WORK DAYS

Project(s):

Project No: STP-S-C011(97)--5E-11

County: BUENA VISTA

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: C63 Length: 4.04 miles

Location: C63: FROM CO. LINE TO M31

ROADWAY ITEMS

2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 6,945 TON 2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC 6,945 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 153 Proposal ID: 12-C012-091

Proposed Contract Period: Late Start Date of 06/13/16 with 70 WORK DAYS

Project(s):

Project No: STP-S-C012(91)--5E-12

County: BUTLER

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: T-16 Length: 7.40 miles

Location: ON T-16, FROM HWY 57 TO 250TH STREET

Project No: STP-S-C012(92)--5E-12

County: BUTLER

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
Route: T-43 Length: 3.40 mile
Location: T43: FROM MAIN STREET TO 180TH ST Length: 3.40 miles

Item Description ______

SECTION NO. 0001

ROADWAY ITEMS

STP-S-C012(91)--5E-12

2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC

17,965 TON

SECTION NO. 0002

ROADWAY ITEMS

STP-S-C012(92)--5E-12

2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC

8,106 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 154 Proposal ID: 21-C021-130

Proposed Contract Period: Late Start Date of 07/25/16 with 15 WORK DAYS

Project(s):

Project No: HSIP-S-C021(130)--6C-21

County: CLAY

Type of Work: HMA PAVED SHOULDER - NEW
Route: N14 AND N18 Length: 0.68 miles

Location: 2 LOCATIONS. LOCATION 1, 1/2 SOUTH OF THE DICKINSON COUNTY L INE ON N14. LOCATION 2, 2 1/4 MILES NORTH OF HWY 18 ON N18

______ Item No. Item Description

Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 155 Proposal ID: 48-C048-075

Proposed Contract Period: Late Start Date of 09/12/16 with 20 WORK DAYS

Project(s):

Project No: FM-C048(75)--55-48

County: IOWA

Type of Work: HMA RESURFACING

Route: V38 Length: 2.90 miles

Location: V-38: FROM I-80 TO 190TH ST

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2303-0042750 HMA (3M ESAL) INTERMEDIATE, 3/4" 5,710 TON 2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC 4,015 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 156 Proposal ID: 50-0651-704

Proposed Contract Period: Late Start Date of 09/12/16 with 30 WORK DAYS

Project(s):

Project No: MP-065-1(704)96--76-50

County: JASPER

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 65 Length: 1.62 miles

Location: FROM NEAR 75TH AVE W TO INDIAN CREEK (NB ONLY)

Project No: MP-030-1(704)179--76-64

County: MARSHALL

Type of Work: HMA RESURFACING WITH MILLING
Route: U.S. 30 Length: 1.05 m
Location: 0.75 MI W OF IA 330 EAST 1.05 MI (EB) 1.05 miles

Item Description ______

SECTION NO. 0001

ROADWAY ITEMS

JASPER COUNTY MP-065-1(704)96--76-50

2303-0052500 HMA (10M ESAL) INTERMEDIATE, 1/2" 1,860 TON 2303-0053502 HMA (10M ESAL) SURF, 1/2", FRIC L-2 1,860 TON

SECTION NO. 0002

ROADWAY ITEMS

MARSHALL COUNTY MP-030-1(704)179--76-64

2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 1,421 TON 2303-0043503 HMA (3M ESAL) SURF, 1/2", FRIC L-3 1,449 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 157 Proposal ID: 52-C052-108

Proposed Contract Period: Late Start Date of 07/11/16 with 30 WORK DAYS

Project(s):

Project No: FM-C052(108)--55-52

County: JOHNSON

Type of Work: HMA PAVEMENT WIDENING / HMA RESURFACING Route: X14 Length: 2.70 miles

Location: ON X14 (WAPSI AVENUE) FROM 660TH STREET SOUTH 2.7 MILES TO T

HE COUNTY LINE

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 5,150 TON 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 5,330 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 158 Proposal ID: 56-C056-093

Proposed Contract Period: Late Start Date of 08/29/16 with 35 WORK DAYS

Project(s):

Project No: FM-C056(90)--55-56

County: LEE

Type of Work: HMA RESURFACING

Route: 205TH AVE Length: 0.50 miles

Location: 205TH AVE: FROM NORTH LINE OF SECTION 23-69-6 SOUTH TO 2ND S

TREET, IN THE CITY OF ST. PAUL

Project No: FM-C056(92)--55-56

County: LEE
Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING
Route: W74 Length: 0.45 miles
Location: W74: FROM PILOT GROVE TO J38

Project No: STP-S-C056(93)--5E-56

County: LEE

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: J38 Length: 3.50 miles Location: J38: FROM HWY 218 TO ST, PAUL TO HIGHWAY 16

Item No. Item Description Quantity/Unit ______

SECTION NO. 0001

ROADWAY ITEMS

FM-C056(90)--55-56

2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 281 TON

SECTION NO. 0002

ROADWAY ITEMS

FM-C056(92)--55-56

2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 365 TON 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 771 TON

SECTION NO. 0003

ROADWAY ITEMS

STP-S-C056(93)--5E-56

2303-0032500 HMA (1M ESAL) INTERMEDIATE, 1/2" 3,304 TON 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 4,637 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 159 Proposal ID: 56-C056-094

Proposed Contract Period: Late Start Date of 09/26/16 with 15 WORK DAYS

Project(s):

Project No: FM-TSF-C056(94)--5B-56

County: LEE

Type of Work: HMA PAVEMENT WIDENING

Route: J40 Length: 8.70 miles

Location: ON J40, FROM WEST POINT CORP. LIMITS S4 T68N R5W SE 8.6 MIL

ES TO FORT MADISON CORP. LIMITS S5 T67N R4W, S3 T68 R05

Item No. Item Description Quantity/Unit ------

SECTION NO. 0001

ROADWAY ITEMS

2529-5070111 PATCH, FULL-DEPTH FINISH, BY AREA(=>50 FT)
2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 85 SY 1 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 160 Proposal ID: 61-0924-027

Proposed Contract Period: Late Start Date of 04/04/16 with 100 WORK DAYS

Project(s):

Project No: HSIPX-092-4(27)--3L-61

County: MADISON

Type of Work: HMA PAVED SHOULDER - NEW

Route: IOWA 92 Length: 12.41 miles

Location: FROM WINTERSET EAST TO I-35.

Project No: MP-092-5(705)107--76-61

County: MADISON

Type of Work: PCC PATCHING
Route: IOWA 92
Location: WINTERSET TO I-35

Length: 11.50 miles

Item No. Item Description ______

SECTION NO. 0001

CITY OF WINTERSET

HSIPX-092-4(27)--3L-61

2102-2713070 EXCAVATION, CL 13, RDWY+BORROW 150 CY 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 881 TON

SECTION NO. 0002

ROADWAY ITEMS

MP-092-5(705)107--76-61

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 1,309 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 114 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 161 Proposal ID: 62-0927-048

Proposed Contract Period: Late Start Date of 04/04/16 with 100 WORK DAYS

Proposal Note:

*** INCENTIVE/DISINCENTIVE ***

SECTION 1111 OF THE STANDARD SPECIFICATIONS FOR INCENTIVE/DISINCENTIVE (I/D) FOR EARLY COMPLETION SHALL APPLY TO THIS PROJECT WITH THE FOLLOWING CONDITIONS:

SITE NUMBER 01:

30 CLOSURE DAYS/CALENDAR DAYS, I/D RATE \$6,000.00 PER DAY

THERE ARE NO MAXIMUM INCENTIVE OR DISINCENTIVE (LIQUIDATED DAMAGES) AMOUNTS. THE INCENTIVE/DISINCENTIVE AMOUNT WILL BE PAID/COLLECTED BY THE CONTRACTING AUTHORITY UPON COMPLETION OF THE CRITICAL CLOSURE ACTIVITY.

CRITCAL CLOSURE ACTIVITY

WHEN THE ROAD IS CLOSED AND THE DETOUR IS IN EFFECT.

SITE 01 WORK RESTRICTION

NO WORK THAT REQUIRES THE ROAD TO BE CLOSED WILL BE ALLOWED PRIOR TO JUNE 15, 2016.

WORKING DAYS

WORKING DAYS WILL BE CHARGED FOR WORK COMPLETED NOT REQUIRING THE DETOUR.

Project(s):

Project No: NHSX-092-7(47)--3H-62

County: MAHASKA
Type of Work: HMA RESURFACING WITH MILLING
Route: IOWA 92 Length:

7.24 miles Length:

Location: 3.6 MI E OF MARION CO TO THE IA 163 INTERCHANGE

Project No: NHSX-092-7(48)--3H-62

County: MAHASKA

Type of Work: HMA RESURFACING WITH MILLING

Route: IOWA 92 Length: 11.21 miles Location: JUST E OF OSKALOOSA ECL TO THE KEOKUK CO LINE

Item No. Item Description Quantity/Unit -----

SECTION NO. 0001

ROADWAY ITEMS

NHSX-092-7(47)--3H-62

2102-2625000 EMBANKMENT-IN-PLACE 1,284 CY 2303-0001000 HMA WEDGE/LEVEL/STRENGTH 1,544 TON 2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 12,456 TON 2303-0043504 HMA (3M ESAL) SURF, 1/2", FRIC L-4 11,894 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

SECTION NO. 0001	
ROADWAY ITEMS	
NHSX-092-7(47)3H-62	
2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA	64 SY
2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT	4 EACH
SECTION NO. 0003	
ROADWAY ITEMS	
NHSX-092-7(48)3H-62	
2102-2625000 EMBANKMENT-IN-PLACE	38,561 CY
2301-1033095 STD/S-F PCC PAV'T, CL C CL 3, 9.5"	15,218 SY
2303-0001000 HMA WEDGE/LEVEL/STRENGTH	3,780 TON
2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2"	20,363 TON
2303-0043504 HMA (3M ESAL) SURF, 1/2", FRIC L-4	17,669 TON
2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA	733 SY
2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT	46 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 162 Proposal ID: 69-6360-619-A

Proposed Contract Period: Late Start Date of 07/25/16 with 35 WORK DAYS

Project(s):

Project No: STP-U-6360(619)--70-69

County: MONTGOMERY

Type of Work: HMA RESURFACING WITH MILLING

Route: OAK STREET Length: 1.85 miles

Location: IN CITY OF RED OAK, OAK ST FROM BROADWAY TO 8TH ST, SUMMIT S

T FROM OAK ST TO ECL, EASTERN AVE FROM HAMMOND ST TO SUMMIT

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 295 CY 2303-0001000 HMA WEDGE/LEVEL/STRENGTH 1,592 TON 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 1,592 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 163 Proposal ID: 77-0061-722

Proposed Contract Period: Late Start Date of 09/19/16 with 20 WORK DAYS

Site 01: TO COMPLETE PROJECT MPIN-080-1(710)148--0N-77. No Start Date Specified with 3 WORK DAYS

Project(s):

Project No: MP-006-1(722)144--76-77

County: POLK

Type of Work: HMA RESURFACING WITH MILLING

Route: U.S. 6 Length: 0.71 miles

Location: IN ALTOONA FROM NORTH OF ADVENTURELAND DR. NORTHEASTERLY

TO APPROX 0.3 MI. NORTH OF I-80.

Project No: MPIN-080-1(710)148--0N-77
County: POLK
Type of Work: HMA RESURFACING WITH MILLING
Route: I-80 Length: 0.30 miles
Location: MITCHELLVILLE REST AREA 1.2 MI W OF S27 (WB)

Ite	em No.	Item Description	Quantity/Unit
	SECTION	NO. 0001	
	R	OADWAY ITEMS	
	М	P-006-1 (722) 14476-77	

2303-0052500 HMA (10M ESAL) INTERMEDIATE, 1/2" 1,700 TON 2303-0053502 HMA (10M ESAL) SURF, 1/2", FRIC L-2 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 2,422 TON 32 SY

2 EACH

SECTION NO. 0002

ROADWAY ITEMS

MPIN-080-1(710)148--0N-77

2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 253 TON 2303-0043503 HMA (3M ESAL) SURF, 1/2", FRIC L-3 253 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 164 Proposal ID: 77-1425-625

Proposed Contract Period: Late Start Date of 05/23/16 with 100 WORK DAYS

Project(s):

Project No: STP-U-1425(625)--70-77

County: POLK

Type of Work: HMA RESURFACING

Route: UNIVERSITY AVENUE Length: 1.81 miles Location: IN THE CITY OF CLIVE, FROM NW 86TH ST

TO EAST EXIT/ENTRANCE I-35 RAMP

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2303-0042500 HMA (3M ESAL) INTERMEDIATE, 1/2" 7,038 TON 2303-0043500 HMA (3M ESAL) SURF, 1/2", NO FRIC 7,038 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 165 Proposal ID: 82-C082-056

Proposed Contract Period: Late Start Date of 08/29/16 with 30 WORK DAYS

Project(s):

Project No: FM-C082(56)--55-82

County: SCOTT

Type of Work: HMA RESURFACING/COLD IN-PLACE RECYCLING Route: Y48 Length: 3.97 miles

Location: Y48: FROM F-65 NORTH TO F-58

Quantity/Unit Item No. Item Description ______

SECTION NO. 0001

ROADWAY ITEMS

2303-0031750 HMA (1M ESAL) BASE, 3/4" 2303-0033500 HMA (1M ESAL) SURF, 1/2", NO FRIC 7,728 TON

5,796 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 166 Proposal ID: 85-C085-133-A

Proposed Contract Period: Late Start Date of 09/12/16 with 20 WORK DAYS

Project(s):

Project No: FM-C085(133)--55-85

County: STORY

Type of Work: HMA RESURFACING

Route: 320TH ST Length: 3.50 miles

Location: ON E63, FROM R38 EAST APPROX. 3.5 MILES TO N. 5TH AVE. IN HU

XLEY

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

FM-C085(133)--55-85

2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 8,883 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 167 Proposal ID: 85-C085-135-A

Proposed Contract Period: Late Start Date of 09/12/16 with 20 WORK DAYS

Project(s):

Project No: STP-S-C085(135)--5E-85

County: STORY

Type of Work: HMA RESURFACING

Route: E63 Length: 3.25 miles

Location: ON E63, FROM A POINT 870 FEET NE OF THE CAMBRIDGE CITY LIMIT

S EAST 3.25 MILES TO S14

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2303-0023500 HMA (300K ESAL) I-S, 1/2", NO FRIC 7,241 TON

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 168 Proposal ID: 85-0691-709

Proposed Contract Period: Specified Start Date of 06/13/16 with 25 WORK DAYS

Project(s):

Project No: MP-069-1(709)117--76-85

County: STORY

Type of Work: HMA RESURFACING WITH MILLING

2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT

Route: U.S. 69 Length: 0.60 miles

Location: IN THE CITY OF AMES, FROM 500 FT N OF 16TH ST. TO 900 FT N

OF 24TH ST.

Item No.	Item Description	Quantity,	/Unit
SECTION	NO. 0001		
R	OADWAY ITEMS		
2102-2713070	EXCAVATION, CL 13, RDWY+BORROW	93	CY
2303-0042500	HMA (3M ESAL) INTERMEDIATE, 1/2"	1,351	TON
2303-0043500	HMA (3M ESAL) SURF, 1/2", NO FRIC	1,351	TON
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	4	SY

1 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 201 Proposal ID: 27-0351-143

Proposed Contract Period: Late Start Date of 09/12/16 with 50 WORK DAYS

Project(s):

Project No: MPIN-035-5(705)34--0N-20

County: CLARKE

Type of Work: HMA CRACK FILLING

Route: I-35 Length: 18.48 miles

Location: 0.7 MI NORTH OF U.S. 34 TO WARREN COUNTY LINE (NB/SB)

Project No: MPIN-035-5(706)29--0N-20

County: CLARKE
Type of Work: HMA JOINT & CRACK SEALING

Route: I-35 Length: 0.00 miles Location: APPROX 0.3 MI SOUTH OF H45 TO 1.3 MI NORTH OF G50 -

RAMPS AND PARKING AREAS (VARIOUS LOCATIONS)

Project No: MP-069-5(703)42--76-20 County: CLARKE Type of Work: PCC PATCHING

Route: U.S. 69 Length: 21.33 miles

Location: FROM OSCEOLA TO U.S. 65.

Project No: IMN-035-1(143)0--0E-27

County: DECATUR

Type of Work: PCC PATCHING Route: I-35 Length: 0.00 miles

Location: FROM MISSOURI STATE LINE N. TO W. I-35/80/235INTERCHANGE

Item No.	Item Description	Quantity/Unit
	NO. 0003 ROADWAY ITEMS	
	CLARKE COUNTY MP-069-5(703)4276-20	
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	2,035 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	228 EACH
SECTION	NO. 0004	
	ROADWAY ITEMS	
	DECATUR COUNTY IMN-035-1(143)00E-27	
	PATCH, FULL-DEPTH FINISH, BY AREA PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT)	2,159 SY 283 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	119 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 202 Proposal ID: 43-0295-228

Proposed Contract Period: Late Start Date of 09/12/16 with 30 WORK DAYS

Project(s):

Project No: IMN-029-5(228)72--0E-43

County: HARRISON
Type of Work: PCC PATCHING

Route: I-29 Length: 79.42 miles

Location: FROM POTTAWATTAMIE CO. LINE, NORTH TO THE SOUTH DAKOTA

STATE LINE

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS
2303-0063502 HMA (30M ESAL) SURF, 1/2", FRIC L-2 491 TON

2303-0063502 HMA (30M ESAL) SURF, 1/2", FRIC L-2
2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA
2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT
47 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 203 Proposal ID: 53-0386-719

Proposed Contract Period: Late Start Date of 09/12/16 with 30 WORK DAYS

Project(s):

Project No: MP-038-6(719)64--76-53

County: JONES

Type of Work: HMA PATCHING

Route: IOWA 38 Length: 1.61 miles

Location: FROM U.S. 151 TO NCL OF MONTICELLO.

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 204 Proposal ID: 56-0275-706

Proposed Contract Period: Late Start Date of 09/19/16 with 25 WORK DAYS

Project(s):

Project No: MP-027-5(706)0--76-56

County: LEE

Type of Work: PCC PATCHING Route: IOWA 27 Length: 82.50 miles Location: FROM THE MISSOURI STATE LINE TO RIVERSIDE.

Item No.	Item Description	Quantity/Unit
SECTION R	NO. 0001 OADWAY ITEMS	
=-	PATCH, FULL-DEPTH FINISH, BY AREA	1,249 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT)	876 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	67 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 205 Proposal ID: 82-0808-274

Proposed Contract Period: By individual sites.

Site 01: TO COMPLETE SPRING PATCHING

Late Start Date of 04/11/16 with 35 WORK DAYS

Site 02: TO COMPLETE FALL PATCHING

Approx Start Date of 09/26/16 with 15 WORK DAYS

Project(s):

Project No: IMN-074-1(212)0--0E-82

County: SCOTT

Type of Work: PCC PATCHING

Route: I-74 Length: 5.36 miles Location: FROM I-80, SOUTH TO THE MISSISSIPPI RIVER.

Project No: IMN-080-8(274)278--0E-82
County: SCOTT
Type of Work: PCC PATCHING
Route: I-80 Length: 28.63 miles
Location: FROM CEDAR CO. LINE, EAST TO MISSISSIPPI RIVER.

Project No: IMN-280-8(151)0--0E-82

County: SCOTT

Type of Work: PCC PATCHING

Route: I-280 Length: 9.70 miles Location: FROM I-80 SOUTH TO MISSISSIPPI RIVER.

Item No.	Item Description	Quantity/Unit
SECTION	NO. 0001	
R	ROADWAY ITEMS	
I	IMN-074-1(212)00E-82	
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	971 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT)	153 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	81 EACH
SECTION	NO. 0002	
R	ROADWAY ITEMS	
I	IMN-080-8 (274) 2780E-82	
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	1,073 SY
2529-5070111	PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT)	171 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	94 EACH
SECTION	NO. 0003	
R	ROADWAY ITEMS	
I	IMN-280-8(151)00E-82	
2529-5070110	PATCH, FULL-DEPTH FINISH, BY AREA	285 SY
2529-5070120	PATCH, FULL-DEPTH FINISH, BY COUNT	25 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 206 Proposal ID: 90-1495-702

Proposed Contract Period: Late Start Date of 10/24/16 with 15 WORK DAYS

Project(s):

Project No: MP-149-5(702)0--76-90

County: WAPELLO

Type of Work: PCC PATCHING

Route: IOWA 149 Length: 11.52 miles

Location: FROM THE DES MOINES RIVER IN OTTUMWA, NORTH TO IOWA 23.

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

RURAL

2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 992 SY 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 94 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 207 Proposal ID: 97-1413-708

Proposed Contract Period: Late Start Date of 09/19/16 with 20 WORK DAYS

Project(s):

Project No: MP-141-3(705)24--76-67

County: MONONA

Type of Work: PCC PATCHING

Route: IOWA 141 Length: 1.98 miles

Location: FROM THE WCL OF MAPLETON, EAST THEN SOUTH TO WEST OF L32.

Project No: MP-141-3(708)5--76-97

County: WOODBURY

Type of Work: PCC PATCHING
Route: IOWA 141 Length: 36.65 miles
Location: FROM 0.7 MI EAST OF K53, SOUTHEASTERLY TO CHARTER OAK.

Item No.	Item Description	Quantity/Unit
SECTIC	N NO. 0001	
	ROADWAY ITEMS	
	MONONA COUNTY MP-141-3 (705) 2476-67	
2529-507011	O PATCH, FULL-DEPTH FINISH, BY AREA	479 SY
2529-507011	1 PATCH, FULL-DEPTH FINISH, BY AREA (=>50 FT)	354 SY
2529-507012	O PATCH, FULL-DEPTH FINISH, BY COUNT	43 EACH
SECTIO	N NO. 0002	
	ROADWAY ITEMS	
	WOODBURY COUNTY MP-141-3 (708) 576-97	

2303-0033503 HMA (1M ESAL) SURF, 1/2", FRIC L-3 2529-5070110 PATCH, FULL-DEPTH FINISH, BY AREA 2529-5070120 PATCH, FULL-DEPTH FINISH, BY COUNT 525 TON 397 SY 30 EACH

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 301 Proposal ID: 27-0691-043

Proposed Contract Period: Late Start Date of 10/03/16 with 15 WORK DAYS

Project(s):

Project No: STPN-069-1(43)--2J-27

County: DECATUR

Type of Work: SLIDE REPAIR

Route: U.S. 69 Length: 0.00 miles

Location: JUST E OF I-35 (NE CORNER OF BRIDGE)

Item No. Item Description Quantity/Unit

SECTION NO. 0001

SLIDE REPAIR ITEMS

2102-2625000 EMBANKMENT-IN-PLACE 455 CY 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 1,089 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 302 Proposal ID: 49-C049-063

Proposed Contract Period: Late Start Date of 09/19/16 with 15 WORK DAYS

Project(s):

Project No: FM-C049(63)--55-49

County: JACKSON

Type of Work: PIPE CULVERTS

Route: 142 AVE Length: 1.00 miles

Location: ON COUNTY HIGHWAY Y46 (142ND AVENUE, FROM 7TH STREET TO HIGH

WAY 64 1.0 MILES, S28 & 33 T84 R2E

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ROADWAY ITEMS

2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8" 366 SY

2301-1033080 STD/S-F PCC PAV'T, CL C CL 3, 8"
2403-0100000 STRUCT CONC (MISCELLANEOUS)
2404-7775000 REINFORC STEEL
715 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 303 Proposal ID: 52-0806-513-A

Proposed Contract Period: Late Start Date of 08/15/16 with 45 WORK DAYS

Project(s):

Project No: MBIN-080-6(513)242--0M-52

County: JOHNSON

Type of Work: SLOPE PROTECTION

Route: I-80 Length: 0.00 miles

Location: 4.2 MI W OF IOWA 1 IN CORALVILLE.

Project No: MB-100-6(502)3--77-57

County: LINN

Type of Work: SLOPE PROTECTION
Route: IOWA 100 Length: 0.00 miles
Location: AT THE I-380 INTERCHANGE IN CEDAR RAPIDS Length: 0.00 miles

Project No: MBIN-380-6(553)24--0M-57
County: LINN
Type of Work: SLOPE PROTECTION
Route: I-380 Leng

Length: 0.00 miles

Location: 0.1 MI SOUTH AND 0.1 MI NORTH OF IOWA 100 IN CEDAR RAPIDS.

Item No. Item Description Quantity/Unit ______

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 304 Proposal ID: 85-C085-138

Proposed Contract Period: Late Start Date of 09/19/16 with 20 WORK DAYS

Project(s):

Project No: FM-C085(138)--55-85

County: STORY

Type of Work: PIPE CULVERTS

Route: 19TH ST Length: 0.10 miles

Location: ON 19TH ST., 0.06 MI NORTH OF THE CENTER OF SEC S29 T83 R22

Item No. Item Description Quantity/Unit

SECTION NO. 0001

ITEMS FOR A 60 IN X 145' METAL PIPE CULVERT

2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 2,290 CY
2403-0100000 STRUCT CONC (MISCELLANEOUS) 11 CY
2404-7775000 REINFORC STEEL 386 LB

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 351 Proposal ID: 00-000S-800

Proposed Contract Period: By individual sites. Site 01: TO COMPLETE DIVISION 1 SIGNS

Late Start Date of 10/10/16 with 10 WORK DAYS

Site 02: TO COMPLETE DIVISION 2 SIGNS

Late Start Date of 03/28/16 with 10 WORK DAYS

Project(s):

Project No: NHSN-000-S(800)--2R-00

County: STATEWIDE Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS STATEWIDE

Item No. Item Description Quantity/Unit ______

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 352 Proposal ID: 00-000S-821

Proposed Contract Period: Late Start Date of 07/18/16 with 60 WORK DAYS

Project(s):

Project No: NHSN-000-S(821)--2R-00

County: STATEWIDE
Type of Work: TRAFFIC SIGNS

Route: MULTIPLE ROUTES Length: 0.00 miles

Location: VARIOUS LOCATIONS IN DISTRICT 3

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 353 Proposal ID: 77-0803-191

Proposed Contract Period: Late Start Date of 07/11/16 with 60 WORK DAYS

Project(s):

Project No: IMN-080-3(191)124--0E-77

County: POLK

Type of Work: BARRIER RAIL

Route: I-80 Length: 0.00 miles

Location: W I-35 / I-235 INTERCHANGE TO E OF W US 65 INTERCHANGE

Project No: IMN-235-2(643)0--0E-77

County: POLK

Type of Work: BARRIER RAIL
Route: I-235 Length: 0.00 miles
Location: 0.5 MILE E. OF THE SWMM EAST TO GUTHRIE AVE.

Item Description

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 354 Proposal ID: 77-1417-046

Proposed Contract Period: Late Start Date of 08/01/16 with 50 WORK DAYS

Project(s):

Project No: STP-A-141-7(46)--86-77

County: POLK

Type of Work: TRAFFIC SIGNALS

Route: IOWA 141 Length: 0.00 miles

Location: IOWA 141: TRAFFIC SIGNAL INTERCONNECTION OF INTERSECTION ON

IOWA 141 IN GRIMES AND URBANDALE

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 401 Proposal ID: 57-1001-116

Proposed Contract Period: Approx Start Date of 04/25/16 with 15 WORK DAYS

Project(s):

Project No: NHSN-100-1(116)--2R-57

County: LINN

Type of Work: SALVAGE AND REMOVAL

Route: IOWA 100 Length: 4.50 miles Location: PARCEL 43, 8000 'E' AVE. NW, CEDAR RAPIDS

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 451 Proposal ID: 45-C045-065

Proposed Contract Period: Late Start Date of 08/08/16 with 60 WORK DAYS

Project(s):

Project No: EDP-C045(065)--7Y-45

County: HOWARD

Type of Work: RECREATIONAL TRAIL

Route: WAPSI-GREAT WESTERN Length: 6.00 miles

Location: ON WGWL TRAIL, FROM RICEVILLE TO INTERSECTION OF DOUGLAS AVE

& 140TH ST

Item No. Item Description Quantity/Unit

SECTION NO. 0001

TRAIL ITEMS

2102-2625000 EMBANKMENT-IN-PLACE 2102-2710070 EXCAVATION, CL 10, RDWY+BORROW 9,900 CY

1,430 CY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 452 Proposal ID: 82-0952-603

Proposed Contract Period: Late Start Date of 08/29/16 with 30 WORK DAYS

Project(s):

Project No: EDP-0952(603)--7Y-82

County: SCOTT

Type of Work: RECREATIONAL TRAIL

Route: REC TRAIL Length: 11.00 miles

Location: IN THE CITY OF BUFFALO, MRT: FROM UTAH AVE TO WILD CAT DEN S

TATE PARK

Item No.	Item Description	Quantity/Unit
	NO. 0001 REC TRAIL ITEMS	
2102-2625000	EMBANKMENT-IN-PLACE	923 CY
2102-2710070	EXCAVATION, CL 10, RDWY+BORROW	771 CY
2511-0301600	RECREATIONAL TRAIL, HMA, 6"	4,660 SY
2511-0302600	RECREATIONAL TRAIL, PCC, 6"	123 SY

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 501 Proposal ID: 86-0306-228

Proposed Contract Period: Late Start Date of 04/25/16 with 60 WORK DAYS

Project(s):

Project No: NHSN-030-6(228)--2R-86

County: TAMA

Type of Work: EROSION CONTROL

Route: U.S. 30 Length: 0.00 miles Location: CO RD T47 TO CO RD M AVE (VARIOUS LOCATIONS)

Item No. Item Description Quantity/Unit

MAJOR ITEMS - PRELIMINARY QUANTITY REPORT (for information only)

Proposed Letting Date: February 16, 2016 10:00 A.M.

Proposed Bid Order: 601 Proposal ID: 29-0349-204

Proposed Contract Period: Late Start Date of 05/16/16 with 15 WORK DAYS

Project(s):

Project No: BRFN-034-9(204)--39-29

County: DES MOINES

Type of Work: BRIDGE CLEANING

Route: U.S. 34 Length: 0.00 miles

Location: BURLINGTON INTERCHANGE AND THE MISSISSIPPI RIVER BRIDGE

BETWEEN BURLINGTON AND GULFPORT.

Item No. Item Description Quantity/Unit
