

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: February 16, 2016
Date of Addendum: February 9, 2016

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
081	17-C017-071	ALTERNATE PAVEMENT TYPES-MAINLINE PAVING	CERRO GORDO	STP-S-C017(71)--5E-17	16FEB081.A01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 0100 2402-0425031 GRANULAR BACKFILL:
From: 250.000 TON
To: 390.000 TON

If the above changes are not made, they will be made as shown here.

Make the following changes to the plans:

Please add the following to the Estimate Reference Information on sheet C.02

Item No. 10:

Granular Backfill shall be used as backfill for rigid pipe culvert trenches beneath paved roadways and shall be placed up to the bottom of the subgrade.

Item No. 22 and No. 23 :

Longitudinal Subdrain shall be installed at a depth (D) of 48 inches from the finished surface.

Item No. 40 and No. 41 :

Subgrade Stabilization shall be included beneath all mainline, widening, auxiliary lane and side road pavement.

Please replace tabulation 104-3 on Sheet C.06 with the attached PDF (tabulation 104-3):

