

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: March 15, 2016
Date of Addendum: February 24, 2016

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
022	86-2932-601	RCB CULVERT REPLACEMENT - TWIN BOX	TAMA	BROS-2932(601)--8J-86	15MAR022.A01

Notice: Only the bid proposal holders receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the proposal holder.

Make the following changes to the PLAN:

SHEET C.01:

Change the following note in the lower left hand corner:

From: Scrape samples of this bridge were taken to get an indication of the existence of and level of total chromium and total lead. The analysis of total chromium in the sample was ppm. The analysis of total lead in the sample was ppm. The analysis shows the existence of these two toxic constituents.

The levels indicated by these tests could create conditions above regulatory limits for health safety requirements. No other substances were analyzed. The bidder should not rely on the LPA's testing and analysis for any purpose other than an indication of the existence of these two constituents.

To: Two scrape samples were taken from this bridge to get an indication of the existence of the level of total Chromium and total Lead. Analysis of total Lead on these samples were 89,800 parts per million (PPM) and 101,000 PPM. Analysis of total Chromium on these samples were 51.0 PPM and <30.0 PPM. These analyses show the existence of these two toxic constituents. Levels indicated by these tests could create conditions above regulatory limits for health and safety requirements. No other constituents were analyzed. The bidder should not rely on the Department's testing and analysis for any purpose other than as an indication of the existence of these two toxic constituents.