
Embankment Quality and Assessment of Moisture Control Implementation

FEBRUARY 2016

Final Report

CENTER FOR

CEER

EARTHWORKS ENGINEERING
RESEARCH



IOWA STATE UNIVERSITY
Institute for Transportation

Sponsored by
Iowa Department of Transportation
(InTrans Project 14-507)
Iowa Highway Research Board
(IHRB Project TR-677)

About the Center for Earthworks Engineering Research

The mission of the Center for Earthworks Engineering Research (CEER) at Iowa State University is to be the nation's premier institution for developing fundamental knowledge of earth mechanics, and creating innovative technologies, sensors, and systems to enable rapid, high quality, environmentally friendly, and economical construction of roadways, aviation runways, railroad embankments, dams, structural foundations, fortifications constructed from earth materials, and related geotechnical applications.

Disclaimer Notice

The contents of this report reflect the views of the authors, who are responsible for the facts and the accuracy of the information presented herein. The opinions, findings and conclusions expressed in this publication are those of the authors and not necessarily those of the sponsors.

The sponsors assume no liability for the contents or use of the information contained in this document. This report does not constitute a standard, specification, or regulation.

The sponsors do not endorse products or manufacturers. Trademarks or manufacturers' names appear in this report only because they are considered essential to the objective of the document.

ISU Non-Discrimination Statement

Iowa State University does not discriminate on the basis of race, color, age, ethnicity, religion, national origin, pregnancy, sexual orientation, gender identity, genetic information, sex, marital status, disability, or status as a U.S. veteran. Inquiries regarding non-discrimination policies may be directed to Office of Equal Opportunity, Title IX/ADA Coordinator, and Affirmative Action Officer, 3350 Beardshear Hall, Ames, Iowa 50011, 515-294-7612, email eooffice@iastate.edu.

Iowa Department of Transportation Statements

Federal and state laws prohibit employment and/or public accommodation discrimination on the basis of age, color, creed, disability, gender identity, national origin, pregnancy, race, religion, sex, sexual orientation or veteran's status. If you believe you have been discriminated against, please contact the Iowa Civil Rights Commission at 800-457-4416 or the Iowa Department of Transportation affirmative action officer. If you need accommodations because of a disability to access the Iowa Department of Transportation's services, contact the agency's affirmative action officer at 800-262-0003.

The preparation of this report was financed in part through funds provided by the Iowa Department of Transportation through its "Second Revised Agreement for the Management of Research Conducted by Iowa State University for the Iowa Department of Transportation" and its amendments.

The opinions, findings, and conclusions expressed in this publication are those of the authors and not necessarily those of the Iowa Department of Transportation.

Technical Report Documentation Page

1. Report No. IHRB Project TR-677	2. Government Accession No.	3. Recipient's Catalog No.	
4. Title and Subtitle Embankment Quality and Assessment of Moisture Control Implementation		5. Report Date February 2016	
		6. Performing Organization Code	
7. Author(s) David White, Shengting Li, and Pavana Vennapusa		8. Performing Organization Report No. InTrans Project 14-507	
9. Performing Organization Name and Address Center for Earthworks Engineering Research Iowa State University 2711 South Loop Drive, Suite 4600 Ames, IA 50010-8664		10. Work Unit No. (TRAIS)	
		11. Contract or Grant No.	
12. Sponsoring Organization Name and Address Iowa Highway Research Board Iowa Department of Transportation 800 Lincoln Way Ames, IA 50010		13. Type of Report and Period Covered Final Report	
		14. Sponsoring Agency Code IHRB Project TR-677	
15. Supplementary Notes Visit www.intrans.iastate.edu and www.ceer.iastate.edu for color pdfs of this and other research reports.			
16. Abstract <p>A specification for contractor moisture quality control (QC) in roadway embankment construction has been in use for approximately 10 years in Iowa on about 190 projects. The use of this QC specification and the development of the soils certification program for the Iowa Department of Transportation (DOT) originated from Iowa Highway Research Board (IHRB) embankment quality research projects. Since this research, the Iowa DOT has applied compaction with moisture control on most embankment work under pavements.</p> <p>This study set out to independently evaluate the actual quality of compaction using the current specifications. Results show that Proctor tests conducted by Iowa State University (ISU) using representative material obtained from each test section where field testing was conducted had optimum moisture contents and maximum dry densities that are different from what was selected by the Iowa DOT for QC/quality assurance (QA) testing. Comparisons between the measured and selected values showed a standard error of 2.9 lb/ft³ for maximum dry density and 2.1% for optimum moisture content. The difference in optimum moisture content was as high as 4% and the difference in maximum dry density was as high as 6.5 lb/ft³. The difference at most test locations, however, were within the allowable variation suggested in AASHTO T 99 for test results between different laboratories. The ISU testing results showed higher rates of data outside of the target limits specified based on the available contractor QC data for cohesive materials. Also, during construction observations, wet fill materials were often observed. Several test points indicated that materials were placed and accepted at wet of the target moisture contents. The statistical analysis results indicate that the results obtained from this study showed improvements over results from previous embankment quality research projects (TR-401 Phases I through III and TR-492) in terms of the percentage of data that fell within the specification limits. Although there was evidence of improvement, QC/QA results are not consistently meeting the target limits/values.</p> <p>Recommendations are provided in this report for Iowa DOT consideration with three proposed options for improvements to the current specifications. Option 1 provides enhancements to current specifications in terms of material-dependent control limits, training, sampling, and process control. Option 2 addresses development of alternative specifications that incorporate dynamic cone penetrometer or light weight deflectometer testing into QC/QA. Option 3 addresses incorporating calibrated intelligent compaction measurements into QC/QA.</p>			
17. Key Words compaction—embankment quality—moisture-density testing		18. Distribution Statement No restrictions.	
19. Security Classification (of this report) Unclassified.	20. Security Classification (of this page) Unclassified.	21. No. of Pages 225	22. Price NA

EMBANKMENT QUALITY AND ASSESSMENT OF MOISTURE CONTROL IMPLEMENTATION

Final Report

February 2016

Principal Investigator

David J. White

Richard L. Handy Professor of Civil Engineering
Director, Center for Earthworks Engineering Research

Co-Principal Investigator

Pavana K. R. Vennapusa

Assistant Director, Center for Earthworks Engineering Research

Research Assistant

Shengting Li

Authors

David White, Shengting Li, and Pavana Vennapusa

Sponsored by
the Iowa Department of Transportation and
the Iowa Highway Research Board
(IHRB Project TR-677)

Preparation of this report was financed in part
through funds provided by the Iowa Department of Transportation
through its Research Management Agreement with the
Institute for Transportation
(InTrans Project 14-507)

A report from
Center for Earthworks Engineering Research (CEER)
Institute for Transportation

Iowa State University
2711 South Loop Drive, Suite 4700
Ames, IA 50010-8664
Phone: 515-294-7910 / Fax: 515-294-0467
www.ceer.iastate.edu

TABLE OF CONTENTS

ACKNOWLEDGMENTS	xv
EXECUTIVE SUMMARY	xvii
CHAPTER 1: INTRODUCTION	1
CHAPTER 2: BACKGROUND	4
IHRB TR-401 Phase I Summary	4
IHRB TR-401 Phase II Summary	5
IHRB TR-401 Phase III Summary	7
IHRB TR-492 Phase IV Summary	8
Intelligent Compaction	9
Preliminary Study	9
Implementation Program	10
Summary of Earthwork QC/QA specifications in the US	10
Alternative Specification Options	12
CHAPTER 3: TESTING AND ANALYSIS METHODS	15
Field Testing Methods	16
Drive Cylinder	16
Dynamic Cone Penetrometer (DCP)	16
Global Positioning System (GPS)	19
Sampling	20
Laboratory Testing	21
Soil Index Properties	22
Compaction Characteristics	22
Statistical Analysis Methods	23
CHAPTER 4: MATERIALS	26
CHAPTER 5: FIELD TEST RESULTS	33
Project 1. Polk County	35
Overview	35
ISU Field Test Results	39
Control Charts	45
Project 2. Warren County	49
Overview	49
ISU Field Test Results	51
Control Charts	58
Project 3. Linn County 77	62
Overview	62
ISU Field Test Results	66
Control Charts	73
Project 4. Linn County-79	81
Overview	81
ISU Field Test Results	85
Control Charts	87

Project 5. Mills County	93
Overview	93
ISU Field Test Results	96
Control Charts	100
Project 6. Pottawattamie County	104
Overview	104
ISU Field Test Results	107
Control Charts	111
Project 7. Woodbury County I-29	115
Overview	115
ISU Field Test Results	118
Control Charts	123
Project 8. Scott County	127
Overview	127
ISU Field Test Results	131
Control Charts	136
Project 9. Woodbury County US 20	140
Overview	140
ISU Field Test Results	143
Control Charts	151
CHAPTER 6: DATA ANALYSIS	154
Field Test Results	154
Statistical Analysis	158
CHAPTER 7: CONCLUSIONS AND RECOMMENDATIONS	163
Summary and Conclusions	163
Recommendations	164
Option1: Enhance the Current Iowa DOT Moisture and Moisture-Density Specifications	166
Option2: Develop Alternative DCP/LWD-based (Strength/Stiffness-based) QC/QA Specifications	166
Option3: Incorporate Calibrated Intelligent Compaction (IC) Measurements into QC/QA Specifications	167
Other Considerations	167
REFERENCES	171
APPENDIX A. STATE SPECIFICATION FOR EMBANKMENT CONSTRUCTION OF GRANULAR MATERIALS	173
APPENDIX B. STATE SPECIFICATION FOR EMBANKMENT CONSTRUCTION OF NON-GRANULAR MATERIALS	187
APPENDIX C. GRAIN SIZE DISTRIBUTION OF EMBANKMENT MATERIALS	201

LIST OF FIGURES

Figure 1. Eleven project sites identified for field evaluation.....	2
Figure 2. IHRB TR-401 Phase I: Histograms of moisture and relative compaction test results from ISU testing	5
Figure 3. IHRB TR-401 Phase II: Histograms of moisture and relative compaction test results from ISU testing	6
Figure 4. IHRB TR-401 Phase III: Histograms of moisture and density test results.....	7
Figure 5. IHRB TR-401 Phase IV: Histograms of moisture and density test results	8
Figure 6. QC/QA requirements for granular materials in the US	11
Figure 7. QC/QA requirements for non-granular materials in the US.....	11
Figure 8. Schematic of drive cylinder (left) and ISU researcher performing in situ testing (right)	16
Figure 9. Schematic of DCP device (left) and ISU research team performing in situ testing (right)	17
Figure 10. Example DCP-CBR values and cumulative blows with depth plots and interpretation of average values for 8 in. and 12 in. depths.....	18
Figure 11. Flow chart used for collecting and analyzing DCP data	18
Figure 12. Location information measured by GPS device	20
Figure 13. Two patterns of in situ testing point selection: Pottawatamie County project (top) and Linn County 77 project (bottom).....	21
Figure 14. Soil classification equipment (left to right: sieve analysis, hydrometer test, and Atterberg limit test).....	22
Figure 15. Density curve.....	23
Figure 16. Polk County Project 1: Caterpillar MT-35 scraper used to collect and place loose fill materials.....	36
Figure 17. Polk County Project 1: Caterpillar 740B dump truck used to place loose fill materials.....	36
Figure 18. Polk County Project 1: Caterpillar 143H motor grader used to level the embankment surface	37
Figure 19. Polk County Project 1: Disc used to dry embankment materials	37
Figure 20. Polk County Project 1: Caterpillar D6T dozer used for grading and lift thickness adjustment.....	38
Figure 21. Polk County Project 1: Pull-behind sheepsfoot roller used for soil compaction.....	38
Figure 22. Polk County Project 1: Geogrid placed near embankment toe.....	39
Figure 23. Polk County Project 1 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	40
Figure 24. Polk County Project 1 TB3: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	41
Figure 25. Polk County Project 1 TB4: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	42
Figure 26. Polk County Project 1 TB1: DCP-CBR values and cumulative blows with depth profiles	43

Figure 27. Polk County Project 1 TB3: DCP-CBR values and cumulative blows with depth profiles	44
Figure 28. Polk County Project 1 TB4: DCP-CBR values and cumulative blows with depth profiles	44
Figure 29. Polk County Project 1: Moisture and density control chart	46
Figure 30. Polk County Project 1: Histograms of moisture and density control results.....	47
Figure 31. Polk County Project 1: Control charts with control limits for DCP index and variation in DCP index.....	48
Figure 32. Polk County Project 1: CBR control charts with CBR quality ratings	49
Figure 33. Warren County Project 2: Caterpillar D6T dozer used to control lift thickness	50
Figure 34. Warren County Project 2: Caterpillar MT-35 scraper used to collect and place loose fill materials.....	50
Figure 35. Warren County Project 2: Sheepsfoot roller used for soil compaction	51
Figure 36. Warren County Project 2 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	52
Figure 37. Warren County Project 2 TB2: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	53
Figure 38. Warren County Project 2 TB3 (gray soil): Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	54
Figure 39. Warren County Project 2 TB3 (brown soil): Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	55
Figure 40. Warren County Project 2 TB1: DCP-CBR values and cumulative blows with depth profiles	56
Figure 41. Warren County Project 2 TB2: DCP-CBR values and cumulative blows with depth profiles	57
Figure 42. Warren County Project 2 TB3: DCP-CBR values and cumulative blows with depth profiles	57
Figure 43. Warren County Project 2: Moisture control chart	59
Figure 44. Warren County Project 2: Histograms of moisture and density control results	60
Figure 45. Warren County Project 2: Control charts with control limits for DCP index and variation in DCP index.....	61
Figure 46. Warren County Project 2: CBR chart with CBR quality rating	62
Figure 47. Linn County Project 3: Caterpillar 390D excavating material from borrow source	63
Figure 48. Linn County Project 3: Caterpillar D6R dozer used to control lift thickness	64
Figure 49. Linn County Project 3: Disc cultivator used to dry embankment materials	64
Figure 50. Linn County Project 3: Sheepsfoot roller used for soil compaction	65
Figure 51. Linn County Project 3: Caterpillar 14M motor grader used to level the embankment surface	65
Figure 52. Linn County Project 3: Seepage at the construction site.....	66

Figure 53. Linn County Project 3 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	67
Figure 54. Linn County Project 3 TB3: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	68
Figure 55. Linn County Project 3 TB4: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	69
Figure 56. Linn County Project 3 TB5: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	70
Figure 57. Linn County Project TB1: DCP-CBR values and cumulative blows with depth profiles	71
Figure 58. Linn County Project 3 TB3: DCP-CBR values and cumulative blows with depth profiles	71
Figure 59. Linn County Project 3 TB4: DCP-CBR values and cumulative blows with depth profiles	72
Figure 60. Linn County Project 3 TB5: DCP-CBR values and cumulative blows with depth profiles	72
Figure 61. Linn County Project 3: Moisture control chart (cohesive materials)	74
Figure 62. Linn County Project 3: Moisture and density control charts (cohesionless materials).....	75
Figure 63. Linn County Project 3: Moisture control chart (cohesionless materials).....	76
Figure 64. Linn County Project 3: Histograms of moisture and density control results (cohesive materials)	77
Figure 65. Linn County Project 3: Histograms of moisture and density control results (cohesionless materials).....	78
Figure 66. Linn County Project 3: Histograms of moisture control results (cohesionless materials).....	79
Figure 67. Linn County Project 3: Control charts with control limits for DCP index and variation in DCP index.....	80
Figure 68. Linn County Project 3: CBR chart with CBR quality rating.....	81
Figure 69. Lynn County Project 4: Caterpillar 740 dump truck used to place loose fill materials.....	82
Figure 70. Linn County Project 4: Sheepsfoot roller used for soil compaction	82
Figure 71. Linn County Project 4: Contractor conducting QC tests.....	83
Figure 72. Linn County Project 4: Iowa DOT engineer conducting QA tests.....	83
Figure 73. Linn County Project 4: ISU in situ drive cylinder test	84
Figure 74. Linn County Project 4: Disc cultivator used to dry embankment materials	84
Figure 75. Linn County Project 4: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	85
Figure 76. Linn County Project 4: DCP-CBR values and cumulative blows with depth profiles	86
Figure 77. Linn County Project 4: Moisture control chart (cohesive materials)	88

Figure 78. Linn County Project 4: Moisture and density control chart (cohesionless materials).....	89
Figure 79. Linn County Project 4: Histograms of moisture and density control results (cohesive materials)	90
Figure 80. Linn County Project 4: Histograms of moisture and density control results (cohesionless materials)	91
Figure 81. Linn County Project 4: Control charts with control limits for DCP index and variation in DCP index.....	92
Figure 82. Linn County Project 4: CBR chart with CBR quality rating.....	93
Figure 83. Mills County Project 5: Caterpillar 621E scraper used to collect and place loose fill materials	94
Figure 84. Mills County Project 5: Caterpillar D6R dozer used to control lift thickness.....	94
Figure 85. Mills County Project 5: Sheepsfoot roller used for soil compaction.....	95
Figure 86. Mills County Project 5: Very wet materials in the center of the construction site.....	95
Figure 87. Mills County Project 5 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	96
Figure 88. Mills County Project 5 TB2: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	97
Figure 89. Mills County Project 5 TB1: DCP-CBR values and cumulative blows with depth profiles	98
Figure 90. Mills County Project 5 TB2: DCP-CBR values and cumulative blows with depth profiles	99
Figure 91. Mills County Project 5: Moisture control chart.....	101
Figure 92. Mills County Project 5: Histograms of moisture and density control results.....	102
Figure 93. Mills County Project 5: Control charts with control limits for DCP index and variation in DCP index.....	103
Figure 94. Mills County Project 5: CBR chart with CBR quality rating.....	104
Figure 95. Pottawattamie County Project 6: Caterpillar dozer used to control lift thickness.....	105
Figure 96. Pottawattamie County Project 6: Caterpillar 851B dozer with sheepsfoot roller wheel used for soil compaction.....	105
Figure 97. Pottawattamie County Project 6: Dynapac CA250-II vibratory smooth drum roller used for soil compaction	106
Figure 98. Pottawattamie County Project 6: Disc cultivator used to dry embankment materials	106
Figure 99. Pottawattamie County Project 6 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	107
Figure 100. Pottawattamie County Project 6 TB2: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	108
Figure 101. Pottawattamie County Project 6 TB1: DCP-CBR values and cumulative blows with depth profiles	109
Figure 102. Pottawattamie County Project 6 TB2: DCP-CBR values and cumulative blows with depth profiles	110

Figure 103. Pottawattamie County Project 6: Moisture control chart	112
Figure 104. Pottawattamie County Project 6: Histograms of moisture and density control results	113
Figure 105. Pottawattamie County Project 6: Control charts with control limits for DCP index and variation in DCP index.....	114
Figure 106. Pottawattamie County Project 6: CBR control charts with CBR quality ratings	115
Figure 107. Woodbury County Project 7: Dump truck used to place loose fill materials	116
Figure 108. Woodbury County Project 7: Caterpillar D6T dozer used to control lift thickness.....	116
Figure 109. Woodbury County Project 7: Caterpillar CS56B vibratory smooth drum roller used for soil compaction	117
Figure 110. Woodbury County Project 7: Seepage at the construction site	117
Figure 111. Woodbury County Project 7 TB1: Laboratory Proctor compaction test results with acceptance zone	118
Figure 112. Woodbury County Project 7 TB2: Laboratory Proctor compaction test results with acceptance zone	119
Figure 113. Woodbury County Project 7 TB3: Laboratory Proctor compaction test results with acceptance zone	120
Figure 114. Woodbury County Project 7 TB1: DCP-CBR values and cumulative blows with depth profiles	121
Figure 115. Woodbury County Project 7 TB2: DCP-CBR values and cumulative blows with depth profiles	121
Figure 116. Woodbury County Project 7 TB3: DCP-CBR values and cumulative blows with depth profiles	122
Figure 117. Woodbury County Project 7: Moisture control chart.....	124
Figure 118. Woodbury County Project 7: Histograms of moisture control results	125
Figure 119. Woodbury County Project 7: Control charts with control limits for DCP index and variation in DCP index.....	126
Figure 120. Woodbury County Project 7: CBR control charts with CBR quality ratings.....	127
Figure 121. Scott County Project 8: Caterpillar 349E used to excavate materials from borrow source.....	128
Figure 122. Scott County Project 8: Caterpillar dozer used to control lift thickness	129
Figure 123. Scott County Project 8: Disc cultivator used to dry embankment materials	129
Figure 124. Scott County Project 8: Sheepsfoot roller used for soil compaction.....	130
Figure 125. Scott County Project 8: Dynapac pad foot roller used for soil compaction	130
Figure 126. Scott County Project 8 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	131
Figure 127. Scott County Project 8 TB2: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	132
Figure 128. Scott County Project 8 TB3: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	133
Figure 129. Scott County Project 8 TB1: DCP-CBR values and cumulative blows with depth profiles	134

Figure 130. Scott County Project 8 TB2: DCP-CBR values and cumulative blows with depth profiles	135
Figure 131. Scott County Project 8 TB3: DCP-CBR values and cumulative blows with depth profiles	135
Figure 132. Scott County Project 8: Moisture control chart.....	137
Figure 133. Scott County Project 8: Histograms of moisture control results	138
Figure 134. Scott County Project 8: Control charts with control limits for DCP index and variation in DCP index.....	139
Figure 135. Scott County Project 8: CBR control charts with CBR quality ratings.....	140
Figure 136. Woodbury County Project 9: Caterpillar 631D motor scraper used to collect and place loose fill materials.....	141
Figure 137. Woodbury County Project 9: Caterpillar D6N dozer used to control lift thickness.....	141
Figure 138. Woodbury County Project 9: Caterpillar 140H motor grader used to level the embankment surface	142
Figure 139. Woodbury County Project 9: Caterpillar CS56 series vibratory smooth drum roller used for soil compaction	142
Figure 140. Woodbury County Project 9: Sheepsfoot roller used for soil compaction.....	143
Figure 141. Woodbury County Project 9 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	144
Figure 142. Woodbury County Project 9 TB2: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	145
Figure 143. Woodbury County Project 9 TB3: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	146
Figure 144. Woodbury County Project 9 TB4: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits.....	147
Figure 145. Woodbury County Project 9 TB1: DCP-CBR values and cumulative blows with depth profiles	148
Figure 146. Woodbury County Project 9 TB2: DCP-CBR values and cumulative blows with depth profiles	149
Figure 147. Woodbury County Project 9 TB3: DCP-CBR values and cumulative blows with depth profiles	149
Figure 148. Woodbury County Project 9 TB4: DCP-CBR values and cumulative blows with depth profiles	150
Figure 149. Woodbury County Project 9: Control charts with control limits for DCP index and variation in DCP index.....	152
Figure 150. Woodbury County Project 9: CBR control charts with CBR quality ratings.....	153
Figure 151. Comparison between Proctor test results (optimum moisture content and maximum dry density) selected by the Iowa DOT for QA testing and measured Proctor test results from the ISU research team for all project sites.....	155
Figure 152. Boxplot of moisture difference for previous and current projects	159
Figure 153. Boxplot of relative compaction for previous and current projects	160

Figure 154. Recommended specification options for future QC/QA	165
Figure 155. Polk County Project 1: Grain size distribution of embankment materials	201
Figure 156. Warren County Project 2: Grain size distribution of embankment materials	201
Figure 157. Linn County Project 3: Grain size distribution of embankment materials	202
Figure 158. Linn County Project 4: Grain size distribution of embankment materials	202
Figure 159. Mills County Project 5: Grain size distribution of embankment materials	203
Figure 160. Pottawattamie County Project 6: Grain size distribution of embankment materials	203
Figure 161. Woodbury County Project 7: Grain size distribution of embankment materials	204
Figure 162. Scott County Project 8: Grain size distribution of embankment materials	204
Figure 163. Woodbury County Project 9: Grain size distribution of embankment materials	205

LIST OF TABLES

Table 1. Summary of bid costs for implementation of Iowa DOT moisture and moisture-density specification.....	3
Table 2. DCP index target values for granular materials.....	13
Table 3. DCP index and LWD deflection target values for non-granular materials.....	14
Table 4. QA requirements using DCP test measurements for different non-granular materials	15
Table 5. DCP index target values	19
Table 6. CBR values for subgrade soils.....	19
Table 7. Soil index properties of embankment materials obtained from Polk County.....	27
Table 8. Soil index properties of embankment materials obtained from Warren County and Linn County 79	28
Table 9. Soil index properties of embankment materials obtained from Linn County 77.....	29
Table 10. Soil index properties of embankment materials obtained from Pottawattamie County and Woodbury County I-29	30
Table 11. Soil index properties of embankment materials obtained from Scott County and Mills County	31
Table 12. Soil index properties of embankment materials obtained from Woodbury County US 20	32
Table 13. Summary of project information.....	33
Table 14. Polk County Project 1: Summary of field testing.....	45
Table 15. Warren County Project 2: Summary of field testing	58
Table 16. Linn County Project 3: Summary of field testing results	73
Table 17. Linn County Project 4: Summary of field testing results	87
Table 18. Mills County Project 5: Summary of field testing results	100
Table 19. Pottawattamie County Project 6: Summary of field testing results	111
Table 20. Woodbury County Project 7: Summary of field testing results.....	123
Table 21. Scott County: Summary of field testing	136
Table 22. Woodbury County Project 9: Summary of field testing	151
Table 23. Summary of the percentage of test points outside of the specification control limits in contractor QC data, Iowa DOT QA data, and ISU data	157

Table 24. Summary of the percentage of test points outside of the specification control limits	159
Table 25. Summary of the mean and standard deviation values for each project	160
Table 26. Summary of <i>t</i> - and <i>p</i> -values from <i>t</i> -test results comparing Δw measurements obtained from Phases I through IV and IHRB TR-677	161
Table 27. Summary of odds ratio and <i>p</i> -values from logistic regressions comparing the percentage of data within the moisture control limits from Phases I through IV and IHRB TR-677.....	161
Table 28. Summary of <i>t</i> - and <i>p</i> -values from <i>t</i> -test results comparing RC measurements obtained from Phases I through IV and IHRB TR-677	162
Table 29. Summary of odds ratio and <i>p</i> -values from logistic regression results comparing the percentage of data above the density control limit (95% RC) from Phases I through IV and IHRB TR-677	162
Table 30. Typical embankment material treatment/stabilization options to improve performance	168
Table 31. Comparison of in situ testing procedures for embankment construction	169
Table 32. Specifications of embankment construction for granular materials	173
Table 33. Specifications of embankment construction for non-granular materials	187

ACKNOWLEDGMENTS

This project was sponsored by the Iowa Highway Research Board (IHRB) and the Iowa Department of Transportation (DOT). Melissa Serio, Steve Megivern, Kevin Jones, and Bob Stanley (retired) of the Iowa DOT provided valuable feedback throughout the course of the project. Resident construction engineers (RCEs) from Harrison, Linn, Mills, Polk, Pottawattamie, Scott, Warren, and Woodbury counties provided access to project sites and quality control/assurance field data. Chao Chen of Iowa State University assisted in performing laboratory testing. All of their efforts are greatly appreciated.

EXECUTIVE SUMMARY

Embankments are critical components of infrastructure that support pavement systems and bridge approaches. Embankments are designed to provide the specified elevation for the performance life of the overlying pavement systems and embedded drainage structures. Because the quality of embankment construction directly influences the performance of the support infrastructure, improvements to embankment compaction quality will reduce cost of future maintenance and reconstruction.

Past research shows that significant variability exists in the final compaction conditions (e.g., moisture content) for embankment fills and that variability in compaction quality is largely influenced by wet Iowa fill materials and variable lift thickness control and compaction operations. Past experimental pilot projects have been conducted in Iowa to document compaction quality using the “walk out” roller specification versus end-result alternative requirements including moisture/density control and use of dynamic cone penetration testing as a measurement of lift thickness, uniformity, and soil strength. The variability of dynamic cone penetrometer (DCP) index values in surficial lifts has been observed to be high. Bergeson et al. (1998) found that a significant contributor to slope instability issues and pavement roughness problems was that embankment fill materials were being placed outside the specified moisture and density control limits. In addition, wet soils compacted near the zero air voids curve can result in high pore pressure as subsequent lifts are placed and compacted, which can lead to reduced shear strength. This action can create shear stresses on potential failure surfaces, which can lead to subgrade instability and/or slope failures.

Based on the outcomes from these past research studies, the Iowa Department of Transportation (DOT) implemented a specification for contractor moisture or moisture-density quality control (QC) in roadway embankment construction that has been in use for approximately 10 years in Iowa on about 190 projects. The motivation for the research described in this report was based on work by Iowa State University (ISU) researchers at a few recent grading projects that demonstrated that embankments were being constructed outside moisture control limits, even though the contractor QC testing and quality assurance (QA) testing showed all work was being performed within the control limits. This finding initiated the need for a more detailed study with testing at several active grading projects across Iowa.

The current study set out to study the impact of the current specifications in terms of quality compaction and to identify further areas for improvement given recent advancements in compaction measurement systems and in situ testing technologies. Field testing was conducted on nine active construction sites in Iowa with materials consisting of glacial till, western Iowa loess, and alluvium sand. Drive cylinder tests were performed to determine in situ moisture content and dry density; DCP tests were performed to determine California bearing ratio (CBR) profiles with depth. Field test results from ISU testing were assessed to determine whether the data were within the moisture control limits ($\pm 2\%$ of optimum moisture content) and above the minimum relative compaction (RC) control limit (95% of standard Proctor test). The data that were available from contractor QC testing and Iowa DOT QA testing were also assessed in comparison with ISU test results. Finally, field test results from this project were compared with

data from previous embankment research projects to assess if there was a statistically significant improvement in terms of the percentage of data within the control limits of the current specifications.

Key findings from this study are as follows:

- For cohesive materials, the contractor QC data showed that 1% to 45% of moisture measurements were outside of the specification and 2% to 75% of density measurements were outside of the specification. Iowa DOT QA data at two project sites showed that 63% to 69% of moisture measurements were outside of the specification. The ISU testing results showed that one project site showed all test measurements within the moisture and density specification limits. At the remaining project sites, 12% to 62% of ISU moisture measurements were outside of the specification, and 4% to 40% of ISU density measurements were outside of the specification.
- For cohesionless materials, the contractor QC results on one site show that 2% of the moisture measurements were outside of the control limits. Iowa DOT QA data at the same site show that 20% of the moisture measurements (11% dry of the lower control limit and 9% wet of the upper control limit) were outside of the specification control limits. ISU testing at the same site show that 66% of the moisture content measurements were outside of the specification control limits (2% dry, 64% wet).
- Two other project sites with cohesionless materials show 85 to 100% of the moisture measurements outside of the control limits, of which a majority of the measurements (81% to 100%) were dry of the lower control limit. One of the sites showed that all density measurements were > 95% RC, while the other showed 14% of density measurements were < 95% RC.
- DCP results showed that the compacted fills have relatively low and variable CBR values, about 0.6% to 8.2% for 8 in. depth and 0.5% to 8.6% for 12 in. depth.
- During in situ construction observations, discing did not effectively aerate wet fill material.
- During in situ observations, cohesionless fill materials were very wet. The CBR values (0.3% to 1.0% at 8 in. depth and 0.3% to 1.7% at 12 in. depth) also indicated weak support conditions.
- Proctor tests conducted by ISU using representative material obtained from each test section where field testing was conducted showed optimum moisture contents and maximum dry densities that are different from what was selected by the Iowa DOT for QC/QA testing. Comparison between the measured and selected values showed a standard error of 2.9 lb/ft³ for maximum dry density and 2.1% for optimum moisture content. The difference in optimum moisture content was as high as 4% and the difference in maximum dry density was as high as 6.5 lb/ft³.

- For maximum dry density, AASHTO T 99 allows 4.5 lb/ft³ variation between two test results from different laboratories, while ASTM D698 allows 2.3 lb/ft³ to 3.9 lb/ft³, depending on the soil type. Results indicated that only 1 of 19 test results fell outside the allowable limits per AASHTO T 99, while 7 of 19 fell outside the allowable limits per ASTM D698.
- For optimum moisture content, AASHTO T 99 allows variation of 15% from the mean of the two test results, while ASTM D698 allows a variation of 1.5% to 1.8%, depending on the soil type. Only 3 of 26 test results fell outside the allowable limits per AASHTO T 99, while 7 of 26 fell outside the allowable limits per ASTM D698.
- Statistical analysis indicated statistically significant differences between the moisture content relative to optimum (Δw) and RC results obtained from this project and the previous embankment research projects. The results indicated that data obtained from the current IHRB TR-677 project had a higher percentage of data that were within the control limits for Δw and above the control limit for RC compared to all previous project phases. This suggests improvement over the previous project results.

Based on the field testing and observations documented in this report, although the results show a statistically significant improvement over previous projects, QC/QA results are not consistently meeting the target limits/values. Recommendations are provided in the final chapter of this report along with a one-page graphic presentation of three proposed options for improvements to the current specifications. Briefly, the three options are as follows:

- Option 1: Enhance the current Iowa DOT moisture and moisture-density specifications in terms of differentiating the material types, developing a spatial random sampling method, and improving process control through control charts.
- Option 2: Develop alternative QC/QA specifications using dynamic cone penetrometer or modulus-based testing using existing specifications and target values as guidance.
- Option 3: Incorporate calibrated intelligent compaction (IC) measurements into QC/QA specifications by developing statistically valid field calibrations and mappings of final layers to determine areas of noncompliance.

CHAPTER 1: INTRODUCTION

Embankments are critical components of infrastructure that support pavement systems and bridge approaches. Embankments are designed to provide the specified elevation for the performance life of the structure. The quality of embankment construction directly influences the performance of the supported infrastructure and the cost of future maintenance and reconstruction. A quality embankment requires proper selection of fill materials, adequate moisture and density control, and adequate compaction. Desirable engineering properties for a quality embankment include adequate strength, stability, and density; low permeability; low shrink swell behavior; and low collapsibility depending on the design requirement.

Embankment subgrade soils in Iowa are generally rated as fair to poor as construction materials, with a majority of the soils classifying as A-4 to A-7-6 according to the AASHTO Soil Classification System (AASHTO 2012). These soils can exhibit low bearing strength, high volumetric instability, and freeze/thaw or wet/dry durability problems. Therefore, proper field construction controls and the accompanying quality control (QC) and quality assurance (QA) processes are important to achieve the desired embankment quality.

Past research in Iowa shows that significant variability exists in the final compaction moisture content for embankment fills and that this is largely influenced by the generally wet ground conditions of borrow materials and rainfall events during the Iowa construction season (Larsen 2007, White and Bergeson 1999). The variability of dynamic cone penetrometer (DCP) index values in surficial lifts has been observed to be high. Bergeson et al. (1998) found that a significant contributor to slope instability issues and pavement roughness problems was that embankment fill materials were being placed outside the specified moisture and density control limits. In addition, wet soils compacted near the zero air voids curve can result in high pore pressure as subsequent lifts are placed and compacted, which can lead to reduced shear strength. This action can create shear stresses on potential failure surfaces, which can lead to subgrade instability and/or slope failures (Lambe and Whitman 1969).

A specification for contractor moisture QC in roadway embankment construction has been in use for approximately 10 years in Iowa on about 190 projects. The use of this QC specification originated from Iowa Highway Research Board (IHRB) embankment quality research projects from the late 1990s. Since then, the Iowa Department of Transportation (DOT) has specified compaction with moisture control on most embankment work under pavements. The motivation for the research described in this report was based on work performed by Iowa State University (ISU) researchers at a few recent grading projects that demonstrated that embankments were being constructed outside moisture control limits, even though the contractor QC and QA testing showed that all work was being performed within the control limits. This finding initiated the need for a more detailed study and testing at several active grading projects across Iowa.

The present IHRB TR-677 project was initiated to evaluate the quality of embankments constructed per current Iowa DOT embankment construction specifications, especially moisture-density QC/QA. An ISU research team conducted in situ moisture-density and stiffness measurements of compacted fill at eight active embankment construction sites in six Iowa

counties. A total of 28 granular and non-granular materials were collected from these sites for laboratory soil classification and soil index property testing.

The primary research tasks for this project were as follows:

- Provide project management to coordinate testing and data collection at selected Iowa DOT earthwork projects
- Review past literature related to Iowa embankment quality and QC/QA practices
- Select project sites for evaluation in partnership with the Iowa DOT
- Collect data, assess results, and develop recommendations

The research team set out to coordinate with the Iowa DOT Office of Construction and Materials and the Iowa DOT Office of Design Soils Design Section to select 8 to 12 projects for field testing. Projects were selected to be representative of the soil and project conditions statewide. Figure 1 shows the selected project locations in reference to surficial soil types in Iowa.




Figure 1. Eleven project sites identified for field evaluation

Once the projects were identified, the research team traveled to the selected sites for in situ testing. The in situ testing areas were typically sections of about 1,000 ft in length. At each site, 10 to 30 moisture and dry density measurements were collected to provide a statistically significant dataset for analysis. Representative bulk samples were collected from each site for laboratory characterization. Using the field test results, comparisons were made to the project target requirements for moisture content and density. DCP tests were also performed to study the lift thickness and stability uniformity. For project sites where data were available, the data

generated by the Iowa DOT and contractor were included with the ISU data to provide additional analysis of the QC/QA results.

In terms of the cost of the implemented moisture and density specifications, Table 1 summarizes the unit bid prices for the awarded contracts for the 11 projects identified in Figure 1.

Table 1. Summary of bid costs for implementation of Iowa DOT moisture and moisture-density specification

County	Specification	Unit Price per Cubic Yard	Total Quantity (Cubic Yards)	Total Cost (USD)
Linn	Moisture	\$0.40	602,243	\$240,897.20
Woodbury	Moisture	\$0.80	360,776	\$288,620.80
Mills	Moisture	\$0.20	224,025	\$44,805.00
Warren	Moisture	\$0.21	170,752	\$35,857.92
Polk	Moisture	\$0.80	166,710	\$133,368.00
Scott	Moisture	\$0.10	119,267	\$11,926.70
Pottawattamie	Moisture	\$1.02	107,753	\$109,908.06
Linn	Moisture	\$0.35	64,331	\$22,515.85
Harrison	Moisture	\$0.40	60,327	\$24,130.80
Linn	Moisture-Density	\$0.80	79,583	\$63,666.40
Linn	Moisture-Density	\$0.75	55,507	\$41,630.25
			TOTAL	\$1,017,327.00

Of these projects, nine included a moisture control specification while two included a moisture-density control specification. On average, the cost of implementing a moisture control specification was about \$0.49/cubic yard (cy), and the cost of implementing a moisture-density control specification was about \$0.78/cy.

Following this Introduction, this report consists of six chapters: Background, Testing and Analysis Methods, Materials, Field Test Results, Data Analysis, and Conclusions and Recommendations.

CHAPTER 2: BACKGROUND

In this chapter, a brief summary of previous embankment quality evaluation projects in Iowa is provided along with the ISU testing results from those projects, an overview of intelligent compaction research and implementation projects undertaken in Iowa for embankment construction is provided, and a summary of the earthwork QC/QA specifications followed by different state departments of transportation is provided along with alternative specification options introduced by some state DOTs for moisture-density control.

IHRB TR-401 Phase I Summary

Phase I research was initiated as a result of internal Iowa DOT studies that raised concerns about the quality of embankments currently being constructed. Some large embankments had recently developed slope stability problems resulting in slides that encroached on private property and damaged drainage structures. In addition, pavement roughness was observed shortly after roads were opened to traffic, especially for flexible pavements at transitions from cut to fill and on grade and pave projects. These problems raised questions regarding the adequacy of the Iowa DOT embankment construction specifications. The primary objective of Phase I was to evaluate the quality of embankments being constructed under the current specifications.

The in situ moisture contents relative to optimum moisture content (Δw) and the relative compaction (RC) test results obtained from the Phase I study are summarized as histograms in Figure 2.




Figure 2. IHRB TR-401 Phase I: Histograms of moisture and relative compaction test results from ISU testing

The results indicate that about 37% of the RC test measurements and 71% of the moisture content test measurements were outside of the control limits. Based on the overall test results and field observations from Phase I, Bergeson et al. (1998) indicated that consistent embankment quality was not being attained under the existing Iowa DOT specifications at that time.

IHRB TR-401 Phase II Summary

Phase II research was initiated to investigate different methods and techniques that could be used to improve the Iowa DOT soil classification and compaction control specifications based on observations and data collected at small-scale pilot compaction studies. Histogram plots of in situ test results are summarized in Figure 3.




Figure 3. IHRB TR-401 Phase II: Histograms of moisture and relative compaction test results from ISU testing

Similar to the Phase I test results, about 31% of the RC test measurements and 84% of the moisture content test measurements were outside of the control limits.

The results from the pilot studies indicated that new specifications were required that better account for the differences between the behavior of cohesive and cohesionless soils. The Iowa Empirical Performance Classification (IEPC) system was developed. Compared with former specifications, the IEPC considered many more of the factors that affect the engineering properties of soil. The use of DCP testing was also proposed as a supplement to field moisture-density quality control testing in both cohesive and cohesionless soils because DCP results provide in situ measurements of fill strength and can be used to assess the variability of fill strength with depth (White and Bergeson 1999).

IHRB TR-401 Phase III Summary

Field testing on active project sites similar that of previous phases was continued during Phase III. The results are summarized in Figure 4, which shows that about 24% of the RC test measurements and 42% of the moisture measurements were outside of the control limits.




Figure 4. IHRB TR-401 Phase III: Histograms of moisture and density test results

Phase III research focused on creating a comprehensive earthwork construction specification, the Quality Management Earthwork (QM-E) program, which incorporated the findings and recommendations of the previous two research phases into a practical field construction specification. The QM-E was then implemented on a full-scale pilot project to field test and refine elements of the proposed program for cohesionless soils. The results of this pilot project were promising. The soil classification system worked well in both the design and construction phases of the project, having required only minor modifications. The special provisions of the

QM-E program, developed jointly with the Iowa DOT, also worked well and required minimal alteration. Ultimately, the overall quality of the embankment fill showed improvement, as indicated by DCP testing and the additional discing that was required. The cost of this improvement was nominal, 3.3% for the additional discing and the application of the QM-E program, in comparison to the perceived improvement in quality (White et al. 2002).

IHRB TR-492 Phase IV Summary

In situ moisture and density field test results from active project sites during Phase IV are summarized in Figure 5, which shows that about 26% of the RC test measurements and 75% of the moisture measurements were outside of the control limits.




Figure 5. IHRB TR-401 Phase IV: Histograms of moisture and density test results

The costs of implementing the QM-E program in the previous project had been relatively small, but it was believed that if the fill material were considerably more difficult to moisture condition, as is the case with cohesive soils, the special provisions might prove unreasonable and expensive. Therefore, a second full-scale pilot project was conducted on cohesive soils. The goals of this pilot project were to (1) field test and refine elements of the QM-E program for cohesive soils, (2) train additional contractor and Iowa DOT personnel in the Certified Grading Technician Level I program, and (3) review other state DOT earthwork specifications for potential modifications to the QM-E special provision. Smaller field studies were also conducted prior to the pilot project to establish the state of the practice in Iowa for construction of earthen embankments in unsuitable soils (White et al. 2007).

Intelligent Compaction

Preliminary Study

The Iowa DOT cosponsored the IHRB TR-495 study for preliminary evaluation of intelligent compaction (IC) technologies in collaboration with Caterpillar, Inc. (CAT). This study was initiated in 2003 to begin evaluating a compaction monitoring technology developed by Caterpillar, Inc. The technology comprised an instrumented prototype padfoot roller to monitor changes in machine power output resulting from soil compaction and the corresponding changes in machine-soil interaction. The roller was additionally outfitted with a global positioning system (GPS), such that coverage and machine power could be mapped and viewed in real-time during compaction operations. White et al. (2004) summarized the findings from the field pilot studies conducted at CAT facilities in Peoria, Illinois, and on an earthwork grading project in West Des Moines, Iowa. The significant research findings from the Phase I study are summarized as follows:

- Multiple linear regression analyses were performed using machine power and various field measurements (nuclear moisture and density, DCP index, and Clegg impact value [CIV]). The coefficient of determination (R^2) values of the models indicated that compaction energy accounts for more variation in dry unit weight than the DCP index or CIV.
- Incorporating moisture content in the regression analyses improved model R^2 values for DCP index and CIV and indicated the influence of moisture content on strength and stiffness.
- The compaction monitoring technology showed a high level of promise for use as a QC/QA tool but was demonstrated for a relatively narrow range of field conditions.

The results of this proof-of-concept study provided evidence that machine power may reliably indicate soil compaction with the advantages of 100% coverage and real-time results. Additional field trials were recommended, however, to expand the range of correlations to other soil types, roller configurations, lift thicknesses, and moisture contents. The observed promise of using such compaction monitoring technology in earthwork QC/QA practices also required the development of guidelines for its use, including a statistical framework for analyzing the near-continuous data.

Implementation Program

The Iowa DOT Intelligent Compaction Research and Implementation program was initiated in summer 2009. Three field demonstration projects were conducted in Iowa as part of Phase I of this research program to evaluate three different IC measurement technologies (White et al. 2010): (1) machine drive power (MDP) measurement technology on a Caterpillar CP56 padfoot roller on a US 30 embankment construction project, (2) continuous compaction value (CCV) technology on a Sakai SW880 dual vibratory smooth drum asphalt roller on an asphalt overlay project, and (3) compaction meter value (CMV) technology on a Volvo SD116DX smooth drum vibratory roller on a granular base/subbase layer construction project on I-29. Phase II focused on hot-mix asphalt (HMA) paving projects and is therefore not discussed in this report.

Data obtained from the embankment construction project on US 30 with Caterpillar's MDP technology indicated that the subgrade materials were relatively wet (on average about 5% wet of optimum) during construction. MDP measurements obtained over multiple lifts of embankment fill materials indicated that a "soft" zone with relatively low values on the bottom lift reflected through four successive lifts with similarly low values in that zone. Geostatistical analysis was conducted on the georeferenced IC data, which indicated that variability decreased and spatial continuity improved as additional lifts were placed. Results also indicated that multiple non-linear regression analysis incorporating moisture content improved correlations between light weight deflectometer elastic modulus (E_{LWD}) values and MDP measurements, while there was no statistically significant correlation between dry density and MDP measurements.

Data obtained from the granular base/subbase layer construction project on I-29 using the CMV system included calibration test strips and production area test beds (TBs) with correlations between CMV measurements and in situ nuclear gauge dry density, DCP-California bearing ratio (CBR), and E_{LWD} values. Data from multiple passes indicated that the CMV data were repeatable. CMV maps were able to effectively delineate "soft" and "stiff" zones effectively. Correlations were statistically significant between CMV IC measurements and E_{LWD} and DCP-CBR point measurements, while there was no statistically significant relationship between dry density and CMV measurements.

Summary of Earthwork QC/QA specifications in the US

The standard and supplemental specifications of 50 state departments of transportation were reviewed and are summarized in this section. These standards and specifications are organized separately for granular and non-granular materials in Appendices A and B, respectively. The critical components of the specifications included in the summary are equipment, gradation, placement of materials and compaction method, disc and compaction passes, lift thickness, and moisture content and density/relative compaction requirements.

The QC/QA requirements varied between states and the material types as follows: (1) moisture control only, (2) density control only, (3) moisture and density control, (4) moisture and density control depending on the compaction method, and (5) only moisture or moisture-density control

depending on the project. Figure 6 and Figure 7 graphically depict which states have different QC/QA requirements for granular and non-granular materials.




Figure 6. QC/QA requirements for granular materials in the US




Figure 7. QC/QA requirements for non-granular materials in the US

For granular materials, the most common requirement is moisture and density control, which 21 states require. The second most frequently used requirement is density control only, which 15 states require. One state requires only moisture control; six states require different moisture and density controls depending on the compaction method; two states require moisture or

and density control depending on the project. The remaining four states do not specify any requirements in their standard specifications.

For non-granular materials, the most common requirement is moisture and density control, which 29 states require. The second most frequently used requirement is density control only, which 11 states require. Eight states require different moisture and density controls depending on the compaction method; the remaining two states require either moisture or moisture and density control depending on the project.

Alternative Specification Options

Two state DOTs (Minnesota and Indiana) provide alternative specification options to moisture and density control for QA. Both states are currently using these as special provisions in their project specifications.

The Minnesota DOT (MnDOT) provides specification target values for granular materials using DCP and light weight deflectometer (LWD) values (Siekmeier et al. 2009). The target values are based on the grading number (GN) and field moisture content (determined by a field oven-dry test) of the material (Table 2).

Table 2. DCP index target values for granular materials

Grading Number	Moisture Content (percent of dry weight)	Maximum Allowable DPI, mm/blow	Target LWD Modulus Using Dynatest, MPa ^{*§}	Target LWD Modulus Using Zorn, MPa ^{*§}	Target LWD Deflection Using Zorn, mm [*]
3.1 – 3.5	< 5.0	10	120	80	0.38
	5.0 – 8.0	12	100	67	0.45
	> 8.0	16	75	50	0.63
3.6 – 4.0	< 5.0	10	120	80	0.38
	5.0 – 8.0	15	80	53	0.56
	> 8.0	19	63	42	0.71
4.1 – 4.5	< 5.0	13	92	62	0.49
	5.0 – 8.0	17	71	47	0.64
	> 8.0	21	57	38	0.79
4.6 – 5.0	< 5.0	15	80	53	0.56
	5.0 – 8.0	19	63	42	0.71
	> 8.0	23	52	35	0.86
5.1 – 5.5	< 5.0	17	71	47	0.64
	5.0 – 8.0	21	57	38	0.79
	> 8.0	25	48	32	0.94
5.6 – 6.0	< 5.0	19	63	42	0.71
	5.0 – 8.0	24	50	33	0.90
	> 8.0	28	43	29	1.05

* LWDs should have a falling mass of 10 kg, plate diameter of 20 cm, and drop height of 50 cm.

§ Modulus calculation assumes a Poisson’s ratio of 0.35, and the loading plate is assumed to be rigid. Modulus calculation for Zorn assumes a constant stress of 0.2 MPa, while applied stress is measured for Dynatest.

Source: Siekmeier et al. (2009)

The GN is determined based on sieve analysis test results. The LWD target values are provided in terms of elastic modulus determined from two different manufacturers (Zorn and Dynatest) and deflection values using a Zorn LWD.

MnDOT also provides specification target values for non-granular materials using DCP and LWD based on the plastic limit and field moisture content of the material (Table 3).

Table 3. DCP index and LWD deflection target values for non-granular materials

Plastic Limit (%)	Estimated Optimum Moisture (%)	Field Moisture as a Percent of Optimum Moisture (%)	DPI at Field Moisture (mm/blow)	LWD Deflection Targets Using Zorn	
				Minimum (mm)	Maximum (mm)
non-plastic	10-14	70-74	12	0.5	1.1
		75-79	14	0.6	1.2
		80-84	16	0.7	1.3
		85-89	18	0.8	1.4
		90-94	22	1.0	1.6
15-19	10-14	70-74	12	0.5	1.1
		75-79	14	0.6	1.2
		80-84	16	0.7	1.3
		85-89	18	0.8	1.4
		90-94	22	1.0	1.6
20-24	15-19	70-74	18	0.8	1.4
		75-79	21	0.9	1.6
		80-84	24	1.0	1.7
		85-89	28	1.2	1.9
		90-94	32	1.4	2.1
25-29	20-24	70-74	24	1.0	1.7
		75-79	28	1.2	1.9
		80-84	32	1.4	2.1
		85-89	36	1.6	2.3
		90-94	42	1.8	2.6
30-34	25-29	70-74	30	1.3	2.0
		75-79	34	1.5	2.2
		80-84	38	1.7	2.4
		85-89	44	1.9	2.7
		90-94	50	2.2	3.0

Source: Siekmeier et al. 2009

The optimum moisture content of the material is estimated using the plastic limit of the material, based on empirical relationships MnDOT developed for Minnesota soils. LWD target values are provided in terms of minimum and maximum deflection values using a Zorn LWD.

The Indiana DOT provides specifications with target limits for using DCP to determine the in situ strength of granular soils, non-granular soils, and chemically modified soils (Indiana DOT 2015a, Indiana DOT 2015b). Table 4 summarizes the criteria the Indiana DOT uses based on the maximum dry density and optimum moisture content for non-granular materials (sandy soils listed in Table 4 are presumed to be sandy clay soils because they are referenced as non-granular material) and granular soils with different maximum particle sizes.

Table 4. QA requirements using DCP test measurements for different non-granular materials

Textural Classification	Maximum Dry Density (lb/ft³)	Optimum Moisture Content Range (%)	Acceptable Minimum DCP Blows for 6 in. Penetration	Acceptable Minimum DCP Blows for 12 in. Penetration
Non-Granular Soils				
Clay Soils	< 105	19 - 24	6	—
	105 - 110	16 - 18	7	
	111 - 114	14 - 15	8	
Silty soils	115 - 116	13 - 14	—	9
	117 - 120			11
Sandy soils	121 - 125	8 - 12	—	12
	> 125			15
Granular Soils A-1, A-2, and A-3 Soils (with 100% Passing)				
No. 30 sieve	N/A			6
No. 4 sieve				7
½ in. sieve				11
1 in. sieve				16

Source: Indiana DOT 2015b

The DCP criteria are provided based on the allowable number of DCP blows to 6 in. penetration for clay soils and to 12 in. penetration for sandy and silty clay soils and granular soils. The maximum dry density and optimum moisture content are determined following a graphical procedure based on the one-point Proctor test for non-granular soils (Indiana DOT 2015b). Indiana DOT specifications also allow using LWD testing for QA, but target limits are not provided in the specifications.

CHAPTER 3: TESTING AND ANALYSIS METHODS

The ISU research team performed field tests at embankment construction sites and conducted laboratory tests of embankment fill materials obtained from those sites.

Field Testing Methods

DCP and in situ drive cylinder tests were conducted to assess newly constructed embankment compaction properties. A GPS was used to record the location of test points in each test section.

Drive Cylinder

Drive cylinder tests were conducted in accordance with ASTM D2937-10 (2010). A thin-wall, 4.0 in. diameter cylinder was driven into a compacted lift with a driving head to obtain relatively undisturbed samples. The cylinders then were carefully excavated (Figure 8), placed in a zip-sealed bag, and transported to the laboratory in a humid cooler for laboratory testing.




Figure 8. Schematic of drive cylinder (left) and ISU researcher performing in situ testing (right)

The samples then were processed in the laboratory to measure the wet unit weight, and a sample was obtained to determine moisture content in accordance with ASTM D2216-10 (2010).

Dynamic Cone Penetrometer (DCP)

DCP testing was conducted in accordance with ASTM D6951-09 (2015). The DCP tip was driven into soil by lifting the 17.6 lb sliding hammer up to the handle and then releasing it (Figure 9).




Figure 9. Schematic of DCP device (left) and ISU research team performing in situ testing (right)

The total penetration for a given number of blows was measured and recorded in mm/blow, which is referred to as DCP penetration index (DPI) and is used to estimate in situ CBR from the following equations:

For CH soils
$$CBR = \frac{1}{0.002871 \text{ (DPI)}} \quad (1)$$

For CL soils and $CBR < 10$
$$CBR = \frac{1}{(0.017019 \text{ DPI})^2} \quad (2)$$

For all other soils
$$CBR = \frac{292}{(\text{DPI})^{1.12}} \quad (3)$$

A chart of CBR versus depth and cumulative blows versus depth was plotted for each test bed. The plots presented the change in CBR with increasing depth and the change in cumulative blows with increasing depth. The charts were visually designed to indicate the stiffness of the compacted fills, with higher CBR values indicating higher stiffness. Depths of 8 in. and 12 in. were selected to present the performance of compaction. The cumulative blows at 8 in. and 12 in. were obtained from this chart, and then corresponding DPI and CBR values were calculated according to Equations 1 through 3, whichever is appropriate (Figure 10).




Figure 10. Example DCP-CBR values and cumulative blows with depth plots and interpretation of average values for 8 in. and 12 in. depths

A flow chart of DCP data collection and analysis is shown in Figure 11.




Figure 11. Flow chart used for collecting and analyzing DCP data

To evaluate the uniformity of the compacted fill, the weighted average and variation of the DCP index values were determined in accordance with the following equations (White et al. 2007):

$$DCP \text{ index (for a test layer of thickness } H) = \frac{1}{H} \sum_{i=1}^n d_i^2 \quad (4)$$

$$\text{Average variation in DCP index} = \frac{1}{H} \sum_{i=2}^n |d_i - d_{i-1}| d_{i-1} \quad (5)$$

where, n = total number of blows, d_i = penetration distance for the i th blow, and H = depth of the test layer.

The average DCP index value and the variation in the DCP index values were compared with the maximum values recommended by White et al. (2007), as summarized in Table 5.

Table 5. DCP index target values

Soil Classification		Average DCP Index (mm/blow)	Variation in DCP Index (mm/blow)
Cohesive	Select	65	35
	Suitable	70	40
	Unsuitable	70	40
Granular	Select	35	35
	Suitable	45	45

Source: White et al. 2007

The CBR values calculated from these data were also compared with the relative ratings presented in Chapter 6 of the Iowa Statewide Urban Design and Specifications (SUDAS) Design Manual (**Error! Not a valid bookmark self-reference.**).

Table 6. CBR values for subgrade soils

CBR (%)	Material	Rating
20 to 30	Subgrade	Very good
10 to 20	Subgrade	Fair-good
5 to 10	Subgrade	Poor-fair
< 5	Subgrade	Very poor

Source: SUDAS 2013

Global Positioning System (GPS)

To locate the in situ testing points at each construction project, a Trimble R8 Model 3 GPS device was used to obtain real-time kinematic (RTK) GPS measurements by connecting to Iowa real-time network stations (Figure 12).



Figure 12. Location information measured by GPS device

Sampling

The ISU research team met with the project's resident construction engineer (RCE) or the Iowa DOT field engineer and/or the contractor foreman to discuss which areas had passed QA with approximate starting and end stations. Depending on the size of the area that was passed, up to 15 locations that were uniformly spaced in a systematic pattern through the middle of the test area were selected for moisture and density testing. Two examples of sampling patterns are shown in Figure 13.




Figure 13. Two patterns of in situ testing point selection: Pottawatamie County project (top) and Linn County 77 project (bottom)

DCP tests were typically only performed at every third test point (i.e., DCP tests were performed only at 5 locations if there were 15 total test locations).

Laboratory Testing

Representative soil materials were collected from each construction site and used for conducting the following laboratory tests.

Soil Index Properties

Particle size analysis was conducted in accordance with ASTM D422-63 (2010). The distribution of particle sizes larger than 75 μm (opening size of the No. 200 sieve) was determined by sieving, and the distribution of particle sizes smaller than 75 μm was determined by the hydrometer method. Atterberg limit testing was conducted in accordance with ASTM D4318-10 (2010) using the wet preparation method. Liquid limit tests were performed using the multipoint method (Figure 14).



Figure 14. Soil classification equipment (left to right: sieve analysis, hydrometer test, and Atterberg limit test)

Based on these results, each sample was classified according to the Unified Soil Classification System (USCS) and AASHTO M 145 (AASHTO 2012) Soil Classification System. The specific gravity of each sample was determined in accordance with ASTM D854-14 (2014) Method A.


Compaction Characteristics

The relationship between the moisture and dry unit weight of embankment materials was determined in accordance with ASTM D698-12e2 (2012) and ASTM D1557-12e1 (2012). The appropriate method was chosen based on the grain size distributions for each sample. Method A was applicable for all soil materials. The tests were performed at five moisture contents, and the optimum moisture-density characteristics were obtained by fitting the data to the Li and Sego Fit model (Equation 5):

$$\gamma_d(w) = \frac{G_s \gamma_w}{\left(1 + \frac{w G_s}{S_m - S_m \left(\frac{w_m - w}{w_m}\right)^{n+1}} \left(\frac{w_m^n + p^n}{(w_m - w) + p^n}\right)\right)} \quad (5)$$

where, γ_d = dry density of the soil, G_s = specific gravity of the soil, γ_w = density of water, w = moisture content of the soil, S_m = maximum of saturation, w_m = moisture content at S_m , and n and p are shape factors.

Figure 15 shows the fit model, the relationship, and the relevant parameters.



Reproduced from Li and Segoo 2000

Figure 15. Density curve

The boundary condition on the wet side of optimum, S_m , can be determined from the wet side of the compaction curve running parallel to the zero air void curve. The boundary condition on the dry side of w_{opt} is the dry density (γ_{dd}). The shape factor n affects the dome portion of the compaction curve. When n is increased, the dome portion becomes sharper; when n is decreased, the dome portion tends to flatten. Shape factor p influences the width of the upper portion of the curve without affecting shape factor n or boundary conditions S_m and γ_{dd} . To make a correct fit, S_m and w_m were first determined based on the data to establish the boundary of the curve, and shape factors n and p were adjusted until a maximum correlation coefficient (R^2) between the measured and the predicted values was achieved.

Statistical Analysis Methods

To compare the differences between the field results obtained from the previous project phases and the field results obtained from the current project, a t -test analysis was performed. The main objective of this analysis was to assess whether there is a statistically significant difference in the number or percentage of test locations that did not meet the moisture and density control limits. A t -test analysis was performed for unequal sample size and unequal variances between the different project phase results. The test was set up with a research hypothesis that the mean

values of the measurements obtained in one project (μ_0) were higher than those obtained in another project (μ_1).

The approximate t -value (represented as t') was calculated using the following equation (Ott and Longnecker 2008):

$$t' = \frac{\mu_0 - \mu_1}{\sqrt{\frac{s_0^2}{n_0} + \frac{s_1^2}{n_1}}} \quad (9)$$

where, n_0 and n_1 = number of measurements from two different projects, μ_0 and μ_1 = mean values of measurements from two different projects, and s_0 and s_1 = standard deviation of measurements from two different projects. The observed t' -values were then compared with the minimum t' -values for a one-tailed test, with the degrees of freedom (DOF) calculated using Equations (10) and (11), at a 95% confidence level (i.e., $\alpha = 0.05$):

$$DOF = \frac{(n_0 - 1)(n_1 - 1)}{(1 - c)^2(n_0 - 1) + c^2(n_1 - 1)} \quad (10)$$

where,

$$c = \frac{s_0^2/n_0}{\frac{s_0^2}{n_0} + \frac{s_1^2}{n_1}} \quad (11)$$

If the observed t -values were higher than the minimum t' -values, then it was concluded that there is sufficient evidence that the mean values of each project were different.

The data obtained from each project phase were assessed using the actual moisture content measurements relative to the optimum moisture content and relative compaction using the t -test analysis described above. In addition, the percentage of data outside the control limits was also calculated for each project phase. These data do not have a standard deviation to conduct t -test analysis. Therefore, a logistic regression technique was used to assess the statistically significant differences between the data sets.

In the logistic regression method, a model with a natural logarithm of the odds ratio is related to the explanatory variables by a linear model (Ott and Longnecker 2008):

$$\ln\left(\frac{p(x)}{1-p(x)}\right) = \beta_0 + \beta_1 x \quad (12)$$

where, $p(x)$ = percentage of measurements within the specification and β_0 and β_1 = coefficient values.

In this study, a response variable with a value of $y = 1$ means that the measurement is within the specification, and $y = 0$ means that the measurement is outside of the specification. A chi-square (χ^2) test was used to compare the likelihoods of two competing models. In this study, the two competing models are (A) a model where all five groups have the same percentage and (B) a model where each group is allowed to have its own percentage. The test statistic was then calculated as follows:

$$D = -2 \ln \left[\frac{\text{likelihood of model a}}{\text{likelihood of model b}} \right] \quad (13)$$

The D value was then compared to the χ^2 distribution, with the degrees of freedom equal to the number of parameters in model B minus the number of parameters in model A. In this study, model A is estimating a single overall mean, so there is one parameter, while model B is estimating a mean for each group, so there are five parameters. Thus, model A would be compared to a χ^2 distribution with four degrees of freedom. A small p -value indicates that the null hypothesis, that the means are equal, was rejected, and it is concluded that the means are different between at least two of the groups.

CHAPTER 4: MATERIALS

The embankment materials consisted of cohesive soils at eight project sites and cohesionless granular soils at one project site. Cohesive materials were collected from 25 test beds, and 6 were classified as select, 18 were classified as suitable, and 1 was classified as unsuitable per Iowa DOT Standard Specifications Section 2102: Soil Classification. Granular soils collected from three test beds were classified as suitable per the same specification.

The parent materials of the cohesive soils were glacial till and loess. The parent material for the granular soils was alluvium material from the Missouri River floodplain. Manufactured materials were used at one project site. Table 7 through Table 12 summarize the parent materials, particle size analyses, Atterberg limits, specific gravities, soil classifications, and Proctor compaction test results for each project location. The grain size distribution curves of the embankment fill materials obtained from each project location are shown in Appendix C.

Table 7. Soil index properties of embankment materials obtained from Polk County

Parameter	Polk County TB1	Polk County TB2	Polk County TB3	Polk County TB4
	5/29/2014	6/7/2014	8/5/2014	8/19/2014
Parent Material	Glacial till	Glacial till	Glacial till	Glacial till
Gravel content (%) (> 4.75 mm)	0.4	3.9	2.6	1.8
Sand content (%) (4.75 mm – 75 µm)	11.6	25.8	28.7	24.6
Silt content (%) (75 µm – 2 µm)	66.4	34.7	45.8	50.9
Clay content (%) (< 2 µm)	21.6	35.6	22.9	22.7
Liquid limit, LL (%)	49	45	36	34
Plastic limit, PL (%)	28	34	20	17
Plastic Index, PI (%)	21	11	16	17
AASHTO classification	A-7-6(21)	A-7-5(8)	A-6(9)	A-6(11)
USCS classification	CL	CL	CL	CL
USCS Description	Lean Clay	Lean clay with sand	Sandy lean clay	Lean clay with sand
Iowa DOT Material Classification	Suitable	Suitable	Suitable	Suitable
Soil Color	Olive Brown	Olive Brown	Very dark greyish brown	Olive Brown
Specific Gravity, G_s	2.673	2.679	2.670	2.672
Std. Proctor, w_{opt} (%)	19.6	20.0	16.0	16.0
Std. Proctor, γ_{dmax} (lb/ft ³)	103.9	104.0	110.6	110.6
Mod. Proctor, w_{opt} (%)	16.0	13.6	11.5	11.5
Mod. Proctor, γ_{dmax} (lb/ft ³)	112.3	120.0	122.0	123.0

Table 8. Soil index properties of embankment materials obtained from Warren County and Linn County 79

Parameter	Warren County TB1	Warren County TB2	Warren County TB3 (Grey)	Warren TB3 County (Brown)	Linn County-79
	6/3/2014	7/22/2014	8/4/2014	8/4/2014	6/6/2014
Parent Material	Glacial till	Glacial till	Glacial till	Glacial till	weathered loess
Gravel content (%) (> 4.75 mm)	2.0	5.0	0.7	0.6	0.7
Sand content (%) (4.75 mm – 75 µm)	27.5	31.6	18.7	29.2	46.0
Silt content (%) (75 µm – 2 µm)	37.3	31.9	39.1	33.7	26.4
Clay content (%) (< 2 µm)	33.2	31.5	41.5	36.5	26.9
Liquid limit, LL (%)	44	40	54	40	31
Plastic limit, PL (%)	31	19	20	20	25
Plastic Index, PI (%)	13	21	34	20	6
AASHTO classification	A-7-5(9)	A-6(11)	A-7-6(28)	A-6(13)	A-4(1)
USCS classification	CL	CL	CH	CL	CL-ML
USCS Description	Lean clay with sand	Sandy lean clay	Fat clay with sand	Sandy lean clay	Sandy silty clay
Iowa DOT Material Classification	Suitable	Select	Unsuitable	Suitable	Suitable
Soil Color	Olive Brown	Light olive Brown	Very dark grey	Olive Brown	Olive Brown
Specific Gravity, G_s	2.676	2.673	2.715	2.674	2.684
Std. Proctor, w_{opt} (%)	16.5	15.8	21.0	17.0	13.5
Std. Proctor, γ_{dmax} (lb/ft ³)	111.1	113.8	102.0	109.5	117.4
Mod. Proctor, w_{opt} (%)	11.0	9.8	13.6	10.5	9.0
Mod. Proctor, γ_{dmax} (lb/ft ³)	123.9	128.5	115.5	125.0	130.8

Table 9. Soil index properties of embankment materials obtained from Linn County 77

Parameter	Linn County- 77 TB1	Linn County- 77 TB2	Linn County- 77 TB3	Linn County- 77 TB4	Linn County- 77 TB5
	6/6/2014	7/8/2014	7/15/2014	8/1/2014	9/8/2014
Parent Material	Glacial till				
Gravel content (%) (> 4.75 mm)	1.8	1.3	11.3	1.1	2.0
Sand content (%) (4.75 mm – 75 µm)	37.6	42.6	36.1	39.9	40.3
Silt content (%) (75 µm – 2 µm)	32.9	30.9	31.2	35.6	34.8
Clay content (%) (< 2 µm)	27.7	25.2	21.4	23.4	22.9
Liquid limit, LL (%)	31	34	33	32	30
Plastic limit, PL (%)	12	16	11	16	16
Plastic Index, PI (%)	19	18	22	16	14
AASHTO classification	A-6(8)	A-6(7)	A-6(7)	A-6(6)	A-6(5)
USCS classification	CL	CL	CL	CL	CL
USCS Description	Sandy lean clay				
Iowa DOT Material Classification	Select	Select	Select	Select	Select
Soil Color	Very dark grey	Olive Brown	Very dark grey	Very dark grey	Very dark grey
Specific Gravity, G_s	2.683	2.670	2.673	2.672	2.674
Std. Proctor, w_{opt} (%)	12.9	13.0	12.0	11.7	12.6
Std. Proctor, γ_{dmax} (lb/ft ³)	118.4	116.0	119.5	119.5	119.0
Mod. Proctor, w_{opt} (%)	8.8	9.0	8.0	8.1	8.6
Mod. Proctor, γ_{dmax} (lb/ft ³)	130.8	129.5	131.0	132.1	130.0

Table 10. Soil index properties of embankment materials obtained from Pottawattamie County and Woodbury County I-29

Parameter	Pottawattamie County TB1	Pottawattamie County TB2	Woodbury County I-29 TB1	Woodbury County I-29 TB2	Woodbury County I-29 TB3
	7/2/2014	7/10/2014	7/9/2014	7/10/2014	8/7/2014
Parent Material	Manufactured materials	Manufactured materials	Alluvium	Alluvium	Alluvium
Gravel content (%) (> 4.75 mm)	7.3	5.3	0.2	0.0	1.7
Sand content (%) (4.75 mm – 75 µm)	10.1	25.5	78.4	83.2	81.1
Silt content (%) (75 µm – 2 µm)	56.2	48.0	15.5	12.6	11.6
Clay content (%) (< 2 µm)	26.4	21.2	5.9	4.2	5.6
Liquid limit, LL (%)	43	42	NP	NP	NP
Plastic limit, PL (%)	18	19	NP	NP	NP
Plastic Index, PI (%)	25	23	NP	NP	NP
AASHTO classification	A-7-6(20)	A-7-6(14)	A-2-4	A-2-4	A-2-4
USCS classification	CL	CL	SM	SM	SM
USCS Description	Lean clay with sand	Sandy lean clay	Silty sand	Silty sand	Silty sand
Iowa DOT Material Classification	Suitable	Suitable	Suitable	Suitable	Suitable
Soil Color	Dark brown	Very dark greyish brown	Olive Brown	Very dark greyish brown	Very dark greyish brown
Specific Gravity, G_s	2.697	2.709	2.657	2.654	2.654
Std. Proctor, w_{opt} (%)	17.5	17.5	17.5	15.5	15.0
Std. Proctor, γ_{dmax} (lb/ft ³)	106.0	106.3	102.5	102.8	104.5
Mod. Proctor, w_{opt} (%)	13.5	12.8	15.5	14.5	13.0
Mod. Proctor, γ_{dmax} (lb/ft ³)	117.5	117.5	109.2	105.0	110.0

Table 11. Soil index properties of embankment materials obtained from Scott County and Mills County

Parameter	Scott County TB1	Scott County TB2	Scott County TB3	Mills County TB1	Mills County TB2
	7/16/2014	7/31/2014	9/19/2014	6/26/2014	6/26/2014
Parent Material	Loess	Loess	Loess	Loess	Loess
Gravel content (%) (> 4.75 mm)	0.1	1.0	2.0	0.1	3.9
Sand content (%) (4.75 mm – 75 µm)	1.0	24.3	29.2	3.1	6.4
Silt content (%) (75 µm – 2 µm)	72.9	45.5	45.9	70.6	34.9
Clay content (%) (< 2 µm)	26.0	29.2	22.9	26.2	54.8
Liquid limit, LL (%)	39	35	28	38	36
Plastic limit, PL (%)	32	24	17	34	31
Plastic Index, PI (%)	7	11	11	4	5
AASHTO classification	A-4(10)	A-6(8)	A-6(5)	A-4(7)	A-4(6)
USCS classification	CL-ML	CL	CL	CL-ML	CL-ML
USCS Description	Silty Clay	Lean clay with sand	Sandy lean clay	Silty clay	Silty clay
Iowa DOT Material Classification	Suitable	Suitable	Suitable	Suitable	Suitable
Soil Color	Dark olive brown	Dark yellowish brown	Olive Brown	Dark yellow brown	Brown
Specific Gravity, G_s	2.680	2.672	2.673	2.725	2.726
Std. Proctor, w_{opt} (%)	16.5	15.5	13.0	17.0	16.0
Std. Proctor, γ_{dmax} (lb/ft ³)	108.0	111.1	119.5	108.5	110.8
Mod. Proctor, w_{opt} (%)	13.0	11.2	9.2	13.0	12.0
Mod. Proctor, γ_{dmax} (lb/ft ³)	118.0	122.5	131.0	117.2	119.5

Table 12. Soil index properties of embankment materials obtained from Woodbury County US 20

Parameter	Woodbury County (US20) TB1	Woodbury County (US20) TB2	Woodbury County (US20) TB3	Woodbury County (US20) TB4
	9/26/2014	9/26/2014	10/18/2014	10/18/2014
Parent Material	very deep loess	very deep loess	very deep loess	very deep loess
Gravel content (%) (> 4.75 mm)	0.0	0.0	0.1	0.0
Sand content (%) (4.75 mm – 75 μ m)	8.8	1.3	4.2	6.4
Silt content (%) (75 μ m – 2 μ m)	68.8	73.3	69.6	72.0
Clay content (%) (< 2 μ m)	22.4	25.4	26.1	21.6
Liquid limit, LL (%)	32	35	35	31
Plastic limit, PL (%)	25	27	23	24
Plastic Index, PI (%)	7	8	12	7
AASHTO classification	A-4(7)	A-4(9)	A-6(12)	A-4(7)
USCS classification	CL-ML	CL	CL	CL-ML
USCS Description	Silty clay	Lean clay	Lean clay	Silty clay
Iowa DOT Material Classification	Suitable	Suitable	Suitable	Suitable
Soil Color	Olive Brown	Olive Brown	Olive Brown	Olive Brown
Specific Gravity, G_s	2.717	2.679	2.673	2.720
Std. Proctor, w_{opt} (%)	16.0	18.4	18.0	16.0
Std. Proctor, γ_{dmax} (lb/ft ³)	110.0	106.0	106.7	110.5
Mod. Proctor, w_{opt} (%)	12.4	14.0	14.0	13.0
Mod. Proctor, γ_{dmax} (lb/ft ³)	120.0	117.0	117.5	119.6

CHAPTER 5: FIELD TEST RESULTS

To evaluate compliance with embankment compaction QC/QA requirements, field testing was conducted on nine active Iowa DOT embankment projects. Field activities included in-place moisture and density testing using drive core testing, and DCP testing. Bulk samples collected from the project sites were tested in the laboratory to determine the soil index properties, as summarized in Chapter 3. Table 13 summarizes the project location information, ISU field testing activities, and the availability of QC/QA testing.

Table 13. Summary of project information

Project Number	Project ID	Location	County	ISU Field Testing		QC Data during ISU Testing	QA Data during ISU Testing
1	IM-035-2(365)67--13-77	Northeast side of Intersection between I-35 and Grand Ave, Polk, IA	Polk	TB1: 5/29/14	15 DC, 5 DCP	NA	NA
		Northeast side of Intersection between I-35 and Grand Ave, Polk, IA	Polk	TB2: 6/7/14	N/A	NA	NA
		Southeast side of Intersection between I-35 and E.P. True Parkway, Polk, IA	Polk	TB3: 8/5/14	15 DC, 5 DCP	NA	NA
		Southeast side of Intersection between I-35 and E.P. True Parkway, Polk, IA	Polk	TB4: 8/19/14	15 DC, 5 DCP	w and γ_d	NA
2	IM-035-2(353)54--13-91	Beside I-35, Hoover St, and NW 97th St, Warren, IA	Warren	TB1: 6/3/14	15 DC, 5 DCP	w	NA
		Beside I-35, Hoover St, and NW 97th St, Warren, IA	Warren	TB2: 7/22/14	15 DC, 5 DCP	w	NA
		Intersection between I-35 and Hwy 92, Warren, IA	Warren	TB3: 8/4/14	15 DC, 5 DCP	w	NA
3	NHSX-100-1(77)--3H-57	New constructed Collins Rd near Old Ferry Rd, Linn, IA	Linn	TB1: 6/6/14	15 DC, 5 DCP	w	NA
		New constructed Collins Rd near Old Ferry Rd, Linn, IA	Linn	TB2: 7/8/14	N/A	w	NA

Project Number	Project ID	Location	County	ISU Field Testing		QC Data during ISU Testing	QA Data during ISU Testing
		New constructed Collins Rd near Covington Rd, Linn, IA	Linn	TB3: 7/15/14	20 DC, 8 DCP	w	NA
		New constructed Collins Rd near Covington Rd, Linn, IA	Linn	TB4: 8/1/14	15 DC, 5 DCP	w	NA
		New constructed Collins Rd near Old Ferry Rd, Linn, IA	Linn	TB5: 9/8/14	15 DC, 5 DCP	w	NA
4	NHSX-100-1(79)--3H-57	New constructed Collins Rd near Edgewood Rd NE, Linn, IA	Linn	6/6/14	15 DC, 5 DCP	w and γ_d	w and γ_d
5	NHSX-534-1(85)--3H-65	West side of Intersection between I-29 and Platteview, Mills, IA	Mills	TB1: 6/26/14	15 DC, 6 DCP	NA	NA
		East side of Intersection between I-29 and Platteview, Mills, IA	Mills	TB2: 6/26/14	15 DC, 6 DCP	NA	NA
6	IM-NHS-080-1(364)3--03-78	Ramp at Intersection between I-80 and S Expressway St, Pottawattamie, IA	Pottawattamie	TB1: 7/2/14	15 DC, 5 DCP	w and γ_d	w and γ_d
		Ramp at Intersection between I-80 and S Expressway St, Pottawattamie, IA	Pottawattamie	TB2: 7/10/14	15 DC, 5 DCP	w and γ_d	w and γ_d
7	IM-029-6(186)136--13-97	Southeast side of Intersection between I-29 and 260th St, Woodbury, IA	Woodbury I-29	TB1: 7/9/14	15 DC, 7 DCP	w	w
		Southeast side of Intersection between I-29 and 260th St, Woodbury, IA	Woodbury I-29	TB2: 7/10/14	15 DC, 6 DCP	w	w
		Southeast side of Intersection between I-29 and 260th St, Woodbury, IA	Woodbury I-29	TB3: 8/7/14	15 DC, 5 DCP	w	w

Project Number	Project ID	Location	County	ISU Field Testing		QC Data during ISU Testing	QA Data during ISU Testing
8	IM-074-1(234)0--13-82	Northeast side of Intersection between I-74 and E 67th St, Scott, IA	Scott	TB1: 7/16/14	15 DC, 5 DCP	NA	NA
		Northwest side of Intersection between I-74 and E 67th St, Scott, IA	Scott	TB2: 7/31/14	15 DC, 5 DCP	NA	NA
		Northeast side of Intersection between I-74 and E 67th St, Scott, IA	Scott	TB3: 9/19/14	15 DC, 5 DCP	NA	NA
9	NHSX-020-1(116)--3H-97	Northwest side of Intersection between US 20 and Jasper Ave, Woodbury, IA	Woodbury (US20)	TB1: 9/26/14	15 DC, 5 DCP	NA	NA
		Northeast side of Intersection between US 20 and Minnesota Ave, Woodbury, IA	Woodbury (US20)	TB2: 9/26/14	15 DC, 5 DCP	NA	NA
		Northwest side of Intersection between US 20 and Jasper Ave, Woodbury, IA	Woodbury (US20)	TB3: 10/18/14	15 DC, 5 DCP	NA	NA
		Northeast side of Intersection between US 20 and Minnesota Ave, Woodbury, IA	Woodbury (US20)	TB4: 10/18/14	15 DC, 5 DCP	NA	NA

DC – Drive core cylinder

DCP – Dynamic cone penetrometer

GPS measurements were obtained at each test location.

NA – Not available

The results of testing and evaluation are described in the following sections.

Project 1. Polk County

Overview

The ISU research team conducted field testing at this grading project site on 05/29/14, 06/07/14, 08/05/14, and 08/19/14. No field testing was performed on 06/07/14 (TB2) due to rain, but material was obtained to conduct Proctor testing. The fill materials obtained at the time of testing consisted of glacial till materials and were classified as A-7-6(21), A-7-5(8), A-6(9), and A-6(11) by the AASHTO Soil Classification System and as CL by the USCS.

At this site, the project specification required achievement of 95% relative compaction and moisture content within $\pm 2.0\%$ of the optimum moisture content determined from the standard Proctor test. The equipment used during construction is shown in Figure 16 through Figure 22.



Figure 16. Polk County Project 1: Caterpillar MT-35 scraper used to collect and place loose fill materials



Figure 17. Polk County Project 1: Caterpillar 740B dump truck used to place loose fill materials



Figure 18. Polk County Project 1: Caterpillar 143H motor grader used to level the embankment surface



Figure 19. Polk County Project 1: Disc used to dry embankment materials



Figure 20. Polk County Project 1: Caterpillar D6T dozer used for grading and lift thickness adjustment

A disc was used to break down and aerate the wet soil. Compaction was achieved in part from the haul equipment and five to eight passes of the pull-behind sheepsfoot roller (Figure 21).



Figure 21. Polk County Project 1: Pull-behind sheepsfoot roller used for soil compaction

Polymer geogrid was used for reinforcement near the embankment toe (Figure 22).



Figure 22. Polk County Project 1: Geogrid placed near embankment toe

Field observations indicated that the material obtained from the borrow area at the time of ISU testing was relatively wet, and pumping was observed under haul truck tires.

ISU Field Test Results

In situ moisture content and dry density test results are compared with laboratory Proctor test results in Figure 23, Figure 24, and Figure 25.




Figure 23. Polk County Project 1 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 24. Polk County Project 1 TB3: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 25. Polk County Project 1 TB4: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits

The Proctor test results used by the Iowa DOT showed optimum moisture contents about 1.6% to 2.8% lower than those determined from ISU testing. Similarly, the Proctor test results used by the Iowa DOT showed maximum dry densities about 1.1 to 4.1 lb/ft³ higher than those determined from ISU testing.

To determine whether the field measurements met the specification requirements, Figures 23 through 25 also show an acceptance range of $\pm 2.0\%$ of the standard Proctor optimum moisture content and 95% of standard Proctor density. Maximum dry density, optimum moisture content, and the acceptance zone used by the Iowa DOT at the time of ISU testing are also shown in the figures for reference and comparison.

The field test results indicated that the relative compaction of the material ranged from approximately 95% to over 100% of the standard Proctor maximum dry density, with in situ

moisture content ranging between -1.5% and +7.2% of the optimum moisture content, as determined from the ISU testing.

The in situ moisture and dry density test results presented in Figure 23 through Figure 25 indicate that a majority of the ISU tests on TB1 and TB4 fell outside the specification limit, with material generally > 2% wet of optimum moisture content and close to the 95% to 100% saturation line.

DCP-CBR values and cumulative blows with depth profiles are shown in Figure 26 through Figure 28 for the three TBs.




Figure 26. Polk County Project 1 TB1: DCP-CBR values and cumulative blows with depth profiles




Figure 27. Polk County Project 1 TB3: DCP-CBR values and cumulative blows with depth profiles




Figure 28. Polk County Project 1 TB4: DCP-CBR values and cumulative blows with depth profiles

The average CBR value (per TB) in the top 8 in. varied between 0.6% and 8.2% and the average CBR value in the top 12 in. varied between 1.4% and 8.6% among the three test beds. The results

indicate that the CBR values are generally higher when the material is within the moisture control limit, as in the case of TB2, and vice versa, as in the cases of TB1 and TB3.

Summary statistics of the field measurements with average, range, standard deviation, and coefficient of variation (COV) are summarized in Table 14.

Table 14. Polk County Project 1: Summary of field testing

Parameter	Polk County TB1	Polk County TB2	Polk County TB3	Polk County TB4
	5/29/2014	6/7/2014	8/5/2014	8/19/2014
Relative Compaction				
Average (%)	97.8	N/A	103.0	96.8
Range (%)	95 to 101.6	N/A	99.6 to 105.5	93.9 to 104.8
Standard Deviation (%)	0.02	N/A	0.02	0.03
COV (%)	2	N/A	2	3
$\Delta w\% = w_{\text{field}}\% - w_{\text{opt}}\%$				
Average (%)	2.6	N/A	-0.7	3.0
Range (%)	-0.2 to +7.2	N/A	-1.5 to +0.5	-3.4 to +4.8
Standard Deviation (%)	1.92	N/A	0.49	1.97
COV (%)	73	N/A	-73	65
CBR_{8 in.}				
Average (%)	1.4	N/A	8.2	0.6
Range (%)	0.1 to 2.7	N/A	4.5 to 12.3	0.4 to 1.1
Standard Deviation (%)	1.0	N/A	2.8	0.3
COV (%)	72	N/A	35	47
CBR_{12 in.}				
Average (%)	1.4	N/A	8.6	3.4
Range (%)	0.2 to 2.1	N/A	2.6 to 11.4	0.7 to 8.0
Standard Deviation (%)	0.9	N/A	3.6	3.0
COV (%)	64	N/A	42	89

Control Charts

The contractor QC data and ISU data are reported in Figure 29 in the form of control charts monitoring the dry unit weight and moisture content of the compacted fills.

**Polk County IM-035-2(365)67--13-77
Embankment Compaction with Moisture and Density Control**

Project CS.1 Sheet: Moisture content shall be within +/- 2% points of w_{opt} with minimum 95% std. Proctor density
DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits. If a single density does not meet requirements, subgrade in this area will be considered unacceptable.




Figure 29. Polk County Project 1: Moisture and density control chart

The control chart data are presented as histograms in Figure 30.

Polk County IM-035-2(365)67--13-77 Moisture and Density Control




Figure 30. Polk County Project 1: Histograms of moisture and density control results

The data presented in the control charts and histograms indicate that a majority (98%) of the QC data showed relative compaction > 95%, and a majority (87%) of the data fell within the moisture control limits. The ISU testing results show that 96% of the data showed relative compaction > 95%, and only 47% of the data were within the moisture control limits.

Figure 31 shows control charts for DCP index values at a depth of 600 mm.




Figure 31. Polk County Project 1: Control charts with control limits for DCP index and variation in DCP index

The weighted average DCP index values ranged between 19 and 116 mm/blow, and three points of all of the data exceeded the upper control limit. The variation in the DCP index control chart shows that DCP index variation fell between 10.8 and 16.6 mm/blow at 13 of the 15 points, with one point showing about 72 mm/blow.

Figure 32 shows control charts for CBR values for the top 8 and 12 in. of the compacted lift.




Figure 32. Polk County Project 1: CBR control charts with CBR quality ratings

The control charts show CBR ratings per the SUDAS Design Manual guidance regarding subgrade design and construction (SUDAS 2013). The results indicate that 67% of the CBR_{8in.} and 67% of the CBR_{12in.} data showed CBR < 5, which is rated as very poor.

Project 2. Warren County

Overview

The ISU research team conducted field testing at this grading project site on 06/03/14, 07/22/14, and 08/04/14. The fill materials obtained at the time of testing consisted of glacial till materials and were classified as A-7-5(9), A-6(11), A-7-6(28), and A-6(13) by the AASHTO Soil Classification System and CL and CH by the USCS.

At this site, the project specification required achievement of moisture content within $\pm 2.0\%$ of the optimum moisture content determined from the standard Proctor test. The equipment used during construction is shown in Figure 33 through Figure 35.



Figure 33. Warren County Project 2: Caterpillar D6T dozer used to control lift thickness



Figure 34. Warren County Project 2: Caterpillar MT-35 scraper used to collect and place loose fill materials



Figure 35. Warren County Project 2: Sheepfoot roller used for soil compaction

During onsite observation, no disc was used to break down and aerate the wet soil. Compaction was achieved in part from the haul equipment and five to eight passes of the pull-behind sheepfoot roller (Figure 35).

ISU Field Test Results

In situ moisture content and dry unit density test results are compared with laboratory Proctor test results in Figure 36 through Figure 39.




Figure 36. Warren County Project 2 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 37. Warren County Project 2 TB2: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 38. Warren County Project 2 TB3 (gray soil): Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 39. Warren County Project 2 TB3 (brown soil): Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits

The Proctor test results used by the Iowa DOT showed optimum moisture contents about 1.2% lower than those determined from ISU testing (Figure 36). Similarly, the Proctor test results used by the Iowa DOT showed maximum dry densities about 3.3 lb/ft³ higher than those determined from ISU testing.

To determine whether the field measurements met the specification requirements, Figures 36 through 39 also show an acceptance range of $\pm 2.0\%$ of the standard Proctor optimum moisture content and 95% of standard Proctor density. Maximum dry density, optimum moisture content, and the acceptance zone used by the Iowa DOT at the time of ISU testing are also shown in the figures for reference and comparison.

Field test results indicate that the relative compaction of the material ranged from approximately 84.1% to over 100% of the standard Proctor maximum dry density, with in situ moisture content

ranging between -3.2% to +11.8% of the optimum moisture content, as determined from the ISU testing.

The in situ moisture and dry density test results presented in Figure 38 indicate that the results of the ISU tests on TB3 (gray soil) fell outside the specification limit, with material generally > 2% wet of optimum moisture content and close to the 90% to 100% saturation line.

DCP-CBR values and cumulative blows with depth profiles are shown in Figure 40, Figure 41, and Figure 42 for the three TBs.




Figure 40. Warren County Project 2 TB1: DCP-CBR values and cumulative blows with depth profiles




Figure 41. Warren County Project 2 TB2: DCP-CBR values and cumulative blows with depth profiles




Figure 42. Warren County Project 2 TB3: DCP-CBR values and cumulative blows with depth profiles

The average CBR value (per TB) in the top 8 in. varied between 4.9% to 5.7% and the average CBR value in the top 12 in. varied between 4.5% to 5.6% among the three TBs. The results

indicate that the CBR values are generally higher when the material is within the moisture control limit, as in the cases of TB1 and TB2, and vice versa, as in the case of TB3.

Summary statistics of the field measurements with average, range, standard deviation, and COV are summarized in Table 15.

Table 15. Warren County Project 2: Summary of field testing

Parameter	Warren County TB1	Warren County TB2	Warren County TB3
	6/3/2014	7/22/2014	8/4/2014
Relative Compaction			
Average (%)	98.8	97.5	93.6
Range (%)	85.4 to 104.8	91.5 to 102.7	84.1 to 107.0
Standard Deviation (%)	0.05	0.04	0.07
COV (%)	5	4	7
$\Delta w\% = w_{\text{field}}\% - w_{\text{opt}}\%$			
Average (%)	0.4	-1.2	3.3
Range (%)	-2.0 to +11.8	-2.2 to +0.3	-3.2 to +9.4
Standard Deviation (%)	3.25	0.65	4.78
COV (%)	842	-54	145
CBR_{8 in.}			
Average (%)	5.6	5.7	4.9
Range (%)	2.1 to 7.4	2.0 to 7.7	2.8 to 9.9
Standard Deviation (%)	2.1	2.3	2.9
COV (%)	37	39	60
CBR_{12 in.}			
Average (%)	5.6	5.6	4.5
Range (%)	2.4 to 7.6	2.3 to 7.7	1.9 to 9.4
Standard Deviation (%)	2.1	2.2	2.9
COV (%)	38	39	65

Control Charts

The contractor QC data and ISU data are reported in Figure 43 in the form of control charts monitoring the dry density and moisture content of the compacted fills.

**Warren County IM-035-2(353)54--13-91
Embankment Compaction with Moisture Control**

Project CS.1 Sheet: Moisture content shall be within +/- 2% points of w_{opt} for all Class 10 fill.

DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits.




Figure 43. Warren County Project 2: Moisture control chart

The control chart data are presented as histograms in Figure 44.

Warren County IM-035-2(353)54--13-91 Moisture Control





Figure 44. Warren County Project 2: Histograms of moisture and density control results

The data presented in the control charts and histograms indicate that 99% of QC data fell within the moisture control limits. The ISU testing results show that 62% of the data showed relative compaction > 95%, and 67% of the data were within the moisture control limits.

Figure 45 shows control charts for DCP index values at a depth of 600 mm.



White et al. 2007

Figure 45. Warren County Project 2: Control charts with control limits for DCP index and variation in DCP index

The weighted average DCP index values ranged between 26.6 and 69.3 mm/blow, and all of the data are within the control limit. The variation in the DCP index control chart shows that DCP index variation fell between 3.0 and 8.25 mm/blow, except for two points with 22.7 and 35.5 mm/blow, respectively.

Figure 46 shows control charts for CBR values for the top 8 and 12 in. of the compacted fills.




Figure 46. Warren County Project 2: CBR chart with CBR quality rating

The control charts show CBR ratings per the SUDAS Design Manual guidance regarding subgrade design and construction (SUDAS 2013). The results indicate that 47% of the CBR_{8in.} and 60% of the CBR_{12in.} data showed CBR < 5, which is rated as very poor.

Project 3. Linn County 77

Overview

The ISU research team conducted field testing at this grading project site on 06/06/14, 07/08/14, 07/15/14, 08/01/14, and 09/08/14. No field testing for TB2 was performed on 07/08/14 (TB2)

due to rain, but material was obtained to conduct Proctor testing. The fill materials obtained at the time of testing consisted of glacial till materials and were classified as A-6(8), A-6(7), A-6(6), and A-6(5) by the AASHTO Soil Classification System and as CL by the USCS.

At this site, the project specification required achievement of 95% relative compaction and moisture content within $\pm 2.0\%$ of the optimum moisture content determined from the standard Proctor test for cohesionless materials, and the specification only required achievement of moisture content within $\pm 2.0\%$ of the optimum moisture content for cohesive materials. The equipment used during construction is shown in Figure 47 through Figure 51.



Figure 47. Linn County Project 3: Caterpillar 390D excavating material from borrow source



Figure 48. Linn County Project 3: Caterpillar D6R dozer used to control lift thickness



Figure 49. Linn County Project 3: Disc cultivator used to dry embankment materials



Figure 50. Linn County Project 3: Sheepfoot roller used for soil compaction



Figure 51. Linn County Project 3: Caterpillar 14M motor grader used to level the embankment surface

A disc was used to break down and aerate the wet soil. Compaction was achieved in part from the haul equipment and five to eight passes of the pull-behind sheepfoot roller (Figure 50).

Field observations indicated that the material obtained from the borrow area at the time of ISU testing was relatively wet, and seepage was observed (Figure 52).



Figure 52. Linn County Project 3: Seepage at the construction site

ISU Field Test Results

In situ moisture content and dry density test results are compared with laboratory Proctor test results in Figure 53 through Figure 56.




Figure 53. Linn County Project 3 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 54. Linn County Project 3 TB3: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 55. Linn County Project 3 TB4: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 56. Linn County Project 3 TB5: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits

To determine whether the field measurements met the specification requirements, Figures 53 through 56 also show an acceptance range of $\pm 2.0\%$ of the standard Proctor optimum moisture content and 95% of standard Proctor density.

Field test results indicate that the relative compaction of the material ranged from approximately 87.8% to over 100% of the standard Proctor maximum dry density, with in situ moisture content ranging between -3.0% and +10.1% of the optimum moisture content, as determined from the ISU testing.

The in situ moisture and dry density test results presented in Figure 53 to Figure 56 indicate that a few of the ISU tests on TB4 fell outside of the specification limit, with material generally $> 2\%$ wet of optimum moisture content and close to the 95% to 100% saturation line.

DCP-CBR values and cumulative blows with depth profiles are shown in Figure 57 through Figure 60 for the four TBs.




Figure 57. Linn County Project TB1: DCP-CBR values and cumulative blows with depth profiles




Figure 58. Linn County Project 3 TB3: DCP-CBR values and cumulative blows with depth profiles




Figure 59. Linn County Project 3 TB4: DCP-CBR values and cumulative blows with depth profiles




Figure 60. Linn County Project 3 TB5: DCP-CBR values and cumulative blows with depth profiles

The average CBR value (per TB) in the top 8 in. varied between 2.3% and 7.6% and the average CBR value in the top 12 in. varied between 2.6% and 6.9% among the four test beds. The results

do not indicate the trend that the CBR values are generally higher when the material is within the moisture control limit.

Summary statistics of the field measurements with average, range, standard deviation, and COV are summarized Table 16.

Table 16. Linn County Project 3: Summary of field testing results

Parameter	Linn County-77 TB1	Linn County-77 TB2	Linn County-77 TB3	Linn County-77 TB4	Linn County-77 TB5
	6/6/2014	7/8/2014	7/15/2014	8/1/2014	9/8/2014
Relative Compaction					
Average (%)	103.5	N/A	100.1	98.8	101.4
Range (%)	96.5 to 107.0	N/A	93.4 to 105.0	87.8 to 103.2	99.0 to 103.5
Standard Deviation (%)	0.03	N/A	0.03	0.05	0.01
COV (%)	3	N/A	3	5	1
$\Delta w\% = w_{\text{field}}\% - w_{\text{opt}}\%$					
Average (%)	-0.8	N/A	-0.6	2.5	0.9
Range (%)	-1.8 to +1.0	N/A	-3.0 to +1.6	-0.9 to +10.1	0.1 to +1.4
Standard Deviation (%)	0.68	N/A	1.13	3.31	0.36
COV (%)	-86	N/A	-175	131	39
CBR_{8 in.}					
Average (%)	7.6	N/A	4.3	3.0	2.3
Range (%)	3.3 to 16.1	N/A	2.7 to 6.6	2.1 to 3.6	1.4 to 3.2
Standard Deviation (%)	5.2	N/A	1.3	0.7	0.7
COV (%)	69	N/A	31	23	3
CBR_{12 in.}					
Average (%)	6.9	N/A	3.4	3.5	2.6
Range (%)	2.9 to 15.1	N/A	1.8 to 5.6	2.7 to 4.3	1.7 to 3.6
Standard Deviation (%)	4.8	N/A	1.3	0.6	0.8
COV (%)	70	N/A	37	17	32

Control Charts

The contractor QC data and ISU data are reported in Figure 61, Figure 62, and Figure 63 in the form of control charts monitoring the dry unit weight and moisture content of the compacted fills.

**Linn County IM-035-2(365)67--13-77
Embankment Compaction with Moisture Control**

Project CS.3 Sheet: Moisture content shall be within +/- 2% points of w_{opt} for all class 10 fill and granular backfill.

DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits.





Figure 61. Linn County Project 3: Moisture control chart (cohesive materials)

**Linn County IM-035-2(365)67--13-77
Embankment Compaction with Moisture and Density Control**

Project CS.3 Sheet: Moisture content shall be within +/- 2% points of w_{opt} with minimum 95% std. Proctor density.

DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits. If a single density does not meet requirements, subgrade in this area will be considered unacceptable.




Figure 62. Linn County Project 3: Moisture and density control charts (cohesionless materials)

**Linn County IM-035-2(365)67--13-77
Embankment Compaction with Moisture Control**

Project CS.3 Sheet: Moisture content shall be within +/- 2% points of w_{opt} for class 10 fill and granular backfill.

DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits.




Figure 63. Linn County Project 3: Moisture control chart (cohesionless materials)

The control chart data are presented as histograms in Figure 64, Figure 65, and Figure 66.

Linn County IM-035-2(365)67--13-77 Moisture Control




Figure 64. Linn County Project 3: Histograms of moisture and density control results (cohesive materials)

Linn County IM-035-2(365)67--13-77 Moisture and Density Control




Figure 65. Linn County Project 3: Histograms of moisture and density control results (cohesionless materials)

Linn County IM-035-2(365)67--13-77 Moisture Control





Figure 66. Linn County Project 3: Histograms of moisture control results (cohesionless materials)

The data presented in the control charts and histograms indicate that 99% of the QC data for cohesive materials fell within the moisture control limits, and all QC data for cohesionless materials showed relative compaction > 95%, with only 3% of the data falling within the moisture control limits. For the moisture control-only project, 15% of the data fell within the moisture control limits. The ISU testing results show that 95% of the data showed relative compaction > 95%, and only 88% of the data were within the moisture control limits for cohesive materials.

Figure 67 shows control charts for DCP index values at a depth of 600 mm.



White et al. 2007

Figure 67. Linn County Project 3: Control charts with control limits for DCP index and variation in DCP index

The weighted average DCP index values ranged from 28.4 to 81.5 mm/blow, and one point of all of the data exceeded the upper control limit. The variation in the DCP index control chart shows that DCP index variation fell between 1.9 and 15.6 mm/blow.

Figure 68 shows control charts for CBR values for the top 8 and 12 in. of the compacted fills.




Figure 68. Linn County Project 3: CBR chart with CBR quality rating

The control charts show CBR ratings per the SUDAS Design Manual guidance regarding subgrade design and construction (SUDAS 2013). The results indicate that 87% of the CBR_{8in.} and 83% of the CBR_{12in.} data showed CBR < 5, which is rated as very poor.

Project 4. Linn County-79

Overview

The ISU research team conducted field testing at this grading project site on 06/06/14. The fill materials obtained at the time of testing consisted of weathered loess materials and were classified as A-4(1) by the AASHTO Soil Classification System and CL-ML by the USCS.

At this site, the project specification required achievement of 95% relative compaction and moisture content within $\pm 2.0\%$ of the optimum moisture content determined from the standard Proctor test for cohesionless materials, and the specification only required achievement of moisture content within $\pm 2.0\%$ of the optimum moisture content for cohesive materials. The equipment used during construction is shown in Figure 69 through Figure 74.



Figure 69. Linn County Project 4: Caterpillar 740 dump truck used to place loose fill materials



Figure 70. Linn County Project 4: Sheep's foot roller used for soil compaction



Figure 71. Linn County Project 4: Contractor conducting QC tests



Figure 72. Linn County Project 4: Iowa DOT engineer conducting QA tests



Figure 73. Linn County Project 4: ISU in situ drive cylinder test



Figure 74. Linn County Project 4: Disc cultivator used to dry embankment materials

A disc was used to break down and aerate the wet soil. Compaction was achieved in part from the haul equipment and five to eight passes of the pull-behind sheepfoot roller (Figure 70). The contractor QC, Iowa DOT QA, and ISU testing processes are shown in Figure 71, Figure 72, and Figure 73, respectively.

ISU Field Test Results

In situ moisture content and dry density test results are compared with laboratory Proctor test results in Figure 75.




Figure 75. Linn County Project 4: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits

The Proctor test results used by the Iowa DOT showed optimum moisture contents about 0.5% lower than those determined from ISU testing. Similarly, the Proctor test results used by the Iowa DOT showed maximum dry densities about 3.4 lb/ft³ higher than those determined from ISU testing.

To determine whether the field measurements met the specification requirements, Figure 75 also shows an acceptance range of $\pm 2.0\%$ of the standard Proctor optimum moisture content and 95% of standard Proctor density. Maximum dry density, optimum moisture content, and the acceptance zone used by the Iowa DOT at the time of ISU testing is also shown in the figure for reference and comparison.

Field test results indicate that the relative compaction of the material was over 100% of the standard Proctor maximum dry density, with in situ moisture content ranging between -0.5% and +1.4% of the optimum moisture content, as determined from the ISU testing.

The in situ moisture and dry density test results presented in Figure 75 indicate that all contractor QC, Iowa DOT QA, and ISU test results fell within the specification limit.

DCP-CBR values and cumulative blows with depth profiles are shown in Figure 76.




Figure 76. Linn County Project 4: DCP-CBR values and cumulative blows with depth profiles

The average CBR value in the top 8 in. was 3.7%, and the average CBR value in the top 12 in. was 4.1%.

Summary statistics of the field measurements with average, range, standard deviation, and COV are summarized in Table 17.

Table 17. Linn County Project 4: Summary of field testing results

Parameter	Linn 79 County
	8/4/2014
Relative Compaction	
Average Relative compaction (%)	103.8
Range of Relative compaction (%)	101.6 to 106.0
Standard Deviation (%)	0.01
COV (%)	1
$\Delta w\% = w_{\text{field}}\% - w_{\text{opt}}\%$	
Average Δw (%)	0.5
Range of Δw (%)	-0.5 to +1.4
Standard Deviation (%)	0.01
COV (%)	97
CBR_{8 in.}	
Average CBR at 8 in. (%)	3.7
Range of CBR at 8 in. (%)	2.9 to 4.6
Standard Deviation (%)	0.7
COV (%)	20
CBR_{12 in.}	
Average CBR at 12 in. (%)	4.1
Range of CBR at 12 in. (%)	3.0 to 5.1
Standard Deviation (%)	1.0
COV (%)	24

Control Charts

The contractor QC data and ISU data are reported in Figure 77 and Figure 78 in the form of control charts monitoring the dry unit weight and moisture content of the compacted fills.

Linn County NHSX-100-1(79)--3H-57 Embankment Compaction with Moisture Control

Project CS.3 Sheet: Moisture content shall be within +/- 2% points of w_{opt} for all Class 10 fill.

DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits.




Figure 77. Linn County Project 4: Moisture control chart (cohesive materials)

**Linn County NHSX-100-1(79)--3H-57
Embankment Compaction with Moisture and Density Control**

Project CS.3 Sheet: Moisture content shall be within +/- 2% points of w_{opt} with minimum 95% std. Proctor density.

DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits. If a single density does not meet requirements, subgrade in this area will be considered unacceptable.




Figure 78. Linn County Project 4: Moisture and density control chart (cohesionless materials)

The control chart data are presented as histograms in Figure 79 and Figure 80.

Linn County NHSX-100-1(79)--3H-57 Moisture Control




Figure 79. Linn County Project 4: Histograms of moisture and density control results (cohesive materials)

Linn County NHSX-100-1(79)--3H-57 Moisture and Density Control




Figure 80. Linn County Project 4: Histograms of moisture and density control results (cohesionless materials)

The data presented in the control charts and histograms indicate that 84% of the QC data showed relative compaction > 95%, and a majority (87%) of the data fell within the moisture control limits for cohesive materials. For cohesionless materials, 86% of the QC data showed relative compaction > 95%, but all of the moisture measurements were dry of the moisture control limits. All of the DOT QA data met the moisture and density specifications for cohesive materials. The ISU testing results show that all data showed relative compaction > 95%, and all data were within the moisture control limits for cohesive materials.

Figure 81 shows control charts for DCP index values at a depth of 600 mm.




Figure 81. Linn County Project 4: Control charts with control limits for DCP index and variation in DCP index

The weighted average DCP index values ranged from 29.5 to 103.0 mm/blow, and one point of all data exceeded the control limit. The variation in the DCP index control chart shows that DCP index variation fell between 7.2 and 33.3 mm/blow.

Figure 82 shows control charts for CBR values for the top 8 and 12 in. of the compacted lift.




Figure 82. Linn County Project 4: CBR chart with CBR quality rating

The control charts show CBR ratings per the SUDAS Design Manual guidance regarding subgrade design and construction (SUDAS 2013). The results indicate that all of the CBR_{8in.} and CBR_{12in.} data showed CBR < 5, which is rated as very poor.

Project 5. Mills County

Overview

The ISU research team conducted field testing at this grading project site on 06/26/14. The fill materials obtained at the time of testing consisted of loess and were classified as A-4(6) and A-4(7) by the AASHTO Soil Classification System and CL-ML by the USCS.

At this project site, the project specification required achievement of moisture content within $\pm 2.0\%$ of the optimum moisture content determined from the standard Proctor test. The equipment used during construction is shown in Figure 83 through Figure 85.



Figure 83. Mills County Project 5: Caterpillar 621E scraper used to collect and place loose fill materials



Figure 84. Mills County Project 5: Caterpillar D6R dozer used to control lift thickness



Figure 85. Mills County Project 5: Sheepfoot roller used for soil compaction

Disc was not used to break down and aerated the wet soil. Compaction was achieved in part from the haul equipment and five to eight passes of the pull-behind sheepfoot roller (Figure 85).

A wet area in the center of the construction site was observed (Figure 86).



Figure 86. Mills County Project 5: Very wet materials in the center of the construction site

ISU Field Test Results

In situ moisture content and dry density test results are compared with laboratory Proctor test results in Figure 87 and Figure 88.




Figure 87. Mills County Project 5 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 88. Mills County Project 5 TB2: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits

The Proctor test results of TB1 used by the Iowa DOT showed optimum moisture contents about 0.7% lower than those determined from ISU testing, and the Proctor test results of TB2 used by the Iowa DOT showed optimum moisture contents about 0.3% higher than those determined from ISU testing. Similarly, the Proctor test results used by the Iowa DOT showed maximum dry densities about 0.2 to 1.5 lb/ft³ lower than those determined from ISU testing.

To determine whether the field measurements met the specification requirements, Figures 87 and 88 also show an acceptance range of $\pm 2.0\%$ of the standard Proctor optimum moisture content and 95% of standard Proctor density. Maximum dry density, optimum moisture content, and the acceptance zone used by the Iowa DOT at the time of ISU testing are also shown in the figures for reference and comparison.

Field test results indicate that the relative compaction of the material ranged from approximately 84.3% to over 100% of the standard Proctor maximum dry density, with in situ moisture content

ranging between -4.0% and +11.6% of the optimum moisture content, as determined from the ISU testing.

The in situ moisture and dry density test results presented in Figure 87 and Figure 88 indicate that a majority of the ISU tests on TB1 and TB2 fell outside the specification limit, with material generally > 2% wet of optimum moisture content and close to the 95% to 100% saturation line.

DCP-CBR values and cumulative blows with depth profiles are shown in Figure 89 and Figure 90 for the two TBs.




Figure 89. Mills County Project 5 TB1: DCP-CBR values and cumulative blows with depth profiles

Table 18. Mills County Project 5: Summary of field testing results

Parameter	Mills County TB1	Mills County TB2
	6/26/2014	6/26/2014
Relative Compaction		
Average Relative compaction (%)	92.4	97.6
Range of Relative compaction (%)	84.3 to 98.3	94.5 to 101.4
Standard Deviation (%)	0.04	0.02
COV (%)	4	2
$\Delta w\% = w_{\text{field}}\% - w_{\text{opt}}\%$		
Average Δw (%)	6.1	1.6
Range of Δw (%)	3.1 to +11.6	-4.0 to +5.1
Standard Deviation (%)	2.96	0.03
COV (%)	48	179
CBR_{8 in.}		
Average CBR at 8 in. (%)	2.9	6.8
Range of CBR at 8 in. (%)	2.5 to 3.7	3.9 to 9.8
Standard Deviation (%)	0.4	2.4
COV (%)	14	35
CBR_{12 in.}		
Average CBR at 12 in. (%)	2.6	6.2
Range of CBR at 12 in. (%)	2.0 to 3.1	3.2 to 8.8
Standard Deviation (%)	0.4	2.4
COV (%)	16	39

Control Charts

The contractor QC data and ISU data are reported in Figure 91 in the form of control charts monitoring the dry unit weight and moisture content of the compacted fills.

**Mills County NHSX-534-1(85)--3H-65
Embankment Compaction with Moisture Control**

Project CS.2 Sheet: Moisture content shall be within +/- 2% points of w_{opt} for all Class 10 fill.

DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits.




Figure 91. Mills County Project 5: Moisture control chart

The control chart data are presented as histograms in Figure 92.

Mills County NHSX-534-1(85)--3H-65 Moisture Control





Figure 92. Mills County Project 5: Histograms of moisture and density control results

The data presented in the control charts and histograms indicate that a majority (99%) of the data fell within the moisture control limits. The ISU testing results show that 60% of the data showed relative compaction > 95%, and 50% of the data were within the moisture control limits.

Figure 93 shows control charts for DCP index values at a depth of 600 mm.



White et al. 2007

Figure 93. Mills County Project 5: Control charts with control limits for DCP index and variation in DCP index

The weighted average DCP index values ranged from 25.4 to 93.2 mm/blow, and five points of all the data exceeded the upper control limit. The variation in the DCP index control chart shows that DCP index variation fell between 2.7 and 29.3 mm/blow.

Figure 94 shows control charts for CBR values for the top 8 and 12 in. of the compacted lift.




Figure 94. Mills County Project 5: CBR chart with CBR quality rating

The control charts show CBR ratings per the SUDAS Design Manual guidance regarding subgrade design and construction (SUDAS 2013). The results indicate that 82% of the CBR_{8in.} and 82% of the CBR_{12in.} data showed CBR < 5, which is rated as very poor.

Project 6. Pottawattamie County

Overview

The ISU research team conducted field testing at this grading project site on 07/02/14 and 07/10/14. The fill materials obtained at the time of testing consisted of manufactured materials classified as A-7-6(20) and A-7-6(14) by the AASHTO Soil Classification System and CL by the USCS.

At this project site, the project specification required achievement of moisture content within $\pm 2.0\%$ of the optimum moisture content determined from the standard Proctor test. The equipment used during construction is shown in Figure 95 through Figure 98.



Figure 95. Pottawattamie County Project 6: Caterpillar dozer used to control lift thickness



Figure 96. Pottawattamie County Project 6: Caterpillar 851B dozer with sheep's foot roller wheel used for soil compaction



Figure 97. Pottawattamie County Project 6: Dynapac CA250-II vibratory smooth drum roller used for soil compaction



Figure 98. Pottawattamie County Project 6: Disc cultivator used to dry embankment materials

A disc was used to break down and aerate the wet soil. Compaction was achieved in part from the haul equipment and five to eight passes of the sheepsfoot roller (Figure 96). Sheepsfoot walkout was observed during the site visits. A vibratory smooth drum roller was used to level the testing strip (Figure 97).

ISU Field Test Results

In situ moisture content and dry density test results are compared with laboratory Proctor test results in Figure 99 and Figure 100.




Figure 99. Pottawattamie County Project 6 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 100. Pottawattamie County Project 6 TB2: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits

The Proctor test results used by the Iowa DOT showed optimum moisture contents about 1.1% lower than those determined from ISU testing. Similarly, the Proctor test results used by the Iowa DOT showed maximum dry densities about 2.9 to 3.2 lb/ft³ higher than those determined from ISU testing.

To determine whether the field measurements met the specification requirements, Figures 99 and 100 also show an acceptance range of $\pm 2.0\%$ of the standard Proctor optimum moisture content and 95% of standard Proctor density. Maximum dry density, optimum moisture content, and the acceptance zone used by the Iowa DOT at the time of ISU testing are also shown in the figures for reference and comparison.

Field test results indicate that the relative compaction of the material ranged from approximately 90.3% to over 100% of the standard Proctor maximum dry density, with in situ moisture content ranging between -1.6% and +6.1% of the optimum moisture content, as determined from the ISU testing.

The in situ moisture and dry density test results presented in Figure 99 and Figure 100 indicate that 43% of the ISU test results on TB1 and TB2 fell outside the specification limit, with material generally > 2% wet of optimum moisture content. The QC test results were obtained from the contractor during the ISU testing visit. One test point did not meet the moisture specification, but there was no information available on the datasheet provided if that was retested.

DCP-CBR values and cumulative blows with depth profiles are shown in Figure 101 and Figure 102 for the two TBs.




Figure 101. Pottawattamie County Project 6 TB1: DCP-CBR values and cumulative blows with depth profiles




Figure 102. Pottawattamie County Project 6 TB2: DCP-CBR values and cumulative blows with depth profiles

The average CBR value (per TB) in the top 8 in. was 6.0% and the average CBR value in the top 12 in. varied between 4.4% and 5.4% between the two test beds. The results indicate that the CBR values are generally higher when the material is within the moisture control limit, as in the case of TB1, and vice versa, as in the case of TB2.

Summary statistics of the field measurements with average, range, standard deviation, and COV are summarized in Table 19.

Table 19. Pottawattamie County Project 6: Summary of field testing results

Parameter	Pottawattamie County TB1	Pottawattamie County TB2
	7/2/2014	7/10/2014
Relative Compaction		
Average Relative compaction (%)	96.9	98.6
Range of Relative compaction (%)	90.3 to 101.7	95.9 to 101.5
Standard Deviation (%)	0.03	0.02
COV (%)	3	2
$\Delta w\% = w_{\text{field}}\% - w_{\text{opt}}\%$		
Average Δw (%)	1.4	1.8
Range of Δw (%)	-1.6 to +6.1	-1.3 to +5.3
Standard Deviation (%)	2.23	0.02
COV (%)	162	105
CBR_{8 in.}		
Average CBR at 8 in. (%)	6.0	6.0
Range of CBR at 8 in. (%)	1.7 to 12.6	1.5 to 11.8
Standard Deviation (%)	4.0	5.3
COV (%)	66	88
CBR_{12 in.}		
Average CBR at 12 in. (%)	5.4	4.4
Range of CBR at 12 in. (%)	1.6 to 8.5	0.9 to 8.7
Standard Deviation (%)	2.7	3.5
COV (%)	50	79

Control Charts

The contractor QC data and ISU data are reported in Figure 103 in the form of control charts monitoring the dry unit weight and moisture content of the compacted fills.

**Pottawattamie County IM-NHS-080-1(364)3--03-78
Embankment Compaction with Moisture Control**

Project CS.1 Sheet: Moisture content shall be within +/- 2% points of w_{opt} for all class 10 fill.

DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits.



Figure 103. Pottawattamie County Project 6: Moisture control chart

The control chart data are presented as histograms in Figure 104.

Pottawattamie County IM-NHS-080-1(364)3--03-78 Moisture Control




Figure 104. Pottawattamie County Project 6: Histograms of moisture and density control results

The data presented in the control charts and histograms indicate that 96% of the QC data showed relative compaction > 95%, and a majority (91%) of the data fell within the moisture control limits. QA testing results showed 37% of the data with relative compaction > 95%; and, 94% of

the data fell within the moisture control limits. The ISU testing results showed 87% of the data with relative compaction > 95%; and ,60% of the data were within the moisture control limits.

Figure 105 shows control charts for DCP index values at a depth of 600 mm.




Figure 105. Pottawattamie County Project 6: Control charts with control limits for DCP index and variation in DCP index

The weighted average DCP index values ranged from 16.7 to 68.5 mm/blow, and all of the data were within the control limit. The variation in the DCP index control chart shows that DCP index variation fell between 1.6 and 12.3 mm/blow, except for one point that showed about 25.0 mm/blow.

Figure 106 shows control charts for CBR values for the top 8 and 12 in. of the compacted lift.




Figure 106. Pottawattamie County Project 6: CBR control charts with CBR quality ratings

The control charts show CBR ratings per the SUDAS Design Manual guidance regarding subgrade design and construction (SUDAS 2013). Results indicated that 40% of the CBR_{8in.} and 50% of the CBR_{12in.} data showed CBR < 5, which is rated as very poor.

Project 7. Woodbury County I-29

Overview

The ISU research team conducted field testing at this grading project site on 07/09/14, 07/10/14, and 08/07/14. The fill materials obtained at the time of testing consisted of alluvium materials and were classified as A-2-4 by the AASHTO Soil Classification System and SM by the USCS.

At this project site, the project specification required achievement of moisture content within $\pm 2.0\%$ of the optimum moisture content determined from the standard Proctor test. The equipment used during construction is shown in Figure 107 through Figure 109.



Figure 107. Woodbury County Project 7: Dump truck used to place loose fill materials



Figure 108. Woodbury County Project 7: Caterpillar D6T dozer used to control lift thickness



Figure 109. Woodbury County Project 7: Caterpillar CS56B vibratory smooth drum roller used for soil compaction

A vibratory smooth drum roller was used to compact the fills, which consisted of cohesionless materials (Figure 109). The lifted fill materials were very wet, and seepage was observed (Figure 110).



Figure 110. Woodbury County Project 7: Seepage at the construction site

ISU Field Test Results

To determine whether the field measurements met the specification requirements, Figure 111 through Figure 113 show an acceptance range of $\pm 2.0\%$ of the standard Proctor optimum moisture content and 95% of standard Proctor density.




Figure 111. Woodbury County Project 7 TB1: Laboratory Proctor compaction test results with acceptance zone




Figure 112. Woodbury County Project 7 TB2: Laboratory Proctor compaction test results with acceptance zone




Figure 113. Woodbury County Project 7 TB3: Laboratory Proctor compaction test results with acceptance zone

Field density measurements were not performed at this site, but moisture content samples were obtained from the TBs and are presented in the control charts.

DCP-CBR values and cumulative blows with depth profiles are shown in Figure 114 through Figure 116 for the three TBs.




Figure 114. Woodbury County Project 7 TB1: DCP-CBR values and cumulative blows with depth profiles




Figure 115. Woodbury County Project 7 TB2: DCP-CBR values and cumulative blows with depth profiles




Figure 116. Woodbury County Project 7 TB3: DCP-CBR values and cumulative blows with depth profiles

The average CBR value (per TB) in the top 8 in. varied between 1.5% and 3.0% and the average CBR value in the top 12 in. varied between 1.5% and 3.9% among the three test beds.

Summary statistics of the field measurements with average, range, standard deviation, and COV are summarized in Table 20.

Table 20. Woodbury County Project 7: Summary of field testing results

Parameter	Woodbury County I-29 TB1	Woodbury County I-29 TB2	Woodbury County I-29 TB3
	7/9/2014	7/10/2014	8/7/2014
Relative Compaction			
Average (%)	N/A	N/A	N/A
Range (%)	N/A	N/A	N/A
Standard Deviation (%)	N/A	N/A	N/A
COV (%)	N/A	N/A	N/A
$\Delta w\% = w_{\text{field}}\% - w_{\text{opt}}\%$			
Average (%)	5.5	6.9	-0.2
Range (%)	-2.1 to +13.8	+3.9 to +8.9	-1.6 to +1.6
Standard Deviation (%)	4.2	1.4	0.9
COV (%)	76	21	-381
CBR_{8 in.}			
Average (%)	2.6	1.5	3.0
Range (%)	2.1 to 3.6	0.8 to 2.2	1.7 to 4.1
Standard Deviation (%)	0.5	0.6	1.0
COV (%)	20	41	32
CBR_{12 in.}			
Average (%)	3.5	1.5	3.9
Range (%)	2.9 to 4.7	0.6 to 2.2	1.8 to 6.2
Standard Deviation (%)	0.7	0.6	1.7
COV (%)	19	39	44

Control Charts

The contractor QC data, Iowa DOT QA data and ISU data are reported in Figure 117 in the form of control charts monitoring the moisture content of the compacted fills.

**Woodbury County IM-029-6(186)136--13-97
Embankment Compaction with Moisture Control**

Project CS.1 Sheet: Moisture content shall be within +/- 2% points of w_{opt} for all Class 10 fill.

DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits.




Figure 117. Woodbury County Project 7: Moisture control chart

The control chart data are presented as histograms in Figure 118.

Woodbury County IM-029-6(186)136--13-97 Moisture Control





Figure 118. Woodbury County Project 7: Histograms of moisture control results

The data presented in the control charts and histograms indicate that most (98%) of the data fell within the moisture control limits. The QA testing results showed that 80% of the data were within the moisture control limits. The ISU testing results showed that only 34% of the data were within the moisture control limits.

Figure 119 shows control charts for DCP index values at a depth of 600 mm.



White et al. 2007

Figure 119. Woodbury County Project 7: Control charts with control limits for DCP index and variation in DCP index

The weighted average DCP index values ranged between 33 and 213 mm/blow, and 13 points of all of the data exceeded the upper control limit. The variation in the DCP index control chart shows that DCP index variation fell between 4.6 and 41.8 mm/blow at 17 of the 18 points, with 1 point showing about 56.5 mm/blow.

Figure 120 shows control charts for CBR values for the top 8 and 12 in. of the compacted lift.




Figure 120. Woodbury County Project 7: CBR control charts with CBR quality ratings

The control charts show CBR ratings per the SUDAS Design Manual guidance regarding subgrade design and construction (SUDAS 2013). The results indicate that all of the CBR_{8in.} and the CBR_{12in.} data showed CBR < 5, which is rated as very poor.

Project 8. Scott County

Overview

The ISU research team conducted field testing at this grading project site on 07/16/14, 07/31/14, and 09/19/14. The fill materials obtained at the time of testing consisted of loess materials and

were classified as A-4(10), A-6(8), and A-6(5) by the AASHTO Soil Classification System and CL and CL-ML by the USCS.

At this project site, the project specification required achievement of moisture content within $\pm 2.0\%$ of the optimum moisture content determined from the standard Proctor test. The equipment used during construction is shown in Figure 121 through Figure 125.



Figure 121. Scott County Project 8: Caterpillar 349E used to excavate materials from borrow source



Figure 122. Scott County Project 8: Caterpillar dozer used to control lift thickness



Figure 123. Scott County Project 8: Disc cultivator used to dry embankment materials



Figure 124. Scott County Project 8: Sheepfoot roller used for soil compaction



Figure 125. Scott County Project 8: Dynapac pad foot roller used for soil compaction

A disc was used to break down and aerate the wet soil. Compaction was achieved in part from the haul equipment and five to eight passes of the pull-behind sheepfoot roller (Figure 124). Sheepfoot walkout was observed during the site visits. Field observations indicated that the material obtained from the borrow area at the time of ISU testing was relatively wet.

ISU Field Test Results

In situ moisture content and dry density test results are compared with laboratory Proctor test results in Figure 126, Figure 127, and Figure 128.




Figure 126. Scott County Project 8 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 127. Scott County Project 8 TB2: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 128. Scott County Project 8 TB3: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits

The Proctor test results used by the Iowa DOT showed optimum moisture contents about 0.6% lower than those determined from ISU testing in the case of TB1 and 0.4% to 2.9% higher than those determined from ISU testing in the cases of TB2 and TB3. Similarly, the Proctor test results used by the Iowa DOT showed maximum dry densities about 0.9 to 4.0 lb/ft³ higher than those determined from ISU testing in the case of TB1 and TB2 and 7.5 lb/ft³ lower than those determined from ISU testing in the case of TB3.

To determine whether the field measurements met the specification requirements, Figures 126 through 128 also show an acceptance range of $\pm 2.0\%$ of the standard Proctor optimum moisture content and 95% of standard Proctor density. Maximum dry density, optimum moisture content, and the acceptance zone used by the Iowa DOT at the time of ISU testing are also shown in the figures for reference and comparison.

Field test results indicate that the relative compaction of the material ranged from approximately 92.4% to over 100% of the standard Proctor maximum dry density, with in situ moisture content ranging between -0.4% and +7.1% of the optimum moisture content, as determined from the ISU testing.

The in situ moisture and dry density test results presented in Figure 126, Figure 127, and Figure 128 indicate that a majority of the ISU tests on TB2 fell outside the specification limit, with material generally > 2% wet of optimum moisture content and close to the 95% to 100% saturation line.

DCP-CBR values and cumulative blows with depth profiles are shown in Figure 129 through Figure 131 for the three TBs.




Figure 129. Scott County Project 8 TB1: DCP-CBR values and cumulative blows with depth profiles




Figure 130. Scott County Project 8 TB2: DCP-CBR values and cumulative blows with depth profiles




Figure 131. Scott County Project 8 TB3: DCP-CBR values and cumulative blows with depth profiles

The average CBR value (per TB) in the top 8 in. varied between 0.6% and 7.6% and the average CBR value in the top 12 in. varied between 0.5% and 7.0% among the three test beds.

Summary statistics of the field measurements with average, range, standard deviation, and COV are summarized in Table 21.

Table 21. Scott County: Summary of field testing

Parameter	Scott County TB1	Scott County TB2	Scott County TB3
	7/16/2014	7/31/2014	9/19/2014
Relative Compaction			
Average (%)	97.1	97.5	98.0
Range (%)	92.4 to 102.4	95.3 to 99.4	92.5 to 100.6
Standard Deviation (%)	0.03	0.01	0.02
COV (%)	3	1	2
$\Delta w\% = w_{\text{field}}\% - w_{\text{opt}}\%$			
Average (%)	1.8	3.3	2.3
Range (%)	-0.4 to +5.5	0.7 to +4.6	0.3 to +7.1
Standard Deviation (%)	0.02	0.93	1.77
COV (%)	96	29	77
CBR_{8 in.}			
Average (%)	7.6	3.1	0.6
Range (%)	6.2 to 11.6	1.8 to 5.5	0.1 to 2.0
Standard Deviation (%)	2.2	1.6	0.8
COV (%)	29	50	147
CBR_{12 in.}			
Average (%)	7.0	2.7	0.5
Range (%)	5.5 to 10.0	1.3 to 3.9	0.1 to 1.6
Standard Deviation (%)	1.8	1.1	0.6
COV (%)	25	41	123

Control Charts

The contractor QC data, Iowa DOT QA data and ISU data are reported in Figure 132 in the form of control charts monitoring the dry unit weight and moisture content of the compacted fills.

**Scott County IM-074-1(234)0--13-82
Embankment Compaction with Moisture Control**

Project CS.2 Sheet: Moisture content shall be within +/- 2% points of w_{opt} for all Class 10 fill.

DS-12021: If a single moisture content falls outside control limits, fill material in this area will be considered unacceptable for compaction. Perform corrective action(s) to bring uncompacted fill material, after a retest, within the specified control limits.




Figure 132. Scott County Project 8: Moisture control chart

The control chart data are presented as histograms in Figure 133.

Scott County IM-074-1(234)0--13-82 Moisture Control




Figure 133. Scott County Project 8: Histograms of moisture control results

The data presented in the control charts and histograms indicate that 25% of the contractor QC data showed relative compaction > 95%, and 55% of the data fell within the moisture control limits. The QA testing results show that 31% of the data fell within the moisture control limits.

The ISU testing results showed that 89% of the data showed relative compaction > 95%, and 38% of the data were within the moisture control limits.

Figure 134 shows control charts for DCP index values at a depth of 600 mm.




Figure 134. Scott County Project 8: Control charts with control limits for DCP index and variation in DCP index

The weighted average DCP index values ranged from 28.4 to 170.8 mm/blow, and four points of all data exceeded the control limit. The variation in the DCP index control chart shows that DCP index variation between 5.5 and 29.4 mm/blow. Four points exceeded the control limit, with values of 148.17, 54.0, 114.1, and 78.1 mm/blow, respectively.

Figure 135 shows control charts for CBR values for the top 8 and 12 in. of the compacted lift.




Figure 135. Scott County Project 8: CBR control charts with CBR quality ratings

The control charts show CBR ratings per the SUDAS Design Manual guidance regarding subgrade design and construction (SUDAS 2013). The results indicate that 87% of the CBR_{8in.} and 93% of the CBR_{12in.} data showed CBR < 5, which is rated as very poor.

Project 9. Woodbury County US 20

Overview

The ISU research team conducted field testing at this grading project site on 09/26/14 and 10/18/14. The fill materials obtained at the time of testing consisted of very deep loess materials and were classified as A-4(7), A-4(9), and A-6(12) by the AASHTO Soil Classification System and CL and CL-ML by the USCS.

At this project site, the project specification required achievement of moisture content within $\pm 2.0\%$ of the optimum moisture content determined from the standard Proctor test. The equipment used during construction is shown in Figure 136 through Figure 140.



Figure 136. Woodbury County Project 9: Caterpillar 631D motor scraper used to collect and place loose fill materials



Figure 137. Woodbury County Project 9: Caterpillar D6N dozer used to control lift thickness



Figure 138. Woodbury County Project 9: Caterpillar 140H motor grader used to level the embankment surface



Figure 139. Woodbury County Project 9: Caterpillar CS56 series vibratory smooth drum roller used for soil compaction



Figure 140. Woodbury County Project 9: Sheepfoot roller used for soil compaction

A disc was used to break down and aerate the wet soil. Compaction was achieved in part from the haul equipment and five to eight passes of the pull-behind sheepfoot roller (Figure 140). Sheepfoot walkout was observed during the site visits.

ISU Field Test Results

In situ moisture content and dry density test results are compared with laboratory Proctor test results in Figure 141 through Figure 144.




Figure 141. Woodbury County Project 9 TB1: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 142. Woodbury County Project 9 TB2: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 143. Woodbury County Project 9 TB3: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits




Figure 144. Woodbury County Project 9 TB4: Comparison of in situ moisture-density measurements with laboratory Proctor compaction test results and Iowa DOT acceptance limits

The Proctor test results used by the Iowa DOT showed optimum moisture contents about 2.3% to 4.7% lower than those determined from ISU testing. The maximum dry density data from the Iowa DOT standard Proctor test are not available.

To determine whether the field measurements met the specification requirements, Figures 141 through 144 also show an acceptance range of $\pm 2.0\%$ of the standard Proctor optimum moisture content and 95% of standard Proctor density. Optimum moisture content and the acceptance zone used by the Iowa DOT at the time of ISU testing are also shown in the figures for reference and comparison.

Field test results indicate that the relative compaction of the material ranged from approximately 87.4% to over 100% of the standard Proctor maximum dry density, with in situ moisture content ranging between -4.4% and +7.1% of the optimum moisture content, as determined from the ISU testing.

The in situ moisture and dry density test results presented in Figure 141 to Figure 144 indicate that a majority of the ISU tests on TB1, TB2, and TB3 fell outside the specification limit, with material generally > 2% wet of optimum moisture content and close to the 90% to 95% saturation line.

DCP-CBR values and cumulative blows with depth profiles are shown in Figure 145 through Figure 148 for the four TBs.




Figure 145. Woodbury County Project 9 TB1: DCP-CBR values and cumulative blows with depth profiles




Figure 146. Woodbury County Project 9 TB2: DCP-CBR values and cumulative blows with depth profiles




Figure 147. Woodbury County Project 9 TB3: DCP-CBR values and cumulative blows with depth profiles




Figure 148. Woodbury County Project 9 TB4: DCP-CBR values and cumulative blows with depth profiles

The average CBR value (per TB) in the top 8 in. varied between 2.8% and 8.1% and the average CBR value in the top 12 in. varied between 2.6% and 7.8% among the four test beds. The results indicate that the CBR values are generally higher when the material is within the moisture control limit, as in the cases of TB2 and TB3, and vice versa, as in the cases of TB1 and TB4.


Summary statistics of the field measurements with average, range, standard deviation, and COV are summarized in Table 22.

Table 22. Woodbury County Project 9: Summary of field testing

Parameter	Woodbury County (US20) TB1	Woodbury County (US20) TB2	Woodbury County (US20) TB3	Woodbury County (US20) TB4
	9/26/2014	9/26/2014	10/18/2014	10/18/2014
Relative Compaction				
Average (%)	95.7	99.9	100.7	97.6
Range (%)	87.4 to 101.9	97.3 to 102.6	94.1 to 109.0	90.8 to 102.0
Standard Deviation (%)	0.04	0.01	0.04	0.04
COV (%)	4	1	4	4
$\Delta w\% = w_{\text{field}}\% - w_{\text{opt}}\%$				
Average (%)	3.2	2.3	1.4	1.0
Range (%)	-4.4 to +7.1	0.5 to +4.3	-4.1 to +4.4	-2.6 to +5.2
Standard Deviation (%)	2.95	1.15	2.27	2.04
COV (%)	93	49	168	196
CBR_{8 in.}				
Average (%)	5.3	2.8	4.5	8.1
Range (%)	1.4 to 10.8	1.7 to 4.3	1.4 to 9.8	5.0 to 11.0
Standard Deviation (%)	3.5	1.0	3.4	2.5
COV (%)	65	38	74	31
CBR_{12 in.}				
Average (%)	6.1	2.6	4.8	7.8
Range (%)	1.3 to 12.7	1.8 to 3.7	1.8 to 11.7	4.2 to 11.8
Standard Deviation (%)	4.2	0.9	4.2	3.3
COV (%)	69	33	87	42

Control Charts

Figure 149 shows control charts for DCP index values at a depth of 600 mm.



White et al. 2007

Figure 149. Woodbury County Project 9: Control charts with control limits for DCP index and variation in DCP index

The weighted average DCP index values ranged between 16.7 and 105.4 mm/blow, and one point exceeded the control limit. The variation in the DCP index control chart shows that DCP index variation fell between 1.4 and 31.2 mm/blow, except for one point that showed 45.9 mm/blow.

Figure 150 shows control charts for CBR values for the top 8 and 12 in. of the compacted lift.




Figure 150. Woodbury County Project 9: CBR control charts with CBR quality ratings

The control charts show CBR ratings per the SUDAS Design Manual guidance regarding subgrade design and construction (SUDAS 2013). The results indicated that 70% of the CBR_{8in.} and 75% of the CBR_{12in.} data showed CBR < 5, which is rated as very poor.

CHAPTER 6: DATA ANALYSIS

Field Test Results

Figure 151 compares the standard Proctor optimum moisture content and maximum dry unit weight selected by the Iowa DOT for QA testing and the corresponding values measured by the ISU research team for all project sites. The dotted line (1:1 line) represents an ideal condition in which the DOT Proctor and ISU Proctor data are in exact agreement, while the black solid line represents the best regression fit. The dash lines represent the acceptable limits of variation between two values obtained from two different laboratories for CL soils, per ASTM D698. A few soils were classified as CH and SM, and these soils are identified as different colored symbols on the figure along with the allowable limits of variation per ASTM D698. The dash-dot lines represent the allowable limits of variation between two values obtained from different laboratories, per AASHTO T 99-01 (2009). Note that AASHTO T 99 does not provide different allowable variation limits for different soil types, as ASTM D698.

Figure 151 shows that there were variations between ISU Proctor data and Proctor data selected for QA by the Iowa DOT. It is possible that these differences resulted from variations in the test methods and procedures that were used to obtain these measurements. For instance, at most sites the field DOT engineers conducted Proctor tests using hand-operated equipment, while ISU Proctor tests were conducted using automatic machine-operated equipment. Also, the materials selected by ISU directly from the test area could have been slightly different from the Proctor database that the DOT used for comparing their field measurements. A comparison between the measured and selected values showed a standard error of 2.9 lb/ft^3 for maximum dry density and 2.1% for optimum moisture content. The difference in optimum moisture content was as high as 4% and the difference in maximum dry density was as high as 6.5 lb/ft^3 .

For maximum dry density, AASHTO T 99 allows 4.5 lb/ft^3 variation between two test results from different laboratories, while ASTM D698 allows 2.3 lb/ft^3 to 3.9 lb/ft^3 , depending on the soil type. Results indicated that only 1 of 19 test results fell outside the allowable limits per AASHTO T 99, while 7 of 19 fell outside the allowable limits per ASTM D698. For optimum moisture content, AASHTO T 99 allows variation of 15% from the mean of the two test results, while ASTM D698 allows a variation of 1.5% to 1.8%, depending on the soil type. Only 3 of 26 test results fell outside the allowable limits per AASHTO T 99, while 7 of 26 fell outside the allowable limits per ASTM D698.

For maximum dry density, AASHTO T 99 allows 4.5 lb/ft^3 variation between two test results from different laboratories, while ASTM D698 allows 2.3 lb/ft^3 to 3.9 lb/ft^3 , depending on soil type. Only 1 of 19 test results fell outside the allowable limits per AASHTO T 99, while 7 of 19 fell outside the allowable limits per ASTM D698. For optimum moisture content, AASHTO T 99 suggests an acceptable variation of 15% from the mean of the two test results, while ASTM D698 suggests an acceptable variation of 1.5% to 1.8%, depending on soil type. Only 3 of 26 test results fell outside the allowable limits per AASHTO T 99, while 7 of 26 fell outside the allowable limits per ASTM D698.

- (A) CL or CL-ML soil - Acceptable range (2.3 pcf for γ_{dmax} and 1.5% for w_{opt}) of two values from different laboratories, per ASTM D698
- (B) CH soil - acceptable range of two values from different laboratories of 3.9 pcf for γ_{dmax} and 1.8% for w_{opt} , per ASTM D698
- (C) SM soil - no acceptable range values provided in ASTM D698
- (D) All soils - Acceptable range (4.5 pcf for γ_{dmax} and 15% of the mean for w_{opt}) of two values from different laboratories, per AASHTO T 99




Figure 151. Comparison between Proctor test results (optimum moisture content and maximum dry density) selected by the Iowa DOT for QA testing and measured Proctor test results from the ISU research team for all project sites

Table 23 shows a summary of the percentage of test points outside of the specification control limits in the contractor QC data, the Iowa DOT QA data, and the ISU testing data.

Table 23. Summary of the percentage of test points outside of the specification control limits in contractor QC data, Iowa DOT QA data, and ISU data

Project [Dates of Testing]	Materials	Specification	No. of Tests	% of Data outside Specification Control Limits for Final Test Results		
				Contractor QC Testing	Iowa DOT QA	ISU Testing
Polk [QC: 8/11/14-9/30/14] [ISU: 5/29/14, 8/5/14, 8/19/14]	Cohesive	Moisture	59 (QC) 45 (ISU)	5 (dry) 7 (wet)	—	2 (dry) 51 (wet)
		Density	56 (QC) 45 (ISU)	2	—	4
Warren [QC: 4/2/14-11/6/14] [ISU: 6/3/14, 7/22/14, 8/4/14]	Cohesive	Moisture	178 (QC) 45 (ISU)	1 (wet)	—	16 (dry) 18 (wet)
		Density	45 (ISU)	*	*	38
Linn-77 [QC: 4/4/14-12/2/14] [ISU: 6/6/14, 7/15/14, 8/1/14, 9/8/14]	Cohesive	Moisture	564 (QC) 60 (ISU)	1 (wet)	—	2 (dry) 10 (wet)
		Density	60 (ISU)	*	*	5
	Cohesionless	Moisture	31 (QC)	97 (dry)	—	—
		Density	31 (QC)	0	—	—
	Cohesionless	Moisture	285 (QC)	81 (dry) 4 (wet)	—	—
Linn-79 [QC: 5/27/14-6/16/14] [ISU: 6/6/14]	Cohesive	Moisture	85 (QC) 3 (QA) 15 (ISU)	11 (dry) 2 (wet)	0	0
		Density	15 (ISU)	*	*	0
	Cohesionless	Moisture	22 (QC)	100 (dry)	—	—
		Density	22 (QC)	14	—	—
Mills [QC: 5/21/14-8/14/14] [ISU: 6/26/14]	Cohesive	Moisture	150 (QC) 30 (ISU)	1 (dry)	—	50 (wet)
		Density	30 (ISU)	*	*	40
Pottawattamie [QC: 11/19/13-7/14/14] [QA: 7/2/14-7/11/14] [ISU: 7/2/14, 7/10/14]	Cohesive	Moisture	93 (QC) 16 (QA) 30 (ISU)	1 (dry) 9 (wet)	50 (dry) 13 (wet)	40 (wet)
		Density	30 (ISU)	*	*	13
Woodbury-I29 [QC: 6/10/14-10/16/14] [QA: 6/25/14-10/3/14] [ISU: 7/9/14, 7/10/14, 8/7/14]	Cohesionless	Moisture	437 (QC) 35 (QA) 45 (ISU)	1 (dry) 1 (wet)	11 (dry) 9 (wet)	2 (dry) 64 (wet)
Scott [QC: 7/16/14-9/22/14] [QA: 7/11/14-9/29/14] [ISU: 7/16/14, 7/31/14, 9/19/14]	Cohesive	Moisture	55 (QC) 48 (QA) 45 (ISU)	9 (dry) 36 (wet)	4 (dry) 65 (wet)	62 (wet)
		Density	5 (QC) 45 (ISU)	75	*	11
Woodbury-US20 [ISU: 9/26/14, 10/18/14]	Cohesive	Moisture	59 (ISU)	—	—	5 (dry) 51 (wet)
		Density	59 (ISU)	*	*	20

— data not available; * not required; dry = dry of optimum moisture content; wet = wet of optimum

Note: The percentage of QC data outside of the specification control limits was calculated according to contractor Proctor results, and the percentage of ISU data outside of the specification control limits was calculated according to ISU Proctor results.

For cohesive materials, 1% to 45% of the QC moisture measurements were outside of the specification control limits (1% to 11% dry of the lower control limit, 1% to 36% wet of the upper control limit), while 2% to 75% of the QC density measurements were less than the 95% RC limit. Iowa DOT QA data for the Scott County and Pottawattamie County projects were available (for limited testing dates) and are summarized in Table 23.

The data show that 63% of the moisture measurements (50% dry of the lower control limit and 13% wet of the upper control limit) were outside of the specification control limits in the Pottawattamie County project. In the Scott County project, 69% of the moisture measurements (4% dry of the lower control limit and 65% wet of the upper control limit) were outside of the specification control limits. The ISU testing results at one project site showed all test measurements met the moisture and density specification limits. At the remaining project sites, 12% to 62% of the ISU moisture measurements were outside of the specification control limits (2% to 16% dry of the lower control limit and 10% to 62% wet of the upper control limit), and 4% to 40% of the ISU density measurements were less than the 95% RC limit.

For cohesionless materials, the contractor QC results on one site (Woodbury I-29) show that 2% of the moisture measurements were outside of the control limits. Iowa DOT QA data at the same site show that 20% of the moisture measurements (11% dry of the lower control limit and 9% wet of the upper control limit) were outside of the specification control limits. ISU testing at the same site show that 66% of the moisture content measurements were outside of the specification control limits (2% dry, 64% wet).

Two other project sites with cohesionless materials (Linn-77 and Linn-79) show 85 to 100% of the moisture measurements outside of the control limits, of which a majority of the measurements (81% to 100%) were dry of the lower control limit. The Linn-77 project showed that all density measurements were > 95% RC, while Linn-79 project showed 14% of density measurements were < 95% RC.

Statistical Analysis

In this section, the results obtained from this project are compared with the results obtained from the previous projects to assess whether there was any statistically significant improvement in the implementation of the current earthwork QC/QA specifications.

Table 24 provides a summary of the percentage of ISU test points outside of the specification control limits for the Δw and RC measurements from each of the previous project phases in comparison with the measurements from the current project (IHRB TR-677).

Table 24. Summary of the percentage of test points outside of the specification control limits

Project	Moisture difference, Δw (%)	Relative compaction, RC (%)
Phase I	71	36
Phase II	84	31
Phase III	42	24
Phase IV	75	26
TR-677 (This project)	42	16

To visualize the data spread from each of the previous project phases and the current project, box plots are presented in Figure 152 and Figure 153 for Δw and RC, respectively.




Figure 152. Boxplot of moisture difference for previous and current projects




Figure 153. Boxplot of relative compaction for previous and current projects

The box plots show the raw data; the mean and median values; and the 5th, 25th, 75th, and 95th percentiles. The mean (μ) and standard deviation (σ) values for the two measurements are summarized in Table 25.

Table 25. Summary of the mean and standard deviation values for each project

Statistic	Phase I	Phase II	Phase III	Phase IV	IHRB TR-677
n	58	32	160	76	374 (Δw), 329 (RC)
$\mu_{0.1} (\Delta w)$	2.4	2.8	1.5	0.3	1.9
$\mu_{0.1} (RC)$	95.2	97.9	97.3	98.8	98.4
$\sigma (\Delta w)$	3.7	2.3	1.7	3.8	3.0
$\sigma (RC)$	4.2	3.8	3.8	5.6	4.2

Table 26 provides the results of *t*-test analyses, showing *t*- and *p*-values in a matrix comparing the Δw measurements for each of the previous projects and the current project.

Table 26. Summary of *t*- and *p*-values from *t*-test results comparing Δw measurements obtained from Phases I through IV and IHRB TR-677

Project	Phase I	Phase II	Phase III	Phase IV	TR-677
Phase I	—	0.587 (0.279)	-1.873 (0.033)	-3.195 (0.001)	-1.127 (0.132)
Phase II	-0.587 (0.279)	—	-3.042 (0.002)	-4.105 (<0.001)	-2.140 (0.019)
Phase III	1.873 (0.033)	3.042 (0.002)	—	-2.494 (0.007)	1.654 (0.049)
Phase IV	3.195 (0.001)	4.105 (<0.001)	2.494 (0.007)	—	3.212 (0.001)
TR677	1.127 (0.132)	2.140 (0.019)	-1.654 (0.049)	-3.212 (0.001)	—

The values below the black shaded boxes compare the Δw of the column - the Δw of the row, and the values above the gray shaded boxes compare the Δw of the row - the Δw of the column. Values in bold are statistically significant at the 95% confidence level (≤ 0.05).

Table 27 provides the results of logistic regressions, showing the odds ratios and *p*-values in a matrix comparing the percentage of data within the moisture control limits for Δw for each of the previous projects and the current project.

Table 27. Summary of odds ratio and *p*-values from logistic regressions comparing the percentage of data within the moisture control limits from Phases I through IV and IHRB TR-677

Project	Phase I	Phase II	Phase III	Phase IV	TR-677
Phase I	—	0.447 (0.155)	3.344 (<0.001)	0.804 (0.577)	3.086 (<0.001)
Phase II	2.238 (0.155)	—	7.519 (<0.001)	1.799 (0.289)	6.897 (<0.001)
Phase III	0.299 (<0.001)	0.133 (<0.001)	—	0.240 (<0.001)	0.923 (0.673)
Phase IV	1.244 (0.577)	0.556 (0.289)	4.164 (<0.001)	—	3.846 (<0.001)
TR677	0.324 (<0.001)	0.145 (<0.001)	1.084 (0.673)	0.260 (<0.001)	—

The values below the black shaded boxes compare the % of data within the limits for the column \div the % of data within the limits for the row, and the values above the gray shaded boxes compare the % of data within the limits for the row \div the % of data within the limits for the column. Values in bold are statistically significant at the 95% confidence level (≤ 0.05).

The results indicate that there are statistically significant differences between the results obtained from previous phases and the current project. The odds ratios indicate that the data obtained from the IHRB TR-677 project had a comparatively higher percentage of data within the control limits compared to all previous project phases, which suggests improvement.

Similarly to the results of the *t*-test and logistic regression analyses for Δw , Table 28 provides the results of *t*-test analyses showing the *t*- and *p*-values for RC, and Table 29 provides the results of

logistic regressions showing the odds ratios and *p*-values to compare the percentage of data within the limits for RC.

Table 28. Summary of *t*- and *p*-values from *t*-test results comparing RC measurements obtained from Phases I through IV and IHRB TR-677

Project	Phase I	Phase II	Phase III	Phase IV	TR-677
Phase I	—	3.155 (0.001)	3.322 (0.001)	4.276 (<0.001)	5.398 (<0.001)
Phase II	-3.155 (0.001)	—	-0.901 (0.186)	0.947 (0.173)	0.761 (0.226)
Phase III	-3.322 (0.001)	0.901 (0.186)	—	2.173 (0.016)	3.034 (0.001)
Phase IV	-4.276 (<0.001)	-0.947 (0.173)	-2.173 (0.016)	—	-0.476 (0.318)
TR677	-5.398 (<0.001)	-0.761 (0.226)	-3.034 (0.001)	0.476 (0.318)	—

The values below the black shaded boxes compare the RC of the column - the RC of the row, and the values above the gray shaded boxes compare the RC of the row - the RC of the column. Values in bold are statistically significant at the 95% confidence level (≤ 0.05).

Table 29. Summary of odds ratio and *p*-values from logistic regression results comparing the percentage of data above the density control limit (95% RC) from Phases I through IV and IHRB TR-677

Project	Phase I	Phase II	Phase III	Phase IV	TR677
Phase I	—	1.248 (0.636)	1.821 (0.069)	1.590 (0.220)	3.096 (<0.001)
Phase II	0.801 (0.636)	—	1.460 (0.373)	1.272 (0.602)	2.475 (0.027)
Phase III	0.549 (0.069)	0.685 (0.373)	—	0.872 (0.669)	1.698 (0.028)
Phase IV	0.629 (0.220)	0.786 (0.602)	1.147 (0.669)	—	1.946 (0.027)
TR677	0.323 (<0.001)	0.404 (0.027)	0.589 (0.028)	0.514 (0.027)	—

The values below the black shaded boxes compare the % of data above the limit for the column ÷ the % of data above the limit for the row, and the values above the gray shaded boxes compare the % of data above the limit for the row ÷ the % of data above the limit for the column. Values in bold are statistically significant at the 95% confidence level (≤ 0.05).

The results indicate that there are statistically significant differences between the results obtained from previous phases and the current project. The odds ratios indicate that the data obtained from the IHRB TR-677 project had a comparatively higher percentage of data within the control limits compared to all previous project phases, which suggests improvement.

CHAPTER 7: CONCLUSIONS AND RECOMMENDATIONS

Summary and Conclusions

The current study set out to study the impact of the current specifications in terms of quality compaction and to identify further areas for improvement given recent advancements in compaction measurement systems and in situ testing technologies. Field testing was conducted on nine active construction sites in Iowa with materials consisting of glacial till, western Iowa loess, and alluvium sand. Drive cylinder tests were performed to determine in situ moisture content and dry density; DCP tests were performed to determine CBR profiles with depth. Laboratory tests consisted of Proctor and soil classification testing. Field test results from ISU testing were assessed to determine whether the data were within the moisture control limits ($\pm 2\%$ of optimum moisture content) and above the minimum relative compaction control limit (95% of standard Proctor test). The data that were available from contractor QC testing and Iowa DOT QA testing were also assessed in comparison with ISU test results.

Key findings from this study are as follows:

- For cohesive materials, the contractor QC data showed that 1% to 45% of moisture measurements were outside of the specification and 2% to 75% of density measurements were outside of the specification. Iowa DOT QA data at two project sites showed that 63% to 69% of moisture measurements were outside of the specification. ISU testing results showed all test measurements within the moisture and density specification limits at one project site. At the remaining project sites, 12% to 62% of ISU moisture measurements were outside of the specification; and, 4% to 40% of ISU density measurements were outside of the specification.
- For cohesionless materials, the contractor QC results at one site showed that 2% of the moisture measurements were outside of the control limits. Iowa DOT QA data at the same site showed that 20% of the moisture measurements (11% dry of the lower control limit and 9% wet of the upper control limit) were outside of the specification control limits. ISU testing at the same site showed that 66% of the moisture content measurements were outside of the specification control limits (2% dry, 64% wet).
- Two other project sites with cohesionless materials showed 85% to 100% of the moisture measurements outside of the control limits, of which a majority of the measurements (81% to 100%) were dry of the lower control limit. One of the sites showed that all density measurements were $> 95\%$ RC, while the other showed 14% of density measurements were $< 95\%$ RC.
- DCP results showed that the compacted fills have relatively low and variable CBR values, about 0.6% to 8.2% for 8 in. depth and 0.5% to 8.6% for 12 in. depth.
- During in situ construction observations, discing did not effectively aerate wet fill material.

- During in situ observations, cohesionless fill materials were very wet and seepage even occurred. The CBR values (0.3% to 1.0% at 8 in. depth and 0.3% to 1.7% at 12 in. depth) also indicated weak support conditions.
- Proctor tests conducted by ISU using representative material obtained from each test section where field testing was conducted showed optimum moisture contents and maximum dry densities that are different from what was selected by the Iowa DOT for QC/QA testing. Comparison between the measured and selected values showed a standard error of 2.9 lb/ft³ for maximum dry density and 2.1% for optimum moisture content. The difference in optimum moisture content was as high as 4% and the difference in maximum dry density was as high as 6.5 lb/ft³.
- For maximum dry density, AASHTO T 99 allows 4.5 lb/ft³ variation between two test results from different laboratories, while ASTM D698 allows 2.3 lb/ft³ to 3.9 lb/ft³, depending on the soil type. Results indicated that only 1 of 19 test results fell outside the allowable limits per AASHTO T 99, while 7 of 19 fell outside the allowable limits per ASTM D698.
- For optimum moisture content, AASHTO T 99 allows variation of 15% from the mean of the two test results, while ASTM D698 allows a variation of 1.5% to 1.8%, depending on the soil type. Only 3 of 26 test results fell outside the allowable limits per AASHTO T 99, while 7 of 26 fell outside the allowable limits per ASTM D698.
- Statistical analysis indicated statistically significant differences between the Δw and RC results obtained from this project and the previous embankment research projects. The results indicated that data obtained from the current IHRB TR-677 project had a higher percentage of data that were within the control limits for Δw and above the control limit for RC compared to all previous project phases. This suggests improvement over the previous project results.

Recommendations

Based on the field testing and observations documented in this report, although the results show a statistically significant improvement over previous projects, QC/QA results are not consistently meeting the specification. Recommendations are provided herein for improvements to the current specifications in terms of three options, as described below. A one-page summary of the proposed recommendations is provided in Figure 154.




Figure 154. Recommended specification options for future QC/QA

Option 1: Enhance the Current Iowa DOT Moisture and Moisture-Density Specifications

This option has three key aspects that will provide enhancements to the current specifications:

1. The moisture and density control limits should differentiate between cohesive versus intergrade versus cohesionless materials. Material-based moisture control limits should be selected, and guidance regarding this topic is provided in the IHRB TR-640 Phase III project report (White et al. 2002).
2. Although the current specifications call for spatial random sampling, it was not conclusive whether or not a truly random sampling pattern was followed during QC/QA field testing. It is recommended that a simple software tool be developed that can generate spatially random locations for a given work area (starting and ending stations) to reduce bias in sampling and improve documentation.
3. The current process involves field engineers (for both QC and QA) to write down data on field data sheets and share data via DocExpress. In many cases, data were not available on DocExpress for at least several months after the testing had been completed. It is recommended that simple online reporting tools be developed for field engineers where the data can be efficiently entered and RCEs can monitor the process through control charts. This reporting system will allow the RCEs to take immediate corrective actions when data are falling outside the control limits.

Option 2: Develop Alternative DCP/LWD-based (Strength/Stiffness-based) QC/QA Specifications

DCP and LWD test procedures provide a measure of strength and stiffness, which is a performance-related measurement. Two state DOTs (Minnesota and Indiana) have developed DCP and LWD specifications with target limits for QA. A summary of these specifications is provided in Chapter 2 under the section titled Alternative Specification Options. These specifications provide guidance on the DCP index or blow count target values based on different material types. Based on Phase IV testing, White et al. (2007) also provided DCP index target values for suitable, select, and unsuitable soils that can be utilized.

Using an existing database for target limits can be challenging and sometimes not appropriate for certain materials. Therefore, pilot projects are recommended to evaluate the feasibility of using those values. As an alternative to using existing target values, material- and project-specific target values can be determined via DCP testing on compacted specimens in 6 in. diameter Proctor or CBR molds at different moisture and density conditions. This testing will require additional training for field engineers to properly implement the procedures and develop target values.

Option 3: Incorporate Calibrated Intelligent Compaction (IC) Measurements into QC/QA Specifications

As noted in previous Iowa DOT projects, the use of IC technology represents a paradigm shift in terms of process control and acceptance procedures for embankment construction when compared to the current moisture or moisture-density specifications. Example specifications for implementing IC technologies for embankment and pavement foundation layer construction have been published in the technical literature (e.g., ISSMGE 2005, Mooney et al. 2010, White et al. 2009, FHWA 2014, Scott et al. 2014). These specifications vary in the way IC data are used in the process control (QC) and acceptance (QA) processes. These alternative specifications should be reviewed for possible implementation in Iowa.

A rather simple way of using IC measurements is to generate color-coded maps to identify “weak” areas and conduct a stratified random sampling in the “weak” areas for testing. This form of specification is rather simple to implement, but it can be expensive in terms of the number of locations to be tested because the IC measurements are not calibrated to soil engineering properties. Examples of such a specification are described in Mooney et al. (2010) and White et al. (2009).

Proper implementation of IC technology requires a specification that has a statistically framed QC/QA approach, wherein the IC measurement values are properly calibrated to the soil engineering properties that are assumed in the design process. When embankment materials are compacted, there is a need to ensure that the resulting soil engineering properties are satisfactory for the intended purposes (e.g., limit the effects of post-construction volume changes on saturation, provide adequate bearing capacity under embankment loads, and/or provide adequate support capacity to the pavement surface layer under traffic loads).

One way to implement this approach is to require the contractor to develop and produce a statistically valid calibration between in situ QA tests (density, moisture, modulus, or strength) and IC measurement values and develop an IC target value based on the calibration. A statistically valid calibration should provide an R^2 value of ≥ 0.80 . Production areas can then be mapped to produce simple maps that show pass/fail areas (green/red or black/white), which can then be used to identify areas for QA testing using a stratified sampling approach. The final pass on each layer should be mapped to ensure achievement of target IC values over 80% of the area, with no contiguous areas (that are at least 3 ft wide x 50 ft long or 150 ft² or greater in area) that have values lower than the IC target values.

Other Considerations

The new process control procedures and specifications should be developed with the objective of achieving the desirable design engineering properties, including adequate strength and stability, low permeability, low shrink-swell behavior, and low collapsibility. In lieu of relying on compaction density and moisture content control, typical embankment material treatment/stabilization options to improve performance are summarized in Table 30.

Table 30. Typical embankment material treatment/stabilization options to improve performance

Treatment/Stabilization Method	Issues that Can Be Mitigated
Engineered Subgrade Compaction with Moisture, Density, and Lift Thickness Control	<ul style="list-style-type: none"> • Excessive and differential settlement • Post-construction volume change (shrink-swell or collapse) due to moisture variations
Portland Cement Stabilization	<ul style="list-style-type: none"> • Frost heave and thaw softening • Post-construction volume change (shrink-swell or collapse) due to moisture variations • Wet/soft subgrade conditions during construction (to serve as construction platform)
Fly Ash Stabilization of Subgrade (Self-Cementing)	<ul style="list-style-type: none"> • Wet/soft subgrade conditions during construction (to serve as construction platform) • Post-construction volume change (shrink-swell or collapse) due to moisture variations
Lime Stabilization	<ul style="list-style-type: none"> • Shrink-swell potential (applicable for high plasticity clays)
Geosynthetic Reinforcement	<ul style="list-style-type: none"> • Poor support (low CBR/shear strength) during construction (to serve as construction platform)

A summary of various QC/QA testing procedures and their relationships to the engineering properties, skill levels required to perform the tests, and the time taken to perform the tests is provided in Table 31.

Table 31. Comparison of in situ testing procedures for embankment construction

Test Method	Parameter Measured	Assessment Depth (in.)	Time per Test (min.)	Training or Skill Level	Materials	Relationship to Engineering Properties
Nuclear Gauge ^a	Moisture Content and Dry Density	12	1 to 5	High	Granular and Non-Granular	Volume-change behavior (collapse or settlement), permeability, and shear strength
Drive Core ^a	Moisture Content and Dry Density	12+ (4 in. sample)	1 to 5	Low	Non-Granular	
Dynamic Cone Penetrometer ^a	Penetration Index	36	1 to 5	Low	Granular and Non-Granular	Shear strength*
Light Weight Deflectometer ^b	Elastic Modulus or Stiffness	12	2	Low	Granular and Non-Granular	Elastic modulus or stiffness ^b
Clegg Impact Hammer Test ^a	Clegg Impact Value	6	< 1	Low	Subbase and Subgrade	Elastic modulus and shear strength
Plate Load Test ^b	Modulus of subgrade reaction, elastic modulus, and shear strength	Up to 2 times the plate diameter	> 120	High	Granular and Non-Granular	Shear strength, volume-change behavior (collapse or settlement), and modulus
Intelligent Compaction ^b	Index parameters	24-72	Continuous real-time measurement	Low to Medium	Granular and Non-Granular	Shear strength, and modulus

a Test method provides measurements with the potential to be empirically related to engineering properties.

b Test method provides a direct measurement of engineering properties.

REFERENCES

- AASHTO M 145-91. 2012. *Standard specification for classification of soils and soil-aggregate mixtures for highway construction purposes*. American Association of State and Highway Transportation Officials (AASHTO), Washington, DC.
- AASHTO T 99-01. 2009. "Moisture-density relations of soil using a 2.5-kg (5.5-lb) rammer and a 305-mm (12-in.) drop." American Association of State and Highway Transportation Officials (AASHTO), Washington, D.C.
- ASTM D422-63. 2010. *Standard test method for particle-size analysis of soils*. ASTM International, West Conshohocken, PA.
- ASTM D698-12. 2012. *Standard test methods for laboratory compaction characteristics of soil using standard effort* (12,400 ft-lbf/ft³ (600 kN-m/m³)). ASTM International, West Conshohocken, PA.
- ASTM D854-14. 2014. *Standard test methods for specific gravity of soil solids by water pycnometer*. ASTM International, West Conshohocken, PA.
- ASTM D1557-12. 2012. *Standard test methods for laboratory compaction characteristics of soil using modified effort* (56,000 ft-lbf/ft³ (2700 kN-m/m³)). ASTM International, West Conshohocken, PA.
- ASTM D2216-10. 2010. *Standard test methods for laboratory determination of water (moisture) content of soil and rock by mass*. ASTM International, West Conshohocken, PA.
- ASTM D2937-10. 2010. *Standard test method for density of soil in place by the drive-cylinder method*. ASTM International, West Conshohocken, PA.
- ASTM D4318-10. 2010. *Standard test methods for liquid limit, plastic limit, and plasticity index of soils*. ASTM International, West Conshohocken, PA.
- ASTM D6951-09. 2015. *Standard test method for use of the dynamic cone penetrometer in shallow pavement applications*. ASTM International, West Conshohocken, PA.
- Bergeson, K., Jahren, C., Wermager, M., and White, D. 1998. *Embankment Quality: Phase I*. IHRB Project TR-401, Center for Transportation Research and Education, Iowa State University, Ames, IA.
- FHWA. 2014. Intelligent compaction technology for soils applications. *Generic-IC Specifications for Soils*, Federal Highway Administration, Washington, DC.
- Indiana DOT. 2015a. *Field determination of strength using dynamic cone penetrometer*. ITM 509-15P, Indiana Department of Transportation. Office of Materials Management. Seymour, IN. www.in.gov/indot/div/mt/itm/pubs/509_testing.pdf.
- ISSMGE. 2005. *Roller-integrated continuous compaction control (CCC): Technical contractual provisions, recommendations*, TC3: Geotechnics for Pavements in Transportation Infrastructure. International Society for Soil Mechanics and Geotechnical Engineering.
- Indiana DOT. 2015b. *Field testing of soil, granular soil, and coarse aggregate*. Indiana Department of Transportation. Office of Materials Management, Office of Geotechnical Services. Seymour, IN. www.in.gov/indot/files/Fieldtesting.pdf.
- Lambe, T. W., and Whitman, R. V. 1969. *Soil mechanics*. John Wiley and Sons, Inc., NY.
- Larsen, B. W. 2007. Application and evaluation of embankment construction specification for cohesive soil using the dynamic cone penetrometer. Master of Science, Iowa State University, Ames, IA.

- Mooney, M. A., White, D. J., Rinehart, R., Vennapusa, P., Facas, N., and Musimbi, O. 2010. *NCHRP Report 676: Intelligent soil compaction systems*. National Cooperative Highway Research Program. Washington, DC.
- Ott, R. L., and Longnecker, M. 2008. *An introduction to statistical methods and data analysis*, 6th Ed., Duxbury, Pacific Grove, CA.
- Scott, S. III., Konrath, L., Ferragut, T., Anderson, S., Damnjanovic, I., Huber, G., Katsafanas, J., McGhee, K., Sprinkel, M., Ozyildirim, C., Diefenderfer, B., Merritt, D., Dawood, D., Molenaar, K., Loulakis, M. C., White, D., Schaeffer, V. 2014. *Performance Specifications for Rapid Highway Renewal*. SHRP 2 R07. Second Strategic Highway Research Program. Washington, DC.
- Siekmeier, J., Pinta, C., Merth, S., Jensen, J., Davich, P., Camargo, F., and Beyer, M. 2009. *Using the Dynamic Cone Penetrometer and Light Weight Deflectometer for Construction Quality Assurance*. Minnesota Department of Transportation. St. Paul, MN.
- SUDAS. 2013. *SUDAS Design Manual*. Iowa Statewide Urban Design and Specifications (SUDAS) Program. Iowa State University, Ames, IA.
- White, D. J., and Bergeson, K. L. 1999. *Embankment Quality: Phase II*. IHRB Project TR-401. Center for Transportation Research and Education, Iowa State University, Ames, IA.
- White, D. J., Bergeson, K. L., and Jahren, C. T. 2002. *Embankment Quality: Phase III*. IHRB Project TR-401, Center for Transportation Research and Education, Iowa State University, Ames, IA.
- White, D. J., Jaselskis, E. J., Schaefer, V. R., Cackler, E. T., Drew, I., and Li, L. 2004. *Field Evaluation of Compaction Monitoring Technology: Phase I*. IHRB Project TR-495, Center for Transportation Research and Education, Iowa State University, Ames, IA.
- White, D. J., Larsen, B., Jahren, C., and Malama, J. 2007. *Embankment Quality Phase IV: Application to Unsuitable Soils*. IHRB Project TR-492, Center for Transportation Research and Education, Iowa State University, Ames, IA.
- White, D. J., Vennapusa, P., Zhang, J., Gieselman, H., and Morris, M. 2009. *Implementation of Intelligent Compaction Performance Based Specifications in Minnesota*. Minnesota Department of Transportation, St. Paul, MN.
- White, D. J., Vennapusa, P., Gieselman, H. 2010. *Iowa DOT Intelligent Compaction Research and Implementation – Phase I*. Institute of Transportation, Iowa State University, Ames, IA.

APPENDIX A. STATE SPECIFICATION FOR EMBANKMENT CONSTRUCTION OF GRANULAR MATERIALS

Table 32. Specifications of embankment construction for granular materials

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
AL	2012	specify density	NR	maximum 8 in. loess thickness	NR	≥ 95% of maximum γ_d	
AK	2015	specify density	NR	maximum 8 in. loess thickness	≤ +/-2% of w_{opt}	≥ 95% of maximum γ_d	
AZ	2011	specify density	NR	less than maximum rock size or 2 ft	at or near w_{opt}	≥ 95% of maximum γ_d	If asphaltic concrete is to be placed directly on the subgrade, the top six in. of the embankment must be compacted to 100 percent of its maximum density. Material to be placed in dikes must be compacted to at least 95 percent of its maximum density.
AR	2014	specify density	The cleared surface shall then be completely broken up by plowing, scarifying, or disking to a minimum depth of 6 in. (150 mm).	8 to 12 in.	near w_{opt}	≥ 95% of maximum γ_d	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements	
CA	2010	specify density	NR	Over 50% by volume use max. rock size; From 25% to 50% by volume use Max. rock size up to 3 feet; Less than 25% by volume, 8 in. in areas between rocks larger than 8 in..	NR	0.5 foot below the grading plane for the width between the outer edges of shoulders and 2.5 ft below the finished grade for the width of the traveled way plus 3 ft on each side require $\geq 95\%$ of maximum γ_d . Others $\geq 90\%$ of maximum γ_d .		
CO	2011	specify density	NR	less than maximum rock size or 3 ft	$\leq \pm 2\%$ of wopt; Soils having greater than 35 percent passing the 75 μm (No. 200) sieve shall be compacted to 0 to +3% of wopt	$\geq 95\%$ of maximum γ_d		
CT	2008	specify density	NR	maximum 3 ft loess thickness	at wopt	$\geq 95\%$ of maximum γ_d in accordance with AASHTO T 180, Method D.		
DE	2001	NR	NR	maximum 2 ft loess thickness	$\leq \pm 2\%$ of wopt	$\geq 95\%$ of maximum γ_d by AASHTO T 99 Method C, Modified.		
FL	2015	NR	NR	NR	NR	Compact top 6 in $\geq 100\%$ of maximum γ_d		
GA	2013	NR	Ensure that thickness of the lifts and the compaction are approved by the Engineer.					

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
HI	2005	NR	NR	maximum 1 ft loess thickness	(a) Two passes of a 50-ton compression-type roller. (b) Two passes of a vibratory roller having minimum dynamic force of 40,000 pounds impact per vibration and minimum frequency of 1,000 vibrations per minute. (c) Eight passes of a 10-ton compression-type roller. (d) Eight passes of a vibratory roller having minimum dynamic force of 30,000 pounds impact per vibration and minimum frequency of 1,000 vibrations per minute.		
ID	2012	Class A Compaction	NR	maximum 18 in. loess thickness	From -4% to +2% of w_{opt} determined by AASHTO T 99 or AASHTO T 180.	NR	
IL	2012	specify density	NR	maximum 6 in. loess thickness or maximum 8 in. approved by engineer	decided by engineer	$\geq 100\%$ of maximum γ_d of the standard laboratory density.	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
IN	2016	The compaction shall be accomplished with an approved vibratory tamping-foot roller in conjunction with a static tamping-foot roller.	Shale and/or Soft Rock Embankment: minimum of 3 passes with the static roller and a minimum of 2 passes with the vibratory roller. The rollers shall not exceed 3 mph (5 km/h) during these passes. Shale and Thinly Layered Limestone: The minimum number of passes with static roller and the vibratory tamping-foot roller shall be 6 static and 2 vibratory.	Rock Embankment: maximum 8 in. loess thickness top 2 ft of embankment. Embankment exceeds 5 feet, less than maximum rock size or 4 ft loess thickness. Embankment is 5 ft or less, less than maximum rock size or 2 ft loess thickness. Shale and/or Soft Rock Embankment: 8 in. (200 mm) maximum loose lifts; Shale and Thinly Layered Limestone: 8 in. (200 mm) maximum loose lifts	from -2% to +1% of w _{opt} , silt or loess material from -3% to w _{opt}	≥ 95% of maximum γ _d in accordance with AASHTO T 99	Maximum density and optimum moisture content shall be determined in accordance with AASHTO T 99 using method C for granular materials
IA	2012	Do not use compaction equipment	NR	NR	≤ +/-2% of w _{opt} based on standard Proctor optimum moisture content	First layer ≥ 90% of maximum γ _d . succeeding layer ≥ 95% of maximum γ _d	For compaction of sand or other granular material, use either a self-propelled pneumatic roller meeting the requirements or self-propelled vibratory roller meeting the requirements
KS	2015	Type B: Roller Walk out/ roller can support on its feet/ 90% of standard density	NR	less than maximum rock size or 2 ft	Specified on construction plans unless approved by Engineer	specified in the Contract Documents	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
KY	2012	specify density	minimum disk diameter of 2 feet	maximum 2 ft loess thickness	$\leq \pm 2\%$ of w_{opt} determined according to KM 64-511.	$\geq 95\%$ of maximum γ_d as determined according to KM 64-511. AASHTO Y 99	
LA	2006	specify density	NR	maximum 15 in. loess thickness or specify on plans	$\leq \pm 2\%$ of w_{opt} established in accordance with DOTD TR 415 or TR 418	$\geq 95\%$ of maximum γ_d determined in accordance with DOTD TR 415 or TR 418	
ME	2014	specify density	NR	maximum 3 ft loess thickness	Adjust to meet specify density	$\geq 90\%$ of maximum γ_d in accordance with AASHTO T 180, Method C or D,	
MD	2008	specify density	NR	less than maximum rock size or 2 ft	$\leq \pm 2\%$ of w_{opt}	1 ft below the top of subgrade $\geq 92\%$ of maximum γ_d per T 180. Top 1 ft $\geq 97\%$ of maximum γ_d .	
MA	1995	specify density	NR	maximum 3 ft loess thickness	at w_{opt}	$\geq 95\%$ of maximum γ_d by AASHTO T 99	
MI	2012	specify density	NR	maximum 3 ft loess thickness	Soil moisture content must be between 5 percent and optimum moisture.	$\geq 95\%$ of maximum γ_d	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
MN	2014	NR	One pass over each strip covered by the tire for granular soils at an operating speed from 2.5 mph to 5 mph. Disc soils with greater than 20 percent passing the No. 200 [75 µm] sieve.	maximum 1 ft loess thickness			Excavation Depth Below Grading Grade < 30 in., Relative Moisture Content 65% to 102% - Compact to 100% of maximum density; / Excavation Depth Below Grading Grade ≥ 30 in., Relative Moisture Content 65% to 115% - Compact to 95% of maximum density or compact with 4 passes of a roller
MS	2007	specify density	NR	less than maximum rock size or 3 ft	maintained by contractor and approved by engineer	For basement and design soils, the required density shall be ≥ 95% of maximum γ _d and ≥ 98% of maximum γ _d , respectively.	
MO	2014	Compaction of Embankment and Treatment of Cut Areas with Moisture and Density Control	The compactive effort on rocky material shall making four complete passes on each layer with a tamping-type roller or two complete passes on each layer with a vibratory roller.	maximum 1 ft loess thickness or maximum 2 ft rock size too big	NR	≥ 90% of maximum γ _d	Tampers or feet of tamping-type roller ≥ 6 in. from the surface of the drum with a minimum load on each tamper of 250 psi. The vibratory roller shall have 16 to 20 tons compacting power.
		Not Constructed with Density or Moisture and Density Control.	All equipment movements over the entire embankment area and of at least 3 complete passes with a tamping-type roller over the entire area to be compacted.			Each layer of compacted by three complete passes of the tamping-type roller. A vibratory roller may be used if approved by the engineer.	Compactive efforts shall be continued, if necessary, until the tamping ft penetrate no more than 2 in. (50 mm) into the layer of material being compacted

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
MT	2014	NR	NR	When the excavated material contains more than 25% rock by volume, 6 in. or larger in its greatest dimension, place the embankment in layers 2 in. thicker than the maximum size rock in the material not to exceed 24 in. loose thickness. Individual rocks and boulders larger than 24 in. in diameter may be placed in the embankment if the rocks do not exceed 48 in. vertical height after placement,	≥ 95% of maximum γ_d with $\leq \pm 2\%$ of w_{opt}		
NE	2007	Class I	NR	maximum 1 ft loess thickness	Class I: NR	Class I: NR	
		Class II	NR	maximum 8 in. loess thickness	Class II: Adjust to meet require density.	Class II: NR	
		Class III	NR		Class III: shown in the plans.	Class III: shown in the plans.	
NV	2014	NR	Minimum of 3 complete passes each layer at speed not exceeding 8 km/hr (5 mph)	minimum 2 ft loess thickness	NR	NR	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
NH	2010	specify density	NR	minimum 4 ft loess thickness	NR	$\geq 95\%$ of maximum γ_d	For earth materials under approach slabs and for earth materials within 10 ft (3 m) of the back of structures not having approach slabs, at least 98 percent of maximum density shall be obtained
NJ	2015	Control Fill Method	Pneumatic-Tired Roller 5 minimum pass; Dynamic Compactor Number of passes to optimize density; 3-Wheel 10-Ton Roller 4 minimum pass; Dynamic Compactor (Vibratory roller with 6-ton min. static weight at drum) 2 to 5	less than 1.5 times maximum rock size or 3 ft	NR	$\geq 95\%$ of maximum γ_d determined according to AASHTO T 99, Method C,	
		Directed Method				passes per lift specify by equipment	
NM	2014	specify density	NR	maximum 8 in. loess thickness	NR	$\geq 95\%$ of maximum γ_d	
NY	2015	specify density	The compactive effort (number of passes and travel speed) is uniformly applied and not less than that specified for the given equipment class and lift thickness.	maximum 6 in. loess thickness	determined by contractor	$\geq 95\%$ of maximum γ_d of Standard Proctor Maximum Density will be required	
NC	2012	specify density	NR	maximum 3 ft loess thickness	NR	$\geq 95\%$ of maximum γ_d in accordance AASHTO T 99	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
ND	2014	NR	NR	less than maximum rock size or 2 ft	NR	NR	
OH	2013	specify density	For soil or granular material, when a test section is used, use a minimum compactive effort of 8 passes with a steel wheel roller having a minimum effective weight of 10 tons (9 metric tons). Compact Type D and Type E granular material using at least ten passes of a smooth drum vibratory roller having a minimum effective weight of 10 tons (9 metric tons).	maximum 6 in. loess thickness, or less than 6 in. more than maximum rock size or 3 ft	NR	specify by pass numbers	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
OK	2014	specify density	for rock fill layers 12 in thick or less, 4 pass using 50 ton compression type roller; 4 pass using vibratory roller with dynamic force of at least 40500 lbf per cycle and frequency of at least 16 Hz; 8 pass using 22 ton compression type roller; 8 pass using vibratory roller with dynamic force of at least 29250 lbf per cycle and frequency of at least 16 Hz for rock layer thicker than 12 in., increase the number of roller-passes for each additional 6 in. increment by the number required for first 12 in.	maximum 2 ft loess thickness	for A-4 or A-5 soil groups, from -4% to 0% of wopt	specify by pass numbers	
OR	2015	specify density	NR	maximum 15 in. loess thickness or less than maximum rock size or 3 ft	from -4% to +2% of wopt	≥ 95% of maximum γ_d	
PA	2015	specify density	NR	less than maximum rock size or 3 ft	from -3% to 0% of wopt	≥ 97% of maximum γ_d determined according to PTM No. 106, Method B. Top 3 ft of embankment ≥100% of maximum γ_d .	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
RI	2013	specify density	NR	maximum 3 ft loess thickness	NR	Embankment of 3 ft below subgrade shall be compacted $\geq 90\%$ of maximum γ_d . The remainder of the roadway section up to subgrade shall be compacted $\geq 95\%$ of maximum γ_d .	
SC	2015	specify density	NR	Maximum 8 in. loess thickness top 2 ft of embankment. Embankment exceeds 5 feet, less than maximum rock size or 4 ft loess thickness. Embankment is 5 ft or less, less than maximum rock size or 2 ft loess thickness.	Suitable moisture	$\geq 95\%$ of maximum γ_d	
SD	2004	Specified Density Method	The disk shall be a tandem disk approximately 12 ft wide with eight disk blades, approximately 36 in. in diameter, per row, and shall weigh approximately 11,800 pounds (5350 kg). This requirement will be waived for A-3 and A-2-4(0) soils.	less than maximum rock size or 3 ft loess thickness	if w_{opt} of embankment soil is 0% to 15%, require 95% or Greater maximum γ_d , and -4% to +4% of w_{opt} control; if w_{opt} of embankment soil is 15% or Greater, require 95% or Greater maximum γ_d , and -4% to +6% of w_{opt} control		
		Ordinary Compaction Method			Adjust to meet require density	Compaction may be accomplished with any type of equipment, which with adequate moisture content will give uniform satisfactory results.	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
TN	2015	specify density	Provide a minimum of 3 passes with the static roller and 2 passes with the vibratory roller. The Engineer may direct additional passes with either or both rollers until satisfactory breakdown and compaction is accomplished.	maximum 3 ft loess thickness	NR	Non-Degradable Rock: Rolling is not required if the rock embankment consists of sound, non-degradable material placed in greater than 10 in. layers; Degradable Rock: provide a minimum of 3 passes with the static roller and 2 passes with the vibratory roller.	
TX	2014	Ordinary Compaction.	NR	maximum 18 in. loess thickness	NR	Compact each layer until there is no evidence of further consolidation	
		Density Control			For $PI \leq 15$, no moisture content required, density $\geq 98\% \gamma_d$		
UT	2015	specify density	NR	maximum 6 in. compacted thickness	Maintain appropriate moisture for compaction during processing.	Acceptance is on a lot-by-lot basis when average density is $\geq 96\%$ of maximum γ_d and no single determination is lower than 92 percent.	
VT	2011	specify density	The water shall be uniformly and thoroughly incorporated into the soil by disking, harrowing, blading, or other approved methods.	maximum 24 in. loess thickness	$\leq +2\%$ of w_{opt} or less than the quantity will cause unstable	$\geq 90\%$ of maximum γ_d determined by AASHTO T 99, Method C. Top 24 in. of any embankment $\geq 95\%$ of maximum γ_d .	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
VA	2014	specify density	disking or punching the mulch partially into the soil;	less than maximum rock size	NR	Density requirements may be waived.	
WA	2015	NR	NR	maximum 18 in. loess thickness unless rock size over 18 in.	NR	Use compression roller or vibratory roller. The roller shall make one full coverage for each 6 in., or any fraction of 6 in. of lift depth. When lift depth is 18 in. or less, the Contractor may use a compression roller or a vibratory roller make four full coverages for each 6 in., or any fraction of 6 in., lift depth.	Use 50-ton compression roller or vibratory roller have at least 40,000 lbs impact per vibration and at least 1,000 vibrations per min. Use a 10-ton compression roller or vibratory roller having a dynamic force of at least 30,000-pounds impact per vibration and at least 1,000 vibrations per min.
WV	2011	NR	NR	maximum 6 in. compacted thickness	NR	≥ 95% of maximum γ_d when less than 40% particles by weight retained on 3/4 in. sieve	
WI	2014	Standard Compaction	NR	maximum 12 in. loess thickness	NR	Compact each layer of the embankment until the compaction equipment achieves no further significant consolidation.	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
		Special Compaction				Embankments \leq 6 ft, \geq 95% of maximum γ_d . Embankments \geq 6 ft, 6 ft below subgrade \geq 90% of maximum γ_d , rest 6 ft to finish subgrade \geq 95% of maximum γ_d	
WY	2015	Special Compaction	NR	maximum 12 in. loess thickness when rock size over 8 in.	from -4% to +2% of wopt	place and compact material above the 6 in scarified layer \geq 95% of maximum γ_d . AASHTO T 99	

APPENDIX B. STATE SPECIFICATION FOR EMBANKMENT CONSTRUCTION OF NON-GRANULAR MATERIALS

Table 33. Specifications of embankment construction for non-granular materials

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
AL	2012	specify density	NR	maximum 8 in. loess thickness	NR	$\geq 95\%$ of maximum γ_d	
AK	2015	specify density	During the winter, compact 3 passes per layer with sheep's foot compactor/roller or vibratory grid roller and until frozen chunks are reduced in size to less than 2 in. in any dimension.	maximum 8 in. loess thickness	$\leq \pm 2\%$ of w_{opt}	$\geq 95\%$ of maximum γ_d	
AZ	2011	specify density	NR	maximum 8 in. loess thickness	at or near w_{opt}	$\geq 95\%$ of maximum γ_d	If asphaltic concrete placed directly on the subgrade, the top 6 in. of the embankment must be compacted to 100% of maximum γ_d . Material to be placed in dikes must be compacted $\geq 95\%$ of maximum γ_d
AR	2014	specify density	The cleared surface shall then be completely broken up by plowing, scarifying, or disking to a minimum depth of 6 in.	maximum 10 in. loess thickness	at or near w_{opt}	$\geq 95\%$ of maximum γ_d	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
CA	2010	specify density	NR	maximum 8 in. loess thickness	NR	0.5 foot below the grading plane for the width between the outer edges of shoulders and 2.5 ft below the finished grade for the width of the traveled way plus 3 ft on each side require $\geq 95\%$ of maximum γ_d . Others $\geq 90\%$ of maximum γ_d .	
CO	2011	specify density	NR	maximum 8 in. loess thickness	$\leq \pm 2\%$ of wopt; Soils having greater than 35 percent passing the 75 μm (No. 200) sieve shall be compacted to 0 to +3% of wopt	$\geq 95\%$ of maximum γ_d determined in accordance with AASHTO T 180	
CT	2008	specify density	NR	maximum 12 in. loess thickness	at wopt	$\geq 95\%$ of maximum γ_d in accordance with AASHTO T 180, Method D.	
DE	2001	specify density	NR	maximum 8 in. loess thickness	$\leq \pm 2\%$ of wopt	$\geq 95\%$ of maximum γ_d as determined by AASHTO T 99 Method C, Modified.	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
FL	2015	specify density	NR	For A-3 and A-2-4 Materials with up to 15% fines: max 12 in. compacted thickness; For A-1, Plastic materials and A-2-4 Materials with greater than 15% fines: max 6 in. compacted thickness	Adjust to meet specify density	$\geq 100\%$ of maximum γ_d as determined by AASHTO T-99, Method C,	
GA	2013	specify density	NR	maximum 8 in. loess thickness	the range of w_{opt}	$\geq 95\%$ of maximum γ_d within 1 ft of the top of the embankment. Top 1 ft of the embankment, $\geq 100\%$ of maximum γ_d .	
HI	2005	specify density	NR	maximum 9 in. loess thickness	$\leq \pm 2\%$ of w_{opt} in accordance with AASHTO T 180.	$\geq 95\%$ of maximum γ_d . Top 6 in. of in-situ material and embankment material below top 2 ft of subgrade, requires $\geq 90\%$ of maximum γ_d	
ID	2012	Class A Compaction. Default compaction method. less than 10% retained on the 3 in. sieve; and more than or equal to 30 percent retained on the $\frac{3}{4}$ " sieve, minimum of 95 percent of maximum dry density by AASHTO T 99 Method C	NR	maximum 8 in. loess thickness	from -4% to +2% of w_{opt} determined by AASHTO T 99 or AASHTO T 180.E13	$\geq 95\%$ of maximum γ_d	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
		<p>Class B Compaction. Top 12 in still using class A compaction. by routing construction equipment uniformly over the entire surface of each layer.</p> <p>Class C Compaction. Shown on the plans or as directed by the Engineer. Use class A compaction to a depth of 8 in.</p> <p>Class D Compaction. approved by engineer</p>		<p>maximum 12 in. loess thickness</p>			
IL	2012	specify density	NR	maximum 8 in. loess thickness	120% of w_{opt} for top 2 ft	<p>If embankment ≤ 1.5 ft, all lifts $\geq 95\%$ of maximum γ_d. If the embankment height is between 1.5 ft and 3 ft inclusive, the first lift $\geq 90\%$ of maximum γ_d, and the balance $\geq 95\%$ of maximum γ_d. If embankment ≥ 3 ft, the lower 1/3 of the embankment, but not to exceed the lower 2 ft, $\geq 90\%$ of maximum γ_d. The next 1 ft $\geq 93\%$ of maximum γ_d, and the balance $\geq 95\%$ of maximum γ_d.</p>	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
IN	2016	Embankment With Density Control: Compacting equipment shall include at least one 3 wheel roller or other approved equipment provide a smooth and even surface. Embankment Without Density Control: compacted with crawler-tread equipment or with approved vibratory equipment, or both.	NR	Embankment With Density Control: maximum 8 in. loess thickness; Embankment Without Density Control: maximum 6 in. loess thickness; location inaccessible to the compacting equipment, maximum 4 in. loess thickness	from -2% to +1% of w_{opt} , silt or loess material from -3% to w_{opt}	$\geq 95\%$ of maximum γ_d in accordance with AASHTO T 99	DCP were used in compaction of chemically modified soils: Acceptance testing for compaction of chemically modified soils will be performed on the finished grade with a DCP in accordance with ASTM D6951
IA	2012	Type A: compaction requiring a minimum of 1 rolling per in. depth of each lift. A further requirement is that the roller continues operation until it is supported on its feet, or the equivalent.	Disk the area with a least one pass of a tandem axle disk or 2 passes with a single axle disk prior to compaction.	maximum 8 in. loess thickness	$\leq \pm 2\%$ of w_{opt}	Compact the first layer $\geq 90\%$ of maximum γ_d . Compact each succeeding layer $\geq 95\%$ of maximum γ_d .	1. If the type of compaction is not specified, Type A compaction will be required. 2. When compaction with moisture and density control is specified, any type of equipment which will produce the desired results may be used for compaction.
		Type B: refers to compaction requiring a specified number of diskings and roller coverages, or the equivalent.	One disking per 2 in. of loose thickness.				

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
		Other Method: Reasonably uniform throughout the compacted lift; At least 95% of maximum density, determined according to Materials Laboratory Test Method No. Iowa 103.	NR				
KS	2015	Type AAA: 100% of Standard Density	NR	maximum 8 in. loess thickness	$\leq \pm 5\%$ of w_{opt}	specified in the Contract Documents	
		Type AA 95% of Standard Density					
		Type A 90% of Standard Density					
KY	2012	specify density	minimum disk diameter of 2 ft	maximum 12 in. loess thickness	$\leq \pm 2\%$ of w_{opt} determined according to KM 64-511.	$\geq 95\%$ of maximum γ_d as determined according to KM 64-511	
LA	2006	specify density	NR	maximum 12 in. loess thickness	$\leq \pm 2\%$ of w_{opt} established in accordance with DOTD TR 415 or TR 418	$\geq 95\%$ of maximum γ_d in accordance with DOTD TR 415 or TR 418	
ME	2014	specify density	NR	maximum 8 in. loess thickness	Adjust to meet specify density	$\geq 90\%$ of maximum γ_d in accordance with AASHTO T 180, Method C or D	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
MD	2008	specify density	the entire surface of each lift shall be traversed by not less than one tread track of heavy equipment or compaction shall be achieved by a minimum of 4 complete passes of a sheepsfoot, rubber tired or vibratory roller.	maximum 8 in. loess thickness	$\leq \pm 2\%$ of wopt	1 ft below the top of subgrade $\geq 92\%$ of maximum γ_d per T 180. Top 1 ft $\geq 97\%$ of maximum γ_d .	
MA	1995	specify density	NR	maximum 12 in. loess thickness	at wopt	$\geq 95\%$ of maximum γ_d by AASHTO T 99	
MI	2012	specify density	NR	maximum 9 in. loess thickness	$\leq +3\%$ of wopt	$\geq 95\%$ of maximum γ_d	
MN	2014	100% Relative Density for ≤ 3 ft Below Grading Grade of Road Core	Make two passes over each strip covered by the tire width for non-granular soils at an operating speed from 2.5 mph to 5 mph. Disc soils with greater than 20	maximum 12 in. loess thickness	Excavation Depth Below Grading Grade < 30 in., Relative Moisture Content 65% to 102% - Compact to 100% of maximum γ_d ; / Excavation Depth Below Grading Grade ≥ 30 in., Relative Moisture Content 65% to 115% - Compact to 95% of maximum γ_d or compact with 4 passes of a roller		Compact the entire lift to achieve a dynamic cone penetration index (DPI) value during embankment compaction
		100% Relative Density Within the Minimum of Either the Horizontal Distance Equal to the Full Height of a Structure or within 3 ft of a Structure					

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
		95% Relative Density Remaining embankment in the road core	percent passing the No. 200 [75 μ m] sieve.				Use the Specified Density method for acceptance for materials not meeting the requirements, and use the granular penetration index method for materials meeting the requirements of 2105.1A7,
MS	2007	specify density	NR	maximum 8 in. loess thickness	maintained by contractor and approved by engineer	For basement and design soils, the required density shall be $\geq 95\%$ of maximum γ_d and $\geq 98\%$ of maximum γ_d , respectively.	
MO	2014	Compaction of Embankment and Treatment of Cut Areas with Moisture and Density Control	At least 3 complete passes with a tamping-type roller over the entire area to be compacted. Compactive efforts shall be continued, if necessary, until the tamping ft penetrate no more than 2 in. (50 mm) into the layer of material being compacted.	maximum 8 in. loess thickness	when embankments less than 30 ft, $\leq +3\%$ of w_{opt} ; Embankment more than 30 ft, $\leq w_{opt}$ for loess soil	$\geq 90\%$ of maximum γ_d	When eliminate rubbery condition of embankment, it may be required soils have a moisture content below the optimum during compacting work, except $LL \geq 40$, where placed in embankments within 5 ft (1.5 m) of the top of the finished subgrade or where encountered in areas of cut compaction.

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
MT	2014	NR	Using a tandem type construction disk with a maximum disk spacing of 14 in. (355 mm) and a minimum worn disk diameter of 25 in. (635 mm).	maximum 8 in. loess thickness			$\geq 95\%$ of maximum γ_d with $\leq \pm 2\%$ of wopt
NE	2007	Class I	NR	maximum 12 in. loess thickness	NR	NR	
		Class II	NR	maximum 8 in. loess thickness	Adjust to meet specify density	NR	
		Class III	NR	maximum 8 in. loess thickness	Adjust to meet specify density	Shown in the plans.	
NV	2014	specify density	NR	maximum 8 in. loess thickness	moisture content within the prescribed limits	$\geq 95\%$ of maximum γ_d by Test method No. Nev. T108	Compact base of cuts, Natural ground less than 1.5m (5ft) not less than 90% of maximum density determined by Test method No. Nev. T108;
NH	2010	specify density	NR	maximum 12 in. loess thickness	NR	$\geq 95\%$ of maximum γ_d	For earth materials under approach slabs, at least 98 percent of maximum density shall be obtained.
NJ	2015	End-Dumping Method	Pneumatic-Tired Roller 5 minimum pass; Pad foot Roller 8 minimum pass	NR	NR	NR	
		Control Fill Method		maximum 12 in. loess thickness		$\geq 95\%$ of maximum γ_d according to AASHTO T 99, Method C,	
		Directed Method		maximum 8 in. loess thickness		passes per lift specify by equipment	
		Density Control Method		maximum 12 in. compacted thickness		$\geq 95\%$ of maximum γ_d	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
NM	2014	specify density	NR	maximum 8 in. loess thickness	General -5% to 0 of wopt. For soils PI ≥ 15, 0% to +4% of wopt	≥ 95% of maximum γd	
NY	2015	specify density	The compactive effort (number of passes and travel speed) is uniformly applied and not less than that specified for the given equipment class and lift thickness.	Not exceed equipment allowance	determined by contractor	≥ 95% of maximum γd of Standard Proctor Maximum Density will be required.	
NC	2012	specify density	NR	maximum 10 in. loess thickness	NR	≥ 95% of maximum γd in accordance AASHTO T 99	
ND	2014	Compaction Control, Type A.	NR	maximum 12 in. loess thickness	for ND T180, 0% to +5% of w _{opt} ; for ND T99, -4% to +5% of wopt	ND T180 requires ≥ 90% of maximum γd; ND T99 requires ≥ 95% of maximum γd	
		Compaction Control, Type B.		maximum 12 in. loess thickness	NR	Use a sheepsfoot roller until the roller pads penetrate the surface a maximum of 0.5 in.	
		Compaction Control, Type C.		maximum 8 in. loess thickness	NR	NR	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
OH	2013	specify density	NR	maximum 8 in. loess thickness	NR	If maximum γ_d from 90 to 104.9 lb/ft ³ , requires at least 102% maximum dry density compaction energy; if maximum γ_d from 105 to 119.9 lb/ft ³ , requires at least 100% maximum dry density; if maximum γ_d more than 120 lb/ft ³ , requires at least 98% maximum dry density	
OK	2014	specify density	NR	maximum 8 in. loess thickness	$\leq \pm 2\%$ of wopt, for A-4 or A-5 soil groups, from -4% to 0% of wopt	$\geq 95\%$ of maximum γ_d	
OR	2015	specify density	NR	maximum 8 in. loess thickness	from -4% to +2% of wopt	$\geq 95\%$ of maximum γ_d	
PA	2015	specify density	NR	maximum 8 in. loess thickness	from -3% to 0% of wopt	Compact embankment for its full width $\geq 97\%$ of maximum γ_d according to PTM No. 106, Method B. Compact top 3 ft of embankment for full width to $\geq 100\%$ of maximum γ_d .	
RI	2013	specify density	NR	maximum 12 in. compacted thickness	NR	Embankment of 3 ft below subgrade shall be compacted $\geq 90\%$ of maximum γ_d . The remainder of the roadway section compacted $\geq 95\%$ of maximum γ_d .	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
SC	2015	specify density	NR	maximum 8 in. loess thickness	Suitable moisture	$\geq 95\%$ of maximum γ_d	
SD	2004	Specified Density Method	The disk shall be a tandem disk approximately 12 ft wide with 8 disk blades, approximately 36 in. in diameter, per row, weigh approximately 11,800 pounds. This requirement waived for A-3 and A-2-4(0) soils.	maximum 8 in. loess thickness	if w_{opt} of embankment soil is 0% to 15%, require 95% or Greater maximum γ_d , and -4% to +4% of w_{opt} control; if w_{opt} of embankment soil is 15% or greater, require 95% or greater maximum γ_d , and -4% to +6% of w_{opt} control		
		Ordinary Compaction Method			Adjust to meet specify density	Compaction may be accomplished with any type of equipment, which with adequate moisture content will give uniform satisfactory results.	
TN	2015	specify density	NR	maximum 10 in. loess thickness	when 95% of maximum density is required, $\leq w_{opt}$. When 100% of maximum density is required, $\leq \pm 3\%$ of w_{opt} .	Compact each layer $\geq 95\%$ of maximum γ_d . Unless otherwise specified, compact the top 6 in. of the roadbed in both cut and fill sections $\geq 100\%$ of maximum γ_d	
TX	2014	Ordinary Compaction.	NR	maximum 8 in. loess thickness	Compact each layer until there is no evidence of further consolidation		
		Density Control		maximum 16 in. loess thickness or 12 in. compacted thickness	For $PI \leq 15$, no moisture content required, density requires $\geq 98\%$ of γ_d ; For $15 < PI \leq 35$, moisture content should not less than W_{opt} , density requires $98\% \text{ of } \gamma_d \leq \gamma_d \leq 102\% \text{ of } \gamma_d$; For $PI > 35$, moisture content should not less than W_{opt} , density requires $95\% \text{ of } \gamma_d \leq \gamma_d \leq 100\% \text{ of } \gamma_d$		

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
Utah	2015	specify density	NR	maximum 12 in. loess thickness	Maintain appropriate moisture for compaction during processing.	$\geq 96\%$ of maximum γ_d and no single determination is lower than 92 percent.	
VT	2011	specify density	The water shall be uniformly and thoroughly incorporated into the soil by disking, harrowing, blading, or other approved methods.	maximum 8 in. loess thickness	$\leq +2\%$ of w_{opt} or less than the quantity will cause unstable	$\geq 90\%$ of maximum γ_d as determined by AASHTO T 99, Method C. the top 24 in. $\geq 95\%$ of maximum γ_d .	
VA	2014	specify density	disking or punching the mulch partially into the soil;	maximum 8 in. loess thickness	$\leq \pm 2\%$ of w_{opt} .	$\geq 95\%$ of maximum γ_d	
WA	2015	Method A	NR	maximum 2 ft loess thickness	NR	The Contractor shall compact each layer by routing loaded haul equipment over its entire width.	
		Method B		Top 2 ft, maximum 4 in. loess thickness. Below top 2 ft, maximum 8 in.	$\leq +3\%$ of w_{opt} .	2 ft below finish subgrade $\geq 90\%$ of maximum γ_d , rest 2 ft to finish subgrade $\geq 95\%$ of maximum γ_d	

State	Spec Date	Placement/compaction Method	Disk/Passes	Lift Thickness	w	DD	Other Requirements
		Method C		loess thickness. Up to maximum 18 in. loess thickness after engineer permit		$\geq 95\%$ of maximum γ_d	
WV	2011	specify density	NR	maximum 4 in. compacted thickness	from - 4% to +3% of w_{opt} while material having less than 40% by weight retained on 3/4 in. sieve	$\geq 95\%$ of maximum γ_d when less than 40% particles by weight retained on 3/4 in. sieve	
WI	2014	Standard Compaction	NR	maximum 8 in. loess thickness	NR	Compact each layer of the embankment until the compaction equipment achieves no further significant consolidation.	
		Special Compaction				Embankments ≤ 6 ft, $\geq 95\%$ of maximum γ_d . Embankments ≥ 6 ft, 6 ft below subgrade $\geq 90\%$ of maximum γ_d , rest 6 ft to finish subgrade $\geq 95\%$ of maximum γ_d	
WV	2015	with moisture and density control	NR	maximum 8 in. loess thickness	from -4% to +2% of w_{opt}	$\geq 90\%$ of maximum γ_d	
		without moisture and density control			NR		

APPENDIX C. GRAIN SIZE DISTRIBUTION OF EMBANKMENT MATERIALS




Figure 155. Polk County Project 1: Grain size distribution of embankment materials




Figure 156. Warren County Project 2: Grain size distribution of embankment materials




Figure 157. Linn County Project 3: Grain size distribution of embankment materials




Figure 158. Linn County Project 4: Grain size distribution of embankment materials




Figure 159. Mills County Project 5: Grain size distribution of embankment materials




Figure 160. Pottawattamie County Project 6: Grain size distribution of embankment materials




Figure 161. Woodbury County Project 7: Grain size distribution of embankment materials




Figure 162. Scott County Project 8: Grain size distribution of embankment materials




Figure 163. Woodbury County Project 9: Grain size distribution of embankment materials