

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: July 19, 2016
Date of Addendum: June 24, 2016

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
104	58-0613-059	PCC PAVEMENT - GRADE AND NEW	LOUISA	HSIPX-061-3(59)--3L-58 NHSX-061-3(68)--3H-58 NHSX-061-3(69)--3H-58	19JUL104.A02

Make the following changes to the PLAN ATTACHMENT SHEETS for Project #
NHSX-061-3(68)--3H-58:

Add attached SHEET J.1

108-23A
08-01-08

TRAFFIC CONTROL PLAN

Contractor shall coordinate with paving project to ensure permanent signing is in place before opening routes to traffic.

Existing US 61

- Any W6-3 signs previously placed in the grading package will become property of the paving Contractor, to be used in Stages 2A through 3D in accordance with Specification 2528.03.
- During work hours only, close inside lanes as needed. During non-work hours, close inside shoulders as needed.

Two-lane segments:

- During work hours only, maintain traffic using lane closure with flaggers. During non-work hours, use shoulder closure as needed.

Mainline US 61

- During work hours only, close inside lanes as needed. During non-work hours, close inside shoulders as needed.

Side Roads

130th St:

- Maintain traffic in each direction.

145th St:

- Closed to traffic during Stage 2A and Stage 3A.

IA 92:

- Maintain traffic in each direction. Refer to Staging Notes tabulation and staging plans for details of specific closures.

160th St:

- Closed to traffic during Stage 3A.

170th St:

- Maintain traffic in each direction. Refer to Staging Notes tabulation and staging plans for details of specific closures.

175th St:

- Maintain traffic in each direction.

180th St:

- Closed to traffic during Stage 2B. Refer to Co Hwy 305 (180th St) Detour.

190th St:

- Maintain traffic in each direction.

111-01
04-17-12

COORDINATED OPERATIONS

Other work in progress during the same period of time will include the construction of the projects listed. Coordinate operations with those of other contractors working within the same area.

Project	Type of Work
NHSN-061-3(74)--2R-58	SALVAGE AND REMOVAL
NHSN-061-3(77)--2R-58	SALVAGE AND REMOVAL
NHSX-061-3(57)--3H-58	GRADING
NHSX-061-3(59)--3H-58	PAVING
NHSX-061-3(70)--3H-58	BRIDGE NEW - PPCB
NHSX-061-3(71)--3H-58	BRIDGE NEW - PPCB
NHSX-061-3(72)--3H-58	BRIDGE NEW - PPCB
NHSX-061-3(69)--3H-58	LIGHTING
NHSX-061-3(68)--3H-58	SIGNING