

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: August 16, 2016
Date of Addendum: July 28, 2016

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
101	10-C010-090	PCC OVERLAY - UNBONDED	BUCHANAN	FM-C010(90)--55-10	16aug101.a01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Change Proposal Line No. 0250 2503-0114218 STORM SEWER GRAVITY MAIN,
TRENCHED, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 18 IN.:
From: 201.960 LF
To: 150.700 LF

Add Proposal Line No. 0285 2503-0124218 STORM SEWER GRAVITY MAIN,
TRENCHLESS, REINFORCED CONCRETE PIPE (RCP), 2000D (CLASS III), 18 IN.;
51.26 LF

Change Proposal Line No. 0580; 2310-5151040 PORTLAND CEMENT CONCRETE
OVERLAY, FURNISH ONLY;
From: 7,129.600 CY
To: 7,317.630 CY

Change Proposal Line No. 0590; 2310-5151551 PORTLAND CEMENT CONCRETE
OVERLAY, PLACEMENT ONLY (WHITE TOPPING);
From: 34,222.200 CY
To: 35,128.9000 CY

If the above changes are not made, they will be made as shown here.

Make the following changes to the PLAN:

On page C.03 under the reference note for "Construction Survey" please change the note to read as stated below

- a. Either string or string-less paving may be utilized on this project. If string-less paving is to be utilized on this project, the contractor shall perform a topo survey of the road. A PNEZD file and a proposed profile and surface shall be submitted to Buchanan County no sooner than two weeks before the start of paving; contractor shall target an 8 inch pavement thickness in Division I through Hazleton and a 6 inch overlay thickness in Division II. Buchanan County shall determine the final grade of the road. Otherwise if string line paving shall be used, all construction staking for P.C.C. paving operations shall be performed by the contractor. Contractor shall perform a topo survey of the road (Edgeline and Centerline shots) and a PNEZD file with a target of an 8 inch pavement in Division I through Hazleton, and a 6 inch overlay in Division II. Contractor shall submit a proposed profile to Buchanan County for review once survey is completed, Buchanan County shall determine the final grade of the road. Contractor shall also preserve all section corner monuments located in the project area. Section corner ties and certificates shall be available to the contractor upon request from Buchanan County. Updated corner certificates shall be submitted to Buchanan County upon completion of the project. All other construction staking shall be performed by Buchanan County.