

A d d e n d u m

Iowa Department of Transportation
Office of Contracts

Date of Letting: September 20, 2016
Date of Addendum: September 15, 2016

B.O.	Proposal ID	Proposal Work Type	County	Project Number	Addendum
104	74-2395-605	PCC SIDEWALK/TRAIL	PALO ALTO	TAP-R-2395(605)--8T-74	20sep104a01

Make the following changes to the PROPOSAL SCHEDULE OF PRICES:

Add Proposal Line No. 0055 2404-7775000, REINFORCING STEEL; 200.000 LB

Add Proposal Line No. 0125 2599-9999009, (LINEAR FEET ITEM) ROLLED HEADER JOINT; 100.000 LF

Make the following changes to the PLAN, SHEET C.01, TAB 100-4A ESTIMATE
REFERENCE INFORMATION:

ADD Item Code 2404-7775000: This item is for reinforcing the “landing” area shown on sheet number S.01 under the Detectable Warning Panels. Reinforcing steel shall be No. 4 bars placed at 3 foot on center for the entire 10’ x 10’ area. The item also includes reinforcing the “HT” Header Joint at the driveways with two No. 4 bars.

ADD Item Code 2599-9999009: This item is for constructing a rolled Header Joint “HT” (See standard road plan PV-101) adjacent to the trail at the existing driveways located at stations 4+00 and 23+00. The headers shall be constructed on both sides of the trail and cover the entire width (25’) of the existing driveways. The header joints shall be reinforced with two No. 4 longitudinal bars, said bars shall be paid for under the reinforcing steel bid item.